

GOVERNMENT OF INDIA
ARCHÆOLOGICAL SURVEY OF INDIA

CENTRAL
ARCHÆOLOGICAL
LIBRARY

ACCESSION NO. 1633

CALL No. 934.018/Ray


D.G.A. 79

1000000.

2

5








152

POLITICAL HISTORY OF ANCIENT INDIA



POLITICAL HISTORY OF ANCIENT INDIA

Acc. No. 1633

FROM THE ACCESSION OF PARIKSHIT TO THE
EXTINCTION OF THE GUPTA DYNASTY

BY

HEMCHANDRA RAYCHAUDHURI,

M.A., PH.D., F.R.A.S.B.

FORMERLY CARMICHAEL PROFESSOR AND HEAD OF THE DEPARTMENTS OF HISTORY
AND ANCIENT INDIAN HISTORY AND CULTURE, CALCUTTA UNIVERSITY;
AUTHOR OF "THE EARLY HISTORY OF THE VAISHNAVA SECT,"
"STUDIES IN INDIAN ANTIQUITIES," "VIKRAMĀDITYA IN
HISTORY AND LEGEND;" JOINT-AUTHOR OF "THE
GROUNDWORK OF INDIAN HISTORY," "AN
ADVANCED HISTORY OF INDIA," "AGE
OF THE NANDAS AND MAURYAS," ETC.

1633

SIXTH EDITION


(Revised and Enlarged)

934.018
Ray



UNIVERSITY OF CALCUTTA
1953

Rs. 20/-



CENTRAL ARCHAEOLOGICAL
LIBRARY, DELHI.

Acc. No. 1633

Date.... 8-6-4


Call No. 934.018. / Ray

PRINTED IN INDIA

PRINTED AND PUBLISHED BY SHENDRANATH KANJILAL
SUPERINTENDENT, CALCUTTA UNIVERSITY PRESS
48, HARDA ROAD, BALLYGUNGE, CALCUTTA.

1829B—December, 1953—B

To
Sir Asutosh Mookerjee
in token of grateful regard and esteem



PREFACE TO THE SIXTH EDITION

The *Political History of Ancient India* now arrives at a sixth edition. The continued illness of the author makes the task of revision extremely difficult. It has not been found possible to eliminate mistakes and misprints that may have crept into the volume.

Few important discoveries have been made in the domain of Ancient Indian History and Culture of the period dealt with in the following pages, since the publication of the fifth edition in 1950. It may, however, be noted that certain copper coins of a king whose name has been read as Rāmagupta have been collected by Śrī Advani and others at Bhilsa, bearing the figure of a lion on the obverse. The identity of the ruler is still undecided. The available evidence is not sufficient to indicate whether the ruler in question was a local prince or a scion of the imperial line of Guptas. Mention may also be made of a seal said to have been discovered in the Ghositārāma monastery in course of excavations at the site of Kauśāmbī carried on by the University of Allahabad. The seal is "impressed" with one of Toramāṇa, the famous Hun ruler, and seems to confirm the evidence of Somadeva, a Jaina contemporary of Kṛishṇa III Rāshtrakūṭa, regarding Hun penetration deep into the interior of the Ganges valley. The representation of Grumbates (of the Chionitai) as a Kushān ruler accepted by several scholars, is by no means certain.

The author has read with interest the learned notes on the Scythian period by Ludwig Bachhofer, Otto Maenchen Halfen, Dr. Lohuizen, and A. L. Basham, to whom recognition is due. His grateful thanks are also due to Professor Louis Renou of Paris for certain suggestions and constructive criticism.

THE UNIVERSITY OF CALCUTTA :

July 2, 1953

H. C. R. C.

PREFACE TO THE FIFTH EDITION

A fifth edition of the *Political History of Ancient India* is now placed before scholars. The author, who has been in very poor health for a long time, has found the task of revision a difficult one. He is conscious of the fact that misprints and other faults justly open to censure have not been avoided. Fresh study of the subject and new discoveries have necessitated a thorough revision of several chapters, preparation of additional notes, omission of parts of the text and other amendments. No pains have been spared to bring the work up-to-date.

Help of various kinds, including revision of Indexes, has been rendered by Mr. Durgadas Mukherji, Dr. Sudhakar Chatterji, Mr. Rabischandra Kar and Dr. Golapchandra Raychaudhuri to whom the author's acknowledgments are due.

THE UNIVERSITY OF CALCUTTA :

March 1, 1950.

H. C. R. C.

PREFACE TO THE FOURTH EDITION

In placing the fourth edition of the *Political History of Ancient India* in the hands of students of Indian Antiquities the author takes the opportunity of expressing his grateful thanks to scholars and explorers who have made accessible the rich stores of ancient learning and the priceless memorials of vanished glory that hitherto lay hidden beyond the ken of students and investigators. Suggestions and criticisms that earlier editions of the present work received in recent times, though not always of an instructive and informed character, have enabled the author to restate his position in regard to many matters treated in the volume. While unwilling to dogmatise on controversial points the writer of the following pages thinks that he has adduced fresh evidence in support of some of the views that were put forward years ago, long before certain recent notes and dissertations on kindred subjects saw the light of the day. He has also sought to incorporate new material which, it is hoped, may be of some little use to the ever-widening circle of eager inquirers who are interested in the chequered annals of this ancient land.

The Cimmerian veil of darkness that enshrouds not a few obscure spaces in the spectrum of the early history of this country cannot be lifted by the wand of the magician or the trick of the conjurer. Even if such a feat were possible the author confesses that he does not possess the requisite implements.

Help in the laborious task of compiling the indexes has been given by Dr. D. C. Sircar and Professor G. C. Raychaudhuri to whom the author's acknowledgments are due.

The volume that now goes forth before the public could not be made as free from mistakes as the present writer would have wished. Some of the errors and misprints have been noted and corrected but many blunders, justly open to censure, may have escaped attention. For these the author can only crave the indulgence of readers.

THE UNIVERSITY OF CALCUTTA :

March 31, 1938.

H. C. R. C.

PREFACE TO THE THIRD EDITION

The *Political History of Ancient India* now arrives at a third edition. An endeavour has been made to make it more accurate and up-to-date. Questions connected with certain dynasties, particularly of the Scythian period, have been treated afresh and several paragraphs have been revised in the light of the new information that may be gathered from literature as well as inscriptions discovered at Shahdaur, Maira, Khatlatse, Nāgarjunikōṇḍa, Guṇāighara and other places. Footnotes and appendices have been added to explain the author's viewpoint with regard to certain controversial matters. A new feature of the revised edition is the insertion in certain chapters, particularly of Part II, of introductory verses from literature to bring out some salient features of those chapters and incidentally, to show that poets and sages of Ancient India were not altogether unmindful of the political vicissitudes through which their country passed. The author craves the indulgence of the reader for certain misprints that have crept into the text. The labour of revising the Indexes has been performed by Sriyuts D. C. Raychaudhuri, G. C. Raychaudhuri and Anilkumar Raychaudhuri.

THE UNIVERSITY OF CALCUTTA :

December 13, 1931.

H. C. R. C.

EXTRACTS FROM THE PREFACE TO THE SECOND EDITION

A New edition of the *Political History of Ancient India from the Accession of Parkshit to the Extinction of the Gupta Dynasty* is placed before the public. The work has been out of print for some times and need has long been felt for a fresh edition. Therefore it goes forth once more having been revised and re-written in the light of the new information that is coming in so rapidly and in such vast bulk. No pains have been spared to bring the book up-to-date and make it more attractive to students. Material emendations have been made in almost every chapter. Some of the extracts in Sanskrit have been provided with English renderings.

A new feature of the present volume is the inclusion of a number of maps, and a few chronological and synchronistic tables, which, it is to be hoped, will increase the usefulness of the work. The incorporation of fresh material has necessitated a recasting of the indexes.

The present writer never intended his work to be a comprehensive survey of the political and dynastic history of every Indian province. He is chiefly concerned with those kingdoms and empires whose influence transcended provincial limits and had an important bearing upon the general course of political events in the heart and nerve-centres of the Indian sub-continent. Dynasties of mere local interest (*e.g.*, the Tamil *Prachamntas* of the far south, or the Himālayan *Pratyantas* in the far north) have received very brief notice, as these did not acquire an all-India importance till after the Gupta

period when a Jayadeva Parachakra-kāma had intimate dynastic relations with several rulers of the Indian interior, a Lalitāditya pushed his conquests as far as Kanauj, and a Rājendra Chola carried his arms to the banks of the Ganges.

Further, the author does not claim for the period from Parikshit to Bimbisāra the same degree of authenticity as for the age of the Mauryas, the Śātavāhanas and the Guptas. The absence of trustworthy contemporary dynastic records makes it preposterous to put forward such a proposition. In regard to the early period it has been his principal endeavour to show that the huge fabric of sacerdotal and rhapsodic legends is not based solely on the mythical fancy of mendacious priests and story-telling Diaskeuasts; that bardic tales sometimes conceal kernels of sober facts not less trustworthy than the current accounts of the dynasties immediately preceding the raid of Alexander; and that chronological relation of the national transactions before 600 B.C. is not impossible. In trying to demonstrate this he has not confined himself to literature of a particular type, but has collated the whole mass of evidence, Vedic as well as Purāṇic, Brāhmaṇical as well as non-Brāhmaṇical, Buddhist as well as Jain, Indian as well as Hellenic.

The writer of these pages wishes to acknowledge with sincere thanks his indebtedness to scholars and critics who have helped him with valuable suggestions, and especially to Dr. Barnett, Professor Schrader, Dr. Jarl Charpentier, Mr. H. Subbaiya and Mr. Asananda Nag. He is also grateful for the kind assistance which he received in many difficulties from his friends and colleagues, among whom Mr. Sailendranath Mitra, Dr. Suniti Kumar Chatterji, Mr. H. C. Ray and Mr. J. C. Chakravorti deserve especial mention. His acknowledgments are also due to Srijiut Golapchandra Raychaudhuri who gave him

much valuable help in the preparation of maps and the revision of the Indexes. The author does not claim that the Indexes are exhaustive, but he has spared no pains to include all important references.

THE UNIVERSITY OF CALCUTTA :

April 12, 1927.

H. C. R. C.

PREFACE TO THE FIRST EDITION

The object of the following pages is to sketch the political history of Ancient India from the accession of Parikshit to the extinction of the Gupta Dynasty. The idea of the work suggested itself many years ago from observing a tendency in some of the current books to dismiss the history of the period from the Bhārata war to the rise of Buddhism as incapable of arrangement in definite chronological order. The author's aim has been to present materials for an authentic chronological history of ancient India, including the neglected post-Bhārata period, but excluding the Epoch of the Kanauj Empires which properly falls within the domain of the historian of Mediaeval India.

The volume now offered to the public consists of two parts. In the first part an attempt has been made to furnish, from a comparison of the Vedic, Epic, Purāṇic, Jaina, Buddhist and secular Brāhmanical literature, such a narrative of the political vicissitudes of the post-Pārikshita-pre-Bimbisārian period as may not be less intelligible to the reader than Dr. Smith's account of the transactions of the post-Bimbisārian age. It has also been thought expedient to append, towards the end of this part, a short chapter on kingship in the Brāhmaṇa-Jātaka period. The purpose of the second part is to provide a history of the period from Bimbisāra to the Guptas which will be, to a certain extent, more up-to-date, if less voluminous, than the classic work of Dr. Smith.

The greater part of the volume now published was written some years ago, and the author has not had

the opportunity to discuss some of the novel theories advanced in recent works like *The Cambridge History of India*, and Mr. Pargiter's *Ancient Indian Historical Tradition*.

The writer of these pages offers his tribute of respect to the Hon'ble Sir Asutosh Mookerjee for providing opportunities for study which render it possible for a young learner to carry on investigation in the subject of his choice. To Professor D. R. Bhandarkar the author is grateful for the interest taken in the progress of the work. His acknowledgments are also due to Messrs. Girindramohan Sarkar and Rameschandra Raychauduri for their assistance in preparing the Indexes. Lastly, this preface cannot be closed without a word of thanks to Mr. A. C. Ghatak, the Superintendent, for his help in piloting the work through the Press.

July 16, 1923.

H. C. R. (C).

CONTENTS

PART I

FROM THE ACCESSION OF PARIKSHIT TO THE CORONATION OF BIMBISARA

PAGE

CHAPTER I—INTRODUCTION

Section I.	Foreword	1
„ II.	Sources	2

CHAPTER II—KURUS AND VAIDEHAS

Section I.	The Age of the Pārikshitas	12
„ II.	The Age of the Great Janaka	48
„ III.	The Later Vaidehas of Mithilā	80
„ IV.	The Deccan in the Age of the Later Vaidehas	85

CHAPTER III—MAHĀJANAPADAS AND KINGSHIP

Section I.	The Sixteen Mahājanapadas	95
„ II.	An Epic Account of the Mahājanapadas	151
„ III.	The Fall of Kāsi and the Ascendancy of Kosalā	153
„ IV.	Kingship	156

PART II

FROM THE CORONATION OF BIMBISARA TO THE EXTINCTION OF THE GUPTA DYNASTY

CHAPTER I—INTRODUCTION

Section I.	Foreword	181
„ II.	Local Autonomy and Imperial Unity	184

CHAPTER II—THE RISE OF MAGADHA

Section I.	General Character of the Period . . .	187
„ II.	Republics in the Age of Bimbisāra. . .	191
„ III.	The Minor Principalities and Great Monarchies	197
„ IV.	Magadha Crescent—Bimbisāra . . .	205
„ V.	Magadha Militant—Kūṇika-Ajātaśatru . .	210
„ VI.	Ajātaśatru's Successors—The Transfer of Capital and the Fall of Avanti . .	216
„ VII.	Chronology of the Haryāṅka-Siśunāga kings	225
„ VIII.	The Nandas	229

CHAPTER III—THE PERSIAN AND MACEDONIAN INVASIONS

Section I.	The Advance of Persia to the Indus . .	239
„ II.	The Last of the Achæmenids and Alexander	244

X CHAPTER IV—THE MAURYA EMPIRE : THE ERA OF
DIGVIJAYA

Section I.	The Reign of Chandragupta Maurya . .	264
„ II.	The Reign of Bindusāra	296
„ III.	The Early Years of Aśoka	302

CHAPTER V—THE MAURYA EMPIRE : THE ERA OF
DHAMMAVIJAYA AND DECLINE

Section I.	Aśoka after the Kalinga War	322
„ II.	The Later Mauryas and the Decline of their Power	349*

CONTENTS

xix

PAGE

CHAPTER VI—THE BAIMBIKA-SUŒGA EMPIRE AND THE BACTRIAN GREEKS

Section I. The Reign of Pushyamitra	368
„ II. Agnimitra and his Successors	391
„ III. Importance of the Baimbika-SuŒga Period of Indian History	397

CHAPTER VII—THE FALL OF THE MAGADHAN AND INDO-GREEK POWERS

Section I. The Kānvas, the Later SuŒgas and the Later Mitras	398
„ II. The Śātavāhanas and the Chetas	403
„ III. The End of Greek Rule in North-West India ¹	422

CHAPTER VIII—SCYTHIAN RULE IN NORTHERN INDIA

Section I. The Śakas	431
„ II. The Pahlavas or Parthians	451
„ III. The Great Kushāns	458
„ IV. The Nāgas and the Later Kushāns	480

CHAPTER IX—SCYTHIAN RULE IN SOUTHERN AND WESTERN INDIA

Section I. The Kshaharātas	483
„ II. The Restoration of the Śātavāhana Empire	491
„ III. The Śakas of Ujjain and Kāthiāwār	505
„ IV. Administrative Machinery of the Scythian Period	514

¹ In this work "India" means usually the entire territory known by that name up to August 15, 1947.

CHAPTER X—THE GUPTA EMPIRE : THE RISE OF THE GUPTA POWER

Section I. The Foundation of the Gupta Dynasty	527
„ II. Chandra Gupta I	530
„ III. Samudra Gupta Parākramāṅka	533

CHAPTER XI—THE GUPTA EMPIRE (*continued*) : THE AGE OF THE VIKRAMĀDITYAS

Section I. Chandra Gupta II Vikramāditya	553
„ II. Kumāra Gupta I Mahendrāditya	566
„ III. Skanda Gupta Vikramāditya	572

CHAPTER XII—THE GUPTA EMPIRE (*continued*) : THE LATER GUPTAS

Section I. Survival of the Gupta Power after Skanda Gupta	581
„ II. Puru Gupta and Narasiṁha Gupta Bālāditya	585
„ III. Kumāra Gupta II and Viṣṇugupta	590
„ IV. Budha Gupta	593
„ V. Successors of Budha Gupta	595
„ VI. The Line of Kṛishṇa Gupta	600

GENEALOGICAL AND SYNCHRONISTIC TABLES

The Pārikshita Family	47
Succession of some Vedic Teachers	51
Traditional Genealogy of the Pradyotas	221
Suggested chronological Table (of the Bimbisārid- Saisunāga Period)	228
Maurya Dynasty	367

CONTENTS

xxi

PAGE

Early Śātavāhanas	418
Satrapas of Mathurā	445n
Pallavas	501
Śakas of Ujjain	513
Vākāṭakas	565
The Early Imperial Guptas	599
The Latest Guptas	613
Synchronistic Table To face page	640

APPENDICES, INDEXES, ETC.

Abbreviations	xxii
Appendix A : The Results of Aśoka's Propaganda in Western Asia	614
Appendix B : A Note on the Chronological Relation of Kanishka and Rudradāman I	618
Appendix C : A Note on the Later Guptas	623
Appendix D : The Decline of the Early Gupta Empire	626
Appendix E : Kingdoms of Trans-Vindhyan India	636
Bibliographical Index	641
General Index	650
Additions and Corrections	669

MAPS

1. India in the Age of Janaka To face page	58
2. Ancient Dakṣiṇāpatha " "	85
3. The Mahājanapadas of Ancient India and East Irān " "	95
4. Bhāratavarsha " "	196
5. India in the Age of the Later Guptas " "	581

ABBREVIATIONS

A. B.	After the Buddha.
A. G. I.	Ancient Geography of India.
A. H. D.	Ancient History of the Deccan.
A. I. H. T.	Ancient Indian Historical Tradition.
A. I. U.	The Age of Imperial Unity (Bhāratiya Vidyā Bhavana).
Ait. Br.	Aitareya Brāhmaṇa.
Alex.	Plutarch's Life of Alexander.
A. N. M.	Age of the Nandas and Mauryas (Pub. Motilal Banarasi Dass for the Bhāratiya Itihāsa Parishad).
Ang.	Āṅguttara Nikāya.
Ann. Bhand. Ins.	Annals of the Bhandarkar Oriental Research Institute.
Āpas. Sr. Sūtra.	Āpastambīya Śrauta Sūtra.
App.	Appendix.
Arch. Rep.	Archaeological Survey Report.
A. R.	Annual Report.
A. R. I.	Aryan Rule in India
A. S. I.	Archaeological Survey of India.
A. S. R. (Arch. Surv. Rep.).	Reports of the Archaeological Survey of India.
A. S. W. I.	Archaeological Survey of Western India.
A. V.	Atharva-Veda.
Baudh. Śr. Sūtra	Bodhāyana Śrauta Sūtra.
Bau. Sūtra.	Baudhāyana Dharma Sūtra.
Bhand. Com. Vol.	Bhandarkar Commemoration Volume.
B. K. S.	Book of Kindred Sayings.
Bomb. Gaz.	Bombay Gazetteer.

Br.	.	.	.	Brāhmaṇa.
Bṛih. S.	.	.	.	Bṛihat Saṁhitā.
Bṛih. Up.	.	.	.	Bṛihadāranyaka Upanishad.
Bud. Ind.	.	.	.	Buddhist India.
C.	.	.	.	Central.
C. A. H.	.	.	.	Cambridge Ancient History.
Cal. Rev.	.	.	.	Calcutta Review.
Camb. Ed.	.	.	.	Cambridge Edition.
Camb. Hist. (Ind.).	.	.	.	Cambridge History of India
(C. H. I.)	.	.	.	(Vol. D).
Camb. Short Hist.	.	.	.	(The) Cambridge Shorter History of India.
Carm. Lec.	.	.	.	Carmichael Lectures, 1918.
Ch.	}	.	.	Chapter.
Chap.		.	.	
Chh. Up.	.	.	.	Chhāndogya Upanishad.
C. I. C. A. I.	.	.	.	Catalogue of Indian Coins, Ancient India.
C. I. I.	}	.	.	Corpus Inscriptionum Indicarum.
Corpus.		.	.	
Com. Vol.	.	.	.	Commemoration Volume.
Cunn.	.	.	.	Cunningham.
D.	.	.	.	Dīgha Nikāya.
Dialogues.	.	.	.	Dialogues of the Buddha.
D. P. P. N.	.	.	.	Dictionary of Pali Proper Names (Malalasekera).
D. K. A.	.	.	.	Dynasties of the Kali Age.
D. U.	.	.	.	Dacca University.
Ed.	.	.	.	Edition.
E. H. D.	.	.	.	Early History of the Dekkan.
E. H. I.	.	.	.	Early History of India.
E. H. V. S.	.	.	.	Early History of the Vaishṇava Sect.
Ep. Ind.	.	.	.	Epigraphia Indica.
Gandhāra (Foucher)	.	.	.	Notes on the Ancient Geography of Gandhāra.
Gaz.	.	.	.	Gazetteer.

G. B. I.	.	.	.	The Greeks in Bactria and India.
G. E.	.	.	.	Gupta Era.
G. E. I.	.	.	.	(The) Great Epic of India.
Gop. Br.	.	.	.	Gopatha Brāhmaṇa.
G. O. S.	.	.	.	Gaekwar Oriental Series.
Greeks.	.	.	.	The Greeks in Bactria and India.
Hariv.	.	.	.	Harivaṃśa.
H. and F.	.	.	.	Hamilton and Falconer's Translation of Strabo's Geography.
H. C. I. P.	.	.	.	The History and Culture of the Indian People (Bhāratīya Vidyā Bhavana)
H. F. A. I. C.	.	.	.	History of Fine Art in India and Ceylon.
Hist. N. E. Ind.	.	.	.	History of North Eastern India.
Hist. Sans. Lit.	.	.	.	(A) History of Sanskrit Literature.
H. O. S.	.	.	.	Harvard Oriental Series.
Hyd. Hist. Cong.	.	.	.	Proceedings of the Indian History Congress, Hyderabad (1941).
I. H. Q.	.	.	.	Indian Historical Quarterly.
Int. Ant. (I. A.)	.	.	.	Indian Antiquary.
Ind. Lit.	.	.	.	History of Indian Literature.
Imp. Gaz.	.	.	.	Imperial Gazetteer.
Inv. Alex.	.	.	.	Invasion of Alexander.
Ins.	.	.	.	Inscriptions.
J.	.	.	.	Jātaka.
J. A. (Journ. As.)	.	.	.	Journal Asiatique.
J. A. H. S.	.	.	.	Journal of the Andhra Historical Society.
J. A. O. S.	.	.	.	Journal of the American Oriental Society.
J. A. S. B.	.	.	.	Journal and Proceedings of the Asiatic Society of Bengal.
J. B. Br. R. A. S.	.	.	.	Journal of the Bombay Branch of the Royal Asiatic Society.
J. B. O. R. S.	.	.	.	Journal of the Bihar and Orissa Research Society.


ABBREVIATIONS

xxv

J. I. H.	Journal of Indian History
J. N. S. I.	Journal of the Numismatic Society of India.
J. R. A. S.	Journal of the Royal Asiatic Society (Great Britain)
J. R. N. S.	Journal of the Royal Numismatic Society and the Numismatic Chronicle.
J. U. P. H. S.	Journal of the United Provinces Historical Society.
Kaush. Up.	Kaushitaki Upanishad.
Kaut.	Arthaśāstra of Kauṭilya, Mysore, 1919.
Kishk.	Kishkindhyā Kāṇḍa of the Rāmāyana.
Life	(The) Life of Hiuen Tsang.
M.	Majjhima Nikāya.
M. A. S. I.	Memoirs of the Archaeological Survey of India.
Mat.	Matsya Purāṇa.
Mbh.	Mahābhārata.
Med. Hind. Ind.	Mediaeval Hindu India.
Mod. Rev.	Modern Review.
M. R.	Minor Rock Edicts.
N.	Nikāya.
N. H. I. P.	The New History of the Indian People (Vol. VI).
N. Ins.	(A) List of Inscriptions of North India.
Num. Chron.	Numismatic Chronicle.
O. S. (Penzer)	The Ocean of Story.
P.	Purāṇa.
P. A. O. S.	Proceedings of the American Oriental Society.
Pratijñā	Pratijñā Yaugandharāyana.
Pro. Or. Conf.	Proceedings of the All-India Oriental Conference.

Pt. (Pat.)	Patañjali.
Rām.	Rāmāyaṇa.
R. D. B.	Rakhal Das Banerji
R. P. V. U.	Religion and Philosophy of the Veda and Upanishads.
R. V.	Rig-Veda.
Śāṅkh. Śr. Sūtra	Śāṅkhāyana Śrauta Sūtra.
Sans. Lit.	Sanskrit Literature.
Śanti.	Śāntiparva of the Mahābhārata.
Sat. Br.	Satapatha Brāhmaṇa.
S. B. E.	Sacred Books of the East.
S. E.	Śaka Era.
Sec.	Section.
S. I. I.	South Indian Inscriptions.
S. Ins.	(A) List of Inscriptions of Southern India.
S. P. Patrika	Vaṅgīya Sābitya-Parishat Patrikā.
Svapna.	Svapnavāsavadatta.
Tr.	Translation.
Up. Br.	Upanishad Brāhmaṇa.
V.	Veda.
Vāj. Sam.	Vājasaneyi-Saṁhitā.
Ved. Ind.	Vedic Index.
Vish.	Vishṇu Purāṇa.
Vizag. Dist. Gaz.	Vizagapatam District Gazetteer.
Vogel Volume	A Volume of Oriental Studies presented to Jean Philippe Vogel (1947).
Z. D. M. G.	Zeitschrift der Deutschen Mor- genlandischen Gesellschaft.

PART I



Political History of Ancient India

PART I

From the Accession of Parikshit to the Coronation of
Bimbisāra

CHAPTER I. INTRODUCTION

SECTION I. FOREWORD

No Thucydides or Tacitus has left for posterity a genuine history of Ancient India. But the patient investigations of numerous scholars and archæologists have opened up rich stores of material for the reconstruction of the ancient history of our country. The first notable attempt to "sort and arrange the accumulated and ever-growing stores of knowledge" was made by Dr. Vincent Smith. But the excellent historian, failing to find sober history in bardic tales, ignored the period immediately succeeding "the famous war waged on the banks of the Jumna, between the sons of Kuru and the sons of Pāṇḍu," and took as his starting point the middle of the seventh century B.C. The aim of the present writer has been to sketch in outline the dynastic history of Ancient India including the neglected period. He takes as his starting point the accession of Parikshit which, according to Epic and Purāṇic tradition, took place shortly after the Bhārata War.

Valuable information regarding the Pārikshita and the post-Pārikshita periods has been given by eminent scholars like Weber, Lassen, Eggeling, Caland, Oldenberg, Jacobi, Hopkins, Macdonell, Keith, Rhys Davids, Fick, Pargiter, Bhandarkar and others. But the attempt to

2 POLITICAL HISTORY OF ANCIENT INDIA

frame an outline of political history from Parikshit to Bimbisāra out of materials supplied by Brāhmaṇic as well as non-Brāhmaṇic literature is, I believe, made for the first time in the following pages.

SECTION II. SOURCES

No inscription or coin has unfortunately been discovered which can be referred, with any amount of certainty, to the post-Pārikshita-pre-Bimbisārian period. The South Indian plates purporting to belong to the reign of Janamejaya¹ have been proved to be spurious. Our chief reliance must, therefore, be placed upon literary evidence. Unfortunately this evidence is, in the main, Indian, and is not supplemented to any considerable extent by those foreign notices which have "done more than any archæological discovery to render possible the remarkable resuscitation" of the history of the post-Bimbisārian epoch. The discoveries at Mahenjo-Daro and Harappa no doubt constitute a welcome addition to the purely literary evidence regarding the ancient history of India. But the civilisation disclosed is possibly that of Sauvīra or Sovīra (Sophr, Ophir)² in the pre-Pārikshita period. And the monuments exhumed "offer little direct contribution to the materials for political history," particularly of the *Madhya-deśa* or the Upper Ganges valley.

Indian literature useful for the purpose of the historian of the post-Pārikshita-pre-Bimbisārian age may be divided into five classes, viz. :—

I. Brāhmaṇical literature of the post-Pārikshita-pre-Bimbisārian period. This class of literature naturally contributes the most valuable information regarding the history of the earliest dynasties and comprises :

¹ Ep. Ind., VII, App., pp. 162-63 ; IA, III, 263 ; IV, 333.

² Cf. IA, XIII, 229 ; I. Kings, 9, 28 ; 10, 11.

(a) The last book of the *Atharva Veda*.

(b) The *Aitareya*, *Śatapatha*, *Pañchaviṃśa* and other ancient *Brāhmaṇas*.¹

(c) The major part of the *Bṛihadāranyaka*, the *Chhândogya* and other classical *Upanishads*.

That these works belong to the post-Pārikshita period is proved by repeated references to Parikshit, to his son Janamejaya, to Janamejaya's successor Abhipratārin, and to Janaka of Videha at whose court the fate of the Pārikshitas was discussed by the assembled sages. That these works are in the main pre-Buddhist and, therefore, pre-Bimbisārian, has been proved by competent critics like Dr. Rājendralāl Mitra,² Professor Macdonell³ and others.

II. The second class comprises Brāhmapical works to which no definite date can be assigned, but large portions of which, in the opinion of scholars, belong to the post-Bimbisārian period. To this class belong the *Rāmāyaṇa*, the *Mahābhārata* and the *Purāṇas*. The present *Rāmāyaṇa* consists of 24,000 *ślokas* or verses.⁴ But even in the first or second century A.D. the epic seems to have contained only 12,000 *ślokas*⁵ as the evidence of the Buddhist *Mahāvibhāṣā*, a commentary on the *Jñānaprasthāna* of Kātyāyanīputra, suggests. It not only mentions Buddha Tathāgata,⁶ but distinctly refers to the struggles of the Hindus with mixed hordes of Yavanas (Greeks) and Śakas (Scythians), *Śakān*

¹ Of special importance are the *gāthās* or songs in the thirteenth *kāṇḍa* of the *Sat. Br.* and the eighth *pañchikā* of the *Aitareya*.

² Translation of the *Chhândogya Upanishad*, pp. 23-24.

³ *History of Sanskrit Literature*, pp. 169, 202-03, 226.

⁴ 1.4.2—*Chaturviṃśa-sahasraṇi ślokanām uttaraṇa* fishiḥ.

⁵ J. R. A. S., 1907, pp. 99 ff. Cf. Banjia Nanjio's Catalogue, No. 1263.

⁶ II. 109, 34.

Yavana-miśritān.¹ In the *Kishkindhyā Kāṇḍa*,² Sugrīva places the country of the Yavanas and the cities of the Sakas between the country of the Kurus and the Madras, and the Himālayas. This shows that the Græco-Scythians at that time occupied parts of the Pañjāb. The *Laṅkā Kāṇḍa*³ apparently refers to the Purāṇic episode of the uplifting of Mount Mandara, or of Govardhana, *Parigrihya girim dorbhyām vapur Vishnor viḍambayan*.⁴

As regards the present *Mahābhārata*, Hopkins says⁵ : "Buddhist supremacy already decadent is implied by passages which allude contemptuously to the eḍukas or Buddhistic monuments as having ousted the temples of the gods. Thus in III. 190. 65 'They will revere eḍukas, they will neglect the gods'; *ib.* 67 'the earth shall be piled with eḍukas, not adorned with godhouses.' With such expressions may be compared the thoroughly Buddhistic epithet, *Cāturmahārājika* in XII. 339. 40 and Buddhistic philosophy as expounded in the same book."

"The Greeks are described as a western people and their overthrow is alluded to.....The Romans, Romakas, are mentioned but once, in a formal list of all possible peoples, II. 51.17, and stand thus in marked contrast to Greeks and Persians, Pahlavas, who are mentioned very often.....The distinct prophecy that 'Scythians, Greeks and Bactrians will rule unrighteously in the evil age to

¹ I. 54. 21.

² IV. 43. 11-12. Note also the references to Vaijayantapura in the Deccan (II. 9. 12), the Drāviḍas (*ibid.* 10. 37), Malaya and Darḍdūra (*ibid.* 91. 24) Morachipattana (Muziris, Oranganore, IV. 42. 3), practices of the people of the Deccan (II. 93. 13), "the seven flourishing realms" of Yavadvīpa (Java), Suvarṇadvīpa (Sumatra) in IV. 40. 30. and Karkāṭaka lagna (II. 15. 3).

³ 69. 92; cf. *Matsya*, 249. 53; *Bhāgavata*, X. 25. *Mbh.* III. 101. 15.

⁴ For some other Purāṇic allusions see *Calcutta Review*, March, 1922, pp. 500-02. For references to *sūtras* see Hopkins, J.A.O.S., 13, 173. For 'empire' *Rām* II. 10. 36.

⁵ *The Great Epic of India*, pp. 391-93.

come' which occurs in III. 188.35 is too clear a statement to be ignored or explained away."

The *Ādiparva*¹ refers to king Aśoka who is represented as an incarnation of a *Mahāsura* or great demon,² and is described as *mahāvīryo'parājitaḥ*, of great prowess and invincible. We have also a reference³ to a Greek overlord, *Yatanādhipaḥ* of Sauvīra and his compatriot Dattāmitra (Demetrios ?). The *Sāntiparva* presupposes the inclusion of the city of Mālinī, in the land of the Aṅgas, within the realm of Magadha.⁴ It mentions Yāska, the author of the *Nirukta*,⁵ Vārshaganya,⁶ the Sāṃkhya philosopher who probably flourished in the fourth or fifth century after Christ⁷ and Kāmandaka,⁸ the authority, on *Dharma* (sacred law) and *Artha* (polity) who is probably to be identified with the famous disciple of Kauṭilya.

The eighteen *Purāṇas* were certainly known to Alberuni⁹ (A.D. 1000), Rājaśekhara (A.D. 900), and the

¹ I. 67.13-14. Cf. also XII. 5.7 where Aśoka is mentioned with Satadhanvan.

² It is interesting to note in this connection that in the *Devīmāhātmya* of the *Mārkaṇḍeya Purāṇa* (88.5) *Maurya* is the name of a class of *Asuras* or demons :—

*Kālakā Daurhṛitā Mauryāḥ Kālakeyāstathāsuraḥ
yuddhāya sajjā niryāntu ājñayā tearitā mama*

"Let the Kālaka, the Daurhṛita, the *Maurya* and the Kālakeya *Asuras*, hastening at my command, march forth ready for battle."

Note also the expression *suradrishām* (of the enemies of the gods, i.e., *Asuras*), used by the *Bhāgavata Purāṇa* (1.3.24) in reference to people "deluded" by the Buddha.

³ *Mbh.*, I 139.21-23.

⁴ 5 1-6.

⁵ 342, 73.

⁶ 318, 59.

⁷ J. R. A. S., 1905, pp. 47-51 ; Keith, *Sāṃkhya System*, pp. 62, 63, 69.

⁸ *Sānti*, 123, 11.

⁹ Cf. Alberuni, Ch. XII ; *Pracharṇa-Pāṇḍava* ed. by Carl Cappeller, p. 5 *ashṭādāsa-purāṇa-sāra-saṃgraha-kārin* ; *Mbh.* XVIII. 6. 97 ; *Harshacharita*, III (p. 86 of Parash's ed., 1918), *Paramāna-prokta Purāṇa*, i. e., *Vāyu Purāṇa* ; Cf. *Sakala-purāṇa-rājārshi charitābhijñāḥ* (III. 87) and *Hareriva Vṛishavirodhini Bālacharitāni* (II. 77) ; EHVS, second ed., pp. 17, 70, 150. The fact that the collection of the essence (*sāra-saṃgraha*) of all the eighteen *Purāṇas* is attributed to a very ancient sage by Rājaśekhara proves that the *Purāṇas* themselves were

latest compiler of the *Mahābhārata* who flourished before A.D. 500. Some of the Purāṇic chronicles are mentioned by Bāṇa (A.D. 600) and earlier writers. But the extant texts which contain lists of kings of the *Kali Age* cannot be placed earlier than the third or fourth century A.D., because they refer to the so-called Andhra kings and even to the post-Andhras.

It is clear from what has been stated above that the Epics and the *Purāṇas*, in their present shape, are late works which are no better suited to serve as the foundation of the history of the pre-Bimbisārian age than are the tales of the *Mahāvamśa* and the *Aśokāvadāna* adapted to form the bases of chronicles of the doings of the great Mauryas. At the same time we shall not be justified in rejecting their evidence wholesale because much of it is undoubtedly old and valuable. The warning to handle critically, which Dr. Smith considered necessary with regard to the Pali chronicles of Ceylon, is also applicable to the Sanskrit Epics and *Purāṇas*.

In a recent work Dr. Keith shows scepticism about the historical value of these texts, and wonders at the "naïve credulity" of those who believe in the historicity of any event not explicitly mentioned in the Vedas, e.g., "a great *Bhāratian* war." It cannot be denied that the Epics and the *Purāṇas*, in their present shape, contain a good deal of what is untrustworthy; but it has been rightly said that "It is absurd to suppose that fiction completely ousted the truth." The epigraphic or numismatic records of the *Śātavāhanas*, *Ābhīras*, *Vākātakas*, *Nāgas*, *Guptas* and many other dynasties fully bear out the

believed by him to have been composed long before the ninth century A. D. The existence of some of the texts in the sixth century A. D. is hinted at by the Nārūr inscription of Maṅgaleśa (IA, VII. 161—*Mānava-Purāṇa-Rāmāyana-Bhārat-etihasa-kutatah...Valubāh*), i. e., Pulikeś I). The reference in the *Matsya Purāṇa*, which is regarded as one of the earliest among the Purāṇic works, to week days (70 : 46 ; 66 ; 72, 27, etc.) is of value in determining the upper limit.

observation of Dr. Smith that "modern European writers have been inclined to disparage unduly the authority of the *Purāṇic* lists, but closer study finds in them much genuine and valuable historical tradition." As to the "great *Bhārata* war" we have indeed no epigraphic corroboration, because contemporary inscriptions are lacking. But, as will be pointed out in a subsequent chapter, Vedic literature contains many hints that the story of the great conflict is not wholly fictitious. Many of the figures in the *Kurukshetra* story, *e.g.*, Bālīhika Prātipēya¹ (Balhika Prātipīya), Dhṛitarāshṭra Vaichitravīrya, Kṛiṣṇa Devakī-putra and perhaps Sikhaṇḍin Yājñasena, are mentioned in some of the early Vedic texts,² and we have a distinct allusion in the *Satapatha Brāhmaṇa* to the unfriendly feeling between the first of these, a prince of the Kurus, and the Sṛiñjayas³. It will be remembered that the great war described in the epic often takes the shape of a trial of strength between these two peoples (*Kurūṇām Sṛiñjayānām cha jigīṣhūnām paraṣparam*)⁴. In the *Jaiminīya Upanishad Brāhmaṇa*⁵ Kurus reproach the Dālbyhas, a clan closely connected with the Pañchālas who appear to have been among the principal antagonists of the Kuru leaders in the *Bhārata* War. The *Chhāndogya Upanishad*, as is well-known, contains a *gāthā* which eulogises the mare that comes to the rescue of the Kurus. Battle-songs describing the struggle of the Kurus against the Sṛiñjayas and associate tribes or clans must have been current at least as early as the fifth century B. C., because Vaiśampāyana and his version of the *Mahābhārata* are well-known to Āśvalāyana and Pāṇini. If, as

¹ *Mbh.*, V. 23.9.

² Cf. also Arjuna identified with Indra in the *Sat. Br.*, V. 4. 3. 7 and Partha in the *Āśvalāyana Śrauta Sūtra*, XII. 10 (*Vedic Index*, I. 529.).

³ *Vedic Index*, II., p. 63, *Sat. Br.*, XII. 9. 3.

⁴ *Mbh.*, VI. 45.2.

⁵ I. 38. 1 (xii, 4).

8 POLITICAL HISTORY OF ANCIENT INDIA

suggested by Vedic evidence discussed in the following pages, the "great *Bhāratan* war" really took place in or about the ninth century B.C., the broad outlines of the story about the conflict dating from a period not later than the fifth century B.C., cannot be dismissed as wholly unworthy of credence.

Pargiter, unlike Keith, is inclined to give more weight to Purāṇic tradition than to Vedic evidence, and his conclusions have apparently been accepted by Dr. Barnett.¹ It has eloquently been urged by the former² that Vedic literature "lacks the historical sense" and "is not always to be trusted." But do the *Purāṇas* which represent Śākya as one individual, include Abhimanyu and Siddhārtha in lists of kings, make Prasenajit the immediate lineal successor of Rāhula, place Pradyota several generations before Bimbisāra, dismiss Aśoka with one sentence, make no mention of the dynastic name Sātavāhana, and omit from the list of the so-called "Andhras," princes like Siri-Kubha (Śrī-Kumbha) Sātakaṇi whose existence is proved by the incontestable evidence of coins³, possess the historical sense in a remarkable degree, and are "always to be trusted"? Pargiter himself, not unoften, rejects Epic and Purāṇic evidence⁴ when it is opposed to certain theories. In this connection it will not be quite out of place to quote the following observations of Mr. V. Gordon Childe.⁵ "The *Kṣatriya* tradition (i.e., Epic and Purāṇic tradition).....is hardly an unpolluted source of history. The orthodox view is not really based on the priestly tradition, as embodied in

¹ *Calcutta Review*, Feb., 1924, p. 249.

² *Ancient Indian Historical Tradition*, pp. 9 ff.

³ Minshi in the *Journal of the Numismatic Society of India*, Vol. II.

⁴ Cf. *A.I.H. T.*, pp. 173, n. 1 ; 299, n. 7.

⁵ *The Aryans*, p. 82.

epexegetical works, but rather on the internal evidence of the Veda itself. The latter carries conviction precisely because the historical and geographical references in the hymns are introduced only incidentally and in a thoroughly ingenuous manner...The same cannot be said of *Kṣatriya* tradition, which in its recorded form dates from an age (perhaps as late as 200 A.D.) when myth-making had had many centuries to work in, and which might serve dynastic ends." Priority of date and comparative freedom from textual corruption are two strong points in favour of Vedic literature.

III. The third class of literature comprises Brāhmaṇical works of the post-Bimbisārian period to which a date in a definite epoch may be assigned, e.g., the *Kauṭilya Arthaśāstra* assignable to the period 249 B. C. to c. 100 A.D.¹, the *Mahābhāṣya* of Patañjali between

¹ The work was known not only to Bāṇa, the author of the *Kādambarī* who flourished in the seventh century A.D., but to the *Nandīśūtra* and *Pañṇas* of the Jains which may have existed in the early centuries A. D. and probably also to the *Nyāya Bhāṣya* of Vātsyāyana, which is criticised by Dignāga and perhaps by Vasubandhu too (I. A. 1915, p. 82, 1918, p. 103). According to some scholars the *Arthaśāstra* literature is later than the *Dharmadāstras*, and dates only from about the third century A. D. But the prevalence of the study of *Arthasāidyā* in a much earlier epoch is proved by the Junāgaḍh Rock Inscription of Rudradāman I and the existence of treatises on *Arthaśāstra* is rendered probable by the mention of technical terms like "*Pragaya*," "*Vishṭi*," etc. It is interesting to note that the *Kauṭilya*, which purports to be a compendium of pre-existing *Arthaśāstras*, does not quote the views of previous *Achāryas* or teachers in the chapter on "*Pragaya*" (Bk. V. Ch. 2) It is, therefore, not unlikely that Rudradāman I, who claims to have studied the *Arthasāidyā* learnt the use of the term from the *Kauṭilya* itself and not from a pre-Kauṭilyan treatise. In this connection it is interesting to note that the Junāgaḍh inscription of Skanda Gupta for instance, refers to the testing of officials by *upadhāḥ—sara-opadhābhīcha viśuddhabuddhiḥ*, "possessed of a mind that (has been tried and) is (found to be) pure by all the tests of honesty." The verse

*Nyāy-ārjane-rthasāyaka kaḥ samarthah
syād-arjitasy-āpy-atha rakṣhaṇa cha
gopāyitāry-āpi cha viddhi-hetau
viddhasya pātra-pratipādanāya*

10 POLITICAL HISTORY OF ANCIENT INDIA

c. 150 B.C. and 100 A.D.),¹ etc. The value of these important works can hardly be overestimated. They form "sheet anchors in the troubled sea of Indian chronology." Their evidence with regard to the pre-Bimbisārian age is certainly inferior to that of the *Brāhmaṇas* and the *Upanishads*, but the very fact that such information as they contain, comes from persons assignable to a known epoch, makes it more valuable than the Epic and Purāṇic tradition, the antiquity and authenticity of which can always be called in question.

"Who is capable both in the lawful acquisition of wealth, and also in the preservation of it, when acquired, and further in causing the increase of it, when protected, (and able) to dispense it on worthy objects, when it has been increased" (Fleet),

reminds us of *Kauṭ.*, I.1—

Danḍantīḥ; alabdha-lābhārthā labdha-parirakṣantī, rakṣita-vicardhantī, vṛddhasya virtheshu pratipādantī cha.

"The science of government, it is a means to make acquisitions, to preserve what is acquired, to increase what is protected and to distribute among the worthy what has been increased."

Johnston (J. R. A. S., 1929, 1 January, p. 77. ff.) points out that the *Kauṭīliya Arthaśāstra* is not separated by a great interval from Aśvaghoṣa, and is distinctly earlier than the *Jātakamāṇā* of Āryasūra (who flourished before 434 A. D. Winternitz *Ind. Lit.*, Vol. II. 276). An early date is also suggested by the absence of any reference to the Denarius in Book II. Chs. 12 and 19. But the mention of *Chīnabhūmi* and *Chīnapaṭṭa* in Bk. II, Ch. 11, precludes the possibility of a date earlier than the middle of the third century B. C. The reference must be to the great country of the Far East (Cf. "China which produces silk," Kosmas Indikopleustes, McCrindle's *Ancient India*, p. 162), and not to any obscure tribe on the outskirts of India. China silk looms large in the pages of classical Sanskrit writers. The great silk-producing country (as well as Kambū, *Kauṭ.*, II. 13) clearly lay outside the horizon of the early Mauryas. The name 'China' applied to the famous land can hardly be anterior to the first emperor of the Ch'in Dynasty (249-210 B.C., Mogi and Redman, *The Problem of the Far East*, p. 15). A post-Chandraguptan date for the *Arthaśāstra* is also suggested by (a) the reference to parapets of brick instead of wooden ramparts (II. 3), in connection with the royal seat, and (b) the use of Sanskrit at the Secretariat (II. 10). The imperial title *Chakravartī* (IX. 1) is not met with in inscriptions before Khāravela. The official designations *Samāhartṛi* and *Sannidhātṛi* find mention in epigraphs of a still later age.

¹ For recent discussions about the date of Patañjali see *Indian Culture*, III, II, *Proceedings of the Indian History Congress*, Third Session, pp. 510-11.

IV. To the fourth class belong the Buddhist *Suttas*, *Vinaya* texts and the *Jātakas*. Several works of the Buddhist canon are noticed in votive inscriptions at Bharhut and Sāñchī assigned to the second and first centuries B.C. Many of the reliefs found on the railings and gateways of *Stūpas* of the age depict stories taken from the *Jātakas*. The texts of the Pali canon are said to have been committed to writing in the first century B.C. They furnish a good deal of useful information regarding the period which immediately preceded the accession of Bimbisāra. They have also the merit of preserving Buddhist versions of ancient stories, and vouchsafe light when the light from Brāhmanical sources begins to fail.

V. To the fifth class belong the sacred texts of the Jainas. Some of the works may go back to a period earlier than the second century A.D. But the canon as a whole was probably reduced to writing in the fifth or sixth century A.D.¹ It gives interesting information regarding many kings who lived during the pre-Bimbisārian Age. But its comparatively late date makes its evidence not always reliable.

¹ Jacobi, *Paridīkṣā parvaṇ*, p. vii; S. B. E., Vol. XXII, p. xxxvii; XLV, p. xi. Cf. Winternitz, *A History of Indian Literature*, Eng. trans., Vol. II, p. 492.

CHAPTER II. KURUS AND VIDEHAS.

SECTION I. THE AGE OF THE PARIKSHITAS.

*Janah sa bhadramedhati
rāshṭre rājñah Parikshitah*

—*Atharva Veda.*

We have taken as our starting point the reign of **Pari-kshit** whose accession, according to tradition, took place shortly after the *Bhārata War*.

Was there really a king named Parikshit? True, he is mentioned in the *Mahābhārata* and the *Purāṇas*. But the mere mention of a king in this kind of literature is no sure proof of his historical existence unless we have corroborative evidence from external sources.

Parikshit appears in a famous laud of the Twentieth Book of the *Atharva Veda Samhitā*¹ as a king of the Kurus (*Kauravya*) whose kingdom (*rāshṭra*) flowed with milk and honey. The passage runs as follows :—

“*Rājño viśvajanīnasya yo deromartyām ati
vaiśvānarasya sushṭutimā sunotā Parikshitah
parichchhinnah kshemamakarot tama āsanamācharan
kulāyan kṛṇvan Kauravyah patirvadati jāyayā
katarat ta ā harāpi dadhi manthām pari śrutam
jāyāh patim vi prichchhati rāshṭre rājñah Parikshitah
abhīva stah pra jihīte yatah paktah patho bilam
janah sa bhadramedhati rāshṭre rājñah Parikshitah.*”

“Listen ye to the high praise of the king who rules over all peoples, the god who is above mortals, who is thought of by all men², of Parikshit! Parikshit has

¹ A. V., XX. 127. 7. 10.

² For the meaning of *Vaiśvānara*, see *Bṛihaddeśatā*, II. 66.

produced for us a secure dwelling when he, the most excellent one, went to his seat. (Thus) the husband in Kuru land, when he founds his household, converses with his wife.

"What may I bring to thee, curds, stirred drink or liquor? (Thus) the wife asks her husband in the kingdom of king Parikshit.

"Like light the ripe barley runs over beyond the mouth (of the vessels). The people thrive merrily in the kingdom of king Parikshit."¹

Roth and Bloomfield regard Parikshit in the *Atharva Veda* as a divine being. But Zimmer and Oldenberg recognize him as a human king, a view supported by the fact that in the *Aitareya* and *Śatapatha Brāhmaṇas* the famous king Janamejaya bears the patronymic *Pārikshita* (son of Parikshit). The *Aitareya Brāhmaṇa*,² for example, informs us that the priest Tura Kāvasheya "anointed Janamejaya *Pārikshita* with the great anointing of Indra" :

"*Etena ha vā Aindreṇa mahābhishekeṇa Turāḥ Kāvasheyo Janamejayam Pārikshitam abhishishecha.*"

Referring to king Parikshit, Macdonell and Keith observe³ : "The epic makes him grandfather of Pratiśravas and great-grandfather of Pratīpa." Now, the epic and the *Purāṇas* have really two Parikshits. Regarding the parentage of one there is no unanimity. He is variously represented as the son of Avikshit, Anaśvā, or Kuru, and is further mentioned as an ancestor of Pratiśravas and Pratīpa. The other Parikshit was a descendant of Pratīpa and, according to a unanimous tradition, a son

¹ Bloomfield, *Atharva Veda*, pp. 197-98, with slight emendations.

² VIII. 21.

³ *Vedic Index*, Vol. I, p. 484.

of Abhimanyu.¹ We shall call the former Parikshit I, and the latter Parikshit II. Was Parikshit I of the Epic and the *Purāṇas* identical with the Vedic Parikshit as suggested by the authors of the *Vedic Index*? In support of this view it may be urged that Indrota Daivāpa Saunaka, priest of Janamejaya, son of the Vedic Parikshit, according to the *Śatapatha Brāhmaṇa*,² is represented in several *Purāṇas*³ as chaplain of the son of Parikshit I who came *before* the Bhārata heroes. Indrota's son Dṛiti was a contemporary of Abhipratārin Kākshaseni,⁴ "son of Kakshasena," and the name of Kakshasena actually appears among the sons of Parikshit I in a genealogical list of the *Mahābhārata*.⁵ Further, like the Vedic Parikshit, Parikshit I had according to a *Purāṇic* passage, four sons, viz., Janamejaya, Śrutasena, Ugrasena, and Bhīmasena,⁶ and the eldest son had a quarrel with the Brāhmanas.

There are, however, other facts which point to an opposite conclusion. The Vedic Parikshit receives in the *Atharvan* laud the epithet *rājā viśvajanīna* (universal king) and is called "a *deva* (god) who is above mortals." In his days the designation *Kauravya* had ceased to be a mere royal patronymic and was applied to ordinary citizens in Kuru land. Kuru had become the eponymous ancestor of the entire race. And lastly, the people thrive merrily (*janah sa bhadramedhati*) in his realm. These particulars hardly apply to the shadowy Parikshit I of Epic and *Purāṇic* lists who is said to have been very near in time

¹ *Mahābhārata*, *Adiparva*, 94. 52 and 95, 41. Regarding Parikshit I, the *Matya Purāṇa* says, 80, 23 :

*Kursta dayitāḥ putrāḥ Sudhanvā Jahnureva cha
Parikshichecha mahatejāḥ pravratā chārimardanaḥ.*

² *Vedic Index*, i. 78.

³ Pargiter, *AHT*, 114.

⁴ *Vedic Index*, i. 373.

⁵ *MBh.* I. 94, 61.

⁶ *Viṣṇu Purāṇa*, iv. 20. 1.

to Kuru himself.¹ On the other hand the Vedic laud corresponds wonderfully, both in content and phraseology with the famous *ākhyāna* (story) of Parikshit II, son of Abhimanyu, narrated in Chapters 16 to 18 of the *Bhāgavata Purāṇa*. We are told that this Parikshit undertook a *dignijaya*, conquest of all the quarters, in the course of which he subjugated all the sub-continent (*varshāṇi*). He is called the *supreme deva* who is not to be regarded as the equal of ordinary men (*na vai nṛibhir-naradevaṁ parākhyam sahmātam arhasi*). He is further styled *samrāt* (emperor) and under his protection people thrive and have nothing to fear (*vindanti bhadraṅyakuto-bhayāḥ prajāḥ*).

Proof of the identity of this Parikshit (son of Abhimanyu) with his Vedic namesake is also furnished by a later passage of the same *Purāṇa*² which mentions Tura Kāvasheya as the priest of his son Janamejaya :

Kāvasheyaṁ purodhūya Turam turagamedharat.

samantāt prithivīm sarvām jītvā yakshyati chādharaiḥ.

It will be remembered that the same sage appears as the priest of Janamejaya Pārikshita in the *Aitareya Brāhmaṇa*.

The *Bhāgavata Purāṇa* is no doubt a late work. But its evidence does not stand alone. This will be made clear by an examination of the names of the sons of Parikshit given in the Vedic texts and the Epic respectively. The Vedic Parikshit, we are told, had four sons namely, Janamejaya, Ugrasena, Bhīmasena and Śrutasena.³ The Epic Parikshit I, on the other hand, had only one son (Bhīmasena) according to Chapter 95,

¹ In the *Vāya Purāṇa*, 93, 31 and the *Harivamśa*, XXX, 9, Parikshit I seems to be identified with Kuru himself as his son (Pārikshita) is called *Kuroḥ putraḥ*, son of Kuru.

² Book IX, Ch. 23, Verses 26-37.

³ *Vedic Index*, Vol. I, p. 520.

verse 42 of the *Ādiparva* of the *Mahābhārata*, and seven sons (Janamejaya, Kakshasena, Ugrasena, Chitrasena, Indrasena, Sushena and Bhīmasena) according to Chapter 94, verses 54-55, and among these the name of *Śrutasena* does not occur. Even Janamejaya is omitted in Chapter 95 and in the *Java text*.¹ There is no king of that name immediately after Parikshit I, also in the Kuru-Pāṇḍu genealogy given in the Chellur or Cocanada grant of Virachōḍa.² The Epic poet and the writer of the Chōḍa inscription, which is much older than many extant manuscripts of the *Mahābhārata*, therefore, were not quite sure as to whether this Parikshit (I) was the father of Janamejaya and *Śrutasena*. On the other hand, according to the unanimous testimony of the *Mahābhārata* and the *Purāṇas*, Parikshit II had undoubtedly a son named Janamejaya who succeeded him on the throne. Thus the *Mahābhārata*, referring to Parikshit II, the son of Abhimanyu, says.³

Parikshit khalu Mādravatīm nāmopayame, tvanmātaram. Tasyām bhavān Janamejayaḥ. "Parikshit married Mādravatī, your mother, and she gave birth to you, Janamejaya."

The *Matsya Purāṇa*⁴ informs us that

"Abhimanyoḥ Parikshittu putraḥ parapurañjayayaḥ

Janamejayaḥ Parikshitah putraḥ paramadhārmikah."

"Abhimanyu's son was Parikshit, the conqueror of his enemy's city. Parikshit's son was Janamejaya who was very righteous."

This Janamejaya had three brothers, namely, *Śrutasena*, *Ugrasena* and *Bhīmasena* :—"Janamejayaḥ Pārikshitah

¹ *J. R. A., S.*, 1913, p. 6.

² Hultzsch, *S. I. I.*, Vol. I, p. 57.

³ I. 95, 85.

⁴ 50, 57.

saha bhrātribhiḥ Kurukshetre dīrgha-satram upāste ; tasya bhrātarastrayaḥ Śrutasena Ugrasena Bhīmasena iti."¹

"Janamejaya, son of Parikshit, with his brothers, was attending a long sacrifice at Kurukshetra. His brothers were three, namely,—Śrutasena, Ugrasena and Bhīmasena."

Particulars regarding the son and successor of the Vedic Parikshit agree well with what we know of the son and successor of the Epic and the Purāṇic Parikshit II. Janamejaya, the son of the Vedic Parikshit, is mentioned in the *Śatapatha Brāhmaṇa* as a performer of the *Aśvamedha* or horse-sacrifice. The priest who performed the famous rite for him was Indrota Daivāpa Śaunaka. On the other hand, the *Aitareya Brāhmaṇa*, which also mentions his *Aśvamedha*, names Tura Kāvasheya as his priest. The statements of the *Śatapatha*, and *Aitareya Brāhmaṇas* are apparently conflicting, and can be reconciled if we surmise that either we are dealing with two different kings of the same name and parentage or the same Janamejaya performed two horse-sacrifices. Which Janamejaya actually did so ? Curiously enough the *Purāṇas* give the information which is needed. The *Matsya Purāṇa* speaking of Janamejaya, the grandson of Abhimanyu, and the son of Parikshit II, says :

*Dvir aśvamedham āhṛtya mahāvājasaneyakam
pravartayitvā taṁ sarvaṁ ṛshim Vājasaneyakam
vivāde Brāhmaṇaiḥ sārddham abhiśapto vanam yayau.*²

The quarrel with the Brāhmaṇas, alluded to in the

¹ *Mbh.* 1. 3. 1. In translating Epic passages use has been made of the renderings of Ray and Dutt. See also Purāṇic texts cited by Pargiter, *Dynasties of the Kālī Age*, p. 404. The view that Śrutasena, Ugrasena and Bhīmasena were sons of Janamejaya (Pargiter, *Ancient Indian Historical Tradition*, p. 113 f.) is clearly opposed to the evidence of the Epic and several *Purāṇas*, as well as that of Harisvāmin. Speaking about Parikshit, son of Abhimanyu, the *Vishṇu Purāṇa*, for example, says (iv. 21. 1) : "Yo'yaṁ sāmpratam avanipatiḥ tasyāpi Janamejaya-Śrutasena-Ugrasena-Bhīmasenah putrās chatvāro bhaviṣyanti."

² 50, 63-64. Cf. N. K. Siddhanta, *The Heroic Age of India*, p. 42.

last line, is also mentioned in the *Aitareya Brāhmaṇa*.¹ According to that text Janamejaya's priestly opponents were the Kaśyapas. That designation hardly applies to the Gārgyas who quarrelled with the son of *Parikshit I*² because the *Baudhāyana Śrauta Sūtra*³ includes them in the Angiras group. On the other hand Vaiśampāyana, who led the opponents of the son of *Parikshit II*, was undoubtedly a Kaśyapa.⁴

Parikshit II has thus a better claim than Parikshit I to be regarded as identical with the Vedic Parikshit. It is, however, possible that Parikshit I and Parikshit II represent a bardic duplication of the same original individual regarding whose exact place in the Kuru genealogy no unanimous tradition had survived. The fact that not only the name Parikshit, but names of most of the sons (in the *Vishṇu* and *Brahma Purāṇas*⁵ the names of all the sons) are common to both, points to the same conclusion. In the case of the son and successor of each of the two Parikshits we have a strikingly similar story of quarrel with the Brāhmaṇas.⁶ It will further be remembered that while Tura Kāvasheya is mentioned in the Purāṇic literature as a *Purohita* of the son of Parikshit II, Indrota Daivāpa Saunaka is represented as the priest of the son of Parikshit I. But it is clear from the Vedic texts that both the royal chaplains served the same king who was separated by five or six generations from Janaka, the contemporary of Uddālaka Āruṇi, Yājñavalkya and Somaśushma. Doubts may thus be legitimately entertained about the existence of two Parikshits each of whom had sons and successors

¹ VII. 27.

² Pargiter, *Ancient Indian Historical Tradition*, 114, *Vāyu*, 93, 22-25.

³ Vol. III, pp. 431 ff.

⁴ *Op. cit.*, p. 449.

⁵ *Vishṇu*, IV. 20.1; 21.1; *Brahma*, XIII, 109.

Vāyu, 93, 22-25; *Matsya*, 50, 63-64, etc.

with identical names, the heroes of tales of a similar character. The probability is that there was really only *one* Parikshit in the Kuru royal family, father of the patron of *both* Tura and Indrota.

Did he flourish *before* or *after* the Bhārata War? The necessity felt for offering an explanation of the name Parikshit given to Abhimanyu's son at the end of the Bhārata War, and the explanation itself, probably suggest that the tradition of an earlier Kuru king with the name of Parikshit had not yet come into existence when the tenth book of the *Mahābhārata* was written.¹ Parikshit I was possibly invented by genealogists to account for such anachronisms as the mention of *Indrota-Pārikshita-saṁvāda* as an old story by Bhīshma in the twelfth book (Chapter 151). The wide divergence of opinion in regard to the name of the father of the so-called Parikshit I, and his position in the list, is also to be noted in this connection. It shows the absence of a clear tradition. On the other hand there is absolute unanimity in regard to the parentage and dynastic position of the so-called Parikshit II.²

¹ *Mbh.* X. 16, 3.

"While the Kuru line will become extinct (*parikṣiṣeshu Kurushu*) a son will be born to you (=Uttarā, wife of Abhimanyu). The child will, for that reason, be named Parikshit."

² The identification of the Vedic Parikshit with the son of Abhimanyu who flourished after the Bhārata War does not seem probable to Dr. N. Dutt, the author of *The Aryanisation of India*, pp. 50 ff., because, in the first place, it goes against the findings of Macdonell, Keith and Pargiter who prefer to identify the Vedic Parikshit with an ancestor of the Pāṇḍus. As to this it may be pointed out that the existence of a Parikshit (father of Janamejaya) *before* the Pāṇḍus, rests mainly on the testimony of those very genealogies which are regarded by Keith as worthless and unreliable (cf. *RPVU* 21, 618). That the name of Janamejaya in this connection is an intrusion into the genealogical texts is evident from its omission from Chapter 95 of the *Mahābhārata*, the *Java text*, the Chellur grant, etc.

Dr. Dutt next argues that the *Vishṇu Purāṇa* makes the four brothers Janamejaya, Śrutasena, etc., sons of Parikshit I. If he had only perused a subsequent passage (IV. 21. 1.) he would have seen that the *Purāṇa* makes the

20 POLITICAL HISTORY OF ANCIENT INDIA

The Vedic hymns throw little light on the domestic life or reign-period of Parikshit. From the epic we learn that he married a Madra princess (Mādravati) and ruled

four brothers sons of "Parikshit II" as well and while this later statement finds corroboration in the *Mahābhārata*, (I. 3. 1.) the earlier does not.

Dr. Dutt next says that it is always risky to attempt identification of kings or the fixing of their dates from an examination of their teacher-priests' names. But why should it be risky if the names and order of succession be genuine? The real risk lies in the rejection of such evidence without sufficient examination. It should be remembered in this connection that the identification of the Vedic Pārikshita Janamejaya with his Epic namesake (descendant of Abhimanyu) does not depend mainly on the teacher-priests' names, but on the following facts, viz., (1) absence of any cogent proof of the existence of an earlier Janamejaya Pārikshita in view of the omission of his name in the *Jata text*, Choḍa inscriptions etc., and (2) agreement of particulars about the Vedic Parikshit and Janamejaya (e. g., words describing the prosperity of the Kuru realm, the performance of two *Aśamedhas*, quarrel with the Kāśyapas), with what we know of Parikshit and Janamejaya who were descendants of Abhimanyu. The question of the chronological relation between the Vedic Parikshit and the Vedic Janaka is entirely independent of this identification. This relation has been determined on the strength of two different lines of evidence. Materials for one have indeed been taken from the *Vaṃśa* list of the Brāhmaṇas. But the succession from Indrota to Somaśushma has been reconstructed from incidental notices in the Brāhmaṇa texts themselves which no critic has represented as late.

Dr. Dutt adds that identity of names does not necessarily imply identity of persons. This is a truism which is not remembered only by those who identify Dhṛitarāshṭra Vaichitravīrya with Dhṛitarāshṭra of Kāśī. It has never been suggested in the *Political History* that the Vedic and Epic Parikshits and Janamejayas are identical merely because their names are identical.

As to Dr. Dutt's contention that there could not be want of motives in later times on the part of the authors belonging to rival families and schools to associate a certain teacher-priest with a famous king of old, etc., it is not clear which particular case he has in mind in making the statement. The association of Indrota and Tura with Janamejaya, and that of Uddālaka and Yājñavalkya with Janaka is found in the *Satapatha* and *Āitareya Brāhmaṇas* and in the *Upanishads*. Is it suggested that such association is a deliberate concoction or fabrication? But no shred of evidence has been brought forward to prove such a charge. No doubt misrepresentations are met with in the Epics and the *Purāṇas* (as pointed out by Pargiter and others). But it would not be reasonable to argue that the *Brāhmaṇas* and the *Upanishads* are guilty of deliberate falsification because forsooth there is confusion in the *Purāṇas* which are undoubtedly of a later date.

Lastly the credibility of the *Vaṃśa* lists in the Vedic texts has been assailed on the following grounds, viz.—

- (1) Silence of Commentators.

for 24 years dying at the age of sixty.¹ Little credit, however, can be given to the bardic tales that cluster round his name. The only facts that can be accepted as historical are that he was a king of the Kurus, that the people lived prosperously under his rule, that he had many sons, and that the eldest, Janamejaya, succeeded him.

It will not be quite out of place here to say a few words about the **realm of the Kurus** over which Parikshit ruled. The kingdom, according to epic tradition, stretched from the Sarasvatī to the Ganges. In the *Digvijaya-parva* it is taken to extend from the border of the land of the Kulindas (near the sources of the Sutlej, the Jumna and the Ganges) to that of the Sūrasenas and the Matsyas (in the Mathurā and Bairāṭ regions respectively), and from the frontier of Rohitaka (Rohtak in the Eastern Punjab) to that of the Pañchālas (of Rohilkhand). It was divided into three parts, Kuru-

(2) Discrepancy between the lists appended to the 10th and 14th books respectively of the *Satapatha Brāhmaṇa* in regard to the authorship of the work and ascription of the work to different teachers.

(3) Scant courtesy shown to an alleged teacher by his pupil.

As to (1), the *Āchārya paramparā*, succession of teachers, is distinctly alluded to by the commentators. If they did not enter into a detailed explanation, it is because they considered it to be *sugamam*, *spashṭam*, easily intelligible plain.

(2) There is no *Vamśa* list at the close of the 14th book of the *Brāhmaṇa* proper excluding the *Bṛihadāranyaka Upanishad*. There are no doubt lists of teachers at the end of the *Upanishad*. It is too much to expect that, in the various lists, the entire *Brāhmaṇa* as well as the *Upanishad* should be ascribed to the same traditional authority. The *Brāhmaṇa* and *Upanishad* text are not works of single individuals. The question of discrepancy, therefore, does not arise. Reference to different traditions regarding the authorship of a particular work, or of particular portions of a work, does not necessarily vitiate any *Āchārya-paramparā* regarding which we have substantial agreement in the texts.

(3) It is too much to expect that in ancient, as in modern times, all pupils should be equally respectful to teachers. Was not Dhṛiṣṭadyumna a pupil of Droṇāchārya whom he killed?

¹ *Mbh.* I. 49, 17-26 with commentary. We learn from the *Bṛihadāranyaka Upanishad* (III. 3. 1.) that the Pārikshita family was intimately known in the Madra country.

jāṅgala, the Kurus proper and Kurukshetra.¹ Kurujāṅgala, as its name implies, was probably the wild region of the Kuru realm that stretched from the Kāmyaka forest on the banks of the Sarasvatī to Khāṇḍava near (*samīpataḥ*) the Jumna.² But in certain passages it is used in a wider sense to designate the whole country (*deśa, rāshtra*³). The Kurus proper were probably located in the district around Hāstinapura (on the Ganges), identified with a place near Meerut.⁴ The boundaries of Kurukshetra are given in a passage of the *Taittirīya Aranyaka*⁵ as being Khāṇḍava on the south, the Tūrghna on the north, and the Parīṇah⁶ on the west (lit. hinder section, *jaghanārdha*). The *Mahābhārata*⁷ gives the following description of Kurukshetra: "South of the Sarasvatī, and north of the Drishadvatī, he who lives in Kurukshetra really dwells in heaven. The region that lies between Taruntuka and Marantuka or Arantuka, the lakes of Rāma and Machakruka⁸—this is Kurukshetra which is also called Sāmanta-pāñchaka and the northern sacrificial altar (*uttara vedī*) of the grandsire (*i.e.*, Brahman)."⁹ Roughly speaking, the Kuru kingdom corresponded to modern Thanesar, Delhi and the greater part of the Upper Gangetic Doāb. Within the kingdom flowed the rivers Aruṇā (which joins the Sarasvatī near Pehoa), Arṇsumatī, Hiranvatī, Āpayā (Āpagā

¹ *Mbh.* I. 109. 1; 149. 5-15; II. 26-32; III. 83. 294; Ptolemy. VII. i. 42.

² *Tataḥ Sarasvatīkūle sameshu marudhanvasu
Kāmyakam nāma dadṛśīsur tanam munijanapriyam.*

"Then they saw before them the forest of Kāmyaka on the banks of the Sarasvatī on a level and wild plain, a favoured resort to anchorites." *Mbh.* III. 5. 3. For the location of the Khāṇḍava forest see I. 222. 14; 223. 1.

³ *Cf. Mbh.*, I. 109. 24; viii. 1. 17. xii. 37. 23.

⁴ Smith, *Oxford History* (1919), p. 31. *cf. Rām.* II. 68. 13; *Mbh.* I. 128. 29ff; 133. 11; Pargiter *DKA*, 5; Patañjali, II. 1. 2. *anuGangam Hāstinapuram.*

⁵ *Vedic Index* 1. pp. 169-70.

⁶ *Cf. the Pareos of Arrian* (*Indika*, iv), a tributary of the Indus.

⁷ III. 83. 4; 9; 15; 25 40; 52; 200; 204-05.

⁸ Machakruka, Taruntuka and Marantuka are Yaksha *dvārapālas* guarding the boundaries of Kurukshetra.

or Oghavatī, a branch of the Chitang), Kauśikī (a branch of the Rakshī), as well as the Sarasvatī and the Dṛishadvatī or the Rakshī.¹ Here, too, was situated Saryāṇavat, which the authors of the *Vedic Index* consider to have been a lake, like that known to the *Satapatha Brāhmaṇa* by the name of Anyataḥplakṣhā.

The royal residence according to the Vedic texts was apparently Āsandivat.² This city may have been identical with Nāgasāhvaya or Hāstinapura, the capital mentioned in the Epics and the *Purāṇas*. But it is more probably represented by the modern Asandh near the Chitang.³

According to epic tradition the kings of Kurukshetra belonged to the **Puru-Bharata** family. The *Paurava* connection of the Kurus is suggested by the *Rigvedic* hymn,⁴ which refers to "Kuru-śravaṇa" (lit. glory of the Kurus) as a descendant of Trasadasyu, a famous king of the Pūrus.⁵ The connection of the Bharatas with the Kuruland is also attested by Vedic evidence. A *Rigvedic* ode⁶ speaks of the two Bhāratas, Devaśravas and Devavāta, as sacrificing in the land on the Dṛishadvatī, the Āpayā and the Sarasvatī. Some famous *gāthās* of the *Brāhmaṇas*⁷ and the epic tell us that Bharata Dauḥshanti made offerings on the Jumna, the Ganges (*Yamunām anu Gaṅgāyām*) and the Sarasvatī. The territory indicated in

¹ For the identification and location of some of the streams see Mbh. III. 83. 95, 151; V. 151. 78; Cunningham's *Arch-Rep.* for 1878-79 quoted in JRAS, 1883, 363n; Smith, *Oxford History*, 29; *Science and Culture*, 1943, pp. 468 ff.

² *Vedic Index*, Vol. I. p. 72.

³ See the map, Smith, *Oxford History*, p. 29. An Āsandi district is mentioned by Fleet in his *Dynasties of the Kanarese Districts* (Bombay Gazetteer, I. 2, p. 492). But there is no reason for connecting it with the Kuru country.

⁴ X. 33, 4.

⁵ *Rigveda*, IV. 38. 1; VII. 19, 3.

⁶ *Rig.* iii. 23; Oldenberg, *Buddha*, pp. 409-10.

⁷ Sat. Br. xiii. 5. 4, 11; Ait. Br. viii. 23; Mbh. vii. 66. 8.

24 POLITICAL HISTORY OF ANCIENT INDIA

these landatory verses is exactly the region which is later on so highly celebrated as Kurukshetra.

In the opinion of Oldenberg "the countless small stocks of the *Samhitā* age were fused together to form the greater peoples of the *Brāhmaṇa* period. The Bharatas found their place, probably together with their old enemies, the Pūrus, within the great complex of peoples now in process of formation, the Kurus; their sacred land now became Kurukshetra."¹

Among those kings who are mentioned in the genealogical lists of the *Mahābhārata*² as ancestors and predecessors of Parikshit, the names of the following occur in the Vedic literature :—

¹ The absorption of the Bharatas by the Kurus is suggested by such passages as *Kururo nāma Bhārataś* (Mbh. XII. 349. 44). In the Rām. IV. 83. 11 Bharatas are still distinguished from the Kurus. It has been suggested by some scholars, e. g., C. V. Vaidya (*History of Mediaeval Hindu India*, Vol. II, pp. 265 ff.) that the Bharata of *Rigvedic* tradition is not to be identified with Daṇṣhanti Bharata, the traditional progenitor of the Kuru royal family, but rather with Bharata, the son of Rishabha, a descendant of the first Manu called Svayambhura. It should, however, be remembered that the story of Bharata, son of Rishabha, is distinctly late. The Bharata princes and people of *Rigvedic* tradition are clearly associated with the Kuru country watered by the Sarasvatī and the Drishadvatī and the names of their rulers, e.g., Divodāsa and Sudāsa occur in Parāpī lists of kings descended from the son or daughter of Manu Vaisvata and not of Manu Svayambhura. The Bharata priests Vasiṣṭha and Viśvāmitra Kauśika are connected in early literature with the royal progeny of Manu Vaisvata and his daughter, and not of Manu Svayambhura. For the association of Vasiṣṭha with the descendants of Bharata Daṇṣhanti see the story of Satvataras and Tapatī in the *Mahābhārata*, I. 94 and 171 f. Viśvāmitra Kauśika's association with the Pūru-Bharata family is, of course, well-known (Mbh. I. 94. 83). It may be argued that Bharata, ancestor of Viśvāmitra, who is called *Bharata-rishabha* in the *Āitareya Brāhmaṇa*, must be distinguished from the later Bharata, the son of Sakuntalā, daughter of Viśvāmitra. But there is no real ground for believing that the story of Viśvāmitra's connection with the nymphs is based on sober history. The *Rigvedic* Viśvāmitra belonged to the family of Kauśika. In the *Mahābhārata* (I. 94. 33) the Kauśikas are expressly mentioned as descendants of Bharata Daṇṣhanti.

² *Adiparva*, Chapters 94 and 95.

Purū-ravas Aila,¹ Āyu,² Yayāti Nahushya,³ Pūru,⁴ Bharata Dauḥshanti Saudyumni,⁵ Ajamīdha,⁶ Riksha,⁷ Sativarana,⁸ Kuru,⁹ Uchchaiṣravas,¹⁰ Pratīpa Prātisatvana or Prāti sutvana,¹¹ Balhika Prātipīya,¹² Saṁtanu,¹³ and Dhṛitarāshṭra Vaichitravīrya.¹⁴

The occurrence of these names in Vedic texts probably proves their historicity,¹⁵ but it is difficult to say how far the epic account of their relationship with one another or with Parikshit, and the traditional order of succession, are reliable. Some of the kings may not have been connected with the Kurus at all. Others, e.g., Uchchaiṣravas Kaupayeya, Balhika Prātipīya and Saṁtanu, were undoubtedly of the same race (*Kauravya*) as Parikshit.¹⁶

Purū-ravas Aila, the first king in the above list, is represented in epic tales as the son of a ruler who migrated from Bāhli in Central Asia to Mid-India.¹⁷ It may be

¹ *Rig-Veda*, X. 95; *Sat. Br.*, XI. 5, 1. 1.

² *Rig Veda* I. 68. 10; II. 14. 7, etc.

³ R. V., I. 31, 17; X. 63. 1.

⁴ R. V., VII. 8. 4; 18. 13.

⁵ Frequently mentioned in the Brāhmaṇa literature, cf. Kuru-śravas, *Rig-Veda*, X. 33.4. see however, foot-note 15 below.

⁶ *Jaiminiya Upanishad Brāhmaṇa*, III. 29.1-3.

⁷ *Atharva-Veda*, XX. 129. 2.

⁸ *Sat. Br.*, XII. 9. 3. 3.

⁹ R. V., X. 98.

¹⁰ *Rāthaka Samhitā*, X. 6.

¹¹ It should, however, be noted that no individual king named Kuru is mentioned in Vedic literature. Kuru is the name of a people in the Vedic texts.

¹² *Jaiminiya Up. Br.*, III. 29. 1; *Sat Br.*, XII. 9. 3; *Nirukta*, ed. by Kahama-rāja Śikṛishṇa Dāsa Śreṣṭhi, p. 180; *Bṛhaddeśat*, VII, 155-156; *Studies in Indian Antiquities*, pp. 7-8.

¹³ *Rām.*, VII. 103, 91-92. This Bāhli lay outside the *Madhyadeśa* and is associated with Kārdama kings. The reference is doubtless to Bacth or Bactria in the Oxus Valley. For a discussion about its identity see *IHQ* 1933, 37-39. The *Matya Purāṇa*, 13. 14 ff, distinctly mentions Ilāvṛta-Varsha (in Central Asia) as the realm of the parent of Purū-ravas. *Mbh.* III. 20, 22-25 however seems to locate the birth place of Purū-ravas on a hill near the source of the Ganges.

noted in this connection that the *Papañcha-sūdani* refers to the Kurus—the most important branch of the Ailas according to the *Mahābhārata* and the *Purāṇas*—as colonists from the trans-Himālayan region known as Uttara Kuru.¹ Bharata, another king mentioned in the epic list is described as a lineal descendant of Purū-ṛavas and of Pūru. But this is doubtful. He is, as we have seen, definitely associated in Brāhmanic and epic *gāthās* with the land on the Sarasvatī, the Ganges and the Jumna, and is credited with victory over the Satvats. The epic tradition that he was the progenitor of the Kuru royal family is in agreement with the Vedic evidence which connects him and his clansmen, Devaśravas and Deva-vāta, with the same territory which afterwards became famous as the land of the Kurus. Uchchaiśravas Kaupayeya had matrimonial relations with the royal family of the Pañchālas. But Balhika Prātipiya could ill conceal his jealousy of the ruler of the Srinjayas, a people closely associated with the Pañchālas in epic tales. The word Balhika in the name Balhika Prātipiya seems to be a personal designation and there is no clear evidence that it is in any way connected with the Balhika tribe mentioned in the *Atharva Veda* and later texts. It may, however, point to the northern origin of the Kurus² of the "Middle country," a theory rendered probable by the association of the Kurus with the Mahāvṛishas³ and the fact that a

¹ Law, *Ancient Mid-Indian Kṣatriya Tribes*, p. 16. Note the association of the Kurus with the Mahāvṛishas, *Vedic Index*, II, 279a, and with the Balhikas, *Mbh.* II, 63. 2-7. In *Mbh.* III, 145. 18-19 the Uttara Kurus are apparently placed near Mount Kailāsa and Badari. In other texts they are located much farther to the north. The Kurus of the *Madhya-desa* are called *Dakṣiṇa-Kurus* in *Mbh.* I, 100. 10.

² Note the association of the Prātipiyas of the Kuru assembly with the Balhikas in *Mbh.* II, 63. 2-7: *Pratipeyāḥ Sāntanavā Bhīmasenāḥ sa Balhikāḥ..... Arigodheam Kāvyaṁ vāchan samocādi Kauravagāḥ.*

³ *Vedic Index* II, 279n 5; *Sat. Br.* (Kāṇva text); for Balhikas and Mahāvṛishas see also *Atharva Veda*, V, 22. 4-8.

section of the Kuru people dwelt beyond the Himālayas in the days of the *Aitareya Brāhmaṇa* and the *Mahābhārata*. The history of the Kuru royal line becomes more definite from the time of Śāntanu who was fifth in the ascending line from Parikshit. Regarding the events of Parikshit's reign we have little reliable information. We only know that the drought that threatened the Kuru realm in the time of Śāntanu had passed away and the people "throve merrily in the kingdom of Parikshit."

The **date of Parikshit** is a matter regarding which the Vedic texts give no direct information. In the Aihole Inscription of Ravikīrti, panegyrist of Pulakeśin II, dated Śaka 556 (expired)=A.D. 634-35, it is stated that at that time 3735 years had passed since the Bhārata War :

*Trimśatsu tri sahasreshu Bhāratād āhavād itaḥ
saptābda śata-yukteshu gateshvabdeshu pañchasu.*¹

The date of the *Bhārata* war which almost synchronised with the birth of Parikshit, is, according to this calculation, and the testimony of Āryabhaṭa (A.D. 499), 3102 B.C. This is the starting point of the so-called *Kali-yuga* era. But, as pointed out by Fleet², the reckoning was not founded in Vedic times. It is an invented one, devised by Hindu astronomers and chronologists for the purposes of their calculations some thirty-five centuries after the initial point which they assigned to it. As a matter of fact another school of Hindu astronomers and historians, represented by Vṛiddha-Garga, Varāhamihira and Kalhaṇa, placed the heroes of the *Bhārata* war 653 years after the beginning of the *Kali-yuga* and 2526 years before the Śaka era, i.e., in B.C. 2449.³ This last date

¹ Ep. Ind., VI, pp. 11, 12.

² JRAS, 1911, pp. 479 ff., 675 ff.

³ *Āraṇ Maḡhāsu munayāḥ śāsātī prithvīm Yudhiṣṭhira nripatau
śhaḍ-śeika-pañcha-dviguṭaḥ Śakakālastasya rājñascha*
Brh. S., XIII. 3. Cf. *Rājatarāṅgiṇī*, I. 48-50.

is as much open to doubt as the one adopted by Āryabhaṭa and Ravikīrti. The literature that embodies the Vṛiddha-Garga tradition cannot claim any higher antiquity or reliability than the composition of the great astronomer of Kusumapura. The chronology to which it gives preference is not accepted by the Aihole inscription of Ravikīrti. A noted writer,¹ who accepts the dating of Vṛiddha-Garga and Varāha, cites only two late cases (*op. cit.* p. 401) to prove its currency in India, *viz.*, the commentary on the *Bhāgavatāmṛita* and certain modern Almanacs. His attempts to support this tradition by astronomical calculation based on certain *Mahābhārata* passages are beset with difficulties. For one thing there is a good deal of uncertainty regarding the starting point of what he calls the "Purāṇic" or "epic" Kaliyuga. He says (p. 399) "most likely the *Mahābhārata* Kaliyuga truly began from the year 2454 B.C. The year of the Bhārata battle according to his finding is however 2449 B.C. In other words the battle was fought *five years after* the epic Kaliyuga *had already begun*. But he himself points out (p. 393) that the battle was fought, according to the *Mahābhārata*, when it was the junction of (*antara*, really interval between) *Kali* and *Dvāpara*, and 36 years before the year of Krishna's expiry (p. 399) which was the true *beginning of the Kaliyuga*. Thus the dates assigned to the beginning of Kali do not agree. These discrepancies demonstrate the unstable character of the ground on which the chronological edifice is sought to be built. It may be remembered in this connection that Kalhaṇa, who places Gonarda I of Kashmir and the Bhārata War in 2449-8 B.C. fixes a date for Aśoka much earlier than Gonarda III (1182 B.C.). This result is opposed to all genuine historical evidence and proves the unreliable

¹ Mr. P. C. Sen Gupta, *Bhārata Battle Traditions*, *JRASB.* IV, 1938, No. 3 (Sept. 1939, pp. 393-413).

character of the scheme of chronology which has for its basis a belief in 2449 B.C. as the date of the Bhārata War. Some writers¹ try to reconcile the conflicting views presented by the schools of Aryabhaṭa and Vṛiddha-Garga by suggesting that the *Śaka-kāla*, of Varāhamihira is really *Śākya-kāla*, i.e., the era of the Buddha's *Nirvāṇa*. This conjecture is not only opposed to the evidence of Kalhaṇa, but is flatly contradicted by Bhaṭṭotpala who explains *Śaka-kāla* of the *Bṛihat Saṃhitā* passage as *Śaka-nṛipa-kāla*, era of the Śaka king.² Varāhamihira himself knew of no *Śaka-kāla* apart from the *Sakendrakāla* or *Śaka-bhūpa-kāla*, i.e., the era of the Śaka king.³

A third tradition is recorded by the compilers of the *Purāṇas*. There is a remarkable verse, found with variants in the historical *Purāṇas*, which places the birth of Parikshit 1050 (or 1015, 1115, 1500 etc. according to some manuscripts), years before Mahāpadma, the first Nanda king of Magadha :

*Mahāpadm-ābhishekāt tu
yāvajjanma Parikshitah
evam varshasahasram tu
jñeyam pañchāśaduttaram.*⁴

¹ *IHQ*, 1932, 85; *Mod. Rev.*, June, 1932, 650 ff.

² The *Bṛihat-Saṃhitā* by Varāhamihira with the commentary of Bhaṭṭotpala, edited by Sudhākara Dvivedi, p. 281

³ *Bṛihat Saṃhitā*, VIII, 20-21.

⁴ Pargiter, *Dynasties of the Kali Age*, p. 58. From the account of Pargiter it appears that the reading *Pañcha-śatottaram*, finds no support in the *Vāyu* and *Brahmaṇḍa* texts. The variant *Śatam pañchadaśottaram* occurs only in some Bhāgavata Mss. 'Pañchadaś-ottaram' is however unknown to the *Matsya*. One *Matsya* Ms. has 'Śato trayam.' The reading generally accepted by the scribes seems to have been *Pañchāśad-uttaram*. The biggest figure (1500) is probably obtained by the wrong inclusion within the Magadhan list of the Pradyotas of Avanti, and taking the period of Bārhadratha rule to cover 1000 instead of 723 years. 1000 (for the Bārhadrathas) + 152 (for the Pradyotas) + 350 (for the Śaiśunāgas) = 1502 years.

If the reading *Pañchāśaduttaram* be correct, the verse would seem to point to a date in the fourteenth or fifteenth century B. C. for the birth of Parikshit. It is, however, doubtful if even this tradition can be regarded as of great value. In the first place the divergent readings in the different Mss. take away from the value of the chronological datum. Secondly, the *Purāṇas* themselves in giving details about the dynasties that are supposed to have intervened between the Bhārata war and the coronation of Mahāpadma mention totals of reigns which when added together neither present a unanimous tradition nor correspond to the figure 1050, which alone finds general acceptance in the *Matsya*, the *Vāyu* and the *Brahmāṇḍa* manuscripts. The discrepancies may no doubt be partially explained by the well-known fact that the Purāṇic chroniclers often represent contemporaneous lines e.g. the Pradyotas and the Bimbisārids, as following one another in regular succession. But there is another point which deserves notice in this connection. The same passage which says that "from Mahāpadma's inauguration to the birth of Parikshit, this interval is indeed 1050 years," adds that "the interval which elapsed from the last Andhra king Pulomāvi to Mahāpadma was 836 years." As most of the *Purāṇas* agree in assigning a period of 100 years to Mahāpadma and his sons who were followed immediately by Chandragupta Maurya, the interval between Chandragupta and Pulomāvi, according to the *Purāṇic* chronology, will be 836—100—736 years. Now as Chandragupta could not have ascended the throne before 326 B.C., Pulomāvi, according to the calculation of the *Purāṇas*, cannot be placed earlier than 410 A.D. But this date can hardly be reconciled with what we know about the history of the Deccan in the first half of the fifth century A.D. Contemporary records show that the territory that had acknowledged the sway of Pulomāvi

and his ancestors was at that time under the Vākātakas and other dynasties that rose on the ruins of the so-called "Andhra," or Śātavāhana empire. This emphasizes the need of caution in utilizing the chronological data of the Purāṇas.¹

An attempt has been made in recent times to support the Purāṇic date for Parikshit and the Bhārata War which is taken to correspond to c.1400 B.C.,² by calculations based on the *Vamśa* lists of teachers and pupils preserved in the Vedic literature. The importance of these lists was emphasized in these very pages as early as 1923. But the data they yield have been made to square with the chronological scheme adumbrated in some of the Purāṇic Mss with the help of a number of assumptions for which no cogent proofs have been adduced. It has, for instance, been taken for granted that the *Vamśa* list given at the end of the *Bṛihadāranyaka Upanishad* is virtually contemporaneous with those found in the *Vamśa Brāhmaṇa* and the *Jaiminīya Upanishad Brāhmaṇa*, and that all the lists "must be" dated "not later than c. 550 B.C." (*op. cit.* p. 70). A few pages further on (p. 77) the date of the *Vamśa Brāhmaṇa* is stated to be "c. 550 B.C." (the words "not later than" being omitted). The mere fact that the *Bṛihadāranyaka Upanishad* and other works of the Śruti literature are generally regarded as Pre-Buddhist cannot be taken to prove that the entire lists of teachers and pupils appended to or inserted in all of them can claim equal antiquity. Scholars in assigning the period before 500 B.C. to the Vedic literature expressly exclude "its latest excrescences."³ Pāṇini⁴ draws

¹ See also Raychaudhuri, *The Early History of the Vaiṣṇava Sect*, second edition, pp. 62ff.

² Dr. Altekar, *Presidential Address to the Archaic Section of the Indian History Congress, Proceedings of the Third Session, 1939*, pp. 68-77

³ Winternitz, *A History of Indian Literature*, p. 27.

⁴ IV. 3. 105.

a distinction between Vedic works which, to him, are *Purāṇaprokta* and those that he does not obviously regard as equally old. The date "c. 550 B.C." has even less justification than the vague words "not later than c. 550 B.C."

It has been stated further that the period separating the priests of Janamejaya from c. 550 B.C. is 800 years. This figure is obtained by accepting the round number 40 for the intervening generations and assigning to each generation in the *gurusishya paramparā* a period of 20 years. The probative value of this mode of calculation is impaired by the fact that the actual number of teachers of the period given in the *Bṛihadāranyaka Upanishad* is 45 and not 40 (p. 70), and the true average length of a spiritual generation is, according to Jaina and Buddhist evidence, about 30 and not 20 years.¹ Moreover, it should not be forgotten that if the lists which form the basis of calculation are really to be dated 'not later than c. 550 B.C.,' c. 1350 B.C. (550+800) can only be regarded as a *terminus ad quem*. The *terminus a quo* still remains to be determined. The uncertainty regarding the date of the particular *Vamśa* lists, on which the whole chronological theory rests, lays even the lower limit open to objection.

Tradition recorded in the *Kathā-sarit-sāgara* points to a date for the Pārikshitas which is much later than that assigned to them by Purāṇic chroniclers and astronomers of the Gupta Age². It refers to Udayana, king of Kauśāmbī (c. 500 B.C.), as fifth in lineal succession from Parikshit. The evidence is late but the text professes to embody tradition that goes back to Guṇāḍhya who is known to Bāṇa (c. 600 A.D.) and is assigned to the Śātavāhana period.

¹ Jacobi, *Parīśiṣṭaparvan*, 2nd ed. xviii; Rhys Davids, *Buddhist. Suttas* Introduction, xlvii.

² *Kathā-sarit-sāgara*, IX. 6-7 ff, Penzer, I. 95

A comparatively late date, albeit not the date suggested by the *Kathā-sarit-sāgara*, can also be inferred from certain passages in the later Vedic texts. We shall show in the next section that Parikshit's son and successor Janamejaya was separated by five or six generations of teachers from the time of Janaka of the *Upanishads* and his contemporary Uddālaka Āruṇi. At the end of the *Kaushītaki* or *Śāṅkhāyana Āraṇyaka*¹ we find a *vaṁśa* or list of the teachers by whom the knowledge contained in that *Āraṇyaka* is supposed to have been handed down. The opening words of this list run thus :—

“Om ! Now follows the *vaṁśa*. Adoration to the Brahman ! Adoration to the teachers ! We have learnt this text from Guṇākhyā Śāṅkhāyana, Guṇākhyā Śāṅkhāyana from Kahola Kaushītaki, Kahola Kaushītaki from Uddālaka Āruṇi”²

The passage quoted above makes it clear that Guṇākhyā Śāṅkhāyana was separated by two generations from the time of Uddālaka who was separated by five or six generations from the time of Janamejaya. Guṇākhyā, therefore, lived seven or eight generations after Parikshit. He could not have flourished much later than Āśvalāyana because the latter, or preferably his pupil, honours his *guru* Kahola.³ It is to be noted that we have no personal name prefixed to Āśvalāyana as we have in the case of Śāṅkhāyana. This probably suggests that Vedic tradition knew only of one great teacher named Āśvalāyana. It is significant that both in Vedic and Buddhist literature this famous scholar is associated with one and the same locality, *viz.*, Kosala, modern Oudh. The *Praśna Upanishad* tells us that Āśvalāyana was a *Kausalya*, *i.e.*, an

¹ *Ādhya* 15.

² *S.B.E.*, Vol. XXIX, p. 4.

³ *Āśvalāyana Gṛhya Sūtra*, III, 4, 4.

inhabitant of Kosala, and a contemporary of Kabandhi Kātyāyana. These facts enable us to identify him with Assalāyana of Sāvattthi (a city in Kosala) mentioned in the *Majjhima Nikāya*¹ as a famous Vedic scholar,² and a contemporary of Gotama Buddha and, hence, of Kakuda³ or Pakudha Kaccabāyana. The reference to Gotama's contemporary as a master of *keṭubha*, i.e., *kalpa* or ritual, makes it exceedingly probable that he is to be identified with the famous Āśvalāyana of the *Gṛihya Sūtras*. Consequently the latter must have lived in the sixth century B.C. Guṇākhyā Sāṅkhāyana, whose teacher Kahola is honoured by the famous *Gṛihyasūtrā-kāra*, cannot be placed later than that century. That the upper limit of Guṇākhyā's date is not far removed from the lower one is suggested in the first place by the reference in his *Āraṇyaka* to Paushkarsādi, Laubitya and a teacher who is styled Magadhavāsī. The first two figure, in the *Ambaṭṭha* and *Lohichcha suttas*, among the contemporaries of the Buddha. The attitude of respect towards a Magadhan teacher in the *Āraṇyaka* points to an age later than that reflected in the *Śrauta Sūtras* which mention Brāhmaṇas hailing from the locality in question in a depreciatory tone as *Brahmabandhu Māgadha-deśīya*.⁴

Goldstücker points out⁵ that Pāṇini used the word *Āraṇyaka* only in the sense of 'a man living in the forest'. It is Kātyāyana (c. fourth century B.C.) who vouchsafes in a *Vārttika* the information that the same

¹ II. 147, et seq.

² "Tīrṇaṁ Vedānaṁ pāragū sanighaṇḍu keṭubhānaṁ "

³ As to the equation *kabandhi*=*kakuda*, see IHQ, 1932, 603 ff. *Kabandha* in the *Atharva Veda*, X. 2.3 means *śroni* and *ūru* (hips and thighs). According to Amara *kakudmatī* has substantially the same meaning.

⁴ *Vedic Index*, II. 116. Isolated references to Paushkarasādi and others may not be of much value. What we have to consider is the cumulative effect of the references in the *Sāṅkhāyana Āraṇyaka* combined with the testimony of Pāṇini and Āpastamba.

⁵ Pāṇini, *His Place in Sanskrit Literature*, 1914, 99.

expression is also used in the sense of treatises 'read in the forest'. The silence of Pāṇini in regard to this additional meaning of the term, when contrasted with the clear statement of the later grammarian, leaves little room for doubt that *Āraṇyaka* in the sense of a forest-treatise was well known to writers traditionally assigned to the fourth century B.C., but not to Pāṇini. It may be recalled in this connection that, unlike Kātyāyana again, Pāṇini does not include the works of Yājñavalkya, a contemporary of Kaḥola, the teacher of Guṇākhyā, among the older (*Purāṇa-prokṭa*) *Brāhmaṇas*.¹ Śvetaketu, another contemporary of Kaḥola, teacher of Guṇākhyā, is mentioned in the *Dharmasūtra* of Āpastamba² as an *avara* or modern authority. The reference to *Yavanāni* in the *sūtras*³ of Pāṇini and the tradition recorded in the *Kāvya-Mīmāṃsā*⁴ that he made his mark in the city of Pāṭaliputra (founded, as we know, after the death of the Buddha, c. 486 B.C., in the reign of Udāyin), clearly suggest that he could not have flourished before the sage of the Śākyas. Profound as his knowledge is in regard to Vedic literature, Pāṇini is unaware of the existence of *Āraṇyakas* as a class of forest-treatises. It is, therefore, not unreasonable to conclude that he could not have been considerably posterior to the great masters of the *Āraṇyakas* among whom Guṇākhyā Sāṅkhāyana holds an honoured place. In other words, the upper limit of the date of this teacher almost coincides with the lower. With a date for him in the sixth century B.C. all the evidence accommodates itself.

We are now left with the task of attempting to measure the distance between Guṇākhyā and Parikṣit. Professor

¹ IV. 3. 105 with commentary quoted on page 106n of Goldstücker's *Pāṇini, Yājñavalkyōdayo hi na chira kālā ityākhyāneṣu vārā*.

² *Dharmasūtra*, I. 2, 5, 4-6.

³ IV. I. 49.

⁴ P. 55.

Rhys Davids in his *Buddhist Suttas* assigns 150 years to the five *Theras* from Upāli to Mahinda. Jacobi, too, informs us that the average length of a patriarchate may be estimated at about 30 years. We may, therefore, assign 240 or 270 years to the eight or nine generations from Parikshit to Guṇākhyā Śāṅkhāyana, and place the former in the ninth century B.C.

Parikshit was succeeded on the Kuru throne by his eldest son **Janamejaya**. The *Mahābhārata* refers to a great snake-sacrifice performed by this king. In this connection it is stated that the king conquered Taxila.¹ It is clear from the *Pañchaviṃśa Brāhmaṇa*² and the *Baudhāyana Śrauta Sūtra*³ that the epic account of the Kuru king's *Sarpa-satra* cannot be regarded as having any historical basis. There is hardly any doubt that the *Satra* mentioned in the Vedic texts is the prototype of the famous sacrifice described in the epic. The story seems to have undergone three stages of development. The original tale is concerned with a mythical rite performed by the serpents one of whom was named Janamejaya, who served as an *Adhvaryu* (priest). "Through this rite the serpents vanquished death."² The next stage is reached in the *Baudhāyana Śrauta Sūtra*. Janamejaya appears among the kings and princes of the serpents assembled for sacrifice in human shape at Khāṇḍavaprastha (in the Kuru country) with the object of obtaining poison. In the epic the performer of the sacrifice is identified with the Kuru king; and the object of the sacrifice is not the acquisition of immortality for the serpents, or of poison, but the extinction of these

¹ *Mbh.*, I. 3. 20. For early references to Taxila, see also Pāṇini, IV. 3. 93; *Vinaya Texts*, Pt. II, p. 174; Malalasekera, *Dictionary*, I, p. 932.

² XXV. 15; *Vedic Index*, I, p. 274.

³ Vol. II, p. 298; XVII. 18.

reptiles. It is impossible to find in the doings of these venomous creatures a reference to an historic strife.¹

The conquest of Taxila by the Kuru king may, however, be an historical fact, because King Janamejaya is represented as a great conqueror in the *Brāhmaṇas*. Thus the *Aitareya Brāhmaṇa* says :² “*Janamejayah Pārikshitah samantam sarvataḥ prithivīm jayan parīyāyāsvena cha medhyeneje, tadeshā yajña-gathā gīyate* :

*Āsandivati dhānyādaṁ rukmiṇaṁ karitasrajam
aśvaṁ babandha sārāṅgaṁ³ devebhyo Janamejaya iti*”

“Janamejaya Pārikhsita went round the earth completely, conquering on every side, and offered the horse in sacrifice.” Regarding this a sacrificial verse is sung :

“In *Āsandivat* Janamejaya bound for the gods a black-spotted grain-eating horse, adorned with a golden ornament and with yellow garlands.”⁴

In another passage of the *Aitareya Brāhmaṇa*⁵ it is stated that Janamejaya aspired to be a “*Sarvabhūmi*”, i.e., a universal sovereign :

“*Evamvidam hi vai māmevānvīdo yājayanti tasmād aham jayāmyabhītvarīm senām jayāmyabhītvarīyā senayā na mā divyā na mānushya ishava richchhantyeshyāmi sarvamāyuh sarvabhūmir bhaviṣhyāmīti.*”

(Janamejaya Pārikshita used to say) “Those who know thus sacrifice for me who know thus ; therefore I conquer the assailing host, I conquer with an assailing host. Me

¹ *Pañchaviṁśa Brāhmaṇa*, translated by Dr. W. Caland, p. 641; cf. Winternitz, *JBBRAS.*, 1926, 74. ff; Pargiter, *AIHT*, p. 285, observes that “the Nāgas killed Parikshit II, but his son Janamejaya III defeated them and peace was made!”

² VIII. 21.

³ Variant—*abadhnādaśvaṁ sārāṅgaṁ*—*Sat. Br.* xiii. 5. 4. 1-2.

⁴ Keith, *Rig-Veda Brāhmaṇas*, 336; Egeling, *Sat. Br.* V, p. 396.

⁵ VIII. 11.

neither the arrows of heaven nor of men reach. I shall live all my life, I shall become lord of all the earth.'²

The possession of Taxila in the extreme north-west implies control over Madra or the central Pañjāb, the homeland of Janamejaya's mother Mādravati.¹ In this connection it may be remembered that the western frontier of the Kuru country once extended as far as the Parīṇah or Parenos, a tributary of the Indus. Princes of the Paurava race ruled in the territory lying between the Jbelam and the Rāvi down to the time of Alexander, while Ptolemy, the geographer, expressly mentions the Pāṇḍus as the rulers of Śākala (Śiālkoṭ) in the heart of this extensive region.

It was presumably after his victorious campaigns that Janamejaya was consecrated with the *Punar-abhisheka* and the *Aindra mahābhisheka*, performed two horse-sacrifices and had a dispute with Vaiśampāyana and the Brāhmaṇas. The *Matsya* version, which is considered by the Pargiter to be the oldest, says the king made a successful stand against them for some time, but afterwards gave in and, making his son king, departed to the forest; but the *Vāyu* version says he perished and the Brāhmaṇas made his son king. The broad facts of the Purāṇic narrative are confirmed by the evidence of the Brāhmaṇas. The *Śatapatha Brāhmaṇa* refers to one of the horse-sacrifices, and says that the priest who performed the rite for him was Indrota Daivāpi Śaunaka. The *Aitareya Brāhmaṇa* mentions the other sacrifice and names Tura Kāvasheya as his priest. It also contains a tale stating that at one sacrifice of his he did not employ the Kaśyapas, but the Bhūtavīras. Thereupon a family of the Kaśyapas called Asita-mṛga forcibly took away the conduct of the

¹ The *Bhāgavata Purāṇa* (II. xvi. 2) mentions Irāvati, daughter of Uttara as the mother of Janamejaya and his brothers.

offering from the Bhūtavīras. We have here probably the germ of the *Purāṇic* stories about Janamejaya's dispute with the Brāhmaṇas. Vaiśampāyana, who headed the opponents of Janamejaya, undoubtedly belonged to the Kaśyapa clan. An allusion to the famous quarrel occurs also in the *Kauṭīliya Arthaśāstra* (*kopāḥ-Janamejayo Brāhmaṇeshu vikrāntaḥ*).

The *Gopatha Brāhmaṇa* narrates an anecdote of Janamejaya and two ganders, pointing out the importance of *Brahmacharya*, and the time which should be devoted to it. The story is obviously mythical but it shows that Janamejaya was already looked upon as a legendary hero in the time of the *Gopatha Brāhmaṇa*.¹

Janamejaya's capital, according to a sacrificial song (*yajña-gāthā*) quoted above, was Āsandivat to which reference has already been made. The *Satapatha Brāhmaṇa* affords an interesting glimpse of life in the royal palace or sacrificial hall :

*Samānāntsadam ukshanti hayān kāshṭhabhṛito yathā
pūrṇān parisrutāḥ kumbhān Janamejayaśādana' iti*

"Even as they constantly sprinkle the equal prize-winning steeds so (they pour out) the cups full of fiery liquor in the palace (or sacrificial hall) of Janamejaya."²

"Curds, stirred drink or liquor" were favourite beverages of the Kurus already in the days of Parikshit.

If the *Mahābhārata* is to be believed, Janamejaya sometimes held his court at Taxila, and it was at Taxila that Vaiśampāyana is said to have related to him the story of

¹ *Gopatha Brāhmaṇa*, ed. by R. L. Mitra and Harachandra Vidyābhūṣaṇa, pp. 25 ff (I. 2. 5). In connection with the legend referred to above we hear of a sage named Dantābala Dhaumra who is identified by some writers with Dantāla Dhaumya of the *Jaiminīya Brāhmaṇa*. The conjecture lacks proof. In the *Baudhāyana Śrauta Sūtra*, Vol. III, p. 449, "Dharmas, Dharmāyana and Dhaumyas" find separate mention as distinct members of the Kaśyapa group.

² *Sat. Br.* XI. 5. 5, 13. Eggeling, V. 95.

the great conflict between the Kurus and the Pāṇḍus¹ who had for their allies several peoples including the Śrīñjayas. No direct independent proof of this war is forthcoming, but allusions to the hostility of Kurus and Śrīñjayas, which forms an important feature of the epic ballads, are met with in the *Satapatha Brāhmaṇa*.² Moreover Hopkins invites attention to a *gāthā* in the *Chhāndogya Upanishad*³ which alludes to the mare which saves the Kurus:—

Yato yata āvarate tat tad gachchhati mānavaḥ
.....*Kurūn aścābhirakshati.*

The verse cannot fail to recall the disaster (*Kurūnām vaiśasaṃ*) referred to in the *Mahābhārata*.⁴

It may be asserted that the Pāṇḍus are a body of strangers unknown to the Vedic texts, and that, therefore, the story of *their* feuds with the Kurus must be post-Vedic. But such a conclusion would be wrong because, firstly, an *argumentum ex silentio* is seldom conclusive, and, secondly, the Pāṇḍus are, according to Indian tradition, not a body of strangers but in fact scions of the Kurus. Hopkins indeed says that they were an unknown folk connected with the wild tribes located north of the Ganges.⁵ But Patañjali⁶ calls Bhīma, Nakula and Sahadeva Kurus.⁷ Hindu tradition is unanimous in representing the Pāṇḍavas as an offshoot of the Kuru race just as the Kurus themselves were an offshoot of the Bharatas.

¹ *Mbh.*, XVIII. 5. 24.

² The battle of Kurukshetra is very often described a fight between the Kurus and the Śrīñjayas (*Mbh.*, VI. 45. 2; 60. 29; 72. 15; 73. 41; VII. 20. 31; 119. 40, VIII. 47. 23; 57. 13; 59. 1; 93. 1). The unfriendly feeling between these two peoples is distinctly alluded to in the *Satapatha Brāhmaṇa* XII. 9. 3. 1 ff., *Vedic Index*, II, p. 63).

³ IV. 17. 9-10, *The Great Epic of India*, p. 385.

⁴ *Mbh.* IX. 35. 20.

⁵ *The Religions of India*, p. 358.

⁶ IV. 1. 4.

⁷ *Ind. Ant.*, I, p. 350.

The very name of the Great Epic betrays the Bhārata (Kuru) connection of the principal heroes and combatants. The testimony of Buddhist literature points to the same conclusion. In the *Dasa-Brāhmaṇa Jātaka*¹ a king "of the stock of Yuddhiṭṭhila" reigning "in the kingdom of Kuru and the city called Indapatta" is distinctly called "Koravya," i.e., Kauravya—belonging to the Kuru race. The polyandrous marriage of the Pāṇḍavas does not necessarily indicate that they are of non-Kuru origin. The system of *Niyoga* prevalent among the Kurus of the *Madhya-deśa* was not far removed from fraternal polyandry,² while the law (*Dharma*) of marriage honoured by the Northern Kurus was admittedly lax.³

Already in the time of Āśvalāyana's *Gṛihya Sūtra*⁴ Vaiśampāyana was known as *Mahābhāratachārya*. He is also mentioned in the *Taittirīya Āraṇyaka*⁵ and the *Ashṭādhyāyī* of Pāpini.⁶ Whether the traditional reciter of the original *Mahābhārata* was actually a contemporary of Janamejaya or not, cannot be ascertained at the present moment. But I have found nothing in the Vedic literature itself which goes against the epic tradition. The early Vedic texts no doubt make no reference to the

¹ *Jātaka* No. 495

² See also my "*Political History*," pp. 95, 96; *Journal of the Department of Letters (Calcutta University)*, Vol. IX; and the *Early History of the Vaiṣṇava Sect*, second edition, pp. 43-45. Also *Mbh.*, I, 103, 9-10; 105, 37-38; Winternitz in *JRAS*, 1897, 755 ff; *Āpastamba* ii, 27, 3; *Bṛhaspati*, xxvii. It is to be noted that in spite of the alleged family custom in the Pāṇḍu line no other wife except Draupadī was shared by the Pāṇḍava brothers, and their children had no common wife. In the epic 'Kuru' and 'Pāṇḍu' no doubt often find separate mention. In a similar way historians distinguish between the related houses of 'Plantagenet,' 'York' and 'Lancaster'; 'Capet,' 'Valois,' 'Bourbon' and 'Orleans'; 'Chaulukya' and 'Vaghela.'

³ *Mbh.*, I, 122, 7.

⁴ III, 4.

⁵ I, 7, 5.

⁶ IV, 3, 194.

Mahābhārata, but they mention *Itihāsa*.¹ It is well-known that the story supposed to have been recited by Vaiśampāyana to Janamejaya was at first called an *Itihāsa* and was named *Jaya*² or song of victory, i.e., victory of the Pāṇḍus, the ancestors of the king :

*Muchyate sarvapāpebhyo Rāhuṇā Chandramā yathā
Jayo nāmetihāso' yaṁ śrotavyo vijigishuṇā.*³

"By listening to this story one escapes from all kinds of sin, like the Moon from Rāhu. This *Itihāsa* (story, legend) is named *Jaya* (Victory); it should be listened to by those that desire victory."

Janamejaya's brothers, Bhīmasena, Ugrasena and Śrutasena, appear in the *Śatapatha Brāhmaṇa*⁴ and the *Śaṅkhāyana Śrauta Sūtra*⁵ as performers of the horse-sacrifice.⁶ At the time of the *Bṛihad-āraṇyaka Upanishad* their life and end excited popular curiosity and were discussed with avidity in learned circles. It is clear that the sun of the Pārikshitas had set before the time of the *Upanishad*,⁷ and it is also clear that they had been guilty of some sinful deeds which they had atoned for by their horse-sacrifice. The *Śatapatha Brāhmaṇa* quotes a *gāthā* which says :—

¹ A. V., XV. 5. 11-12.

² Cf. C. V. Valḍya, *Mahābhārata : A Criticism*, p. 2; and S. Levi in *Bhand. Com.* Vol., pp. 59-599.

³ Mbh., Ādi, 62, 20; Cf. *Udyoga*, 136, 18.

⁴ XIII. 5. 4. 3.

⁵ XVI. 2. 7.

⁶ Did these three brothers take part in the sacrifices of Janamejaya? Such a participation is clearly suggested by Mbh. I. 3. 1.

⁷ The question "Whither have the Pārikshitas gone?" does not imply their extinction; Pargiter himself points out that the answer "Thither where *Aśamedha* sacrificers go" suggests the opposite because such sacrifices procured great blessings. *AIHT.*, 114. The *Rāmāyaṇa*, too, includes Janamejaya (II. 64. 42) in a list of kings who attained to a glorious destiny.

*Pārikshilā yajamānā aśvamedhaiḥ paro'varam
ajahuḥ karmapāpakam puṇyāḥ puṇyena karmaṇā.*¹

“The righteous Pārikshitas, performing horse-sacrifices, by their righteous work did away with sinful work one after another.”

It may be presumed that the breach with the ‘lords spiritual’ of those days was healed in this way and for the time being priests and princes in the Kuru country lived in harmony. The *Purāṇas* state that Janamejaya was succeeded by Śatānika. Śatānika’s son and successor was Aśvamedha-datta. From Aśvamedha-datta was born Adhisīma-kṛishṇa famed in the *Vāyu* and *Matsya Purāṇas*. Adhisīma-kṛishṇa’s son was Nichakshu. During Nichakshu’s reign the city of Hāstinapura is said to have been carried away by the Ganges, and the king is said to have transferred his residence to Kauśāmbī, or Kosam near Allahabad.²

The Vedic texts do not refer in clear terms to any of these successors of Janamejaya or to the city of Hāstinapura which figures as the principal metropolis of the Kurus in the epic and the *Purāṇas*. The antiquity of the city is, however, clearly proved by the evidence of Pāṇini.³ As to the princes the *Rig-Veda* no doubt mentions a (Bhārata) king named Aśvamedha,⁴ but there

¹ *Sat. Br.*, XIII. 5. 4. 3. Cf. *Mbh.* XII. 153, 38. The sinful deeds of which the eldest of the Pārikshitas was guilty, according to the epic, were *Brahmahatyā* and *bhṛūgahatyā* (*ibid.*, 150 Verses 3 and 9). Cf. also *Sat. Br.*, XIII. 5. 4. 1.

² *Gaṅgayāpohite tasmin nagare Nāgasāhvaya
tyakteṣu Nichakshu nagaram Kauśāmbyaṁ so nicotyati.*

When the city of Nāgasāhvaya (Hāstinapura) is carried away by the Ganges, Nichakshu will abandon it and will dwell in Kauśāmbī.

Pargiter, *Dynasties of the Kali Age*, p. 5.

That Hāstinapura stood on the Ganges is clear from the *Rāmāyaṇa* (II. 68. 13), the *Mahābhārata* (I, 125), and the *Mahābhāshya* (*anugaṅgam Hāstinapuram*).

³ VI. 2, 101.

⁴ V. 27. 4—6.

is nothing to show that he is identical with *Aśvamedha-datta*. A *Śatānīka Sātrājita* is mentioned in the *Aitareya Brāhmaṇa* and the *Satapatha Brāhmaṇa* as a powerful king who defeated *Dhṛitarāshṭra* a prince of *Kāśi*, and took away his sacrificial horse. He, too, was probably a *Bharata*,¹ but the patronymic *Sātrājita* probably indicates that he was different from *Śatānīka*, the son of *Janamejaya*. The *Pañchaviṃśa Brāhmaṇa*, the *Jaiminiya Upanishad Brāhmaṇa* and the *Chhāndogya Upanishad* mention a Kuru king named **Abhipratārin** *Kākshaseni*, who was a contemporary of *Girikshit Auchchamanyava*, *Śaunaka Kāpeya* and *Dṛiti Aindrota*. As *Dṛiti* was the son and pupil of *Indrota Daivāpa* (*Daivāpi*) *Saunaka*, the priest of *Janamejaya*,² *Abhipratārin*, son of *Kakshasena*, appears to have been one of the immediate successors of the great king. We have already seen that *Kakshasena* appears in the *Mahābhārata*³ as the name of a brother of *Janamejaya*. *Abhipratārin* was thus *Janamejaya*'s nephew. The *Aitareya Brāhmaṇa* and the *Sāṅkhāyana Śrauta Sūtra*⁴ refer to a prince named **Vṛiddhadyumna** *Abhipratāriṇa*, apparently the son of *Abhipratārin*. The *Aitareya Brāhmaṇa*⁵ possibly mentions his son *Rathagritsa* and priest *Suchivṛiksha Gaupālāyana*.⁶ The *Sāṅkhāyana Śrauta Sūtra*⁷ informs us that *Vṛiddhadyumna* erred in a sacrifice, when a *Brāhmaṇa* uttered a curse that the result would be the expulsion of the Kurus from *Kuru-ksbetra*, an event which actually came to pass.

¹ *Sat. Br.* XIII. 5. 4. 19-23.

² *Vaiṣṇava Brāhmaṇa* ; *Vedic Index*, Vol. I, pp. 27, 373.

³ I. 94, 54.

⁴ XV. 15. 10-13.

⁵ *Trivedi's translation*, pp. 322-23.

⁶ A *Gaupālāyana* also held the important post of the *Sthapati* of the Kurus (*Baudh. St. Sūtra*, XX. 25 ; *Vedic Index*, I. 123). His relationship with *Suchivṛiksha* is however, not known.

⁷ XV. 15. 10-13.

Sacrifices threatened to have serious repercussions on the fortunes of the royal family even in the days of Janamejaya. The performance of ritual in the approved form by proper persons seems to have excited as much interest in the Kuru country as philosophical discussions did at the court of Videha. Even in the fourth century B.C. the great Chandra Gupta Maurya had to attend to sacrifices in the midst of his pressing duties relating to war and judicial administration. A sacrificial error was not a trivial matter, especially in the ancient realm of the Kurus, which was the citadel of Brāhmaṇic ritualism. To religious indiscretions were soon added natural calamities and the effect on the people was disastrous. Mention has already been made of the Purāṇic tradition about the destruction of Hāstinapura by the erosive action of the Ganges. The *Chhāndogya Upanishad* refers to the devastation of the crops in the Kuru country by *Maṭachi* (hailstones or locusts) and the enforced migration of the family of Ushasti Chākṛāyana, who repaired to the village of an unnamed noble or wealthy man, next to a neighbourly prince and ultimately to the court of Janaka of Videha.¹

¹ *Chhāndogya*, I. 10. 1; *Bṛihad. Upanishad*, III. 4. For earlier vicissitudes, see *Rigveda*, X. 98 (drought in the time of Samtanu); *Mbh.* I 94 (story of Satvaraṇa). The *Chhāndogya Upanishad* says: *maṭachihateshu Kurushudāṭikya sahaṭayayā Ushastir ha Chākṛāyana ibhya-grame pradrāṅaka uvāsa*. 'When Kuruland was devastated by hailstones or locusts, Ushasti Chākṛāyana repaired with his virgin wife to a magnate's village and there lived in great distress. The plight of the Brāhmaṇa and his wife offers a sad contrast to the condition of the Kauravya and his lady who "throve merrily in the realm of Parikshit.'" Commentators took *maṭachi* to mean 'thunderbolt', 'hailstone' or 'a kind of small red bird' or 'locust.' The last meaning accords with the evidence of the *Devibhāgavatam*, X. 13. 110. *maṭachi guthacatteshām samudayāstu nirgatāḥ*. The Kanarese word *midiche* has the same sense (Kittel's Dictionary; Jacob, *Seraps from Shad-dartana*, JRAS, 1911, 510; *Vedic Index*, II, 119; Bhand. *Carm. Lac.*, 1918, 26-27; Bagchi, *IHQ*, 1933, 253).

The *Pañchaviṃśa Brāhmaṇa*¹ affords a clue to the royal seat of the 'Ābhipratāriṇa' branch of the Kuru family whose reign witnessed the beginning of those incidents that spelled disaster to the Kurus. We are told that Dṛiti, apparently the priest of king Abhipratārin, son of Kakshasena, completed a sacrifice in Khāṇḍava.² The same *Brāhmaṇa*³ refers to the **Abhipratāriṇas** as the "mightiest of all their relations." The passage is significant. It suggests that the great Janamejaya was no more in the land of the living in the days of Abhipratārin and his descendants, and that the line represented by the latter far outshone the other branches of the Kuru royal family. The existence of distinct offshoots of the line is clearly implied by tradition. One of them held sway in Hāstinapura and later on moved to Kauśāmbī. This is the branch mentioned in the *Purāṇas*. Another line reigned in Ishukāra.⁴ The third and the 'mightiest' branch is, as we have seen, connected with Khāṇḍava, the far-famed region where the great epic locates the stately city of Indraprastha. The famous capital which stood close to the site of modern Delhi finds prominent mention in the *Jātakas* as the seat of a line of kings claiming to belong to the "Yuddhiṭṭhila gotra" (Yudhisṭhira's gotra or clan).

The prosperity of the Ābhipratāriṇas was short-lived. Great calamities befell the Kurus and the disintegration of the kingdom went on apace.⁵ Large sections of the people, including Brāhmaṇas and princes, were apparently forced to leave the country, and to migrate to the eastern part of India. The transference of the royal seat of one

¹ XXV. 3. 6.

² XIV. 1. 12.

³ II. 9. 4, Caland's ed., p. 27.

⁴ SBE, xiv. 62.


⁵ Cf. *Jaimintya Brāhmaṇa*, III. 156; JAOS, 26. 61. "When Abhipratāra was lying dead with old age his sons divided the inheritance and made a great noise about it."

branch of the Kuru or Bharata dynasty to Kauśāmbī is confirmed by the evidence of some of the plays attributed to Bhāsa. Udayana, king of Kauśāmbī, is described in the *Scapnavāsava-datta* as a scion of the Bharata or Bhārata family¹ :—

*Bhāratānām kule jāto vinīto jñānavāñchhuchih
lannārhasi balāddhartum rājadharmasya deśikah*

“Thou art born in the family of the Bharatas. Thou art self-controlled, enlightened and pure. To stop her by force is unworthy of thee, who shouldst be the model of kingly duty.”

GENEALOGY OF THE PARIKSHITA FAMILY



¹ Ed. Gaṅapati Śāstri, p. 140, Trans. V. S. Sukthankar, p. 70. Cf. *Pratiṣṭhā-Yaugandharāyana*, “*Vedāśhara samarāya-pravishṭo Bhārato Vamśah*” “*Bhāratakulopabhukto rājāratnam*,” Act II

*Bhāratānām kule jāto
Vatsānāmṛjitaḥ patih*, Act IV.

SECTION II. THE AGE OF THE GREAT JANAKA.

*Sarve rājño Maithīlasya Mainākasyeva parvatāḥ
nikṛṣṭabhūtā rājāno.....*

—*Mahābhārata*¹.

We have seen that a series of calamities sadly crippled the Kurus. The kingdom fell to pieces and one of the princes had to leave the country. During the age which followed the Kuru people played a minor part in politics.

The most notable figure of the succeeding age was **Janaka**, the great philosopher-king of Videha, mentioned in the Vedic texts as the contemporary of Uddālaka Āruṇi and Yājñavalkya. The waning power of the Kurus and the waxing strength of the Vaidehas are shown by the fact that while Kuru princes are styled *rājan* (king) in certain *Brāhmaṇas*,² Janaka of Videha is called *saṃrāt* (supreme king). In the *Śatapatha Brāhmaṇa*³ the *saṃrāj* is asserted to be of higher dignity than a *rājan*.

That the great Janaka was later than the Pārikshitas admits of no doubt. We shall show later on that he was a contemporary probably of Nichakshu (if Purāṇic tradition is to be accepted), and certainly of Ushasta or Ushasti Chākrāyana during whose time disaster befell the Kurus. In Janaka's time we find the notable achievements, as well as the mysterious fate, of the Pārikshitas, still fresh in the memory of the people and discussed as a subject of general curiosity in the royal court of Mithilā. In the *Bṛihad-āraṇyaka Upanishad*

¹ III. 134. 5. As all other mountains are inferior to Maināka so are kings inferior to the lord of Mithilā.

² *Ait.*, VIII. 14. *Pañchaviṃśa*, XIV. 1. 12. etc.

³ V, I, 1, 12-13.

Bhujyu Lāhyāyani tests Yājñavalkya, the ornament of the court of Janaka, with a question, the solution of which the former is said to have previously obtained from a being of superhuman power through the medium of a Madra girl :

“*Kva Pārikshitā abhavan*¹—whither have the Pārikshitas gone ?”

Yājñavalkya answers : “Thither where the performers of the horse sacrifice abide.” From this it is clear that the Pārikshitas (sons of Parikshit) must at that time have passed away. Yet their life and end must have been still fresh in the memory of the people, and a subject of absorbing interest to men and women in different parts of the country.²

It is not possible to determine with precision the exact chronological relation between Janamejaya and Janaka. Epic and Purāṇic tradition seems to regard them as contemporaries. Thus the *Mahābhārata* says that Uddālaka, a prominent figure of Janaka's court, and his son Śvetaketu, attended the *sarpa-satra* (snake-sacrifice) of Janamejaya :—

Sadasya śchābhavad Vyāsaḥ putra-śishya-sahāyavān
*Uddālakaḥ Pramatakaḥ Śvetaketuścha Piṅgalaḥ*³

“Vyāsa, assisted by his son and disciple, Uddālaka, Pramataka, Śvetaketu, Piṅgala.....officiated as *sadasya* (priest).”

¹ *Bṛihad. Upanishad*, III. 3.1, E. Roer, *Bṛihad. Up.* P. 20 ;

² Weber, *Ind. Lit.* 126 ff. In the *Journal of Indian History*, April, 1936, p. 20, edited by Dr. S. Krishnaasvami Aiyangar and others, appears the amazing insinuation that “Mr. Roy Choudhury has.....attempted to give Weber's thought and language (as rendered) out as his own, without any reference to Weber.” A perusal of the *Bibliographical Index* (pp. 319, 328) appended to the first ed. of the *Political History* and p. 27 of the text ; the foreword to the subsequent editions, etc., will throw interesting light on the veracity of the writer of the article in question in the *Journal of Indian History*.

³ *Mbh., Adi.* 53. 7.

The *Vishṇu Purāṇa* says that Satānīka, the son and successor of Janamejaya, learned the Vedas from Yājñavalkya.¹

The unreliability of the Epic and the Purāṇic tradition in this respect is proved by the evidence of the Vedic texts. We learn from the *Śatapatha Brāhmaṇa*² that Indrota Daivāpa or Daivāpi Śaunaka was a contemporary of Janamejaya. His pupil was Dṛiti Aindrota or Aindroti according to the *Jaiminiya Upanishad* and *Vamśa Brāhmaṇas*. Dṛiti's pupil was Pulusha Prāchīnayogya.³ The latter taught Paulushi Satyayajña. We learn from the *Chhāndogya Upanishad*⁴ that Paulushi Satyayajña was a contemporary of Buḍila Āśvatarāśvi and of Uddālaka Āruṇi, two prominent figures of Janaka's court.⁵ Satyayajña was, therefore, certainly a contemporary of Janaka of Videha. He was an elder contemporary because his pupil Somaśushma Sātyayajñi Prāchīnayogya is mentioned in the *Śatapatha Brāhmaṇa*⁶ as having met Janaka. As Sātyayajñi certainly flourished long after Indrota Daivāpi Śaunaka, his contemporary Janaka must be considerably later than Janamejaya, the contemporary of Indrota.

We should also note that in the lists of teachers given at the end of the tenth book of the *Śatapatha Brāhmaṇa*, and the sixth chapter of the *Bṛihad-āraṇyaka Upanishad* Tura Kāvasbeya, the priest of Janamejaya, appears as a very ancient sage who was tenth in the ascending line from Sāñjiviputra, whereas Yājñavalkya and Uddālaka Āruṇi, the contemporaries of Janaka, were only fourth and fifth in

¹ *Vishṇu P.*, IV. 31.2.

² XIII. 5. 4. 1.

³ *Vedic Index*, II. p. 9.

⁴ V. 11. 1. 2.

⁵ *Vide Bṛihad-āraṇyaka Upanishad*, V. 14. 18: "Janako Vaideho Buḍilam Āśvatarāśvim, uśācha;" and III. 7. 1.

⁶ XI. 8. 2. 1-3.

the ascending line from the same teacher. The lists are given below :—

Janamejaya. Tura Kāvasheya

Yājñavachas Rājastambāyana	
Kuśri	Kuśri Vājaśravasa ¹
Śaṇḍilya	Upaveśi
Vātsyā	Aruṇa
Vāmakashāyana	Uddālaka Āruṇi
Mābitthi	Yājñavalkya
Kautsa	Āsuri
Māṇḍavya	Āsurāyana
Māṇḍūkāyani	Prāśnīputra Āsurivāsin
Sāñjivīputra	Sāñjivīputra

} Janaka
the Great

It is clear from what has been stated above that Janaka was separated by five or six generations from Janamejaya's time.² Jacobi and Rhys Davids³ agree in

¹ IC, III.747.

² It has been stated by certain writers that Janamejaya should be placed "only a step above Janaka." They point to the use of *lah* in the verb *bhā* in the interrogation *Kva Pārikshitā abharan* quoted above. They further identify Dantābala Dhaumra, a contemporary of Janamejaya, according to a legend narrated in the *Gopatha Brāhmaṇa*, with Dantāla Dhanuṃya of the *Jaiminīya Brāhmaṇa*, who may be assigned to the period of Janaka. It is also suggested that Bhāllaveya of a certain Brāhmaṇa passage is no other than Indradymna, *JIH.*, April 1936, 15 ff., etc. Apart from the fact that in the Vedic texts *lah* and *li* are at times used alternatively to convey the same meaning (Cf. 37 ante,) it should be noted that the question '*Kva Pārikshitā abharan*' with its answer was not framed for the first time at the court of Janaka. It is a *mūrdhābhishikṭa* (traditional)—*udāharana* attributed to superhuman agency—and, therefore, it cannot be regarded as establishing the synchronism of Janamejaya, Pārikshita and Janaka Valdeha. As to Dantābala it has already been pointed out (p. 39 above), that the *Baudhāyana Śrauta Sūtra* mentions Dhanuṃra and Dhanuṃyas as distinct members of the Kaṭyapa group. Janamejaya must have passed away in the days of Dṛiti and the Ābhipratāriṇas. See ante p. 46. See also *1HQ*, Vol. VIII, 1932, 600 ff. As to Bhāllaveya, serious students should remember that it is a patronymic like *Ātreya*, *Bhāradvāja* etc. In the absence of the personal name, it is uncritical to identify every Bhāllaveya with Indradymna himself as it is unreasonable to equate every *Ātreya* with Udamaya or every *Bhāradvāja* with Droṇa or Piṇḍola.

³ *Parīkṣhita parvaṃ*, 2nd ed. xviii and *Buddhist Suttas*. Introduction, p. xlvii

estimating the average length of a patriarchate or generation (in lists relating to spiritual succession) at 30 years. To the five or six teachers from Indrota to Somaśushma, and from Tura to Uddālaka Āruṇi and Janaka, we may, therefore, assign a period of 150 or 180 years.¹ It is, therefore, reasonable to think that Janaka flourished about 150 or 180 years after Janamejaya, and two centuries after Parikshit. If, following a Purāṇic tradition, we place Parikshit in the fourteenth century B.C., we must place Janaka in the twelfth century B.C. If, on the other hand, we accept a date for Guṇākhyā Sāṅkhāyana, the pupil's pupil of Uddālaka according to the *Sāṅkhāyana Āraṇyaka*, in the sixth century B.C., we must place Parikshit in the ninth century B.C., and Janaka in the seventh century B.C.

The kingdom of **Videha**, over which Janaka ruled seems to be mentioned for the first time in the *Samhitās* of the *Yajur Veda*.² It corresponds roughly to the modern Tirhut in North Bihār.³ It was separated from Kosala by the river Sadānīrā, usually identified with the modern Gaṇḍak which, rising in Nepāl, flows into the Ganges opposite Patna.⁴ Oldenberg, however, points out⁵

¹ It has been urged by some critics that pupils are not necessarily younger in age than their preceptors. It may freely be admitted that in particular cases pupils may be of the same age with, or even elder than, the *guru*. But it is idle to suggest that in a long list of successive *āchāryas* and *śiṣhyas* the presence of elderly pupils must be assumed except where the *guru* is known to be the father of the pupil. Individual cases of succession of elderly *śiṣhyas* do not invalidate the conclusion that the average duration of a generation is as is suggested by Jacobi and Rhys Davids.

² *Vedic Index*, II. 298.

³ According to Pargiter, *JASB*, 1897, 89—"Videha comprised the country from Gorakhpur on the Rāptī to Darabharṅga, with Kosala on the west and Aṅga on the east. On the north it approached the hills, and to the south it was bounded by the small kingdom of Vaiśālī."

⁴ *Vedic Index* II. 299.

⁵ *Buddha*, p. 398 n. Cf. Pargiter, *JASB*, 1897, 87. *Mbh.* II. 20. 27.

that the *Mahābhārata* distinguishes the Gaṇḍakī from the Sadānīrā: “*Gaṇḍakīñcha Mahāsoṇam Sadānīrām tathaiva cha.*” Pargiter, therefore, identifies the Sadānīrā with the Rāptī.¹ We learn from the *Suruchi Jātaka*² that the measure of the whole kingdom of Videha was three hundred leagues. It consisted of 16,000 villages.³

Mithilā, the capital of Videha, is not referred to in the Vedic texts, but is constantly mentioned in the *Jātakas* and the Epics. It has been identified with the small town of Janakpur just within the Nepāl border north of the place where the Muzaffarpur and Darbhanga districts meet. It is stated in the *Suruchi* and *Gandhārā*⁴ *Jātakas* that the city covered seven leagues. At its four gates were four market towns.⁵ We have the following description of the city in the *Mahājanaka Jātaka*⁶:—

By architects with rule and line laid out in order fair to see;
 With walls and gates and battlements, traversed by streets
on every side,
 With horses, cows and chariots thronged with tanks and
gardens beautified,
 Videha's far-famed capital, gay with its knights and
warrior swarms,
 Clad in their robes of tiger-skins, with banners spread
and flashing arms,
 Its Brahmins dressed in Kāśī cloth, perfumed with
sandal, decked with gems,
 Its palaces and all their queens with robes of state and diadems.⁷

¹ If the epic enumeration of the rivers quoted above follows a geographical order as is suggested by the use of the expression *krameṇa* in the Mbh. II. 20. 27, Sadānīrā may be the Burhi Gaṇḍak which is distinguished from the Gaṇḍak proper. Cf. map in JASB, 1895.

² J. 489.

³ J. 406. These are apparently conventional figures.

⁴ J. 489 and 406.

⁵ J. 546.

⁶ No. 539; Cowell's *Jātaka*, Vol. VI, p. 30.

⁷ For another description of Mithilā, see Mbh. III. 206.6-9.

According to the *Rāmāyaṇa*¹ the royal family of Mithilā was founded by a king named Nimi. His son was Mithi, and Mithi's son was Janaka I. The epic then continues the genealogy to Janaka II (father of Sītā) and his brother Kuśadhvaja, king of Sāṅkāśya. The *Vāyu*² and the *Vishṇu*³ *Purāṇas* represent Nimi or Nemi as a son of Ikshvāku, and give him the epithet Videha.⁴ His son was Mitthi whom both the *Purāṇas* identify with Janaka I. The genealogy is then continued to Sīradhvaja who is called the father of Sītā, and is, therefore, identical with Janaka II of the *Rāmāyaṇa*. Then starting from Sīradhvaja the *Purāṇas* carry on the dynasty to its close. The last king is named Kṛiti, and the family is called *Janaka-vamśa*.

*Dhṛiteṣṭu Bahulāśvo' bhūd Bahulāśva-sutaḥ Kṛitih
tasmin santishṭhate vamśo Janakānām mahātmanām*⁵

The Vedic texts know a king of Videha named Namī Sāpya.⁶ But he is nowhere represented as the founder of the dynasty of Mithilā. On the contrary, a story of the *Satapatha Brāhmaṇa* seems to indicate that the Videhan kingdom owes its origin to Videgha Māthava who came from banks of the Sarasvatī.⁷ We are told that the fire-god went burning along this earth from the Sarasvatī towards the east, followed by Māthava and his priest, Gotama Rāhūgaṇa till he came to the river

¹ I. 71.3

² 85. 7-8; 89. 3-4.

³ IV. 5, 1.

⁴ *Sa śāpena Vaśiṣṭhasya Videhaḥ samapadyata*—*Vāyu P.* The story of Vaśiṣṭha's curse on a Videhan king is known to the *Bṛihaddevatā* (vii. 59).

⁵ *Vāyu Purāṇa* 89, 23, For Janaka as a dynastic designation see also *Mbh.* III. 133, 17; *Rām.* I. 67. 8. The use of the expressions *Janakānām*, *Janakaiḥ* etc., does not necessarily indicate that every member of the line bore the personal name Janaka. Cf. *Ikṣvākūnām* (*Rām.* I. 5.3), which refers to those who were *Ikṣvākū-vamśa-prabhavāḥ* (I. 1. 8); *Raghūnām antayam*, etc.

⁶ *Vedic Index*, I, 426.

⁷ *Macdonell Sans. Lit.*, pp. 214-15; *Ved., Ind.*, II. 298; *Sat. Br.*, 1, 4, 1, etc.; Oldenberg's *Buddha*, pp. 398-99; Pargiter, J.A.S.B., 1897, p. 86 *et seq.*

Sadānīrā which flows from the northern (Himālaya) mountain, and which he did not burn over. No Brāhmaṇas went across the stream in former times, thinking "it has not been burnt over by *Agni Vaiśvānara* (the fire that burns for all men)." At that time the land to the eastward was very uncultivated, and marshy,¹ but after Māthava's arrival many Brāhmaṇas went there, and it was cultivated, for the Brāhmaṇas had caused Agni, the Fire-god, to taste it through sacrifices. Māthava the Videgha then said to Agni, "where am I to abide?" "To the east of this river be thy abode," he replied. Even now, the writer of the *Śatapatha Brāhmaṇa* adds, this stream forms the boundary between the Kosalas and the Videhas. The name of Mithi Vaideha, the second king in the Epic and the Purāṇic lists, is reminiscent of Māthava Videgha.

If Māthava Videgha was the founder of the royal line of Mithilā, Namī Sāpya cannot claim that distinction. The *Majjhima Nikāya*² and the *Nimi Jātaka* mention Makhādeva as the progenitor of the kings of Mithilā, and a Nimi is said to have been born to "round off the royal house, the family of hermits." The evidence of Buddhist texts thus shows that the name Nimi was borne not by the first, but probably by some later king or kings.³

As the entire dynasty of Maithila monarchs was called *Janaka-vaṃśa*, *Vaṃśo Janakānām mahātmanām*, the family of the high-souled Janakas, in post-Vedic literature, and there were several kings bearing the name of Janaka, it is very difficult to identify any of these with the great **Janaka** of the Vedic texts, the contemporary of

¹ This is the territory which the *Mahābhārata* refers to as "Jalodbhava" i.e., reclaimed from swamp (Mbh., II. 30. 4. Pargiter, *ibid*, 88n).

² II. 74-83.

³ The evidence of the *Bṛihad-devatā* (vii. 59) suggests that connection was maintained by Videhan monarchs with their old home on the banks of the Sarasvatī, cf. *Pañchaviṃśa Brāhmaṇa*, XXV. 10. 16-18 (story of Namī Sāpya).

Āruṇi and Yājñavalkya. But there is one fact which seems to favour his identification with Śiradhvaṇṇa of the Purāṇic list, i. e., the father of Sītā. The father of the heroine of the *Rāmāyaṇa* is a younger contemporary of Aśvapati, king of the Kekayas (maternal grandfather of Bharata¹), Janaka of the Vedic texts is also a contemporary of Aśvapati, prince of the Kekayas, as Uddālaka Āruṇi and Buḍila Āśvatarāśvi frequented the courts of both these princes.² But as the name Aśvapati is also apparently given to Bharata's maternal uncle,³ it seems that it was possibly not a personal name but a secondary epithet or a family designation like 'Janaka.'⁴ In that case it is impossible to say how far the identification of the Vedic Janaka with the father of Sītā is correct. The identification seems, however, to have been accepted by Bhavabhūti. Referring to the father of the heroine, the poet says in the *Mahāvīra-charita*⁵ :—

*Teshāmidānīm dāyādo
vṛiddhaḥ Śiradhvaṇṇo nṛpaḥ
Yājñavalkyo muniryasmai
Brahmapārāyaṇam jagau.*⁶

It is equally difficult to identify our Janaka with any of the kings of that name mentioned in the Buddhist

¹ *Rāmāyaṇa*, II. 9. 22.

² Ved. Ind., II, 69; Chh. Up., V. 11. 1-4; Brh. Up., III. 7.

³ *Rāmāyaṇa*, VII. 113. 4.

⁴ Against the view that Aśvapati was a family designation common to all members of the line it may, however, be urged that in the Mbh. vii. 104. 7; 123. 5 Bṛhatkashatra, chief of the Kekayas, does not bear that epithet.

⁵ Act I, Verse 14.

⁶ Cf. Act II, verse 43; *Uttara-Charita*, Act IV, verse 9. In the Mbh. III. 183. 4 the contemporary of Uddālaka and Kahoḍa seems to be called Aindraadyumni. (Cf. *AIHT*, 96.) In Mbh. XII. 310. 4; 318. 95, the contemporary of Yājñavalkya is styled Daivarātri. The *Satapatha Brāhmaṇa* is attributed to this Yājñavalkya (*ibid.*, XII. 318. 11f). Both Aindraadyumni and Daivarātri are patronymics and hardly afford a clue to the personal name of the king in question.

Jātakas. Professor Rhys Davids¹ seems to identify him with Mahā-Janaka of the *Jātaka* NO. 539. The utterance of Mahā-Janaka II of that *Jānaka*

'Mithilā's palaces may burn

But naught of mine is burned thereby

indeed reminds us of the great philosopher-king.

In the *Mahābhārata*² we find the saying attributed to Janaka 'Janadeva' of Mithilā. In the Jaina *Uttar-ādhyayana*, however, the saying is attributed to Namī.³ This fact coupled with the mention of Nemi in juxtaposition with Arishṭa in the *Vishṇu-Purāṇa*⁴ may point to the identification of Namī or Nemi with Mahā-Janaka II whom the *Jātaka* represents as the son of Aritṭha. If Mahā-Janaka II be identical with Namī, he cannot be identified with Janaka who is clearly distinguished from Namī in the Vedic texts. One may be tempted to identify the Vedic Janaka with Mahā-Janaka I of the *Jātaka*. But proof is lacking.

In the *Satapatha Brāhmaṇa*, the *Bṛihad-āraṇyaka Upanishad* and the *Mahābhārata*⁵ Janaka is called *Samrāj*. This shows that he was a greater personage than a mere *Rājan*. Although there is no clear evidence in the Vedic literature of the use of the word *Samrāj* as emperor in the sense of a king of kings,

¹ Bud. Ind., P. 26.

² XII. 17. 18-19: 219. 50.

"Mithilāyām pradīptāyām
na me dahyati kiñchana"

"Api cha bhavati Māthilena gītān
nagaram upāhitam agnirābhicikshya
na khalu mama ki dahyate' tra kiñchit
svayam idam āha kilo sma bhūmipālāḥ"

"Seeing his city burning in a fire, the king of Mithilā himself sang of old,
'in this (conflagration) nothing of mine is burning'."

³ S. B. E., XLV. 37.

⁴ IV. 5. 13.

⁵ III. 133. 17.

still the *Śatapatha Brāhmaṇa* distinctly says that the *Samrāj* was a higher authority than a *Rājan*; "by offering the *Rājasūya* he becomes king, and by the *Vājapeya* he becomes *Samrāj*; and the office of king is the lower, and that of *Samrāj* the higher"¹ In the *Āśvalāyana Śrauta-Sūtra*² Janaka is mentioned as a great sacrificer.

But Janaka's fame rests not so much on his achievements as a king and a sacrificer, as on his patronage of culture and philosophy. The court of this monarch was thronged with Brāhmaṇas from Kosala, the Kuru-Pañchāla countries and perhaps Madra, *e.g.*, Aśvala, Jāratkāra, Ārtaḥbhāga, Bhujyu Lāhyāyani, Ushasta(-ī) Chākṛāyana, Kaboḍa Kaushītakeya. Gārgī Vāchaknavi, Uddālaka Āruṇi and Vidagdha Śākalya. The tournaments of argument which were here held form a prominent feature in the third book of the *Bṛihad-āranyaka Upanishad*. The hero of these was Yājñavalkya Vājasaneyā, who was a pupil of Uddālaka Āruṇi.³ Referring to Janaka's relations with the Kuru-Pañchāla Brāhmaṇas, Oldenberg observes:⁴ "The king of the east, who has a leaning to the culture of the west, collects the celebrities of the west at his court—much as the intellects of Athens gathered at the court of Macedonian princes."

The *Brāhmaṇas* and the *Upanishads* throw some light on the political condition of Northern India during the age of the great Janaka. From those works we learn that besides Videha, there were nine states of considerable importance. *viz.* :


- | | | |
|-------------|------------|-------------|
| 1. Gandhāra | 4. Uśīnara | 7. Pañchāla |
| 2. Kekaya | 5. Matsya | 8. Kāśi |
| 3. Madra | 6. Kuru | 9. Kosala |

¹ *Sat. Br.*, V, 1, 1. 12-13; XII, 8, 3, 4; XIV, 1, 3, 8.

² X, 8, 14.

³ *Bṛih. Up.* VI, 5, 3.

⁴ *Buddha*, P. 308.





The Vedic texts seldom furnish any definite clue as to the exact geographical position of these states. For the location of most of these territories we must, therefore, turn to the evidence of later literature.

The inhabitants of **Gandhāra** are included by epic poets among the peoples of *Uttarāpatha* or the northernmost region of India :—

*Uttarāpatha-janmānaḥ kīrtayishyāmi tān api
Yauna-Kāmboja-Gāndhārāḥ Kirātā Barbaraiḥ saha.*¹

The country lay on both sides of the Indus,² and contained two great cities, viz., Takshaśilā and Pushkarāvati, alleged to have been founded by two heroes of epic fame :

*Gandhāra-vishaye śiddhe, tayoh puryau mahātmanoh
Takshasya dikshu vikhyātā ramyā Takshaśilā puri
Pushkarasyāpi vīrasya vikhyātā Pushkarāvati.*³

The *vishaya* (territory) described in these lines must have embraced the Rāwalpindī district of the Western Pañjāb and the Peshāwar district of the North-West Frontier Province. A few miles to the north-west of Rāwalpindī and 2,000 leagues away from Banaras,⁴ stood the famous city of Takshaśilā or Taxila. The remains of the great city

¹ *Mbh.*, XII. 207. 43.

² *Rāmāyaṇa*, VII. 113. 11; 114. 11; *Sindhor-ubhayataḥ pārśve*. According to *Jātaka* no. 406 the kingdom of Gandhāra included Kaśmīra. Hekataios of Miletus (B. C. 549-486) refers to a Gandaric city called Kaspapyros. Stein (*JASB*, 1899, extra no. 2, 11) equates Kaspapyros with Kaspatyros of Herodotus and says that it must have been situated in that territory where the Indus first becomes navigable, i.e., in the ancient Gandhāra. Kaspatyros was the place at which the expedition under Skylax, sent by Darius to explore the course of the Indus, embarked. Stein (pp. 12-13) rejects the view according to which Kaspapyros represents the Sanskrit Kaśyapapura from which the name Kaśmīra is said to have been derived. Kaśyapapura as a place-name is known to Alberuni (I 298), but he mentions it as an original designation of Multan. Kaśyapa's traditional connection with Kaśmīra is, however, clear from *Rājatarāṅgiṇī*, 1, 27.

³ *Vāyu Purāṇa*, 88, 189-90; cf. *Rāmāyaṇa*, VII. 114. 11.

⁴ *Talapatta and Susīma Jātakas*, Nos. 96, 163.

"are situated immediately to the east and north-east of Sarai-kala, a junction on the railway, twenty miles north-west of Rāwalpindī. The valley in which they lie is watered by the Haro river. Within this valley and within three and a half miles of each other are the remains of three distinct cities. The southernmost (and oldest) of these occupies an elevated plateau, known locally as Bhir-mound."¹

Pushkarāvati or Pushkalāvati, the Lotus City, (Prākṛit *Pukkalāoti*, whence the 'Peukelaotis' of Arrian) is represented by the modern Prang and Obārsadda, 17 miles north-east of Peshāwar, on the Swāt river.²

Gandhāra is a later form of the name of the people called Gandhāri in the *Rig-Veda* and *Atharva-Veda*. In the *Rig-Veda*³ the good wool of the sheep of these tribesmen is referred to. In the *Atharva-Veda*⁴ the Gandhāris are mentioned with the Mūjavats, apparently as a despised people. The *Brāhmaṇa* texts refer to Nagnajit, king of Gandhāra, and his son Svarjit. The former receives Brāhmanic consecration, but observations of the family on ritual are treated with contempt.⁵ In later times the 'angle of vision' of the men of the *Madhya-deśa* (Mid-India) changed, and Gandhāra became a resort of scholars of all classes who flocked to its capital for instruction in the three *Vedas* and the eighteen⁶ branches of knowledge.

¹ Marshall, *A Guide to Taxila*, pp. 1-4; *AGI*, 1924, 120, 123 f.

² Schoff, *The Periplus of the Erythraean Sea*, pp. 193-84; Foucher, *Notes on the Ancient Geography of Gandhāra*, p. 11; cf. V. A. Smith, *JASB*, 1889, 111; Cunningham, *AGI*, 1924, 57 f. Strabo (XV. 96) extends Gandaritis westwards to the Caucasus (Kunar ?).

³ I. 126. 7.

⁴ V. 22. 14. cf. *Mbh.* VIII, 44, 45; 45, 8 etc.

⁵ *Āitareya*, vii. 34. *Satapatha*, vii. 1. 4. 10. *Vedic Index*, i. 432.

⁶ Cf. Rhys Davids and Stede, *Pali-English Dictionary*, 76 (*Vijja-tthānā*) ; *Vāyu*, 61, 79. *Brahmaṇḍa* 67, 82; *Milinda* I, 9. mentions 19 *Sippas*; cf. IV, 5, 26.

In a significant passage of the *Chhândogya Upanishad*¹ Uddālaka Āruṇi, the contemporary of the Vedic Janaka, mentions Gandhāra to illustrate the desirability of having a duly qualified teacher from whom a pupil "learns (his way) and thus remains liberated (from all worldly ties) till he attains (the Truth or Beatitude, *Moksha*)."² A man who attains *Moksha* is compared to a blindfold person who reaches at last the country of Gandhāra. The passage runs as follows :

"*Yathā somya puruṣhaṁ Gandhārebhyaḥ* bhinaddhākṣhaṁ ānīya tam tato' ti jāne viśṛjjet, sa yathā tatra prāṇ vā udān vādharāṇ vā pratyāṇ vā pradhmayīta—abhinaddhākṣha ānīto' bhinaddhākṣho viśṛiṣṭaḥ. Tasya yathā-bhinahanam pramuchya prabrūyād etāṁ diśaṁ Gandhārā etāṁ diśaṁ vṛjēti. Sa grāmād grāmaṁ prichchhan paṇḍito medhāvī Gandhārān avopasampadyeta, evam eveh-āchāryavān puruṣho veda."

"O my child, in the world when a man with blindfold eyes is carried away from Gandhāra and left in a lonely place, he makes the east and the north and the south and the west resound by crying 'I have been brought here blindfold, I am here left blindfold.' Thereupon (some kind-hearted man) unties the fold on his eyes and says 'This is the way to Gandhāra; proceed thou by this way.' The sensible man proceeds from village to village enquiring the way and reaches at last the (province) of Gandhāra. Even thus a man who has a duly qualified teacher learns (his way)."³

The full import of the illustration becomes apparent when we remember that the *Uddālaka Jātaka*⁴ represents Uddālaka as having journeyed to Takṣaśīlā (Takkaśīlā) and learnt there of a world-renowned teacher. The

¹ VI, 14.

² Cf. Dr. R. L. Mitra's translation of the *Chhândogya Upanishad*, p. 111.

³ No. 487.

Setaketu Jātaka¹ says that Śvetaketu, son of Uddālaka, went to Takshaśilā and learned all the arts. The *Śatapatha Brāhmaṇa* mentions the fact that Uddālaka Āruṇi used to drive about amongst the people of the northern country.² It is stated in the *Kaushītaki Brāhmaṇa*³ that Brāhmaṇas used to go to the north for purposes of study. The *Jātaka* tales are full of references to the fame of Takshaśilā as a university town. Pāṇini, himself a native of Gandhāra, refers to the city in one of his *Sūtras*.⁴ An early celebrity of Takshaśilā was perhaps Kauṭilya.⁵

The **Kekayas** were settled in the Western Pañjab between Gandhāra and the Beas. From the *Rāmāyaṇa*⁶ we learn that the Kekaya territory lay beyond the Vipāśā or Beas and abutted on the Gandharva or Gandhāra *Vishaya*. The *Mabābhārata*⁷ associates them with the Madras (*Madraścha saha Kekayaiḥ*). Arrian⁸ places the "Kekians" on the river Saranges, apparently a tributary of the Hydraotes or the Rāvi.

The Vedic texts do not mention the name of its capital city, but the *Rāmāyaṇa* informs us that the metropolis was Rājagriha or Girivraja :

"Ubhau Bharata-Satrughnau Kekayeshu parantapau
pure Rājagrihe ramye mātāmaha-niveśane."⁹

"Both Bharata and Satrugbna, repressers of enemies, are staying in Kekaya in the charming city of Rājagriha, the abode of (the) maternal grandfather (of the former)."

¹ No. 377.

² *Sat. Br.* XI. 4. 1. 1, et seq. *Udichyānērito dhārayāṁ chakāra*.

³ VII. 6. *Vedic Index* II. 279.

⁴ *Sūtra* iv. 3, 90; AGI (1924), 67.

⁵ Turnour, *Mahawanso*, vol. I (1837), p. xxxix.

⁶ II. 68, 19-23; VII. 113-14.

⁷ VI. 61. 12; VII. 19. 7. *Madra-Kekayāḥ*.

⁸ *Indika*, iv; *Ind. Ant.* V. 382; *Mc Crindle, Megasthenes and Arrian*, 1926, pp. 163, 196.

⁹ *Rām.*, II. 67. 7.

“*Girivrajam puranaram śīghram āsedur añjasā*”

“(The messengers bound for Kekaya) quickly arrived at Girivraja, the best of cities.”

The journey from Ayodhyā to the Kekaya capital, a distance of about 650 miles, took seven days. Videha could be reached from Ayodhyā on the fourth day. The distance is about 200 miles. The slower rate is explained by Pargiter by absence of good roads. Cunningham identifies the capital of the Kekayas with Girjak or Jalalpur on the river Jhelam.²

There was another Rājagriha-Girivraja in Magadha, while Hiuen Tsang mentions a third Rājagriha in Po-ho or Balkh.³ In order to distinguish between the Kekaya city and the Magadhan capital, the latter city was called “Girivraja of the Magadhas.”⁴

The *Purāṇas*⁵ tell us that the Kekayas along with the Madrakas and the Uśīnaras, were branches of the family of Anu, son of Yayāti. The Anu tribe is frequently mentioned in the *Ṛig-Veda*.⁶ It appears from a hymn of the eighth *Maṇḍala*⁷ that they dwelt in the Central Pañjab, not far from the Parusbpī, the same territory which we find afterwards in possession of the Kekayas and the Madrakas.

The king of Kekaya in the time of the Vedic Janaka was Aśvapati, a name borne also by the maternal grandfather and maternal uncle of Bharata.⁸ The *Śatapatha Brāhmaṇa*⁹ and the *Chhāndogya Upanishad*¹⁰ suggest that the Kekaya monarch was a man of learning and that he instructed a number of Brāhmaṇas, viz. Aruṇa Aupayesi

¹ Rām., II. 68, 92.

⁶ I. 108. 8, VII. 18. 14; VIII. 10. 5.

² Rām., I. 69, 7; II. 71. 19. *AGI*,

⁷ 74.

1924, 188; *JASB*, 1895, 260 ff.

⁸ Rām. II. 9, 22; VII. 113. 4.

³ Beal, *Si-yu ki*, Vol. 1, p. 44.

⁹ X. 6. 1. 2.

⁴ S. B. E., XIII, p. 150.

¹⁰ V. 11. 4 *et seq.*

⁵ *Matsya*, 48. 10-20; *Vāyu*, 99. 12-23.

Gautama, Satyayajña Paulushi, Mahāśāla Jābāla, Buḍila, Āśvatarāśvi, Indradyumna Bhāllaveya, Jana Śārkārākshya, Prāchīnaśāla Aupamanyava, and Uddālaka Āruṇi. The reference to Aruṇa Aupaveśi who belongs to an older generation than Uddālaka, shows that Āśvapati was an elder contemporary of the great philosopher-king of Videha.

The Jaina writers tell us that one-half of the kingdom of Kekaya was Aryan, and refer to the Kekaya city called "Seyaviyā."¹ A branch of Kekayas seems to have migrated to Southern India in later times and established its authority in the Mysore country.²

The Madra people were divided into several sections viz., the northern Madras, the eastern Madras, the southern Madras or Madras proper etc. The northern Madras known as Uttara-Madras, are referred to in the *Aitareya Brāhmaṇa*, as living beyond the Himavat range in the neighbourhood of the Uttara-Kurus, possibly, as Zimmer and Macdonell conjecture, in the land of Kāśmīr. The eastern Madras probably occupied some district to the east of Siālkoṭ, not far from Trigartta or Kangra.³

The southern Madras were settled in the Central Pañjab in the territory lying to the west of the river Irāvati or Rāvi.⁴ In later times the eastern limits extended to the Amritsar district which was included within the Madra-deśa in the days of Guru Govind Singh.⁵ The ancient capital (properly *puṭa-bhedana*) was Śākala or Sāgala-nagara (modern Siālkoṭ). This city is mentioned in the *Mahābhārata*⁶

¹ *Ind. Ant.*, 1891, p. 375.

² *A.H.D.*, 88, 101.

³ Pāṇini, IV. 2. 107-8; Cf. Association of Madras and Trigarttas, *Mbh.* VI. 61 19. In I. 191. 36 the number of 'Madras' is given as four.

⁴ Cf. *Mbh.*, VIII. 44. 17.

⁵ Malcolm, *Sketch of the Sikhs*, p. 55.

⁶ II. 32. 14. *Tataḥ Śākalamebhuyetya Mādṛāṇāṃ puṭabhedanam.*

and several *Jātakas*¹ and is probably hinted at in the name 'Sākalya,' given to a Vedic teacher who graced the court of Janaka. It stood on the banks of the Āpagā² in a tongue of land between two rivers styled the Sākala-dvīpa,³ apparently corresponding to a part of the Rechna Doāb.

The Madras proper are represented in early post-Vedic works as living under a monarchic constitution. The name of the ruler of the territory in the time of Janaka is not known. It was politically not of much importance. But, like the northern realms described above, it was the home of many famous scholars and teachers of the *Brāhmaṇa* period such as Madragāra Śauṅgāyani and Kāpya Patañchala,⁴ one of the teachers of the celebrated Uddālaka Āruṇi.⁵ The early epic knows the Madra royal house⁶ as a virtuous family. But in later times Madra earned notoriety as the seat of outlandish peoples with wicked customs.⁷

The country of the Uśīnaras was situated in the *Madhya-deśa* or Mid-India. The *Aitareya Brāhmaṇa*⁸ says "*asyām dhruvāyām madhyamāyām pratishṭhāyām dīśi*," "in this firmly established middle region," lie the realms of the Kuru-Pañchālas together with Vaśas and Uśīnaras. In the *Kaushītaki Upanishad* also the Uśīnaras are associated with the Matsyas, the Kuru-Pañchālas and the

¹ E. g. *Kālīṅgabodhi Jātaka*, No. 479; and *Kusa Jātaka*, No. 531.

² Mbh. VIII. 44. 10; Conn. ASI, 1921, 2111. Cunningham identifies this Āpagā with the Aysk rivulet which rises in the Jamru hills and joins the Chenāb.

³ Mbh. II. 26. 5.

⁴ Weber, *Ind. Lit.*, 126.

⁵ *Bṛhad. Up.*, III. 7. 1.

⁶ Cf. *Āyaspati* and his daughter *Sāvitrī*.

⁷ For detailed accounts of the Madras see Dr. H. C. Ray in *JASB*, 1922, 257; and Law, *Some Kṣatriya Tribes of Ancient India*, p. 214. Mr. S. N. Mitra points out that the *Paramattha-dipani* on the *Therīgāthā* (p. 127) (wrongly) places Śākala-nagara in Magadha-raṭṭha. But the *Apadāna* quotations on p. 131 leave no room for doubt that Madra is the correct name of the kingdom of which Śākala (Sākala) was the capital.

⁸ VIII. 14.

9—1829B.

Gautama, Satyayajña Paulushi, Mahāśāla Jābāla, Buḍila, Āśvatarāśvi, Indradyumna Bhāllaveya, Jana Śārkarākshya, Prāchīnāśāla Aupamanyava, and Uddālaka Āruṇi. The reference to Aruṇa Aupaveśi who belongs to an older generation than Uddālaka, shows that Āśvapati was an elder contemporary of the great philosopher-king of Videha.

The Jaina writers tell us that one-half of the kingdom of Kekaya was Aryan, and refer to the Kekaya city called "Seyaviyā."¹ A branch of Kekayas seems to have migrated to Southern India in later times and established its authority in the Mysore country.²

The Madra people were divided into several sections viz., the northern Madras, the eastern Madras, the southern Madras or Madras proper etc. The northern Madras known as Uttara-Madras, are referred to in the *Aitareya Brāhmaṇa*, as living beyond the Himavat range in the neighbourhood of the Uttara-Kurus, possibly, as Zimmer and Macdonell conjecture, in the land of Kāśmīr. The eastern Madras probably occupied some district to the east of Siālkoṭ, not far from Trigartta or Kangra.³

The southern Madras were settled in the Central Pañjab in the territory lying to the west of the river Irāvati or Rāvi.⁴ In later times the eastern limits extended to the Amritsar district which was included within the Madra-deśa in the days of Guru Govind Singh.⁵ The ancient capital (properly *puṭa-bhedana*) was Śākala or Sāgala-nagara (modern Siālkoṭ). This city is mentioned in the *Mahābhārata*⁶

¹ *Ind. Ant.*, 1891, p. 375.

² *A H D.*, 88, 101.

³ Pāṇini, IV. 2. 107-8; Cf. Association of Madras and Trigarttas, *Mbh.* VI. 61. In I. 121, 36 the number of 'Madras' is given as four.

⁴ Cf. *Mbh.*, VIII. 44. 17.

⁵ Malcolm, *Sketch of the Sikhs*, p. 55.

⁶ II. 32, 14. *Tataḥ Śākalamahyetya Madrāṇāṃ puṭabhedanam.*

and several *Jātakas*¹ and is probably hinted at in the name 'Sākalya,' given to a Vedic teacher who graced the court of Janaka. It stood on the banks of the Āpagā² in a tongue of land between two rivers styled the Sākala-dvīpa,³ apparently corresponding to a part of the Rechna Doāb.

The Madras proper are represented in early post-Vedic works as living under a monarchic constitution. The name of the ruler of the territory in the time of Janaka is not known. It was politically not of much importance. But, like the northern realms described above, it was the home of many famous scholars and teachers of the *Brāhmaṇa* period such as Madragāra Śauṅgāyani and Kāpya Patañchala,⁴ one of the teachers of the celebrated Uddālaka Āruṇi.⁵ The early epic knows the Madra royal house⁶ as a virtuous family. But in later times Madra earned notoriety as the seat of outlandish peoples with wicked customs.⁷

The country of the Uśīnaras was situated in the *Madhya-deśa* or Mid-India. The *Aitareya Brāhmaṇa*⁸ says "*asyām dhruvāyām madhyamāyām pratishṭhāyām diśi*," "in this firmly established middle region," lie the realms of the Kuru-Pañchālas together with Vaśas and Uśīnaras. In the *Kaushītaki Upanishad* also the Uśīnaras are associated with the Matsyas, the Kuru-Pañchālas and the

¹ E. g. *Kāliṅgabedhi Jātaka*, No. 479; and *Kusa Jātaka*, No. 531.

² Mbh. VIII. 44. 10; Cunn. *AGI*, 1924, 211f. Cunningham identifies this Āpagā with the Aysk rivulet which rises in the Jammu hills and joins the Chenāb.

³ Mbh. II. 26. 5.

⁴ Weber. *Ind. Lit.*, 126

⁵ *Brīhad. Up.*, III. 7. 1.

⁶ Cf. Aśvapati and his daughter Śavitri.

⁷ For detailed accounts of the Madras see Dr. H. C. Ray in *JASB*, 1922, 257; and Law, *Some Kṣatriya Tribes of Ancient India*, p. 211. Mr. S. N. Mitra points out that the *Paramattha-dīpani* on the *Therīgāthā* (p. 127) (wrongly) places Sāgula-nagara in Magadha-raṭṭha. But the *Apadāna* quotations on p. 131 leave no room for doubt that Madra is the correct name of the kingdom of which Sāgala (Sākala) was the capital.

⁸ VIII. 14.

9—1829B.

Vaśas. They probably lived in the northernmost part of the *Madhya-deśa*, for in the *Gopatha Brāhmaṇa* the Uśīnaras and the Vaśas are mentioned just before the *Udīchyas* or northerners:¹ *Kuru-Pañchāleshu Aṅga-Magadheshu Kāsi-Kausalyeshu Śālva-Matsyeshu sa Vaśa-Uśīnaresh-Udīchyeshu*.

The *Mahābhārata* speaks of 'Uśīnara' as sacrificing on two small streams near the Jumna.² In the *Kathā-saritsāgara* Uśīnara giri is placed near Kanakhala, the "sanctifying place of pilgrimage at the point where the Ganges issues from the hills."³ It is, doubtless, identical with Usira-giri of the *Divyāvadāna*⁴ and Usira-dhvaṇya of the *Vinaya* Texts.⁵ Pāṇini refers to the Uśīnara country in several *sūtras*.⁶ Its capital was Bhoja-nagara.⁷

The *Ṛig-Veda*⁸ mentions a queen named Uśīnarāṇī. The *Mahābhārata*, the *Anukramaṇī* and several *Jātakas* mention a king named Uśīnara and his son Śibi.⁹ We do not know the name of Janaka's Uśīnara contemporary. The *Kaushītaki Upanishad* tells us that Gārgya Bālāki, a contemporary of Ajātaśatru of Kāsi, and of Janaka of Videha, lived for some time in the Uśīnara country.

Matsya is usually taken to "include parts of Alwar, Jaipur and Bharatpur," being "the kingdom of the king Virāṭa of the *Mahābhārata*, in whose court the five Pāṇḍava

¹ *Gop. Br.* II. 9.

² *Mbh.* III. 130. 21.

³ Edited by Pandit Durgāprasād and Kāśīnāth Pāndurang Parab, third edition, p. 5. Kanakhala stands near Hardwar in the Saharanpur district of the Uttar Pradesh. Cf. also *Mbh.* V. 111. 16-23.

⁴ P. 22.

⁵ Part II, p. 39. See Hultzsch, *Ind. Ant.*, 1905, p. 179.

⁶ II. 4. 20; IV. 2. 118.

⁷ *Mbh.*, V. 112. 2. For Ahvara, a fortress of the Uśīnaras, see *Ind. Ant.*, 1885, 322.

⁸ X, 59. 10.

⁹ *Mbh.*, XII. 29. 39; *Vedic Index*. Vol. I, p. 103; *Mahā-Kaṇha Jātaka*. No. 469; *Nimi Jātaka*, No. 511; *Mahā-Nārada Kassapa Jātaka*, No. 544, etc.

brothers resided *incognito* during the last year of their banishment.¹ But Alwar seems to have been the territory of a neighbouring people—the Śālvas.² The Matsya country lay to the south of the Kurus of the Delhi region and to the west of the Śūrasenas of Mathurā. Southward it may have approached the river Chambal, westward it reached the Sarasvatī. The Mahābhārata mentions a people called the Aparā-Matsyas whom Pargiter places on the hill tracts on the north bank of the Chambal. The Rāmāyaṇa has a reference to the Vīra-Matsyas in connection with the Sarasvatī and the Ganges.³ The Matsya capital has been identified by Cunningham⁴ with Bairat in the Jaipur State. Pargiter thinks⁵ that the capital was Upaplavya. But according to Nīlakaṇṭha, the commentator, Upaplavya was "*Virāṭa-nagara-samīpastha-nagarāntaram*," a city close to the metropolis, but not identical with it.⁶

The Matsyas first appear in a passage of the *Rig-Veda*⁷ where they are ranged with the other antagonists of Sudās, the great Rigvedic conqueror. The *Śatapatha Brāhmaṇa*⁸ mentions a Matsya king named Dhvasan Dvāitavana who celebrated a horse-sacrifice near the

1 Bhandarkar, *Cormichael Lectures*, p. 53.

2 Cf. *Ind. Ant.*, 1913, N. L. Day's *Geographical Dictionary*, p. ii.

3 Mbh. II. 31.2-7; III. 24-25; IV. 5.4; Rām. II. 71.5 Pargiter points out (JASB, 1895, 250ff) that the Matsya Country lay southward from Khāṇḍava-prastha (Delhi region). Its position to the west of Śūrasena (Mathurā district) is brought out clearly by the description of the journey of the Pāṇḍu princes to the court of Virāṭa. Crossing the Jumna the heroes passed through the territory, north of the Dadārṇas and south of the Pañchālas and then proceeded through the countries of the Yākyi-Bomas and the Śūrasenas to the Matsya realm. From Upaplavya, a suburb of the Matsya capital, to Hastinapura, the metropolis of the Kurus in the epic age, was less than two days' journey by chariot. Vyikasthala on the way could be reached by a traveller in the evening on the first day.

4 AGI. 1924, 387; I. A. V. 179. For a Virāṭa-nagara in South India, see *Bomb. Gaz.*, I. ii, 558.

5 JASB, 1895, 252.

6 Mbh. IV. 72. 14. Cf. *Ind. Ant.*, 1882, 327.

7 VII. 19.6.

Sarasvatī. The *Brāhmaṇa* quotes the following *gāthā* (song) :—

*Chaturdaśa Dvaitavano rājā saṁgrāmajidd-hayān
Indrāya Vṛitraghne' badhnāttasmād Dvaitavanam sara(iti).*

'Fourteen steeds did king Dvaitavana, victorious in battle, bind for Indra Vṛitraghan, whence the lake Dvaitavana (took its name)'. The *Mahābhārata* mentions the lake as well as a forest called Dvaitavana which spread over the banks of the river Sarasvatī.¹

In the *Gopatha Brāhmaṇa*² the Matsyas appear in connexion with the Śālvas, in the *Kaushītaki Upanishad*³ in connexion with the Kuru-Pañchālas, and in the *Mahābhārata* in connexion with the Trigarttas⁴ of the Jālandar Doāb, and the Chedis of Central India.⁵ In the *Manu-Saṁhitā*⁶ the Matsyas together with Kuru-kshetra, the Pañchālas, and the Śūrasenakas comprise the holy enclave of the Brāhmaṇa sages (*Brahmarshi-deśa*).

The name of Janaka's contemporary ruler is not known. That the country was important in the time of the great philosopher-king of Videha, is known from the *Kaushītaki Upanishad*.

The **Kuru** country tried to maintain its reputation as a home of Brāhmaṇical culture in the age of Janaka. But scholars hailing from that region appear now in the role of students thirsting for philosophical knowledge rather than authorities on sacrificial ritual. This probably points to a new development in the social life of the people, a development that synchronises with the end of the period of prosperity under Parikshit and his immediate successors and the beginning of economic distress hinted at in the *Chhāndogya Upanishad*.⁷ The

1 Mbh. III.24-25

2 1. 2. 9

3 IV. 1

4 Mbh., Bk. IV. 391-2; 321-3

5 V. 74-16

6 II. 19

7 1. 10. 1-7.

time was soon to come when they would listen even to the heterodox teaching of new faiths that grew up in Eastern India. For the present Kuru Brāhmaṇas (*e.g.*, Ushasti Chākrāyana) took an active part in discussions about *Brahman* and *ātman* at the court of Videha. The intellectual life of the eastern kingdom must have been greatly stirred by the exodus of Kurus and perhaps also of the Pañchālas that took place about this time. An exodus from Constantinople in a like manner enriched the life of the people of western Europe in the fifteenth century A.D.

If the Purāṇic list of Janamejaya's successors be accepted as historical, then it would appear that Nichakshu was probably the Kuru king of Hāstinapura in the time of Janaka.

- | | | | | |
|---------------------|-----|---------------|---------------|---------------------------------|
| 1. Janamejaya | ... | 1. Indrota | Daivāpa | Saunaka |
| 2. Śatānika | ... | 2. Dṛiti | Aindrota | (son and pupil) |
| 3. Aśva-medha-datta | | 3. Pulusha | Prāchīnayogya | (pupil) |
| 4. Adhisīma-kṛishṇa | | 4. Pulushi | Satyayajña | (pupil) |
| 5. Nichakshu | ... | 5. Somaśushma | Sātyayajñi | (pupil); Janaka's contemporary. |

Curiously enough, it is Nichakshu who is represented in the *Purāṇas* as the remover of the seat of government from Hāstinapura to Kauśāmbī. We have some indication that the city of Kauśāmbī really existed about this time.¹ The *Śatapatha Brāhmaṇa* makes Proti Kauśāmbeya a contemporary of Uddālaka Āruṇi who figured in the court of Janaka. It is thus clear that Kauśāmbeya was a contemporary of Janaka. Now, Harisvāmin in his commentary on the *Śatapatha Brāhmaṇa* understood

¹ Cf. Weber, *Ind. Lit.*, p. 123; *Vedic Index*, I. 193.

Kauśāmbeya to mean a 'native of the town of Kauśāmbi.' It is, therefore, permissible to think that Kauśāmbi existed in the time of Janaka, and hence of Nichakshu. There is thus no difficulty in the way of accepting the Purāṇic statement. According to the Purāṇas the change of capital was due to the inroad of the river Ganges. Another, and a more potent, cause was perhaps the devastation of the Kuru country by *Maṭachī*. It is also possible that the attitude of the Ābbipratāriṇa branch of the royal family towards sacrificial ritual had something to do with the exodus. From this time the Kurus in the homeland appear to have gradually lost their political importance. They sank to the level of a second-rate power. But the memory of the majesty and power of the Bharata dynasty survived till the time of the *Satapatha Brāhmaṇa*.²

Pañchāla comprised the Bareilly, Budaun, Furrukhabad and the adjoining districts of Rohilkhand and the Central Doab in the modern Uttar Pradesh. It appears to have been bounded on the east by the Gumti and on the south by the Chambal. On the west lay the Yakṛillomas and the Sūrasenas of Mathurā. Belts of dense forests separated it from the Ganges and the realm of the Kurus on the north-west. Northward it approached the jungles that cover the region near the source of the Ganges.³ There is no clear trace in the Vedic literature of the Epic and *Jātaka* division of the Pañchālas into northern (*Uttara*) and southern (*Dakshina*). But it knew an eastern

¹ Kauśāmbeya may no doubt also mean "a descendant of Kuśāmba." Even then the city can hardly be dissociated from the eponymous hero of the family. Cf. Kramadīśvara, p. 791—*Kuśāmbena nireṣitā Kauśāmbi-nagarī*.

² XIII. 5. 4. 11-14; 21-23.

Mahadadya Bharatānām na pārve nāpare janāḥ

dicyam martya iva pakṣābhyām nodāpuḥ sapta mānava (iti)

³ *Rig-Veda*, V. 61. 17-19; Mbh. I. 138. 74; 150f; 166; IV. 5. 4; IX. 41.

division because the *Samhit-opanishad Brāhmaṇa* makes mention of the *Prāchya* (eastern) Pañchālas.¹ The existence of the other two may, however, be hinted at in the expression *tryanīka*, "threefold", occurring in the Vedic texts.² One of the ancient capitals of Pañchāla was Kāmpilya which has been identified with Kampil on the old Ganges between Budaun and Furrukhabad.³ Another Pañchāla town Parivakrā or Parichakrā is mentioned in the *Śatapatha Brāhmaṇa*.⁴ It is identified by Weber with Ekaachakrā of the *Mahābhārata*.⁵

The Pañchālas, as their name indicates, probably consisted of five clans—the Krivis, the Turvaśas, the Keśins, the Śrīñjayas and the Somakas.⁶ Each of these clans is known to be associated with one or more princes mentioned in the Vedic texts—the Krivis with Kravya Pañchāla, the Turvaśas or Taurvaśas with Sona Sātrāsaha, the Keśins with Keśin Dālbhya, the Śrīñjayas with Daivavāta, Prastoka, Vītahavya, Suplan or Sāhadeva Sārñjaya and Dush-tarītu, and the Somakas with Somaka Sāhadevyā. Of the kings only the first three are definitely associated with Pañchāla.

The **Krivis** appear in a *Rigvedic* hymn which also mentions the Sindhu (Indus) and the Asiknī (Chenāb). But their actual habitation is nowhere clearly indicated.

1 *Ved. Ind.*, I. 469. Cf. also Patañjali (Kielhorn's ed., Vol. I, p. 19) and Ptolemy's *Prasiake* (vii. 1. 53) which included the towns of Adisidara (? Ahiccatra) and Kanagora (? Kanauj).

2 *Vedic Index*, I. 187.

3 *Vedic Index*, I. 149; Cun. in *JASB*, 1865, 178; *AGI*, 1924, 413.

4 XIII. 5. 4. 7.

5 *Ved. Ind.*, I. 494.

6 According to the *Purāṇas* (*Brahma P.* XIII. 94 f, Cf. *Matsya*, 50. 3) 'Mudgala,' 'Śrīñjaya,' 'Bṛihadishu,' 'Yavinara' and 'Kṛimilāsya' were the constituent elements of the Pañchala Janapada.

They are identified with the Pañchālas in the *Satapatha Brāhmaṇa*¹ and connected with Parivakrā.

A *gāthā* of the same work² says, "When Sātrāsāha (King of the Pañchālas) makes the *Āśvamedha* offering, the **Taurvaśas** arise, six thousand and six (*sic*) and thirty clad in mail."

*Sātrāsāhe yajamāne' śvamedhena Taurvaśāḥ
udīrate trayastrimśāḥ śaṭsahasrāṇi varmiṇām.*

This points to a very close connexion between the Pañchālas and the Taurvaśas. The fusion of the two folks does not seem to be improbable in view of the Purāṇic statement that, after Marutta, the line of Turvaśu (Turvaśa, Taurvaśa) was merged into the Paurava line³ of which the Pañchālas are represented as an offshoot. The line of rulers to which Śona belonged seems to be connected in later times with Abhicchhatra (in the Bareilly District).⁴

The **Keśina**⁵ who are connected with the Pañchālas in Vedic literature probably dwelt on the Gumti. The **Srinjayas**⁶ are associated with the Pañchālas in post-

1 xiii, 5, 4, 7; *Kṛitaya itī ha vai purā Pañchālān āchakshate. Vedic Index*, I. 198. According to Kasten Rönnow, *Acta Orientalia*, XVI, iii, 1937, p. 165 Krivis were named after a dragon-demon who was their tribal divinity.

2 Oldenberg, *Buddha*, p. 404; *Sat. Br.* XIII. 5. 4, 16. H. K. Deb (*Vedic India and Mediterranean men*, Verlag Otto Harrassowitz, Leipzig) suggests the identification of the Turvaśas with the Teresh, or Tursha, one of the allied peoples who fought against Merneptah, or Meneptah, Pharaoh of Egypt (c. 1234-25 B.C.). Breasted, however, identifies the Teresh with the Tyrsenians or Etruscans (*A History of Egypt*, p. 467).

3 A. I. H. T., p. 108. *Turvasoḥ Pauravaṃ vaṃśaṃ pravivēṣa purā kila* (*Vāyu.* 99, 4).

4 *Camb. Hist., Ind. I.* p. 525.

5 *Ved. Ind.*, I. 186-187. The name Keśin Dālbyas suggests a close connexion between the Keśins and the Dālbyas whom the *Ṛig-Veda* (V, 61. 17-19) places on the Gomati. From *Mbh.* IX. 41. 1-3 it is clear that this Gomati connected with the Dālbya family or clan, could not have been far away from Naimisha and the country of the Pañchālas. It must, therefore, be identified with the Gumti which flows past Nimsār near Sitāpur.

6 Pargiter, *Mārkaṇḍeya Purāṇa*, p. 353; *Mbh.*, I. 138. 37; V. 48. 41. *Bṛahmapurāṇa*, XIII, 94f.

Vedic tradition. In the *Mahābhārata*,¹ Uttamañjas is called a Pañchālya as well as a Srinjaya. The clan probably lived on the Jumna in epic times.² As to the **Somakas**, their connection with the Pañchālas is known throughout the great epic.³ They occupied Kāmpilya and its neighbourhood.

The royal family of the Pañchālas is represented in bardic tradition as an offshoot of the Bharata dynasty.⁴ Divodāsa, Sudās (a) and Drupada are included among the kings of this line. Divodāsa and Sudās also figure in the *Rig-Veda* where they are closely connected with the Bharatas.⁵ But they are not mentioned as Pañchāla kings. In the *Mahābhārata* Drupada is also called Yājñasena and one of his sons is named Śikhaṇḍin.⁶ A Śikhaṇḍin Yājñasena is mentioned in the *Kaushītaki Brāhmaṇa*,⁷ but it is not clear whether we are to regard him as a prince, or as a priest of Keśin Dālbya, King of the Pañchālas.

The external history of the Pañchālas is mainly that of wars and alliances with the Kurus. The *Mahābhārata* preserves traditions of conflict between these two great peoples. We are told by the epic that Uttara-Pañchāla was wrested from the Pañchālas by the Kurus and given away to their preceptor.⁸ Curiously enough, the *Somanassa Jātaka*⁹ places Uttara-Pañchāla-nagara in Kuru raṭṭha. The relations between the two peoples (Kurus and

¹ Mbh. VIII. 11, 31; 75. 9.

² Mbh. iii. 90. 7. with commentary.

³ Cf. Mbh., I. 185. 31; 193. I; II. 77. 10: *Dhṛiṣṭa-dyumnaḥ Somakānām pravarhaḥ; Saumakir Yājñasena iti.*

⁴ Mbh., *Ādi.*, 91. 33; *Matsya*, 50. 1-16; *Vāyu*, 99. 194-210.

⁵ *Ved. Ind.*, I, p. 363; II., pp. 59. 454

⁶ Mbh., *Ādi.*, 166. 24; *Bhishma*, 190, *et seq.*

⁷ VII. 4.

⁸ Mbh. i. 166.

⁹ No. 595. The union of Kuru-Pañchālas is hinted at in *Jaim. Up. Br.* III. 7. 6.

Pañchālas) were sometimes friendly and they were connected by matrimonial alliances. Keśin Dālbyha or Dārbhya, king of the Pañchālas, was sister's son to Uchchaiśravas, king of the Kurus.¹ In the epic a Pañchāla princess is married to the Pāṇḍavas who are represented as scions of the Kuru royal family.

Of the famous kings of the Pañchālas mentioned in the Vedic literature Pravahapa Jaivali is known definitely to have been Janaka's contemporary. This prince appears in the *Upanishads* as engaged in philosophical discussions with Āruṇi, Svetaketu, Śilaka Śālāvatya, and Cbaikitāyana Dālbyha.² The first two teachers are known to have met the Vedic Janaka.

The kingdom of **Kāśi** was 300 leagues in extent.³ It had its capital at Vārāṇasī (Benares) also called Ketumati, Surundhana, Sudassana, Brahma-vaddhana, Pupphavatī, Ramna, and Molinī.⁴ The walls of the city were twelve leagues round by themselves.⁵

The Kāśis, i.e., the people of Kāśi or Kāsi, first appear in the *Paippalāda* recension of the *Atharva-Veda*.⁶ They were closely connected with the Kosalas and the Videhas. Jala Jātūkarnya is mentioned in the *Śāṅkhāyana Śrauta Sūtra*⁷ as having obtained the position of *Purohita* or priest of the three peoples of Kāśi, Videha and Kosala in the lifetime of Svetaketu, a contemporary of Janaka. Curiously enough, a king named Janaka is mentioned in the

¹ *Ved. Ind.*, I, 81, 187, 408. Uchchaiśravas occurs as the name of a Kuru prince in the dynastic list of the *Mahābhārata*, I, 94, 53.

² *Bṛhad. Up.*, VI, 2; *Chh. Up.*, I, 8, 1; V, 3, 1.

³ A stock phrase, *Dhajaviheṭha Jātaka*, No. 391.

⁴ *Dialogues*, Part III, p. 73, *Carmichael Lectures*, 1918, pp. 50-51. The name Vārāṇasī is derived from two little rivers between which the city was situated—*Varaṇāyāstathā ch Ārya madhya Vārāṇasī parī* (*Pādma, Svarga khanda*, xvii, 50).

⁵ *Tanpulanāli Jātaka*, No. 5.

⁶ *Ved. Ind.*, II, 116 n.

⁷ XVI, 29, 5.

*Sattubhastā Jātaka*¹ as reigning in Benares. This prince cannot be the Janaka of the *Upanishads*, for we learn from those works that, in the time of the famous Janaka, Ajātaśatru was on the throne of Kāsi.

Very little is known regarding the ancestors of Ajātaśatru. His name does not occur in the Purāṇic lists of Kāsi sovereigns,² nor does the name of Dhṛitarāshṭra, king of Kāsi, who was defeated by Śatānīka Sātrājita with the result that the Kāsis down to the time of the *Satapatha Brāhmaṇa* gave up the kindling of the sacred fire. A clue to the lineage of Dhṛitarāshṭra is afforded by the *Mahāgovinda-Suttanta*³ which represents "Dhataratṭha," King of Kāsi, as a Bharata prince. The *Purāṇas* represent the Kāsi family as a branch of the house of Purūravas, the traditional ancestor of the Bharatas. Of the kings mentioned in the chronicles the names of two only (Divodāsa and his son or descendant Daivādāsi Pratardana) can be traced in the Vedic literature. But the later Vedic texts connect them with the Naimishīyas and not with Kāsi.⁴

The *Jātakas* often refer to the failure of heirs at Benares (*aputtakaṃ rājakulam*), or the deposition of princes in favour of more competent rulers taken from other families. It is clear that tradition does not regard the Kāsi monarchs as belonging to one and the same dynasty. Some of the kings hailed from Magadha.⁵ Several others were probably of Videhan origin. Many of the princes belonging to these groups had the cognomen, 'Brahmadatta.' That Brahmadatta was not the name of one individual

¹ No. 402.

² *Vāyu*, 99, 21-74; *Vishṇu*, IV, 8, 2-9.

³ *Rhys Davids, Dialogues of the Buddha*, Part II, p. 270.

⁴ *Kaush. Br.* xxvi, 5.

⁵ Cf. *Jātakas*, 378, 40f, 529.

ruler, has been suggested by Mr. Hārītkṛishṇa Dev.¹ The *Matsya* and *Vāyu Purāṇas* refer to a group of one hundred (i. e. many) Brahmadattas :

*Śataṁ vai Brahmadattānāṁ
vīrāṇāṁ Kuravaḥ śataṁ.*²

The "hundred" Brahmadattas are also mentioned in the *Mahābhārata*.³ In the *Dummedha Jātaka*⁴ the name is borne both by the reigning king and his son (Kumāra).⁵ In the *Gaṅgamāla Jātaka*⁶ king Udaya of Benares is addressed by a *Pachcheka Buddha* as "Brahmadatta" which is distinctly stated to be a *kulanāma* or family designation.

The Brahmadattas were not, however, all of the same extraction. The king-elect of the *Darīmuka Jātaka* was originally a Magadhan prince. Some of the other Brahmadattas were of Videhan lineage. The *Mātiposaka Jātaka*,⁷ for instance, referring to a Brahmadatta of Kāsi, has the following line :

mutta'mhi Kāsirājena Vedhena yasassinā ti.

In the *Sambula Jātaka*⁸ prince Sotthisena, son of Brahmadatta, king of Kāsi, is called Vedhaputta :

*Yo putta Kāsirājassa Sotthiseno ti tam vidū
tassāham Sambulā bhariyā, evaṁ jānāhi dānava,
Vedhaputto bhaddan te vane vasati āturo.*

Ajātaśatru, Janaka's contemporary on the throne of Kāsi, may have been a Brahmadatta though his exact

¹ The suggestion has been accepted by Dr. D. R. Bhandarkar, *Carmichael Lectures*, 1916, p. 56.

² *Matsya*, Ch. 273, 71; *Vāyu*, Ch. 99, 454.

³ II, 8, 23.

⁴ No. 50; Vol. I, p. 126.

⁵ Cf. also the *Suzima Jātaka* (411), the *Kumma Sapinḍa Jātaka* (416), the *Atthānu Jātaka* (425), the *Lomasa Kappapa Jātaka* (433), etc.

⁶ 421.

⁷ No. 455.

⁸ No. 519.

lineage is not known. The Upanishadic evidence shows that he was a contemporary of Uddālaka. The *Uddālaka Jātaka* tells us that the reigning king of Benares in the time of Uddālaka was Brahmadaṭṭa.

Ajātaśatru appears in the *Upanishads* as engaged in philosophical discussions with Gārgya Bālāki. In the *Kaushītaki Upanishad* he is represented as being jealous of Janaka's fame as a patron of learning. The *Satapatha Brāhmaṇa*¹ mentions a person named Bhadrāsena Ajātaśatrava who is said to have been bewitched by Uddālaka Āruṇi. Macdonell and Keith call him a king of Kāśi. He may have been the son and successor of Ajātaśatru.²

The kingdom of **Kosala**³ corresponds roughly to the modern Oudh. It seems to have extended northward to the foot of the Nepāl hills. In the east it was separated from Videha by the river Sadānīrā, which was for a time the limit of the Aryan world in that direction. Beyond it was an extensive marshy region, not frequented by Brāhmaṇas which, after Māthava Videgba's occupation, developed into the flourishing kingdom of Videha. The story of Māthava makes it clear that the Kosalas fell later than the peoples dwelling on the banks of the Sarasvatī but earlier than the Videhas under the influence of Brāhmanical civilization. In the south Kosala was bounded by the river Sarpikā or Syandikā⁴ and on the west probably by the Gumtī which flowed past the famous Naimisha forest and apparently formed the boundary between the Kosalas and sundry peoples including the

¹ V. 5, 8, 14.

² S. B. E., XLII, p. 141.

³ The form Kosala is met with in the *Gopatha Brāhmaṇa* (*Vedic Index*), I, 195) and later literature.

⁴ Rām. II, 49, 11-12; 50, 1; Cf. *Sundarikā, Kindred Sayings* I, 200.

Pañchālas.¹ In the epic Kosalas proper are distinguished from the Uttara-Kosalas, the Kosalas near the Venvā (Waingāṅgā) and the Prāk-Kosalas. The last two peoples were clearly in South India.² The Pūrva-Kosalas, apparently not identical with the Prāk-Kosalas of the Deccan, dwelt between the river Sarayū and Mithilā.³

The Vedic texts do not mention any city in Kosala. But if the *Rāmāyaṇa* is to be believed the capital of Kosala (Kosalapura) in the time of the Janakas was Ayodhyā. It stood on the banks of the Sarayū and covered twelve *yojanas*.⁴ The *Ṛig-Veda* mentions the river Sarayū and refers to an Aryan settlement on its banks.⁵ One of the Ārya settlers bears the name of Chitraratha which occurs also in the *Rāmāyaṇa*,⁶ as the appellation of a contemporary of Daśaratha. A prince styled Daśaratha is eulogised in a *Ṛigvedic* hymn,⁷ but there is nothing to identify him with the Ikshvāku king of that name who appears in the *Rāmāyaṇa* as the Kosalan contemporary of Śiradhvaja Janaka. Daśaratha's eldest son, according to the epic, was Rāma who married Sītā, daughter of Janaka. The *Ṛig-Veda*⁸ mentions an *Asura* (powerful being) named Rāma but does not connect him with Kosala. The *Daśaratha Jātaka* makes Daśaratha and Rāma kings of Vārāṇasī and disavows Sītā's connection with Janaka.

¹ Rām. II. 68. 13; 71. 16-18; VII. 101. 15. (Kosalan king sacrificing in the Naimisha forest on the Guntī); cf. Mbh. XII. 355. 2; IX. 41. 3 (Pañchālas apparently not far from Naimisha). In *Rig* V. 61. 17-19, the Dāibhyas, a Pañchāla people, are placed on the Guntī.

² Mbh. II. 30. 2-3; 31. 12-13.

³ Mbh. II. 20. 28.

⁴ Rām. I. 55. 7. It is in the Fyzabad District of Oudh. For the name Kosalapura see Rām. II. 18. 38.

⁵ IV. 30. 18.

⁶ II. 32. 17.

⁷ I. 126. 4.

⁸ X. 93. 14.

Kosala was probably the fatherland of Janaka's *hotri* priest, Aśvala, who was very probably an ancestor of Āśvalāyana Kausalya¹ mentioned in the *Praśna Upanishad* as a disciple of Pippalāda and a contemporary of Sukeśā Bhāradvāja and of Hiraṇyanābha, a Kosalan prince. The details of Kosalan history will be discussed in a subsequent chapter.

¹ *Āśvalaryāpaṅgam Āśvalāyanah* (Śaṅkara's commentary on *Praśna Upanishad*, 1. 1).

SECTION III. THE LATER VAIDEHAS OF MITHILA:

NIMI AND KARALA.

The *Purāṇas* give long lists of the successors of Śirādhvaja Janaka¹ whom Bhavabhūti seems to identify with the contemporary of Yājñavalkya.² With one or two exceptions none of the kings in these lists can be satisfactorily identified with the Videhan monarchs mentioned in the Vedic, Buddhist and Jaina literature. It is, therefore, difficult to say how far the lists are reliable. The identification of any of the kings named in the bardic chronicles with the Vedic Janaka is the most knotty of all problems. We have already noted the arguments that can be urged in support of the view of Bhavabhūti. The mere fact that Śirādhvaja is placed high in the Purāṇic lists does not necessarily prove that he actually flourished long before the extinction of the dynasty. It should be remembered in this connection that Pradyota who was in reality a contemporary of Bimbisāra, king of Magadha, is placed by the Purāṇic chroniclers or scribes some nine generations before that ruler, and Siddhārtha of the Ikshvāku list, a contemporary of Prasenajit of Kosala, is represented as the grandfather of the latter. The evidence of the *Vishṇu Purāṇa*³ suggests that there were at times several collateral lines of Janakas who ruled contemporaneously. The problem of Śirādhvaja must, therefore, be regarded as *sub judice*. In view of the uncertainty about the identification of this king and his proper place in the

¹ *Vāyu*, 69. 18-23; *Vishṇu*, IV. 5. 12-13; 4th edition of this work, pp. 67 ff.

² *Mahāvira-charita*, I. verse 14; II. verse 43; *Uttara-Rama-Charita*, IV. verse 9.

³ VI. 6. 7 ff. Cf. *Rāmāyaṇa*, I. 72. 15.

dynastic list, it is not easy to determine which of the Videhan kings mentioned in the *Purāṇic* chronicles actually came *after* the contemporary of Āruṇi and Yājñavalkya. The evidence of the *Jātakas*, however, suggests that a king named Nimi, at any rate, ruled after the great Janaka, as he is called the penultimate sovereign of the dynasty. Pargiter¹ places all the kings of the *Purāṇic* lists down to Bahulāśva *before* the Bhārata war, and apparently identifies his son Kṛiti with Kṛitakshaṇa of the *Mahābhārata*,² a contemporary of Yudhisṭhira. But as there were "Janakas," even *after* Yudhisṭhira, and as two *Purāṇas* conclude with the remark that with Kṛiti *ends* the race of the Janakas,"³ the identification of Kṛiti, the *last* of the race, with Kṛitakshaṇa does not seem to be plausible. It is more reasonable to identify Kṛiti of the *Purāṇas* with Karāla Janaka who, as we shall see below, brought the line of Vaideha kings to an end. The only objection to this view is that Karāla is represented as the son of Nimi, whereas Kṛiti was the son of Bahulāśva. But the cognomen Nimi may have been borne by several kings and Bahulāśva may have been one of them. An alternative theory would be to represent Kṛiti and Karāla as the last members of two collateral lines of Janakas.

The Vedic texts mention besides Māthava and Janaka two other Vaideha kings, namely, Namī Sāpya and Para Ahlāra. Macdonell and Keith identify the latter with Para Āṇāra, king of Kosala, about whom we shall speak in a subsequent chapter. Namī Sāpya is mentioned in the *Pañchaviṃśa* or *Tāṇḍya Brāhmaṇa*⁴ as a famous sacrificer. His identification with king Namī of the *Uttar-ādhyayana*

¹ AHT, p. 149.

² AHT, pp. 96, 330.

³ II. 4. 27.

⁴ XXV. 10. 17-18.

*Sūtra*¹ Nemi of the *Viṣṇu Purāṇa*, and Nimi of the *Makhādeva Sutta* of the *Majjhima Nikāya*, and the *Kumbhakāra*² and *Nimi Jātaka*³ is more or less problematical. In the last-mentioned work it is stated that a Nimi was the penultimate sovereign of the Maithila family. According to the *Kumbhakāra Jātaka* and the *Uttar-ādhyayana Sūtra* he was a contemporary of Dummukha (Dvimukha), king of Pañchāla, Naggaji (Naggati) of Gandhāra and of Karaṇḍu (Karakaṇḍu) of Kalinga. This synchronism accords with Vedic evidence. Durmukha, the Pañchāla king, had a priest named Bṛihaduktha⁴ who was the son of Vāmadeva.⁵ Vāmadeva was a contemporary of Somaka, the son of Sahadeva.⁶ Somaka had close spiritual relationship with Bhīma, king of Vidarbha, and Nagnajit, king of Gandhāra.⁷ From this it seems very probable that Durmukha was a contemporary of Nagnajit. This is exactly what we find in the *Kumbhakāra Jātaka* and the *Uttar-ādhyayana Sūtra*.

The *Nimi Jātaka* says that Nimi was "born to round off" the royal family "like the hoop of a chariot wheel." Addressing his predecessor the soothsayers said, "Great king, this prince is born to round off your family. This your family of hermits will go no further."

Nimi's son Kalāra Janaka⁸ is said to have actually brought his line to an end. This king is apparently identical with Karāla Janaka of the *Mahābhārata*.⁹ In the *Arthaśāstra* attributed to Kauṭilya it is stated that "Bhoja,

¹ S.B.E., XLV. 87.

² No. 408.

³ No. 541.

⁴ *Vedic Index*, I. 370

⁵ *Ibid.*, II. 71.

⁶ *Rig-Veda*, IV. 15, 7-10 with *Anukramoṇi*.

⁷ *Aitareya Brāhmaṇa*, VII 34.

⁸ *Makhādeva Sutta* of the *Majjhima Nikāya*. II. 82; *Nimi Jātaka*.

⁹ XII. 302. 7.

LATER VAIDEHAS

known by the name of Dāṇḍakya, making a lascivious attempt on a Brāhmaṇa maiden, perished along with his kingdom and relations; so also Karāla, the Vaideha."¹ Karāla, the Vaideha, who perished along with his kingdom and relations, must be identified with Kalāra (Karāla) who, according to the *Nimi Jātaka*, brought the line of Videhan kings to an end. The downfall of the Vaidehas reminds us of the fate of the Tarquins who were expelled from Rome for a similar crime. As in Rome, so in Videha, the overthrow of the monarchy was followed by the rise of a republic—the Vajjian Confederacy.

There is reason to believe that the Kāsi people had a share in the overthrow of the Videhan monarchy. Already in the time of the great Janaka, Ajātaśatru, king of Kāsi, could hardly conceal his jealousy of the Videhan king's fame. The passage "*yathā Kāśyo vā Vaideho vā Ugraputra ujyāṃ dhanur adhiyaṃ kṛtvā drau vāṇavantau sapatnatieyādhinau haste kṛite-opatishṭhed*"² probably refers to frequent struggles between the heroes of Kāsi and Videha. The *Mahābhārata*³ refers to the old story (*itihāsam purāṭanam*) of a great battle between Prataardana, king of Kāsi according to the *Rāmāyana*,⁴ and Janaka, King of Mithilā. It is stated in the Pāli commentary *Param-attha-jōtikā*⁵ that the Lichchhavis who succeeded Janaka's dynasty as the strongest political power in North

¹ The evidence of the *Arthashastra* is confirmed by that of the *Buddha-charita* of Aśvaghoṣa (IV. 80). "And so Karāla Janaka, when he carried off the Brāhmaṇa's daughter, incurred loss of caste thereby, but he would not give up his love."

² *Bṛihad Upanishad*, III. 8. 2. "As the Ugra's son from Kāsi or from Videha strings the slackened bow and arises with two foe-piercing arrows in his hand" (Winternitz, *Ind. Lit.* translation I, 229 with slight emendations).

³ XII. 99. 1-2.

⁴ VII. 48. 15.

⁵ Vol. I, pp. 158-165.

Bihar, and formed the most important element of the Vajjian Confederacy, were the offsprings of a queen of Kāsi. This indicates a belief in later ages that cadets from the royal family of Kāsi established themselves in Videha.

SECTION IV. THE DECCAN IN THE AGE OF THE
LATER VAIDEHAS

The expression "*Dakshināpadā*" occurs in the *Rig-Veda*¹ and refers to the region where the exile goes on being turned out. In the opinion of several scholars this simply means "the south" beyond the limits of the recognised Aryan world. *Dākshinātya* is found in Pāṇini,² *Dakshināpatha* is mentioned by Baudhāyana coupled with *Surāshṭra*.³ It is difficult to say what Pāṇini or Baudhāyana exactly meant by *Dākshinātya* or *Dakshināpatha*. In early Pāli literature the name *Dakshināpatha* is sometimes coupled with Avanti (Malwa), and in one text it is placed on the banks of the upper Godāvarī. In the *Nalopākhyāna* of the *Mahābhārata*, *Dakshināpatha* is placed beyond Avanti and the Vindhya, and to the south of the Vidarbhas and the (Southern) Kosalas. The last-mentioned peoples lived on the banks of the Wardhā and the Mahanadī. In the *Digvijaya-parva*, *Dakshināpatha* is distinguished from the Pāṇḍyan realm in the southernmost part of the Madras Presidency. In the Gupta Age it certainly stretched from the land of the Kosalas to the kingdom of Kāñchī. In later times it embraced the whole of Trans-Vindhyan India from the *Setu* (Adam's Bridge) to the Narmadā.⁴

Whatever may have been the exact denotation of the terms discussed above in the earliest times it is certain that already in the age of the later Vaidehas, Nimi and Karāla,

¹ X. 61. 8, *Vedic Index*, I. 337.

² IV. 2. 98.

³ *Baudh. Sūtra*, I. 1. 29.

⁴ DPPN, I. 1050; Mbb. II. 31. 10-17; III. 61. 21-23. Allahabad Pillar Inscription of Samudra Gupta; Fleet, *Dynasties of the Kanarese Districts*, 341 n. The *Periplus* distinguishes *Dachinabades* (*Dakshināpatha*) from *Damirica* (Tamil land).

the Aryans had crossed the Vindhya and established several kingdoms in the territory that stretched from the Revā or the Narmadā to the Godāvarī. One of these realms was **Vidarbha**. It comprised modern Bérar, the Varadātata of the *Āin-i-Ākbarī*, and a considerable portion of the Central Provinces lying between the Wardhā (Varadā) and the Waingangā. In the north it reached the Payoshnī, a tributary of the Tāptī.¹ Vidarbha was certainly a famous kingdom in the time of Nimi. We have already seen that the *Kumbhakāra Jātaka* and the *Uttar-ādhyayana* make him a contemporary of Nagnajit, king of Gandhāra, who is known from the *Aitareya Brāhmaṇa*² to have flourished about the same time as Bhīma, king of Vidarbha :

“*Etamu haiva prochatuḥ Parvata-Nāradau Somakāya Sahadevyāya Sahadevāya Sārñjayāya Babhrave Daivāvṛidhāya Bhīmāya Vaidarbhāya Nagnajite Gāndhārāya.*”

“This Parvata and Nārada proclaimed to Somaka Sāhadevya, Sahadeva Sārñjaya, Babhru Daivāvṛidha, Bhīma Vaidarbha (i.e. of Vidarbha) and Nagnajit of Gandhāra.”

Vidarbha, therefore, existed as an independent kingdom in the time of Nimi. From the Purāṇic account of the Yadu family it appears that the eponymous hero of the Vidarbhas, was of Yadu lineage.³ The country is mentioned in the *Jaiminīya Brāhmaṇa*.⁴ It was famous for its *Māchalas*, perhaps a species of dog, which killed tigers⁵—“*Vidarbheṣu mācalās sārameyā apīha śārdulān mārāyanti.*”⁶ The *Praśna Upanishad*⁶ mentions a sage of

¹ Mbh. III. 61. 23-23 : 120. 31.

² VII. 34.

³ *Matsya Purāṇa*, 44. 36; *Vāyu Purāṇa*, 95. 35-36.

⁴ II. 449 : *Ved. Ind.*, II. 297.

⁵ *JAOS*, 19, 100.

⁶ I. 1; II. 1.

Vidarbha named Bhārgava as a contemporary of Āśvalāyana. Another sage called Vidarbhbī Kaunḍinya is mentioned in the *Bṛihadāraṇyaka Upanishad*.¹ The name Kaunḍinya is apparently derived from the city of Kuṇḍina, the capital of Vidarbha,² represented by the modern Kaunḍinya-pura on the banks of Wardhā in the Chāṇḍur tāluk of Amraoti.³ The association of Vidarbha with Kuṇḍina clearly suggests that Vidarbha of the Vedic texts lay in the Deccan, and not in some hitherto unknown region outside its boundaries as contended by a wellknown writer.⁴

If the evidence of the *Kumbhakāra Jātaka* has any value, then Nimi, king of Videha, mentioned in the work, Nagnajit, king of Gandhāra, and Bhīma, king of Vidarbha, must be considered to have been contemporaries of Karaṇḍu of Kaliṅga. It follows from this that the kingdom of **Kaliṅga**, too, was in existence in the time of Nimi and his contemporaries of the *Brāhmaṇa* period. The evidence of the *Jātaka* is confirmed by that of the *Uttar-ādhyayana Sūtra*. The *Mahāgorinda Suttanta*,⁵ makes Sattabhu, king of Kaliṅga, a contemporary of Reṇu, king of Mithila and of Dhataraiṭṭha or Dhritarāshṭra, king of Kāsi, mentioned in the *Satapatha Brāhmaṇa*.⁶ There can thus be no doubt that Kaliṅga existed as an independent

¹ *Vedic Index*, II. 297.

² *Mbb.*, III. 73, 1-2; V. 157. 14; *Harivaṃśa*, *Viṣṇuparva*, 59-60.

³ *Gaz.*, *Amraoti*. Vol. A, p. 406.

⁴ *Indian Culture*, July, 1926, p. 12. Curiously enough, the same writer, who characterises the provisional acceptance of the uncontradicted testimony of the *Purāṇas* and lexicons in locating tribes mentioned in Vedic literature as unhistorical, has no hesitation in identifying the Satvats of the *Aitareya Brāhmaṇa* with the Yādavas and in placing them in the Mathurā region and adjoining districts (*ibid.*, 15). He has not referred to any Vedic text which supports his conjecture regarding the identity of the Satavats and their association with the particular city named by him.

⁵ *Dialogues of the Buddha*, II. 370.

⁶ XIII. 5. 4. 29.

kingdom in the time of which the Brāhmaṇas speak. It is mentioned both by Pāṇini¹ and Baudhāyana.² The latter regards it as an impure country but evidently not unfrequented by Aryans.³ According to epic tradition it comprised the whole coast from the river Vaitaraṇī⁴ in Orissa to the borders of the Andhra territory. The southern boundary of the *Janapada* was not well-defined. It reached Yellamanchili and Chipurupalle in the Vizagapatam district and at times even Pishṭapura or Pitbapuram, north-east of the Godāvarī, but not the river itself which flowed through the Andhra country. Pargiter says that Kalinga as a settled kingdom appears to have consisted properly of the plain between the Eastern Ghats (*Mahendra* range) and the sea. But its kings seem to have exercised suzerainty over the Jungle tribes which inhabited the hills far inland, for the Amarakaṇṭaka range, in which the Narmadā rises, is said to be in the western part of Kalinga. That large tracts of the country were covered with forests appears from references to *Kaliṅgā-vaṇya* in Pāli texts. The windows of the capital city in the days of Kālidāsa looked out on the sea, and the deep roar of the waves drowned the sound of trumpets.⁵ In the days of Yuan Chwang Kalinga occupied a much smaller area. It is distinguished from Wu-t'u (Orissa) and Kung-yü-t'o (Kongoda in the Ganjam district) in the north, and An-to-lo (Andhra or Veṅgi) in the south, and seems to have embraced parts of the Ganjam and Vizagapatam districts. We learn from the Jātakas that an

¹ IV. I. 170.

² I. i. 30-31.

³ There was a considerable Brāhmaṇa population in Kalinga in the days of Aśoka (cf. Edict XIII).

⁴ Mbh., III. 114, 4.

⁵ Ind. Ant., 1923, 67; Ep. Ind., XL. 2; JASB, 1897, 98 ff; Kārma, P. II. 39, 9; Pādma, Svarga-Khaṇḍa, VI. 22; Vāyu, 77, 4-13; Malalasekera, DPPN, 584; Baghurahia, vi, 56.

ancient capital of Kaliṅga was Dantapura-nagara.¹ The *Mahābhārata* mentions Rājapura as the metropolis.² The *Mahāvastu*³ refers to another city named Sindhapura. The Jaina writers mention a fourth town called Kaih-chaṇapura⁴

The *Mahāgovinda Suttanta* refers to another southern realm, namely, **Assaka** or **Aśmaka** on the God(h)āvari,⁵ which existed in the time of the monarchs Reṇu and Dhata-ratṭha (Dhṛita-rāshṭra). It was ruled by king Brahmadatta who held his Court at Potana.

The *Aitareya Brāhmaṇa* alludes⁶ to princes of the South who are called **Bhojas** and whose subjects are called

¹ Cf. *Ep. Ind.*; XIV, p. 361. *Danta-pura-vāṇakāt*; Dantakūra, *Mbh.* V. 48 76. Daodagula (Pliny. M'Grindle, *Megasthenes and Arrian*, 1926, p. 144). The name of the city probably survives in that of the fort of Dantavakra near Chicacole in the Gañjam district. Many other Kaliṅga capitals stood in the same district, e. g., Sindhapura (Singupuram) near Chicacole, Dabreuil, *A. H. D.*, p. 94. Kaliṅga-nagara (Mukhaliṅgam on the Vaitṣadharā, *Ep. Ind.*, IV. 187; Kaliṅga-pātana is preferred in *Ind. Ant.*, 1887, 132; JBORS. 1929, pp. 623 f. But the arguments adduced are not all plausible).

² XII. 4. 3.

³ Smart's edition, p. 432.

⁴ *Ind. Ant.*, 1891, p. 875. The *Bhūmikhaṇḍa* of the *Padmapurāṇa* (47.9) mentions Śrīpura as a city in Kaliṅga.

⁵ *Sutta Nipāta*, 977, SBE, X, pt. ii, 184 Cf. Asmāgi (*Bomb. Gaz.* I. 1. p. 532; *Megasthenes and Arrian*, 1926, 145) of classical writers. Aśmaka is also mentioned by Pāṇini, IV. 1. 173. As the name signifies "the stony region", it can hardly refer to Aśvaka, the land of the Assakenoi in the north-west, which the *Cambridge History of India*, Vol. I, connects with the Sanskrit *aśva*, and Iranian *aspa*, horse. The Commentator Bhaṭṭasvāmin identifies Aśmaka with Mahārāshṭra. The capital was Potali or Potana (*Chullakālīṅga Jātaka* No. 301; *Assaka J.* (207); D. 2. 235; *Parisishṭa paracan*, I. 93. *nagara Potanāśbhidhe*, *Bomb. Gaz.* I. 1. 535; *Laws, Heaven and Hell in Buddhist Perspective*, 74; *Mbh.* I. 177. 47; cf. Pāṇana of Lüders' List, 616, and N. G. Majumder's List, 658 (*Monuments*, p. 305—*Vidhkhana Padā(n)ya*). Dr. Saktibankar points out that the Pandanya of the printed editions of the *Mahābhārata* is a late corruption. The older Mss. give the name as Potana or Podana. This name reminds one of Bodhan in the Nizam's dominions which lies to the south of the confluence of the Manjirā and the Godāvari. The city of Podana is said to have been founded by a prince of the Ikshvāku family, who is the eponymous hero of the land of Aśmaka. The neighbouring people of Mālaka also claimed Ikshvāku descent (*Vāyu*, 88, 177-178).

⁶ VIII. 14

Satvats: "dakṣiṇasyām diśi ye ke cha Satvatām rājāno Bhaṁjyāyaiva le'bhishichyante Bhoj-etye-nān-abhishiktān-āchakshata—" "in the southern region whatever kings there are of the Satvats, they are anointed for *Bhaṁjya*; 'O Bhoja' they style them when consecrated (in accordance with the action of the deities)." In the *Satapatha Brāhmaṇa*¹ the defeat by Bharata of the Satvats, and his taking away the horse which they had prepared for an *Aśvamedha* or horse-sacrifice are referred to. These Satvats must have been living near Bharata's realm, i.e., near the Ganges and the Yamunā.² But in the time of the *Aitareya Brāhmaṇa* they probably moved farther to the south. They are placed in the southern region (*dakṣiṇā diś*) beyond the "fixed middle region"—the land of the Kurus, Pāñchālas and some neighbouring tribes. The Pāñchāla realm, according to epic testimony, extended as far south as the Chambal.³ The Satvat people of the "southern region" mentioned in the *Aitareya Brāhmaṇa*, therefore, in all probability, lived beyond that river. Their kings were called Bhojas. This account of the Satvats and the Bhojas, deduced from the Brāhmaṇic statements, accords with Purāṇic evidence. It is stated in the *Purāṇas* that the Sātvat(a)s and the Bhojas were offshoots of the Yadu family which dwelt at Mathurā on the banks of the Yamunā.⁴ We are further told by the same authorities that they were the kindreds of the southern realm of Vidarbha.⁵ We have evidence of a closer connection between the Bhojas and the last-mentioned territory. A place called Bhojakaṭa, is included

¹ XIII, 5, 4, 21.

² *Ibid*, XIII, 5, 4, 11.

³ Mbh., I, 133, 74; *Dakṣiṇādiśāpi Pāñchālan yātrach Charamavati nadī*.

⁴ *Matsya*, 43, 48; 44, 46-48; *Vāyu*, 94, 52; 95, 18; 96, 1-2; *Vishṇu* IV 18, 1-6.

⁵ *Mat.*, 44, 36; *Vāyu*, 95, 35-36.

within Vidarbha both by the *Mahābhārata*¹ and the *Harivaṃśa*.² The Chammak grant of the Vākāṭaka king Pravarasena II makes it clear that the Bhojakāṭa territory included the Ilichpur district in Berar, a part of ancient Vidarbha.³ As pointed out by Dr. Smith, the name of Bhojakāṭa, 'castle of the Bhojas,' implies that the province was named after a stronghold formerly held by the Bhojas, an ancient ruling race mentioned in the edicts of Aśoka.⁴ Kālidāsa in his *Raghuvamśa*⁵ calls the king of Vidarbha a Bhoja.⁶

But Vidarbha was not the only Bhoja state. The *Āitareya Brāhmaṇa* refers to several Bhoja kings of the south. A line of Bhojas must have ruled **Daṇḍaka**. A passage in the *Kauṭīliya Arthaśāstra*⁷ runs thus :—

"*Dāṇḍakyo nāma Bhojaḥ kāmāt Brāhmaṇa-kanyām abhimanyamānas sabandhu-rāshṭro vinanāśa*"—a Bhoja known as Dāṇḍakya, or king of Daṇḍaka, making a lascivious attempt on a Brāhmaṇa girl, perished along with his relations and kingdom. We learn from the *Sarabhaṅga Jātaka*⁸ that the kingdom of Daṇḍaki (Daṇḍaka) had its capital at Kumbhavatī. According to the *Rāmāyaṇa*⁹ the name of the metropolis was Madhumanta, while the *Mahāvastu*¹⁰ places it at Govardhana (Nāsik).

It is clear, from what has been stated above, that there were in the age of the later Vaidehas, and the treatises called Brāhmaṇas, many kingdoms in the south, both

¹ V. 187. 15-16.

² *Viṣṇu purāṇa*, 60. 32.

³ *JRAS.*, 1914, p. 329.

⁴ In *Ind. Ant.*, 1923, 262-63, Bhojakāṭa is identified with Bhat-kuli in the Amraoti district.

⁵ V. 30-40.

⁶ Cf. also *Mbh.*, V. 43. 74; 157. 17; *Harivaṃśa*, *Viṣṇu purāṇa*, 47. 5.

⁷ Ed. 1919, p. 11.

⁸ No. 522.

⁹ VII. 92. 18.

¹⁰ Senart's Edition, p. 363.

Aryan and non-Aryan, namely, the Bhoja kingdoms, one of which was Vidarbha, and another, probably, Daṇḍaka, as well as Aśmaka and Kalinga. With the exception of these organised states the whole of Trans-Vindhyan India was occupied by non-Aryan (*dasyu*) tribes such as the Andhras, Savaras, Pulindas and probably also the Mūtibas.¹

In the opinion of Dr. Smith the **Andhras** were a Dravidian people, now represented by the large population speaking the Telugu language, who occupied the deltas of the Godāvarī and the Kṛishṇā. Mr. P. T. Śrīnivās Iyengar argues that the Andhras were originally a Vindhyan tribe and that the extension of Andhra power was from the west to the east down the Godāvarī and Kṛishṇā valleys.² Dr. Bhandarkar points out that the Śerivāṇij Jātaka places Andhapura, *i.e.*, the *pura* or capital of the Andhras, on the river Telavāha which he identifies with the modern Tel or Telingiri.³ But if 'Seri' or *Śrī-rājya*⁴ refers to the Gaṅga kingdom of Mysore, Telavāha may have been another name of the Tuṅgabhadra-Kṛishṇā, and Andhapura identical with Bezvāḍa or some neighbouring city.⁵ The Mayidavolu plates of the early Pallava ruler Śiva-skanda-varman prove that the Andhra country (*Andhrāpatha*) embraced the lower valley of the Kṛishṇā and had its centre at Dhañṇakaḍa *i.e.*, Bezvāḍa, or some neighbouring city on the south bank of the

¹ *Art. Br.*, VII. 18.

² *Ind. Ant.*, 1913, pp. 276-78.

³ *Ind. Ant.*, 1918' p. 71. There is also a river called 'Ter' in 'South India, Ep. Ind., XXII. 29.

⁴ *Mysore and Coorg from Inscriptions*, 38. 'Seri' may also refer to Śrī Vijaya or Śrī Vishaya (Sumatra?).

⁵ The name Telavāha, oil-carrier, reminds one of the passages "*Vikhyāta Kṛishṇā-ternā (=Kṛishṇā) taila-snehopalabdha saralata*" (IA, VIII. 17, cf. Ep. XII. 163.)—"with a smoothness caused by sesame oil of the famous (river) Kṛishṇā."

Krishṇā.¹ Yuan Chwang applies the name An-to-lo (Andhra) to the district round Ping-ki-lo (Venṅipura) near Ellore. In later times the *Andhra-Khaṇḍa* extended from the Godāvari to the borders of Kalinga (*ārabhya Gautamanadītaṭam ākalingam*) and included Piṭhāpurī (Pithapuram).²

The *Śavaras* and the *Pulindas* are described in the *Matsya* and the *Vāyu Purāṇas* as *Dakṣiṇā-patha-vāsinah*, inhabitants of the Deccan, together with the *Vaidarbhas* and the *Daṇḍakas* :

Teshām pare janapadā Dakṣiṇā-patha-vāsinah.

* * * *

*Kārūshāścha saha-Ishikā Āṭavyāḥ Śavarās tathā
Pulindā Vindhya-Pushikā (?) Vaidarbhā Daṇḍakaiḥ saha.³
Ābhīrāḥ saha cha-Ishikāḥ Āṭavyāḥ Śavarāscha ye
Pulindā Vindhya-Mūlikā Vaidarbhā Daṇḍakaiḥ saha.⁴*

The *Mahābhārata* also places the Andhras, Pulindas and *Śavaras* in the Deccan :

*Dakṣiṇā-patha-janmānaḥ sarve naravar-Āndhrakāḥ
Guhāḥ Pulindāḥ Śavarās Chuchukā Madrakaiḥ (?) saha⁵*

The precise position and extent of the country of the *Śavaras* in the *Brāhmaṇa* period cannot be shown. They are usually identified with the *Suari* of Pliny and the *Sabarae* of Ptolemy, and are probably represented by the

¹ Hultzsch (Ep. Ind. VI. 85) identified the city with Amarāvati. Burgess suggested Dharanikoṭa which lies about 15 miles to the westward from Bezvāḍa, on the right bank of the Krishṇā. Fergusson, Sewell and Watters prefer Bezvāḍa itself (Yuan Chwang, II. 216). In the days of the great Chinese pilgrim An-to-lo (Andhra) had its capital at Ping-ki-lo or Venṅipura in the Krishṇā district.

² Watters : II. 2091 IA, xx, 93; Ep. Ind., IV, 357.

³ Matsya, 114. 46-48.

⁴ Vāyu, 45. 126.

⁵ Mbh., XII. 207. 42.

Savaralu, or Sauras of the Vizagapatam Hills, and the Savaris of the Gwalior territory.¹

The capital of the **Pulindas** (Pulinda-nagara) probably lay to the south-east of the Daśārṇas² who dwelt on the river Dasān (Dhasan) in Bundelkhand.³

The location of the territory of the **Mūtibas**, another *Dasyu* tribe mentioned in the *Āitareya Brāhmaṇa* along with the Andhras, Pulindas, and Savaras, is not so certain. Pliny refers to a tribe called "Modubae," and places them along with other peoples between the "Modogalingae," who inhabited a very large island in the Ganges and the *Andaræ* (Andhras).⁴ The Modubae are associated with the Molindae and the Uberae, perhaps corresponding to the Pulindas and the Savaras of the *Āitareya Brāhmaṇa*. In the *Sāṅkhāyana Śrauta Sūtra*⁵ the Mūtibas are called Mūvīpa or Mūchīpa. It is not altogether improbable that the last name is connected with that of the river Musi in the Deccan on which Hyderabad now stands.⁶

¹ *Ind. Ant.*, 1879, p. 262; Conn. *AGI*, new ed., pp. 583, 586; *The Imp. Gaz. The Indian Empire*, I, 384. Savaras are also found in the south-east portion of the district of Raipur (*JASB*, 1890, 289), in Sambalpur and Ganjam (*ibid.*, 1891, 33), the western part of the Cuttack district as well as the north-western portion of Vizagapatam (*ibid.*, 1897, 321).


² *Mbh.*, II, 5-10.

³ *JASB*, 1896, 253; Kalidāsa places them in the Viditā or Bhilsa region (*Meghadūta*, 24-25).

⁴ M' Crindle, *Megasthenes and Arrian*, 1926, p. 139-140.

⁵ XV, 26, 6.

⁶ cf. Mūshikāsa, Pargiter, *Mārkaṇḍeya Purāṇa*, p. 366.





CHAPTER III. MAHĀJANAPADAS AND KINGSHIP

SECTION I. THE SIXTEEN MAHĀJANAPADAS.

The Vedic texts do not throw much light on the political condition of the period which elapsed from the fall of the Videhan monarchy, probably early in the sixth century B.C., to the rise of Kosala under Mahākosala, the father-in-law of Bimbisāra, about the middle of that century. But we learn from the Buddhist *Āṅguttara Nikāya* that during this period there were sixteen states of considerable extent and power known as the "*Solasa Mahājanapada*."¹ These states were :—

- | | |
|--------------------|-----------------------|
| 1. Kāsi (Kāśi) | 9. Kuru |
| 2. Kosala (Kośala) | 10. Pañchāla |
| 3. Aṅga | 11. Machchha (Matsya) |
| 4. Magadha | 12. Sūrasena |
| 5. Vajji (Vṛjji) | 13. Assaka (Aśmaka) |
| 6. Malla | 14. Avanti |
| 7. Chetiya (Chedi) | 15. Gandhāra |
| 8. Vamśa (Vatsa) | 16. Kamboja |

These *Mahājanapadas* flourished together during a period posterior to Karāla-Janaka but anterior to Mahākosala, because one of them, Vajji, apparently rose to power after the fall of the Videhan monarchy, while another, namely, Kāsi, lost its independence before the time of Mahākosala and formed an integral part of the Kosalan empire in the latter half of the sixth century B.C.

The Jaina *Bhagavatī Sūtra*² gives a slightly different list of the sixteen *Mahājanapadas* :

¹ P. T. S. I., 213; IV, 252, 256, 260. The *Mahāvastu* (I. 34) gives a similar list, but omits Gandhāra and Kamboja, substituting in their place Śibi and Daśārṇa in the Punjab (or Rājputāna) and Central India respectively. A less complete list is found in the *Jana-vasabha-suttanta*.

² *Saya xv Uddessa I* (Hoernle, the *Uvāsagadasāo*, II Appendix); W. Kiefel, *Die Kosmographie Der Inder*, 225.

- | | |
|--------------------------|--------------------------------|
| 1. Aṅga | 9. Pāḍha (Pāḍya or Paṇḍra) |
| 2. Baṅga (Vaṅga) | 10. Lāḍha (Lāṭa or Rāḍha) |
| 3. Magaha (Magadha) | 11. Bājji (Vājji) |
| 4. Malaya | 12. Moli (Malla) |
| 5. Mālava (ka) | 13. Kāsi (Kāśi) |
| 6. Achehha | 14. Kosala |
| 7. Vachehha (Vatsa) | 15. Avāha |
| 8. Kochehha (Kachehha ?) | 16. Sambhuttara (Sumhottara ?) |

It will be seen that Aṅga, Magadha, Vatsa, Vājji, Kāsi, and Kosala are common to both the lists. Mālava of the *Bhagavatī* is probably identical with Avanti of the *Aṅguttara*. Moli is probably a corruption of Malla. The other states mentioned in the *Bhagavatī* are new, and indicate a knowledge of the far east and the far south of India. The more extended horizon of the *Bhagavatī* clearly proves that its list is later than the one given in the Buddhist *Aṅguttara*.¹ We shall, therefore, accept the Buddhist list as a correct representation of the political condition of India after the fall of the House of Janaka.

Of the sixteen *Mahājanapadas* Kāśi was probably at first the most powerful. We have already seen that Kāśi probably played a prominent part in the subversion of the Videhan monarchy. Several *Jātakas* bear witness to the superiority of its capital Benares over the other cities, and the imperial ambition of its rulers. The *Guttila Jātaka*² says that the city of Benares is the chief city in all India. It extended over twelve leagues³ whereas

¹ Mr. E. J. Thomas suggests (*History of Buddhist Thought*, p. 6) that the Jaina author who makes no mention of the northern Kambojas and Gandhāras but includes several south Indian peoples in his list, "wrote in South India and compiled his list from countries that he knew." If the writer was really ignorant of the northern peoples his Mālavas could not have been in the Peshāb and must be located in Central India. In that case his account can hardly be assigned to a very early date.

² No. 243.

³ "Deśāssa-gejanikham sakala-Bārāṇasī-nagaram" —*Sombhava Jātaka* No. 115; *Sarabha-miga J.*, 483; *Bhāridatta J.*, 545.

Mithilā and Indapatta were each only seven leagues in extent.¹ Several Kāsi monarchs are described as aspirants for the dignity of the chief king of all kings (*sabbarājūnam aggarājā*), and lord of the whole of India (*sakala-Jambudīpa*).² The *Mahāvagga* also mentions the fact that Kāsi was in former times a great and prosperous realm, possessed of immense resources :

“*Bhūtapubbaṃ bhikkhave Bārāṇasīyam Brahmaddatto nāma Kāsirājā ahosi addhō mahaddhano mahābhogo mahadbalo mahāvāhano mahāvijito paripuṇṇakosa-kotṭhā-gāro.*”³

The Jains also afford testimony to the greatness of Kāsi, and represent Aśvasena, king of Benares, as the father of their *Tirthaṅkara* Pārśva who is said to have died 250 years before Mahāvīra, i.e., in or about 777 B.C.

Already in the *Brāhmaṇa* period a king of Kāsi, named Dhṛitarāshṭra, attempted to offer a horse-sacrifice, but was vanquished by Śatānīka Sātrājita with the result that the Kāsis down to the time of the *Śatapatha Brāhmaṇa*, gave up the kindling of the sacred fire.⁴ Some of the other Kāsi monarchs were more fortunate. Thus in the *Brahmachatta Jātaka*⁵ a king of Benares is said to have gone against the king of Kosala with a large army. He entered the city of Sāvattihī and took the king prisoner. The *Kosāmbī Jātaka*,⁶ the *Kunāla Jātaka*,⁷ and the *Mahāvagga*⁸ refer to the annexation of the kingdom of Kosala

¹ *Suruchi*, J., 489; *Vidhurapandita J.*, 545.

² *Dhaddasūla Jātaka*, 465; *Dhonasākhā Jātaka*, 853.

³ *Mahāvagga*, X, 2, 3; *Finaya Piṭakam*, I, 319.

⁴ *Śat. Br.*, XIII. 5. 1, 19.

⁵ No. 396.

⁶ No. 428.

⁷ No. 596.

⁸ S. B. E., Vol. XIII, pp. 294-99.

by the Brahmādattas of Kāsi.¹ The *Assaka Jātaka*² refers to the city of Potali, the capital of Assaka on the Godāvarī, as a city of the kingdom of Kāsi. Evidently the reigning prince of Potali was a vassal of the sovereign of Kāsi. In the *Sona-Nanda Jātaka*³ Manoja, king of Benares, is said to have subdued the kings of Kosala, Aṅga and Magadha. In the *Mahābhārata*⁴ Pratardana, king of Kāsi, is said to have crushed the power of the Vitabavyas or Haihāyas.⁵ In the absence of corroborative evidence it is difficult to say how far the account of the achievements of individual kings, mentioned in the *Jātakas* and the epic, is authentic. But the combined testimony of many *Jātakas* and the *Mahāvagga* clearly proves that Kāsi was at one time a great, almost an imperial power, stronger than many of its neighbours including Kosala.

We learn from the *Bhojājāniya Jātaka*⁶ that "all the kings round coveted the kingdom of Benares."⁷ We are told that on one occasion seven kings encompassed Benares.⁷ Benares in this respect resembled ancient Babylon and mediæval Rome, being the coveted prize of its more warlike but less civilized neighbours.

¹ The reference in the *Mahābhārata* (I. 105. 47. ff; 106. 2, 13; 113. 43; 114. 3f; 126. 16; 127. 24) to Kāsi princesses, the mothers of Dhṛitarāshṭra and Pāṇḍu, as Kausalyā, possibly points to the traditional union of the two realms of Kāsi and Kosala in the period when part of the epic was compiled. The expression Kāsi-Kausalya already occurs in the *Gopatha Brāhmaṇa* (*Vedic Index*. I. 195).

² No. 207.

³ No. 532.

⁴ XIII. 30.

⁵ Dr. Bhandarkar points out that several Kāsi monarchs, who figure in the *Jātakas*, are also mentioned in the *Purāṇas*, e. g., Viśvasena of *Jātaka* No. 263, Udaya of *Jātaka* No. 458, and Bhallāṭiya of *Jātaka* No. 504 are mentioned in the *Purāṇas* as Viśhvaksena, Udayasena and Bhallāṭa. *Matsya*, 49. 57 *et seq.* *Vāyu*. 99. 180 *et seq.*; *Vishṇu*, IV. 19. 13.

⁶ No. 23.

⁷ *Jātaka*, 181.

The Kingdom of **Kosala**, as we have seen, was bounded on the west by the Gumti, on the south by the Sarpikā or Syandikā (Sai) river,¹ on the east by the Sadānīrā which separated it from Videha, and on north by the Nepāl hills. It included the territory of the Kālāmas of Kesaputta,² possibly on the Gumti, and that of the Śākya of Kapilavastu in the Nepalese Tarai. In the *Sutta Nipāta*³ the Buddha says, "Just beside Himavanta there lives a people endowed with the power of wealth, the inhabitants of *Kosala*.⁴ They are *Ādicchhas*⁵ by family, Śākiyas by birth; from that family I have wandered out, not longing for sensual pleasures." The *Majjhima Nikāya*,⁶ too, mentions the Buddha as a Kosalan :

"**Bhagavā pi Kosalako aham pi Kosalako**"

The political subjection of the Śākya to the king of Kosala in the latter half of the sixth century B. C. is clear from the evidence of the *Aggañña Suttanta*⁷ and the introductory portion of the *Bhaddasāla Jātaka*.⁸

Kosala proper contained three great cities, namely Ayodhyā, Sāketa and Sāvattthī or Śrāvastī, besides a number of minor towns like Setavyā⁹ and Ukkatṭha.¹⁰ Ayodhyā (Oudh) was a town on the river Sarayū now

¹ Rām. II. 49.11-12; 50. 1; VII. 104. 15.

² *Aṅguttara Nikāya*, I. 188 (PTS); *IG*. II. 808. In the *Ṛig-veda*, V, 61, the Dālbyhas, a family or clan closely connected with the Keśins (who possibly gave their name to Kesaputta), are placed on the Gumti.

³ S.B.E., X, Part II, 68-69.

⁴ *Kosalesu niketino*. As pointed out by Rhys Davids and Stede, *Niketin* means 'having an abode,' 'being housed,' 'living in,' cf. J. III, 482—*dumasākhā-niketini*.

⁵ Belonging to the Āditya (Solar) race (cf. Lüders, *Ins.*, 929 i).

⁶ II. 124.

⁷ *Dīgha Nikāya*, III (P.T.S.), 83; *Dialogues* III. 80.

⁸ No. 465; Fausboll, IV. 145.

⁹ *Pāyāsi Suttanta*.

¹⁰ *Ambatṭha Sutta*.

included in the Fyzabad district. Sāketa is often supposed to be the same as Ayodhyā, but Professor Rhys Davids points out that both cities are mentioned as existing in the Buddha's time. They were possibly adjoining like London and Westminster.¹ Sāvattthī is the great ruined city on the south bank of the Achiravatī or Rāptī called Sāhēṭ-Māhēṭ, which is situated on the borders of the Goṇḍa and Bahraich districts of the present Uttar-Pradesh.²

In the *Rāmāyaṇa* and in the *Purāṇas* the royal family of Kosala is represented as being descended from a king named Ikshvāku. Branches of this family are represented as ruling at Kusinārā,³ at Mithilā⁴ and at Viśālā or Vaiśālī.⁵ A prince named Ikshvāku is mentioned in a passage of the *Rig-Veda*.⁶ In the *Atharva-Veda*⁷ either this king, or one of his descendants, is referred to as an ancient hero. The *Purāṇas* give lists of kings of the *Aikshvāka* dynasty from Ikshvāku himself to Prasenajit, the contemporary of Bimbisāra. The names of many of these kings are probably found in the Vedic literature. For example :—

Mandhātṛi Yuvanāśva⁸ is mentioned in the *Gopatha Brāhmaṇa*.⁹ Purukutsa¹⁰ is referred to in the *Rig-Veda*.¹¹

¹ *Buddhist India*, p. 39.

² Cunningham, *Ancient Geography of India*, 1924, p. 469; Smith, E. H. I., 3rd ed., p. 159. The royal palace at Śrāvastī overlooked the Achiravatī (DPPN, II, 170n).

³ The *Kuśa Jātaka*, No. 531. The *Mahāvastu* (III. 1) places an Ikshvāku king in Benares—*Abhūshi Rājā Ikshvāku Vārāṇasyām mahābala*.

⁴ *Vāyu P.*, 89, 3.

⁵ *Rāmāyaṇa*, I. 4, 11-12.

⁶ X. 60. 4

⁷ XIV. 39. 9.

⁸ *Vāyu*, 88. 67.

⁹ I. 2. 10 *et. seq.*

¹⁰ *Vāyu*, 88, 72.

¹¹ I, 63. 7; 112. 7. 14; 174. 2, VI. 20. 10.

In the *Satapatha Brāhmaṇa*¹ he is styled an Aikshvāka.² Trasadasyu,³ too, finds mention in the *Ṛig-Veda*.⁴ Tryarūpa⁵ is also mentioned in the same *Veda*.⁶ In the *Pañchaviṃśa Brāhmaṇa*⁷ he is called an Aikshvāka. Triśaṅku⁸ is referred to in the *Taittirīya Upanishad*.⁹

Hariśchandra¹⁰ figures in the *Aitareya Brāhmaṇa*¹¹ and is styled Aikshvāka. Rohita, the son of Hariśchandra¹² is also alluded to in the same *Brāhmaṇa*¹³. Bhagīratha¹⁴ figures prominently in the *Jaiminīya Upanishad Brāhmaṇa* under the slightly different name of Bhageratha¹⁵ and is called Aikshvāka and 'Ekarāt' (sole ruler). Under the name of Bhajeratha he is probably referred to in the *Ṛig-Veda*¹⁶ itself. Ambarisha¹⁷ is mentioned in the same *Veda*.¹⁸ The name Rītuparṇa¹⁹ finds mention in a Brāhmaṇa-like passage of the *Baudhāyana Śrauta Sūtra*.²⁰ Daśaratha and Rāma²¹ bear names that are known to the *Ṛig-Veda*.²² But these personages and a few others mentioned above are not connected in the Vedic texts with the Ikshvāku family or with Kosala.

Hiraṇyanābha Kausalya,²³ is mentioned in the *Praśna Upanishad* as a *rājaputra* or prince.²⁴ He is undoubtedly

¹ XIII. 5. 4. 5.

² Cf. reference to the *Ṛig-Veda*, IV. 42. 8 in this connection.

³ *Vāyu*, 88. 74.

⁴ IV. 33. 1; VII. 19. 3, etc.

⁵ *Vāyu*, 88. 77.

⁶ V. 27.

⁷ XIII. 3. 12.

⁸ *Vāyu*, 88. 100.

⁹ I. 19. 1.

¹⁰ *Vāyu*, 88. 117.

¹¹ VII. 13. 16.

¹² *Vāyu*, 88. 119.

¹³ VII. 14.

¹⁴ *Vāyu*, 88. 167.

¹⁵ IV. 6. 1 ff.

¹⁶ X. 60. 2.

¹⁷ *Vāyu*, 88. 171.

¹⁸ I. 100. 17.

¹⁹ *Vāyu*, 88. 173.

²⁰ XVIII. 12 (Vol. II, p. 337).

²¹ *Vāyu*, 88. 183-184.

²² I. 126. 4; X. 93. 14.

²³ *Vāyu*, 88. 207.

²⁴ VI. 1. In the *Jaim. Up.* Br. II. 6. he (cf. *Sāhkh. Sr. Sūtra*, XVI. 9. 13) or his son (*Sat. Br.* XIII. 5. 4. 4) is styled a *mahārāja*. Too much significance should not be attached to the designation *rājaputra* (as distinguished from *rāja*). In the *Mbh.* V. 165. 18, *Bṛihadvala* is a *rāja* of Kosala (Kausalya). In a later passage of the epic (XI. 25. 10) the same ruler is referred to as *Kosalānāmadhī-patiḥ rājaputrah Bṛihadvalah*.

connected with Para Āṭṭāra (Āhlāra), the Kosala-Videhan king, mentioned in a *gāthā* (song) occurring in the *Satapatha Brāhmaṇa*¹ and the *Saṅkhāyana Śrauta Sūtra*,² as well as a passage of *Jaiminīya Upanishad Brāhmaṇa*.³ The *gāthā* as quoted in the *Satapatha Brāhmaṇa* gives to Para the patronymic 'Hairanyanābha', while the *Śrauta Sūtra* identifies Para with Hiranyanābha himself. It is difficult to say whether the original *gāthā* extolling the deeds of Para Āṭṭāra (Āhlāra) gave to that conqueror the name 'Hiranyanābha' or the patronymic 'Hairanyanābha.' The *Satapatha Brāhmaṇa* is the older of the two works mentioning the prince's exploits and is, therefore, more likely to preserve the original text than the *sūtra*. According to the *Praśna Upanishad*, Hiranyanābha, the father, was a contemporary of Sukeśā Bhāradvāja,⁴ who was himself a contemporary of Kausalya Āśvalāyana.⁵ If it be true, as seems probable, that Āśvalāyana of Kosala is identical with Assalāyana of Sāvattthī mentioned in the *Majjhima Nikāya*⁶ as a contemporary of Gotama Buddha, he must be placed in sixth century B. C. Consequently Hiranyanābha and his son, Hairanyanābha too, must have flourished in that century.

Some of the later princes of the Purāṇic list, e.g., Śākya, Suddhodana, Siddhārtha, Rāhula and Prasenajit, are mentioned in Buddhist texts. The exact relations of Hiranyanābha (and Hairanyanābha) with Prasenajit, who also flourished in the sixth century B. C. are not known. The Purāṇic chroniclers make Hiranyanābha an ancestor of Prasenajit, but are not sure about his position in the dynastic list.⁷ Further they refer to

¹ XIII. 5. 4. 4. *Āṭṭārasya Paraḥ putro'svaṃ medhyamabāndhayat*
Hiranyanābhaḥ Kausalyo dīśaḥ pūrṇā amāṇhata (iti)

² XVI. 9. 13.

³ II. 6.

⁴ VI. 1.

⁵ *Praśna*, I. 1.

⁶ II. 147 *et. seq.*

⁷ *AIHT.*, 173.

Prasenajit as the son and successor of Rāhula, and grandson of Siddhārtha (Buddha). This is absurd, because Prasenajit was of the same age as the Buddha and belonged to a different branch of the Ikshvāku line. The Tibetans represent him as the son of Brahmadata.¹ It is clear that no unanimous tradition about the parentage of Prasenajit and the position of Hiranyanābha in the family tree has been preserved. Hiranyanābha, or preferably his son, performed an *Aśvamedha* sacrifice and was apparently a great conqueror. Is this ruler identical with the "Great Kosalan" (Mahākosala) of Buddhist tradition? If he really flourished in the sixth century B.C., he may have been identical with 'Mahākosala' of Buddhist texts.

Pargiter admits that several Purāṇic passages make Hiranyanābha (and therefore also his son) one of the "future" kings after the Bhārata battle.² He was the only prince of antiquity who is styled in the Vedic literature both a Kausalya and a Vaideha. That description admirably fits Mahākosala whose daughter, the mother of Ajātaśatru according to Buddhist tradition, is called Kosalādevī as well as Vedehī (Vaidehī).

A word may be added here regarding the value of the Purāṇic lists. No doubt they contain names of some real kings and princes. But they have many glaring defects, defects which are apt to be forgotten by writers who make these the basis of early Indian chronology.

(1) Ikshvākuids of different branches and perhaps princes of other tribes, *e.g.*, Trasadasyu, king of the Pūrus,³ Rituparṇa, king of Śaphālā,⁴ Śuddhodana of

¹ *Essay on Guṇādhya*, p. 173.

² *A.I.H.T.*, 173.

³ *Rig-Veda*, IV. 38, 1; VII. 19, 3.

⁴ *Baud. Śrauttra Sūtra*, XVIII. 12 (Vol. II, p. 357); *Āpas. Śr. Sūtra*, XXI. 20, 3. Rituparṇa is, however, not distinctly called an Aikshvāka. But from the rarity of the name it is possible to surmise that the epic and Purāṇic king of that designation is meant.

Kapilavastu and Prasenajit, king of Śrāvastī, have been mixed up in such a way as to leave the impression that they formed a continuous line of monarchs who ruled in regular succession.

(2) Contemporaries have been represented as successors and collaterals have been represented as lineal descendants, *e.g.*, Prasenajit, king of Śrāvastī, is represented as the lineal successor of Siddhārtha and Rāhula, though he was actually a contemporary of Siddhārtha, *i.e.*, the Buddha, and belonged to a separate line of the Ikshvākuids.

(3) Certain individuals have been omitted, *e.g.*, Vedhas (father, or ancestor of Hariśchandra), Para Āṇāra (unless he is identical with Hiranyanābha), and Mahākosala.

(4) Names in the list include Śākya, the designation of a clan, and Siddhārtha (Buddha) who never ruled.

It is not easy to find out all the kings of the Purāṇic chronicles who actually ruled over Kosala. Some of the earlier princes, *e.g.*, Purukutsa, Trasadasyu, Hariśchandra, Rohita, Rītuparna and a few others, are omitted from the list of the kings of Ayodhyā given in the *Rāmāyaṇa*.¹ We gather from the Vedic literature that many, if not all, of these monarchs ruled over territories lying outside Kosala. The only kings or princes in the Purāṇic list who are known from the Vedic and early Buddhist texts to have reigned in Kosala, or over some outlying part of it, are Hiranyanābha,² Prasenajit and Śuddhodana.

¹ I. 70.

² In the *Sat. Br.* XIII. 5. 4, 4-5, Hiranyanābha is described as *Kausalya-rāja*, but not as an Ikshvāka. On the other hand, Purukutsa Daśgaha is styled *Aikṣvāka-rājā* but not as *Kausalya*, as if a distinction between *Kausalya* and *Aikṣvāka* is meant. The two terms need not refer to kings of the same dynasty ruling over exactly the same territory. As a matter of fact Trasadasyu is known to be a king of the Pūru. An Ikshvākuid styled Vārahpa, connected with the Vṛishnis (?), is mentioned in *Jaim. Up. Br.* 1, 5, 4.

The Buddhist works mention a few other sovereigns of Kosala, but their names do not occur in the epic and Purāṇic accounts. Some of these kings had their capital at Ayodhyā, others at Sāketa, and the rest at Śrāvastī. Of the princes of Ayodhyā, the *Ghata Jātaka*¹ mentions Kālasena. A Kosalarāja reigning in Sāketa is mentioned in the *Nandiyamiga Jātaka*.² Vaṅka, Mahākosala and many others³ had their capital at Sāvattthī or Śrāvastī. Ayodhyā seems to have been the earliest capital, and Sāketa the next. The last capital was Śrāvastī. Ayodhyā had sunk to the level of an unimportant town in the Buddha's time,⁴ but Sāketa and Śrāvastī were included among the six great cities of India.⁵

The chronology of ancient Kosala is in a state of utmost confusion. If the *Purāṇas* are to be believed, a prince named Divākara occupied the throne of Ayodhyā in the time of Adhisīma-kṛishṇa, great-great-grandson of Parīkshit. But, as has already been pointed out above, the princes who are mentioned as his successors did not form a continuous line of rulers who reigned over the same territory in regular succession. It is, therefore, a hopeless task to measure the distance separating him from the Buddha and his contemporary with the help of the traditional dynastic lists alone. It is also not known when the older capitals were abandoned in favour of Śrāvastī. But it must have been some time before the accession of Prasenajit, the contemporary of the Buddha, of Bimbisāra, and of Udayana of Kauśāmbī, supposed to be a descendant of Adhisīma-Kṛishṇa.

¹ No. 454.

² No. 385.

³ E.g., the Kosalarāja of J. 75; Catta (336); Sabbamitta (512); and Prasenajit.

⁴ *Buddhist India*, p. 34.

⁵ *Mahā-parinibbāna Sutta*, S. B. E., XI, p. 93.

We learn from the *Mahāvagga*¹ that during the period of the earlier Brahmadattas of Kāsi, Kosala was a poor and tiny state with slender resources: *Dighīti nāma Kosalarājā ahosi daliddo appadhano appadhogo appabalo appavāhano appavijito aparipuṇṇa-kosa-koṭṭhāgāro*.

In the sixth and fifth centuries B. C., however, Kosala was a mighty kingdom which contended first with Kāsi, and afterwards with Magadha for the mastery of the upper Ganges valley. The history of these struggles is reserved for treatment in later sections. The rivalry with Magadha ended in the absorption of the kingdom into the Magadhan Empire.

Aṅga was the country to the east of Magadha and west of the chieftains who dwelt in the Rajmahal Hills (*Parvatavāsinaḥ*). It was separated from Magadha (including Modāgiri or Monghyr) by the river Champā, probably the modern Chāndan.² The Aṅga dominions, however, at one time included Magadha and probably extended to the shores of the sea. The *Vidhura Paṇḍita Jātaka*³ describes Rājagriha as a city of Aṅga. The *Śāntiparva* of the *Mahābhārata*⁴ refers to an Aṅga king who sacrificed on Mount Viṣṇupada (probably at Gayā). The *Sabhāparva*⁵ mentions Aṅga and Vaṅga as forming one *Vishaya* or kingdom. The *Kathā-sarit-sāgara* says⁶ that Viṭaṅkapur,

¹ S. B. E., XVII, p. 294.

² According to Pargiter (JASB, 1897, 95) Aṅga comprised the modern districts of Bhāgalpur and Monghyr, and also extended northwards up the river Kauśiki or Kośi and included the western portion of the district of Purnea. For it was on that river that Kāśyapa Vibhāṇḍaka had his hermitage. His son Rishyaśringa was beguiled by courtesans of Aṅga into a boat and brought down the river to the capital. In Mbh. ii. 30. 20-22, however, Modāgiri (Monghyr) and Kauśiki-Kachchha had rulers who are distinguished from Karṇa whose realm (Aṅga) clearly lay between the Māgadhas and the Rājās styled *Parvatavāsina*.

³ No. 545.

29, 35, JASB, 1897, 94.

44. 9; cf. VI. 18. 28. Aṅgas and Prāchyas.

25, 35; 26, 115; §2. 3-16.

a city of the Aṅgas, was situated on the shore of the sea. The imperial glory of Aṅga is doubtless reflected in the songs of the *Aitareya Brāhmaṇa*¹ which describe the 'world-conquest' (*Samantam sarvataḥ prithivīm jayan*) of one of its ancient kings in the course of which girls of aristocratic families (*ādhyā-duhitri*) were brought as prizes from different climes.

Champā, the famous capital of Aṅga, stood at the confluence of the river of the same name² and the Ganges.³ Cunningham points out that there still exist near Bhāgalpur two villages, Champānagara and Champāpura, which most probably represent the actual site of the ancient capital. It is stated in the *Mahābhārata*, the *Purāṇas* and the *Harivaṃśa* that the ancient name of Champā was Mālinī:⁴

*Champasya tu purī Champā
yā Maliny-abhavat purā.*

In the *Jātaka* stories the city is also called Kāla-Champā. The *Mahā-Janaka Jātaka*⁵ informs us that Champā was sixty leagues from Mithilā. The same *Jātaka* refers to its gate, watch-tower, and walls. Down to the time of Gautama Buddha's death it was considered as one of the six great cities of India, the other five being Rājagriha, Srāvastī, Sāketa, Kauśāmbī, and Benares.⁶ Champā was noted for its wealth and commerce, and traders sailed from it to Suvarṇa-bhūmi in the Trans-Gangetic region for trading purposes.⁷ Hindu

¹ *Ait. Br.* VIII. 22.

² *Jātaka* 506.

³ *Mbh.* iii, 84, 169; 307, 26 (*Gaṅgāyāḥ Sūtarishayaṁ Champāmanu yayan purim*); Watters, *Yuan Chwang* II. 181; *Daśakumāra Charita*, II. 2.

⁴ *Matsya*, 48. 97; *Vāyu*, 99. 105-106; *Hariv.*, 31. 49; *Mbh.*, XII. 5. 6-7; XIII. 42, 16.

⁵ No. 539.

⁶ *Mahā-parinibbāna Sutta*.

⁷ *Jātaka*, 539, Fausboll's Ed., VI, p. 34.

emigrants to southern Annam and Cochin China are supposed to have named their settlement after this famous Indian city.¹ Other important cities in Aṅga were Assapura (Aśvapura) and Bhaddiya (Bhadrika).²

The earliest appearance of Aṅga is in the *Atharva Veda*³ in connection with the Gandhāris, Mūjavats, and Magadhas. The *Rāmāyaṇa* tells an absurd story about the origin of this Janapada. It is related in that epic that Madana or Anaṅga, the god of love, having incurred the displeasure of the God Śiva fled from the hermitage of the latter to escape his consuming anger, and the region where "he cast off his body (*aṅga*)" has since been known by the name of Aṅga.⁴ The *Mahābhārata* and the *Purāṇas* attribute the foundation of the kingdom to a prince named Aṅga.⁵ The tradition may claim some antiquity as Aṅga Vairochana is included in the list of anointed kings in the *Āitareya Brāhmaṇa*.⁶ The consecration of this ruler with the Aryan ritual styled the *Aindra mahābhisheka* causes some surprise as the *Bodhāyana Dharma Sūtra* groups the Aṅgas with peoples

¹ *Ind. Ant.*, VI, 229, Itanog, 58, Rhys Davids, *Buddhist India*, p. 35. Nandolal Dey, *Notes on Ancient Aṅga*, JASB, 1914. For the Hindu colonisation of Champā, see Eliot, *Hinduism and Buddhism*, Vol., III, pp. 137 ff. and R. C. Majumdar, *Champā*. The oldest Sanskrit inscription (that of Vo-can) dates, according to some scholars, from about the third century A. D. The inscription mentions a king of the family of Śrī Māra-rāja.

² Malalasekera, *DPPN*, 16; *Dhammapada Commentary*, *Harvard Oriental Series*, 29, 59. Cf. Bhaddiya (Bhadrika or Bhadrīkā of Jaina writers). It is possibly represented by Bhadariyā, 8 miles south of Bhāgalpur (JASB, 1914, 337).

³ V. 22, 14.

⁴ JASB, 1914, p. 317; *Rām.*, I, 23, 14.

⁵ *Mbh.* I, 104, 53-54; *Maṭya P.* 48, 19.

⁶ VIII, 22; cf. Pargiter, JASB, 1897, 97. In connection with the gifts of the Aṅga King mention is made of a place called Avachatnuka:

Dadanāgasahasrāpi dattatātreya' vachatnuka

āraṇṭah pārikulān praprad dānen-Aṅgasya Brāhmaṇah.

The epithet 'Vairochana' given to the Aṅga King reminds one of 'Vairochani' of the *Maṭya P.* 48, 53.

of mixed origin, and the *Mahābhārata* brands an Āṅga prince who, by the way, is distinguished from Karṇa, and is described as skilful in handling elephants, as a *Mlechchha* or outlandish barbarian. In the *Matsya Purāṇa* the father of the eponymous hero of the Āṅgas is styled *Dānavarshabhaḥ* (chief among demons).¹

About the dynastic history of Āṅga our information is meagre. The *Mahāgovinda Suttanta* refers to king Dhataratṭha of Āṅga.² The Buddhist texts mention a queen named Gaggarā who gave her name to a famous lake in Champā. The *Purāṇas*³ give lists of the early kings of this country. One of these rulers, Dadhivāhana, is known to Jaina tradition. The *Purāṇas* and the *Harivamśa*⁴ represent him as the son and immediate successor of Āṅga. Jaina tradition places him in the beginning of the sixth century B. C. His daughter Chandanā or Chandrabālā was the first female who embraced Jainism shortly after Mahāvira had attained the *Kevaliship*.⁵ Śātānika, king of the Vatsas of Kauśāmbī, near Allahabad, is said to have attacked Champā, the capital of Dadhivāhana, and in the confusion which ensued, Chandanā fell into the hands of a robber, but all along she maintained the vows of the order.

Between the Vatsas and the realm of Āṅga lived the Magadhas, then a comparatively weak people. A great struggle was going on between this kingdom and its great

¹ *Bodh. Dh. S.* I. 1. 29; *Mbh.* VIII. 22. 18-19; *Mat. P.* 48. 60. Note also the connection of Āṅgas with *Nishada*s in *Vāyu*, 62, 107-23. The *Purāṇa* describes the royal family as *Ātrīkandhasamutpanna*. In the *Āitareya Brāhmaṇa*, however, an Ātreya appears as the priest of the Āṅga King. For a discussion of the origin of the Āṅgas and other kindred tribes, see. S. Lévi *pre-Aryen et Pre-Dravidien dans l'Inde*, "J. A. Juillet-septembre, 1923.

² *Dialogues of the Buddha*, II. 270.

³ *Matsya*, 48. 91-108; *Vāyu*, 69. 100-112.

⁴ 32. 43.

⁵ *JASB*, 1914, pp. 320-21. For the story of Chandanabālā see also *Ind. Culture*, II. pp. 682 ff.

eastern neighbour.¹ The *Vidhura Paṇḍita Jātaka*² describes Rājagṛiha, the Magadhan capital, as a city of Aṅga while the *Mahābhārata* refers to a sacrifice which an Aṅga king probably performed at Gayā. These details may indicate that Aṅga succeeded in annexing Magadha. Its frontier thus approached the Vatsa Kingdom whose monarch's alarm may have been responsible for an attack on Champā. The Aṅga king preferred to have friendly relations with Kauśāmbī, possibly because he was threatened by the reviving power of Magadha. Śrī Harsha speaks of a ruler of Aṅga named Dṛiḍhavarman who gave his daughter in marriage to Udayana, son and successor of Śatānīka³ and secured his help in regaining his throne.

The success of Aṅga did not last long. About the middle of the sixth century B. C. Bimbisāra Śreṇika, the Crown Prince of Magadha, is said to have killed Brahmadata, the last independent ruler of Ancient Aṅga. He took Champā, the capital, and resided there as his father's Viceory.⁴ Henceforth Aṅga becomes an integral part of the growing empire of Magadha.

Magadha corresponds roughly to the present Patna and Gayā districts of South Bihār. It seems to have been bounded on the north and the west by the rivers Ganges and the Son, on the south by spurs of the Vindhyan range, and on the east by the river Champā which emptied itself into the Ganges near the Aṅga capital.⁵ Its earliest capital was Girivraja, the mountain-girt

¹ *Champeyya Jātaka*.

² Cowell, VI. 133.

³ *Priyadarśikā*, Act IV.

⁴ Hardy, *A Manual of Buddhism*, p. 163n (account based on the Tibetan *Dulva*), *JASB*, 1914, 321.

⁵ *Mbh.* II. 20. 29; *Mahā-parinibbāna Suttanta* (*Dialogues* ii. 94) and *DPPN*, I. 331 which show that the Vpiji frontier commenced from the northern bank of the Ganges as Ukkāvelā or Ukkachelā, was included within the limits of that state; *Champeyya Jātaka* (506); *Fleet*, *CII*, 227; *DPPN*, 408. In the epic period the eastern boundary of Magadha proper may not have extended as far as the Champā river as Modāgiri (Monghyr) finds mention as a separate state.

city,¹ or old Rājagṛiha, near Rājgir among the hills in the neighbourhood of Gayā. The *Mahāvagga*² calls it "Giribbaja of the Magadhas" to distinguish it from other cities of the same name, e.g., Girivraja in Kekaya. The *Mahābhārata* refers to it not only as Girivraja, but as Rājagṛiha,³ Bārhadhratha-pura⁴ and Māgadha-pura,⁵ and says that it was an almost impregnable city, *puram durādharshaṁ samantataḥ*, being protected by five hills, viz. Vaihāra, the grand rock (*Vipūlaḥ śailo*), Varāha, Vṛishabha, Rishigiri and Chaityaka⁶ with their compact bodies (*rakshantīvābhisamhatya samhataṅgā Girivrajam*). From the *Rāmāyaṇa* we learn that the city had another name, Vasumatī.⁷ The *Life of Hiuen Tsang* mentions still another name, Kuśāgra-pura.⁸ Indian Buddhist writers give a seventh name, Bimbasāra-purī.⁹

In a passage of the *Ṛig-Veda*¹⁰ mention is made of a territory called Kīkaṭa ruled by a chieftain named Pramaganda. Yāska¹¹ declares that Kīkaṭa is the name

¹ Broadley in *JASB.* 1872, 290. Girivraja was at one time identified with Giryek on the Pañchana river about 36 miles north east of Gayā, 6 miles east of Rajgir (Pargiter in *JASB.* 1897, 86).

² S. B. E., XIII. 150.

³ *Mbh.* I. 113. 27; 204. 17; II, 21. 34; III. 84, 104.

⁴ II. 24. 44.

⁵ *Gorathanḥ girimāsādyā dadṛṣur Māgadhaṁ puram*, II, 20. 30; 21, 13.

⁶ The names given in the Pāli texts (*DPPN*, II. 721) are Paṇḍava, Gijjhakūṭa, Vebhāra, Isigili and Vepulla (or Vaṅkaka). The Pāli evidence may suggest that *Vipula* in the *Mbh.* verse is a name, and not an epithet. In that case Dr. J. Wenger suggests *Chaityakapañchakāḥ* (five goodly *Chaityakas*) for *Chaityakapañchamā*, (with *Chaityaka* as the fifth). For a note by Keith see *IHQ.* 1939, 163-64.

⁷ I. 32. 8.

⁸ P. 113. Apparently named after an early Magadhan prince (*Vāyu.* 99, 224; *AIHT.* 149).

⁹ Law, *Buddhaghosha*, 87 n.

¹⁰ III. 53. 14.

¹¹ *Nirukta*, VI, 32.

of a non-Aryan country. In later works Kikaṭa is given as a synonym of Magadha.¹

Like Yāska the author of the *Bṛihad-dharma Purāṇa* apparently regarded Kikaṭa as an impure country which however, included a few holy spots :—

*Kikaṭe nāma deśe' sti Kāka-karṇākhyako nṛipaḥ
prajānām hitakṛinnityam Brahma-dveshakarastathā
tatra deśe Gayā nāma puṇyadeśo' sti viśrutah
nadī cha Karṇadā nāma pitṛiṇām svargadāyini²
Kikaṭe cha mṛito' pyesha pāpabhūmau na saṁśayaḥ.³*

It is clear from these verses that Kikaṭa included the Gayā district, but the greater part of it was looked upon as an unholy region (*pāpabhūmi*, doubtless corresponding to the *anārya-nivāsa* of Yāska). Kāka-karṇa of line 1, may be the same as Kāka-varṇa of the Śaiśunāga family.

The name Magadha first appears in the *Atharva-Veda*⁴ where fever as wished away to the Gandbāris, Mūjavats, Aṅgas, and Magadhas. The bards of Magadha are, however, mentioned as early as the *Yajur-Veda*.⁵ They are usually spoken of in the early Vedic literature in terms of contempt. In the *Vrātya* book of the *Atharva Samhitā*,⁶ the *Vrātya* i.e., the Indian living outside the pale of Brāhmaṇism, is brought into very special relation to the *puṁśchalī*

¹ *Kikaṭeshu Gayā puṇyā puṇyam Rājagṛiham vanam*

Chyāvanasyāśramaṁ puṇyam nadī puṇyā Punahpunā.

Cf. *Vāyu*, 108. 73; 105. 23. *Bhāgavata Purāṇa*, 1, 3. 24: *Buddho namnānjana-sutah Kikaṭeshu bhaviṣhyati*; ibid vii 10, 19; Sridhara: "*Kikaṭeshu madhye Gayā-pradeśe*". *Abhidhāna-chintāmaṇi*: "*Kikatā Magadhāhṛayāḥ*." For an epigraphic reference to Kikata see *Ep. Ind.* II. 222, where a prince of that name is connected with the Maurya family, See also '*Kekateyaka*' (*Monuments of Sānchi*, I. 302)

² *Madhya-Khaṇḍam*, XXVI. 20, 22.

³ XXVI. 47; cf. *Vāyu* p. 78. 22, *Pādma Pātālakhanda*, XI. 45.

⁴ V. 22. 14.

⁵ *Vāṣ. Saṁ* XXX. 5; *Vedic Index*, II. 116. For the connection of the Magadhas with Magadha, see *Vāyu* P. 62. 147.

⁶ XV. ii. 5—*Śraddhā puṁśchalī Mitro Māgadho...* etc; Griffith II. 186,

(harlot) and the *Māgadha*. "In the eastern region (*Prāchyām diśi*)" faith is his harlot, *Mitra* his *Māgadha* (bard or panegyrist).¹ In the *Śrauta Sūtras* the equipment characteristic of the *Vrātya* is said to be given, when the latter is admitted into the Aryan Brāhmanical community, to the so-called Brāhmaṇas living in Magadha, *Brahmabandhu Māgadha-deśīya*.² The Brāhmaṇas of Magadha, are here spoken of in a disparaging tone as *Brahmabandhu*.³ In the *Sāṅkhāyana Aranyaka*, however, the views of a *Magadha-vāsī* Brāhmaṇa are quoted with respect. The Vedic dislike of the Magadhas in early times was due, according to Oldenberg⁴, to the fact that the Magadhas were not wholly Brāhmanised. Pargiter suggests⁵ that in Magadha the Aryans met and mingled with a body of invaders from the east by sea.

With the exception of Pramaganda no king of Magadha appears to be mentioned in the Vedic literature. The earliest dynasty of Magadha according to the *Mahābhārata*⁶ and the *Purāṇas* is that founded by Brihadratha, the son of Vasu Chaidya-Uparichara, and the father of Jarāsandha. *Rāmāyaṇa*⁷ makes Vasu himself the founder of Girivraja or Vasumatī. A Brihadratha is mentioned twice in the *Rig-Veda*,⁸ but there is nothing to show that he is identical with the father of Jarāsandha. The *Purāṇas* give lists of the "Brihadratha kings" from Jarāsandha's son Sahadeva to Ripuñjaya, and apparently make Senājit, seventh in descent from Sahadeva, the

¹ Cf. Weber, *Hist. Ind. Lit.*, pp. 112.

² *Vedic Index*, II, 116.

³ Note also the expression *rājānaḥ kṣātra-bandhavaḥ* applied to Magadhan kings in the *Purāṇas* (Pargiter, *Dynasties of the Kali Age*, p. 92).

⁴ *Buddha*, 100b.

⁵ *JASB*, 1897, 111; *J. R. A. S.*, 1906, pp. 851-53. *Bodh. Dh. Sūtra*, I. i. 29 refers to Aṅgas and Magadhas as *sāṅkīrṇa-gaṇa-gaḥ*, "of mixed origin".

⁶ I. 63, 30.

⁷ I. 83, 7.

⁸ I. 86, 16; X, 49, 6.

contemporary of Adhisīma-Kṛishṇa of the Pārikshita family and Divākara of the Ikshvāku line. But in the absence of independent external corroboration it is not safe to accept the Purāṇic chronology and order of succession of the princes as authentic.¹ Bṛihadhrathas and certain princes of Central India are said to have passed away when Pulika (Puṇika) placed his son Pradyota on the throne of Avanti,² i.e., the Ujjain territory. As Pradyota was a contemporary of Gautama Buddha, and as the Purāṇic passage, "*Bṛihadhratheshvātīteshu Vītihotreshu-Avantishu*," 'when the Bṛihadhrathas, Vītihotras and Avantis (or the Vītihotras in Avanti) passed away', suggests that the events alluded to here were synchronous, it is reasonable to conclude that the Bṛihadhratha dynasty came to an end in the sixth century B.C.

Jaina writers mention two early kings of Rājagṛiha named Samudra-vijaya and his son Gaya.³ Gaya is said to have reached perfection which had been taught by the

¹ Cf. *supra*, pp. 80f, 104, discussion about later Vaideha and Kosalan kings. The number of 'the future Bṛihadhrathas' is given as 15, 22 or 32, and the period of their rule, 723 or 1000 years (DKA, 17, 68). The last King Ripuñjaya or Ariṇjaya (ibid 17 n 96) reminds one of Arindama of the Pāli texts (DPPN.ii. 402).

² *Dynasties of the Kali Age*, p. 18 : cf., IHQ, 1930, p. 683. There is no reason to believe with the late authors of the *Kathā-sarit-sāgara* and certain corrupt passages of the *Purāṇas*, (IHQ, 1930, pp. 679, 691), that there was a Pradyota of Magadha distinct from Mahāsena of Avanti who is called Pradyota by several earlier writers, Buddhist as well as Brāhmanical. The use of the expression 'Avantishu' (DKA, 18) in the Purāṇic passage which refers to the dynastic revolution brought about by Pulika, the identity of the names of the Purāṇic family of Pradyota with those of the Avanti line of Mahāsena, and the mention in reference to Pradyota of the *Purāṇas*, of epithets like '*Pranatasāmanta*' and '*naṇavarjita*' which remind one irresistibly of Chaṇḍa Pradyota Mahāsena of Avanti as described in Buddhist literature, leave little room for doubt that the Pradyota of the *Purāṇas* and Pradyota of Avanti cannot be regarded as distinct entities.

³ S.B.E. XLV. 86, A king named Gaya is mentioned in *Mbh.*, vii. 64. But he is described there as a son of Amūrtarayas.

Jinas. But little reliance can be placed on uncorroborated assertions of this character.

The second Magadhan dynasty, according to the less corrupt texts of the Purāṇas, was the Śaiśunāga line which is said to have been founded by a king named Śiśunāga. Bimbisāra, the contemporary of the Buddha, is assigned to this family. Aśvaghoṣa, an earlier authority,¹ refers however, in his *Buddha-charita*² to Śreṇya i.e., Bimbisāra, as a scion, not of the Śaiśunāga dynasty, but of the **Haryaṅka-kula**, and the *Mahāvamśa* makes 'Susunāga' i.e., Śiśunāga, the founder of a distinct line of rulers which succeeded that of Bimbisāra. The *Purāṇas* themselves relate that Śiśunāga "will take away the glory of the Pradyotas" whom we know from other sources to be contemporaries of the Bimbisārīds :—

*Ashta-trimśachchhatam bhāvyāḥ
Pradyotāḥ pañcha te sutāḥ
hatvā teshām yaśaḥ kṛitsnam
Śiśunāgo bhaviṣyati.*³

If this statement be true, then Śiśunāga must be later than the first Pradyota, namely Chanḍa Pradyota Mahāsena, who was, judged by the evidence of the Pāli texts, which is confirmed in important details by the ancient Sanskrit poets and dramatists,⁴ a contemporary of Bimbisāra and his son. It follows that Śiśunāga according to the last-mentioned authorities, must be later than those kings. But we have seen above that the Purāṇas make Śiśunāga an ancestor of Bimbisāra and the progenitor of his family. This part of the Purāṇic

¹ Aśvaghoṣa was a contemporary of Kanishka (C. 100 A.D.) (Winternitz, *Ind. Lit.* II. 257). On the other hand the Purāṇic chronicles pre-suppose Gupta rule in the Ganges Valley (*DKA*, 53), C. 320 A.D.

² XI. 2; Raychaudhuri, *IHQ*, I (1925), p. 87.

³ *Vāyu Purāṇa*, 99; 314.

⁴ *Indian Culture*, VI, 411.

account is not corroborated by independent external evidence.¹ The inclusion of Vārāṇasī and Vaiśālī within Śiśunāga's dominions² proves that he came after Bimbisāra and Ajātaśatru who were the first to establish Magadhan rule in those regions. The *Mālālaṅkāravatthu*, a Pali work of modern date, but following very closely the more ancient books, tells us that Śiśunāga had a royal residence at Vaiśālī which ultimately became his capital.³ "That monarch (Śiśunāga) not unmindful of his mother's origin⁴ re-established the city of Veśālī (Vaiśālī), and fixed in it the royal residence. From that time Rājagṛiha lost her rank of royal city which she never afterwards recovered. The last statement indicates that Śiśunāga came after the palmy days of Rājagṛiha, i.e., the period of Bimbisāra and Ajātaśatru. It may be argued that the Purāṇas make Girivraja, and not Vaiśālī, the abode of Śiśunāga (*Vārāṇasyām sutam sthāpya śrayishyati Girivrajam*); and as Udāyin, son of Ajātaśatru was the first to transfer the capital from that stronghold to the newly founded city of Pāṭaliputra, Śiśunāga's residence in the older capital points to a date earlier than that of the founder of the more famous metropolis. But the fact that Kālāśoka, son and successor of Śiśunāga, is known to have ruled in Pāṭaliputra shows that he came *after* Udāyin,

¹ We may go even further and characterise certain statements of the Purāṇic bards as self-contradictory. Thus (a) Pradyota is said to have been anointed when the Vitihoṭras had passed away, (b) Śiśunāga destroyed the prestige of the Pradyotas and became king, and yet (c) contemporaneously with these Śiśunāga kings 20 Vitihoṭras (and other lines) are said to have endured the same time.

ete sarve bhaviṣyanti

ekakālaṁ mahikṣitaḥ (DKA, 24).

² *Dynasties of the Kali Age*, 21; S. B. E., XI, p. xvi.

³ If the *Drātrīśat-Puttalikā* is to be believed, Vaiśālī continued to be graced by the presence of the king till the time of the Nandas.

⁴ Śiśunāga, according to the *Mahāvamśatikā* (Turnour, *Mahāvamśa*, xxxvii), was the son of a Lichchhavi rāja of Vaiśālī. He was conceived by a nagaraśobhinī and brought up by an officer of state.

the founder of that city. The further fact of removal of capital in his reign too—which must be regarded as a second transfer¹—shows that his predecessor had reverted to the older stronghold apparently as a place of refuge. The event alluded to in the words “*śrayishyati*” *Girivrajam* need not necessarily imply that Girivraja continued to be the capital uninterruptedly till the days of Śiśunāga.

The origin of the Haryanka line, to which Bimbisāra belonged according to Aśvaghoṣa, is wrapped up in obscurity. There is no cogent reason why this dynastic designation should be connected with Haryaṅga of Champā mentioned in the *Harivaṁśa*² and the *Purāṇas*. *Haryaṅka-kula* may simply be an expression like “*aulikara-lāñchhana ātma vaṁśa*” of a Mandasor Inscription, pointing to the distinctive mark or emblem of the family.³ Bimbisāra was not the founder of the line. The *Mahāvamśa* states that he was anointed king by his own father when he was only 15 years old.⁴ He avenged a defeat of his father⁵ by the Aṅgas and launched Magadha into that career of conquest and aggrandisement which only ended when Aśoka sheathed his sword after the conquest of Kalinga.

¹ SBE, XI, p. xvi.

² 31, 49; *Vāyu*, 99, 108; J.C. Ghosh in ABORI, 1938 (xix), pp. i. 82.

³ Hari has the sense of ‘yellow’, ‘horse’, ‘lion’, ‘snake’, etc.

⁴ Geiger’s translation, p. 12. This disposes of the view of Dr. D. R. Bhandarkar (*Curm. Lec.* 1918) who makes Bimbisāra the founder of his dynasty and says that he was a general who carved out a kingdom for himself at the expense of the Vajjis.

⁵ Turnour, N. L. Day and others mention Bhātiya or Bhaṭṭiya as the name of the father. The Tibetans, on the other hand, call him *Mahāpadma*. Turnour, *Mahāvamśa*, I. p. 10; *J. A. S. B.*, 1872, i 298; 1914, 321; *Essay on Guṇāḍhya*, p. 173. The *Purāṇas* name Hemajit, Kshemajit, Kshetrojā or Kshatraujā as the father of Bimbisāra. If the *Purāṇic* account is correct Bhātiya or Bhaṭṭiya may have been a secondary name or epithet comparable to the names ‘Seniya’ and Kūpiya of Bimbisāra and Ajātaśatru respectively. But it is not safe to rely on an uncorroborated statement of the *Purāṇas*, particularly when there is hardly any unanimity with regard to the form of the name.

The **Vajji** (Vṛjī) territory lay north of the Ganges and extended as far as the Nepāl hills. On the west the river Gaṇḍak possibly separated it from the Mallas and perhaps also the Kosalas. Eastwards, it may have approached the forests that skirted the river Kośī and the Mahānandā. It is said to have included eight confederate clans (*aṭṭhakula*), of whom the old *Videhas*, the *Licchhavis*, the *Jñātrikas* and the *Vṛjis* proper were the most important. The identity of the remaining clans remains uncertain. It may, however, be noted that in a passage of the *Sūtrakṛitāṅga*, the *Ugras*, the *Bhogas*, the *Aikshvākas* and the *Kauravas* are associated with the *Jñātris* and the *Licchhavis* as subjects of the same ruler and members of the same assembly.¹ The *Āṅguttara Nikāya*,² too, refers to the close connection of the *Ugras* with *Vaiśālī*, the capital of the *Vṛjīan* confederation.

The old territory of the **Videhas** had, as already stated in an earlier section, its capital at Mithilā which has been identified with Janakpur within the Nepāl border. The *Rāmāyaṇa* clearly distinguishes it from the region round *Vaiśālī*.³ But in Buddhist and Jaina texts the distinction is not always maintained and *Videha* is used in a wider sense to include the last-mentioned area.⁴

The **Licchhavi** capital was definitely at *Vaiśālī* which is represented by modern Besarh (to the east of the Gaṇḍak) in the Muzaffarpur district of Bihār. It is

¹ S. B. E., XLV, 330. cf. Hoernal, *Urāsaga-dashā*, II, p. 138, fn. 304.

² I, 26; III, 49; IV, 208.

³ *Rām*, I, 47-48.

⁴ The *Achārāṅga Sūtra* (II, 15, § 17; S. B. E., XXII, Intro.) for instance places the *Saṃniveda* of Kuṇḍagrāma near *Vaiśālī* in *Videha*. The mothers of Mahāvira and Ajātaśatru are called *Videha-datta* and *Vedehī* (*Vaidehī*) respectively.

probably identical with the charming city called Viśālā in the epic.¹

Viśālām nagarīm ramyām divyām svargopamām tadā.

We learn from the introductory portion of the *Ekaṇṇa Jātaka*² that a triple wall encompassed the town, each wall a league distant from the next, and there were three gates with watch-towers.

The Lichchhavi territory may have extended northwards as far as Nepāl where we find them in the seventh century A.D.

The **Jñātrikas** were the clan of Siddhārtha and his son Mahāvīra, the *Jina*. They had their seats at Kuṇḍapura or Kuṇḍagrāma and Kollāga, suburbs of Vaiśālī. In the *Mahā-parinibbāna Suttanta*,³ however, the abode of the "Nādikas" (identified by Jacobi with the Nātikas or Jñātrikas)⁴ is distinguished from Koṭigāma (Kuṇḍagrāma?). Though dwelling in suburban areas Mahāvīra and his fellow clansmen were known as "Vesālīe," i.e., inhabitants of Vaiśālī.⁵

The **Vrijis** proper are already mentioned by Pāṇini. Kauṭilya⁶ distinguishes them from the 'Lichchhivikas'. Yuan Chwang⁷ too, draws a distinction between the *Fu-li-chih* (Vrijī) country and *Pei-she-li* (Vaiśālī). It seems that Vrijī was not only the name of the confederacy but also of one of its constituent clans. But the Vrijis, like the Lichchhavis, are often associated with the city of Vaiśālī (including its suburbs) which was not only the capital of the Lichchhavi clan, but

¹ *Rām, Ādi*, 45, 10.

² Ch. 2.

³ S. B. E. XXII. Intro.

⁴ No. 149.

⁵ Hoernle *Urāsaya-danda*, II, p. 4 n.

⁶ IV, 2, 131.

⁷ *Arthadāstra*, Mysore Edition, 1919, p. 378.

⁸ *Walters*, II, 81. Cf. also *DPPN*, II, 814; *Gradual sayings*, III, 62; IV, 10.

According to Smith (*Walters*, II, 310) the Vrijī country is roughly equivalent to the northern part of the Dairbhanga district and the adjacent Nepalese Terai.

also the metropolis of the entire confederacy.¹ A Buddhist tradition quoted by Rockhill² mentions the city proper as consisting of three districts. These districts were probably at one time the seats of three different clans. The remaining peoples of the confederacy viz., the **Ugras**, **Bhogas**, **Kauravas**, and **Aikshvākas**, resided in suburbs, and in villages or towns like Hatthigāma, Bhoganagara, etc.³

We have seen that during the Brāhmaṇa period Videha (Mithilā) had a monarchical constitution. The *Rāmāyaṇa*⁴ and the *Purāṇas*⁵ state that Viśālā, too, was at first ruled by "kings." The founder of the Vaiśālīka dynasty is said to have been Viśālā, a son of Ikshvāku according to the *Rāmāyaṇa*, a descendant of Nabhāga the brother of Ikshvāku, according to the *Pūrāṇas*. Viśālā is said to have given his name to the city. After him came Hemachandra, Suchandra, Dhūmrāśva, Srinjaya, Sahadeva, Kuśāśva, Somadatta, Kākutstha and Sumati. We do not know how many of these Vaiśālīka "kings" (*nṛipas*) can be accepted as historical and

¹ Cf. *Majjhima Nikāya*, II, 101: *The Book of the Kindred Sayings*, I. (*Samyutta Nikāya*), by Mrs. Rhys Davids, p. 257.—"A certain brother of the Vajjian clan was once staying near Vesālī in a certain forest tract".

² *Life of Buddha*, p. 62.

³ For the *Ugras* and *Bhogas* see Hoernle, *Uvāsaga-dasāo*, II, p. 139 (§210); *Bṛh. Up.* III. 8. 2; S. B. E., XLV, 7n. in the *Āṅguttara Nikāya*, I. 26 (Nipāta I. 14. 6), the *Ugras* are associated with Vaiśālī (*Ugga gahapati Vesālīko*), and in IV. 212 with Hatthigāma. A city of Ugga is mentioned in the *Dhammapada commentary*, Harvard Oriental Series, Vol. 30, 184. Hoernle refers (*Uvāsaga-dasāo*, II, App. III, 57) to a place called Bhoganagara, or 'City of the Bhogas'. The *Mahā-parinibbāna Sutta* mentions Bhaṇḍagāma, Hatthigāma, Ambagāma, Jambugāma and Bhoganagara on the way from Vaisālī to Pāvā (*Digha*, II, 122-26). Cf. also *Sutta Nipāta*, 194. The association of a body of *Kauravas* with the Vajjian group of clans is interesting. Kuru Brāhmaṇas, e.g., Ushasti Chākrāyāna had begun to settle in the capital of Videha long before the rise of Buddhism. For the *Aikshvākas* of Vaisālī, see *Rām.* I. 47, 11.

I. 47, 11. 17.

⁵ *Vāyu*, 86. 16-22; *Vishṇu*, IV. 1. 18.

as having actually ruled as *monarchs* in North Bihār. A king named Sahadeva Sārñjaya is mentioned in the *Satapatha Brāhmaṇa*.¹ In the *Aitareya Brāhmaṇa*² he is mentioned with Somaka Sāhadevyā. None of these kings, however, are connected with Vaiśālī in the Vedic literature. The *Mahābhārata* speaks of a Sahadeva (son of Sṛñjaya) as sacrificing on the Jumna,³ and not on the Gaṇḍak. The presence of Ikshvākuids as a constituent element of the Vṛjīan confederacy, which had its metropolis at Vaiśālī, is, however, as already stated, suggested by the *Sūtrakṛitāṅga*.

The Vṛjīan confederation must have been organised after the decline and fall of the royal houses of Videha. Political evolution in India thus resembles closely the developments in the ancient cities of Greece where also the monarchies of the Heroic Age were succeeded by aristocratic republics. The probable causes of the transformation in Greece are thus given by Bury : "In some cases gross misrule may have led to the violent deposition of a king; in other cases if the succession to the sceptre devolved upon an infant or a paltry man, the nobles may have taken it upon themselves to abolish the monarchy. In some cases, the rights of the king might be strictly limited in consequence of his seeking to usurp undue authority; and the imposition of limitations might go on until the office of the king, although maintained in name, became in fact a mere magistracy in a state wherein the real power had passed elsewhere. Of the survival of monarchy in a limited form we have an example at Sparta; of its survival as a mere magistracy, in the Archon Basileus at Athens."

¹ II. 4. 4. 3-4.

² VII. 34. 9.

³ *Mbh.* III. 90. 7, with commentary.

The cause of the transition from monarchy to republic in Mithilā has already been stated. Regarding the change at Viśālā we know nothing.

Several scholars have sought to prove that the Lichchhavis, the most famous clan of the Vrijian confederacy (*Vajjirattḥavāsi hi pasatthā*)¹, were of foreign origin. According to Smith they had Tibetan affinities. He infers this from their judicial system and the disposal of their dead, viz., exposing them to be devoured by wild beasts.² Pandit S. C. Vidyābhūṣaṇa held that the name Lichchhavi (Nichchhivi of Manu) was derived from the Persian city of Nisibis.³ The inadequacy of the evidence on which these surmises rest has been demonstrated by several writers.⁴ Early Indian tradition is unanimous in representing the Lichchhavis as Kshatriyas. Thus we read in the *Mahā-parinibbān Suttanta*: "And the Lichchhavis of Vesālī heard the news that the Exalted One had died at Kusināra. And the Lichchhavis of Vesālī sent a messenger to the Mallas, saying: 'The

¹ DPPN, II, 814.

² *Ind. Ant.*, 1903, p. 233 ff. In the case of Tibet we have only three courts as against the seven tribunals of the Lichchhavis (viz. those of the *Vinichchhaya mahāmattas*) (inquiring magistrates), the *Vohārikas* (jurist-judges), *Suttadharas* (masters of the sacred code), the *Aṭṭhakulakas* (the eight clans, possibly a federal court), the *Senāpati* (general), the *Uparāja* (Viceroy or Vice-Consul), and the *rāja* (the ruling chief) who made their decisions according to the *paveṇi pothaka* (Book of Precedents). Further, we know very little about the relative antiquity of the Tibetan procedure as explained by S. C. Das which might very well have been suggested by the system expounded in the *Aṭṭhakathā*. This fact should be remembered in instituting a comparison between Tibetan and Vajjian practices. Regarding the disposal of the dead attention may be invited to the ancient practices of the 'Indus' people (Vats, *Excavations at Harappā*, I. ch. VI.) and the epic story in *Mbh.* IV. 5. 28-33.

³ *Ind. Ant.*, 1902, 143, ff; 1908, p. 78. There is very little in Vidyābhūṣaṇa's surmise except a fancied resemblance between the names Nichchhivi and Nisibis. Inscriptions of the Achaemenids are silent about any Persian settlement in Eastern India in the sixth or fifth century B.C. The Lichchhavi people were more interested in Yaksha *Chaityas* and the teaching of Mahāvīra and the Buddha than in the deities and prophets of Iran.

⁴ *Modern Review*, 1919, p. 50; Law, *Some Kshatriya Tribes*, 26ff.

Exalted One was a Kshatriya and so are we. We are worthy to receive a portion of the relics of the Exalted One." In the Jaina *Kalpa Sūtra* Triśalā, sister to Cheṭaka of Vesālī, is styled *Kshatriyānī*.¹

Manu concurs in the view that the Lichchhavis are *Rājanyas* or *Kshatriyas*.²

*Jhallo Mallaścha rājanyād vrātyān Nichchhivireva cha
Naṭaścha Karaṇaśchaiva Khaso Drāviḍa eva cha.*

It may be argued that the Lichchhavis, though originally non-Aryans or foreigners, ranked as Kshatriyas when they were admitted into the fold of Brāhmaṇism like the Drāviḍians referred to in Manu's *śloka* and the Gurjara-Pratibhāras of mediæval times. But unlike the Pratibhāras and Draviḍas, the Lichchhavis never appear to be very friendly towards the orthodox form of Hinduism. On the contrary, they were always to be found among the foremost champions of non-Brāhmaṇical creeds like Jainism and Buddhism. Manu testifies to their heterodoxy when he brands them as the children of the *Vrātya Rājanyas*. The great mediæval Rājput families (though sometimes descended from foreign immigrants) were never spoken of in these terms. On the contrary, they were supplied with pedigrees going back to Śrī Rāma, Lakshmaṇa, Yadu, Arjuna and others. A body of foreigners who did not observe ceremonies enjoined in the Brāhmaṇic code, could hardly have been accepted as Kshatriyas. The obvious conclusion seems to be that the Lichchhavis were indigenous Kshatriyas who were degraded to the position of *Vrātya* when they neglected Brāhmaṇic rites and showed a predilection for heretical doctrines. The *Rāmāyaṇa*, as we have seen, represents

¹ SBE, XXII, pp. xii, 227.

² X. 22.

the Vaiśālīka rulers as Ikshvākuids. The Pāli commentary *Paramatthajotikā*¹ traces their origin to Benares. The comparison of the Lichchhavis to the "Tāvatisa gods" hardly accords with the theory that represents them as kinsmen of snub-nosed peoples who lived beyond the Himalayas.² "Let those of the brethren" we are told by a personage of great eminence "who have never seen the *Tāvatisa* gods, gaze upon this company of the Lichchhavis, behold this company of the Lichchhavis, compare this company of the Lichchhavis—even as a company of *Tāvatisa* gods."

The date of the foundation of the Lichchhavi power is not known. But it is certain that the authority of the clan was well established in the days of Mahāvīra and Gautama, in the latter half of the sixth century B.C., and was already on the wane in the next century.

Buddhist tradition has preserved the names of eminent Lichchhavis like prince Abhaya, Oṭṭhaddha (Mahāli), generals Sīha and Ajita, Dummukha and Sunakkhatta.³ In the introductory portion of the *Ekaṇṇa*⁴ and *Chulla Kālīṅga*⁵ *Jātakas* it is stated that the Lichchhavis of the ruling family numbered 7,707.⁶ There was a like number of vice-roys, generals, and treasurers. Too much importance should not be attached to these figures which are merely traditional and may simply point to the large number of

¹ Vol. I, pp. 158-65.

² S. B. E., XI, p. 32; DPPN, II, 779.

³ *Aṅguttara Nikāya*, Nipāta III, 74 (P. T. S., Part I, p. 220 f.); *Mahāli Sutta*, *Dialogues of the Buddha*, Part I, p. 198, Part III, p. 17. *Mahāvagga*, S. B. E., XVII, p. 109; *Majjhima N.*, I. 234; 68; II. 252; *The book of the Kindred Sayings*, I, 295. For a detailed account of the Lichchhavis, see now Law, *Some Kṣatriya Tribes of Ancient India*.

⁴ 149.

⁵ 301.

⁶ Another tradition puts the number at 68,000 (DPPN, II. 781 n). The *Dhammapada Commentary* (Harvard Oriental Series, 30, 168) informs us that the *rājās* ruled by turns.

*mahallakas*¹ or elders in the clan. The real power of administration especially in regard to foreign affairs seems to have been vested in a smaller body of nine *Gaṇarājās* or archons. The Jaina *Kalpasūtra*² refers to the **nine Lichchhavis** as having formed a league with nine Mallakis and eighteen clan-lords of Kāśī-Kośala.³ We learn from the *Nirayāvalī Sūtra* that an important leader of this alliance was Cheṭaka whose sister Triśalā or Videha-dattā was the mother of Mahāvira, and whose daughter Chellanā or Vaidehī was, according to Jaina writers, the mother of Kūpika-Ajātaśatru.

The league was aimed against Magadha. Tradition says that even in the time of the famous Bimbisāra the Vaisālīans were audacious enough to invade their

¹ Cf. The Vajji Mahallakā referred to in *Dīgha*, II. 74; *Aṅguttara*, IV. 19.

² § 128.

³ *Nava Mallā (Mallatī) nava Lechchhā (Lechchhatī) Kāśī Kosalaṅgā* (variant *Kosalakā*) *aṭṭhārasa vi gaṇarāyāno*.

The *Kalpasūtra* of Bhadrabāhu, ed by Hermann Jacobi, 1879, *Jinacarita*, p. 65 (§ 128); *Nirayāvalī Sūtram* (Dr. S. Warren), 1879, § 26: *SBE*, XXII, 1884, p. 266.

Dr. Barua is inclined to identify the nine Lichchhavis and the nine Mallakis with the eighteen *gaṇarājās* who belonged to Kāśī and Kośala. He refers in this connection to the *Kalpadrūmakalikāvyaḥkhyā* which represents the Mallakis as *adhipas* (or overlords) of Kāśī-deśa, and the 'Lichchhakis' as *adhipas* of Kośala-deśa, and further describes them as *sāmantas* or vassals of Cheṭaka, maternal uncle of Mahāvira (*Indian Culture*, Vol. II, p. 810). It is new to students of Indian history that in the days of Mahāvira the kingdoms of Kāśī and Kośala acknowledged the supremacy of the Mallas and Lichchhavis respectively, and formed part of an empire over which Cheṭaka presided. Even Dr. Barua hesitates to accept this interpretation of the late Jaina commentator in its entirety and suggests that the nine Mallas and the nine Lichchhavis derived their family prestige from their original connection with the dynasties of Kāśī and Kośala. The *Paramattha-jōtikā* (Khuddaka pāṭha commentary), however, connects the Lichchhavis not with the dynasty of Kośala but with that of Kāśī. The divergent testimony of these late commentators shows that they can hardly be regarded as preserving genuine tradition. There is no suggestion in any early Buddhist or Jaina text that either the Lichchhavis or the Mallas actually ruled over any *grāma* or *nigama* in Kāśī-Kośala (see *Indian Culture*, II, 803). The *gaṇarājās* of Kāśī-Kośala apparently refer to the Kālāmas, Śākyas and other clans in the Kosalan empire.

neighbours across the Ganges.¹ In the reign of Ajātaśatru the tables were turned, and the great confederacy of Vaiśālī was utterly destroyed.²

The **Malla** territory, ancient *Malla-raṭṭha*, the *Malla-rāshṭra* of the *Mahābhārata*,³ was split up into two main parts which had for their capitals the cities of Kusāvati or Kusinārā and Pāvā.⁴ The river, Kakutthā, the *Cacouthes* of the classical writers, identified with the modern Kuku, probably formed the dividing line.⁵ The division of the people is also known to the great epic⁶ which draws a distinction between the Mallas proper and the Dakṣiṇa or Southern Mallas. There is no agreement among scholars regarding the exact site of **Kusinārā**. In the *Mahā-parinibbāna Suttanta* it is stated that the *Sāla* Grove of the Mallas, the *Upavattana* (outskirt or suburb)⁷ of Kusinārā, lay near the river *Hiranyavatī*. Smith identifies the stream with the Gaṇḍak and says that Kuśīnagara (Kusinārā) was situated in Nepāl, beyond the first range of hills, at the junction of the Little, or Eastern Rāptī with the Gaṇḍak.⁸ He, however, admits that the discovery in the large *stūpa* behind the *Nirvāṇa* temple near Kasiā on the Choṭa Gaṇḍak, in the east of the Gorakhpur district, of an inscribed copper-plate bearing the words "[*parini*]r *vāṇa-chaitye tāmrapaṭṭa iti*,"⁹ supports the old theory, propounded by Wilson and accepted by Cunningham, that the remains near Kasiā represent Kuśī-nagara.

¹ *Si-yu-ki*, bk. IX.

² *DPPN*, II. 781-92.

³ VI. 9. 34.

⁴ *Kusa Jātaka*, No. 531; *Mahā-parinibbāna Suttanta*, *Dialogues of the Buddha*, Part II, pp. 136 ff., 161-62.

⁵ *AGI* (1924), 714.

⁶ *Mbh.* II. 30. 3 and 12.

⁷ *JRAS*, 1906, 669; *Dīgha*, II. 137.

⁸ *EHI*, third ed., p. 169 n.

⁹ *ASI*, A. R. 1911-12, 17 ff.; *JRAS*, 1913, 162. Kasiā is a village that lies about 35 miles to the east of Gorakhpur (*AGI*, 493).

Pāvā was identified by Cunningham¹ with the village named Padaraona, 12 miles to the N.N.E. of Kasiā, and separated from it by the Bādhi Nala (identified with the ancient Kakutthā). Carlleyle, however, proposes to identify Pāvā with Fāzilpur, 10 miles S.E. of Kasiā and separated from it by the Kuku.² In the *Saṅgīti Suttanta* we have a reference to the Mote Hall of the Pāvā Mallas named Ubbhaṭaka.³

The Mallas together with the Licchavis are classed by Manu as *Vrātya* Kshatriyas. They, too, like their eastern neighbours were among ardent champions of Buddhism.

Like Videha, Malla had at first a monarchical constitution. The *Kusa Jātaka* mentions a Malla king named Okkāka (Ikshvāku). The name probably suggests that like the Śākya⁴ the Malla princes also claimed to belong to the Ikshvāku family. And this is confirmed by the fact that in the *Mahā-parinibbāna Suttanta* they are sometimes called Vāsetṭhas, i.e., "belonging to the Vasishṭha gotra."⁵ The *Mahāsudassana Sutta* mentions another king named Mahāsudassana.⁶ These rulers, Okkāka and Mahāsudassana, may or may not have been historical individuals. But the tales that cluster round their names imply that Mallaratṭha was at first ruled by kings. This conclusion is confirmed by the evidence of the *Mahābhārata*⁷ which refers to an overlord (*adhipa*) of the Mallas. During the monarchical period the metropolis was a great city and was styled

¹ *AGI*, 1924, 498.

² Kakutthā; *AGI*, 1924, 714.

³ *DPPN*, II, 194.

⁴ Cf. *Dialogues*, Part I, pp. 114-15.

⁵ *Dialogues of the Buddha*, Part II, pp. 162, 179, 181. Vasishṭha figures in the *Rāmāyaṇa* as the *purohita* of the Ikshvākuids.

⁶ *S. B. E.*, XI, p. 248.

⁷ II, 30, 3.

Kusāvati. Other important cities were Anupiyā and Uruvelakappa.¹

Before Bimbisāra's time the monarchy had been replaced by republics² and the chief metropolis had sunk to the level of a "little wattle and daub town," a "branch township" surrounded by jungles.³ It was then styled Kusinārā.

The relations of the Mallas with the Lichchhavis were sometimes hostile and on other occasions friendly. The introductory story of the *Bhaddasāla Jātaka*⁴ contains an account of a conflict between Bandhula the Mallian, Commander-in-chief of the king of Kośala, and 500 elders of the Lichchhavis. The Jaina *Kalpasūtra*, however, refers to "nine Mallakis" as having combined with the Lichchhavis, and the seigniors of Kāsi-Kośala against Kūṇika-Ajātaśatru who, like Philip of Macedon, was trying to absorb the territories of his republican neighbours. The Malla territory was finally annexed to Magadha. It certainly formed a part of the Maurya Empire in the third century B.C.

Chedi was one of the countries encircling the Kurus, *paritah Kurūn*, and lay near the Jumna.⁵ It was closely connected with the Matsyas beyond the Chambal, the Kāśis of Benares, and the Kārushas in the valley of the Son,⁶ and

¹ Law, *Some Kṣatriya Tribes*, p. 149. *Dialogues*, Pt. III (1921), 7; *Gradual Sayings*, IV. 293. Anupiyā stood on the banks of the river Anomā which lay thirty leagues to the east of Kapilavastu. It was here that the future Buddha cut off his hair and put on the robes of the ascetics. (DPPN, I, 81, 102).

² *Cj. S. B. E.* XI, p. 102; Kauṭilya's *Arthaśāstra*, 1919, p. 378.

³ *Khudda-nagaraka, ujjāṅgala-nagaraka, sākā-nagaraka.*

⁴ No. 465.

⁵ Pargiter, *JASB*, 1895, 253 ff; *Mbh.* I. 63. 2-58; IV. i. 11.

Santi ramyā janapadā

bahvannāḥ paritah Kurūn

Pañchālāś-Chedi-Matsyāścha

Sūrasenāḥ Paṭachcharāḥ

Daśārnā Navarāṣṭrāścha

Mallāḥ Sāleā Yugandharāḥ.

⁶ *Mbh.* V. 22, 25; 74 16; 198. 2; VI. 47. 4; 54. 8.

is distinguished from the Daśārṇas who lived on the banks of the Dhasan.¹ In ancient times it corresponded roughly to the eastern part of modern Bundelkhand and some adjoining tracts.² In the mediæval period, however, the southern frontiers of Chedi extended to the banks of the Narmadā (*Mekala-Sutā*):—

Nadīnām Mekala-sutā nṛipānām Raṇavigrahaḥ

*kavīnām cha Surānandaś Chedi-maṇḍala-maṇḍanam*³

We learn from the *Chetiya Jātaka*⁴ that the metropolis was Soththivatī-nagara. The *Mahābhārata* gives its Sanskrit name Śuktimatī, or Śukti-sāhvaya.⁵ The Great Epic mentions also a river called Śuktimatī which flowed by the capital of Rājā Uparichara of the *Chedi-vishaya* (district).⁶ Pargiter identifies the stream with the Ken, and places the city of Śuktimatī in the neighbourhood of Banda.⁷ Other towns of note were Sahajāti,⁸ and Tripurī,⁹ the mediæval capital of the *Janapada*.

¹ Princesses of Daśārṇa were given in marriage to Bhima of Vidarbha and Virabāhu or Subāhu of Chedi (*Mbh.* III, 69, 14-15).

² Pargiter (*JASB*, 1895, 253) places Chedi along the south bank of the Jumna from the Chambal on the north-west as far as Karwi on the south-east; its limits southwards may have been, according to him, the plateau of Malwa and the hills of Bundelkhand.

³ Attributed to Rājasekhara in Jahlaṇa's *Śuktimuktāvalī*, Ep. Ind. IV. 280. Kouow. *Karpūramajjarī*, p. 182.

⁴ No. 422.

⁵ III. 20. 50; XIV. 83. 2; N. L. Dey, *Ind. Ant.*, 1919, p. vii of *Geographical Dictionary*.

⁶ I, 63. 35.

⁷ *JASB*, 1895, 255, *Mārkaṇḍeya P.*, p. 359.

⁸ *Aṅguttara*, III. 355 (P.T.S.). *Ayasmā Mahāchundo Chetisu viharati Sahajātiyaṃ*. Sahajāti lay on the trade route along the river Ganges (*Buddhist India*, p. 103). Cf. the legend on a seal-die of terra-cotta found at Bhitā, 10 miles from Allahabad (*Arch. Expl. Ind.*, 1909-10, by Marshall, *JRAS*, 1911, 128 f.).—*Sahjītiye nigamaśa*, in letters of about the third century B.C. see also *JBORS*, XIX, 1933, 293.

⁹ Tripurī stood close to the Nerbudda not far from modern Jubbalspre. In the *Haimakosha* it is called Chedinagarī (*JASB*, 1895, 249). The city finds mention in the *Mbh.* III. 253. 10, along with Kośalā, and its people, the Traipuras, are referred in VI. 87. 9. together with the Mekalas and the Kurubindas.

The Chedi people are mentioned as early as the *Rig-Veda*. Their king Kasu Chaidya is praised in a *Dānastuti* (praise of gift) occurring at the end of one hymn.¹ Rapson proposes to identify him with 'Vasu' of the Epics.

The *Chetiya Jātaka* gives a legendary genealogy of Chaidya kings, taking their descent from Mahāsammata and Māndhātā. Upachara, a King of the line, had five sons who are said to have founded the cities of Hatthipura, Assapura, Sihapura, Uttarapañchāla and Daddarapura.² This monarch is probably identical with Uparichara Vasu, the Paurava king of Chedi, mentioned in the *Mahābhārata*,³ whose five sons also founded five lines of kings.⁴ But epic tradition associates the scions of Vasu's family with the cities of Kauśāmbī, Mahodaya (Kanauj) and Girivraja.⁵

The *Mahābhārata* speaks also of other Chedi kings like Damaghosha, his son Śiśupāla Sunītha and his sons Dhṛiṣṭaketu and Śarabha who reigned about the time of the Bhārata war. But the *Jātaka* and epic accounts of the early kings of Chedi are essentially legendary and, in the absence of more reliable evidence, cannot be accepted as genuine history.

We learn from the *Vedabbha Jātaka*⁶ that the road from Kāśī to Chedi was unsafe being infested with roving bands of marauders.

¹ VIII. 5. 37-39.

² Hatthipura may be identified with Hatthinipura or Hāstinapura in the Kuru country. Assapura with the city of that name in Aṅga, and Sihapura with the town of Lāla from which Vijaya went to Ceylon. There was another Sihapura in the Western Punjab (Watters I. 248). Uttarapañchāla is Ahichakhtra in Rohilkhand. Daddarapura was apparently in the Himalayan region. (DPPN, I. 1054).

³ I. 63. 1-2.

⁴ I. 63. 30.

⁵ *Rāmāyaṇa*, I. 32. 6-9; *Mahābhārata*, I. 63. 30-33.

⁶ No. 46.

Vaiśā or **Vatsa** was the country south of the Ganges¹ of which Kauśāmbī, modern Kosam, on the Jumna, near Allahabad, was the capital.² Oldenberg³ is inclined to identify the Vaiśas with the Vaśas of the *Aitareya Brāhmaṇa*. But the conjecture lacks proof. The *Satapatha Brāhmaṇa* mentions a teacher named Proti Kauśāmbeya⁴ whom Harisvāmin, the commentator, considers to be a native of the town of Kauśāmbī.⁵ Epic tradition attributes the foundation of this famous city to a Chedi prince.⁶ The origin of the Vatsa people, however, is traced to a king of Kāśī.⁷ It is stated in the *Purāṇas* that when the city of Hāstinapura was washed away by the Ganges, Nichakshu, the great-great-grandson of Janamejaya, abandoned it, and removed his residence to Kauśāmbī. We have already seen that the Purāṇic tradition about the Bhārata or Kuru origin of the later kings of Kauśāmbī is confirmed by two plays attributed to Bhāsa. Udayana, king of Kauśāmbī, is described in the *Svapnavāsavadatta* and the *Pratijñā Yaugandharāyaṇa*⁸ as a scion of the *Bhārata-kula*.

The *Purāṇas* give a list of Nichakshu's successors down to Kshemaka, and cite the following genealogical verse :—

¹ Rām. II, 52. 101.

² Nariman, Jackson and Ogden, *Priyadarśikā*. lxxvi; the *Bṛihat Kathā-Sloka Saṃgraha* (4. 14, cf. 8, 21) explicitly states that Kauśāmbī was on the Kālindī or Jumna. Malalasekera, DPPN, 694. The reference in one text to the position of the city on the Ganges is possibly due to its proximity to the confluence of the Ganges and the Jumna in ancient times, or to a copyist's error.

³ *Buddha*, 393 n.

⁴ *Sat. Br.*, XII, 2, 2. 13.

⁵ See p. 70 *ante*.

⁶ *Rām.*, I, 32. 3-6; *Mbh.* I. 63. 31.

⁷ *Harivamśa*, 29. 73; *Mbh.*, XII. 49. 80.

⁸ *Svapna*, ed. Gaṇapati Śāstrī, p. 140; *Pratijñā*, pp. 61, 121.

*Brahma-kshatrasya¹ yo yonir
 vaṁśo devarshi-satkṛitah
 Kshemakam prāpya rājānam
 saṁsthām prāpsyati vai kalau.*

“The family honoured by gods and sages (or divine sages), from which sprang Brāhmaṇas and Kshatriyas (or those who combined the Brāhmaṇa and Kshatriya status) will verily, on reaching Kshemaka, come to an end (or be interrupted) in the Kali Age.”

The criticism that has been offered in this work in regard to the Ikshvāku and Magadha lists of kings applies with equal force to the Paurava-Bhārata line. Here, too, we find mention of princes (*e.g.*, Arjuna and Abhimanyu) who can hardly be regarded as crowned *nṛipas* or monarchs. It is also by no means improbable that, as in the case of the Ikshvākus and the royal houses of Magadha and Avanti, contemporaries have been represented as successors and collaterals described as lineal descendants. There is, moreover, no unanimity in regard to the names of even the immediate predecessors of Udayana, the most famous among the later kings of the family. These facts should be remembered in determining the chronology and order of succession of the Bhārata dynasty of Kauśāmbī. The earliest king of the line about whom we know anything definite is Śatānīka II of the Purāṇic lists. His father's name was Vasudāna according to the *Purāṇas*, and Sahaśrānīka according to ‘Bhāsa.’ Śatānīka himself was also styled Parantapa.² He married a princess of Videha as his son is called

¹ Cf. *Brahma-Kshatriyāḍyām kula* of the inscriptions of the Sena kings who claimed descent from the Lunar Race to which the Bhāratas, including the Kurus, belonged.

² *Buddhist India*, p. 8.

Vaidehīputra.¹ He is said to have attacked Champā, the capital of Aṅga, during the reign of Dadhivāhana.² His son and successor was the famous Udayana, the contemporary of the Buddha and of Pradyota of Avanti and therefore, of Bimbisāra and Ajātaśatru of Magadha.

The *Bhagga* (Bhargha) state of Surūsumāragiri, 'Crocodile Hill', was a dependency of Vatsa.³ The *Mahābhārata*⁴ and the *Harivaṃśa*⁵ testify to the close connection of these two territories and their proximity to the principality of a Nishāda chieftain, while the *Apadāna* seems to associate Bhargha with Kārusha.⁶ The evidence points to the location of Surūsumāragiri between the Jumna and the lower valley of the Śon.

The **Kuru** realm was according to the *Mahā-Sutasoma jātaka*⁷ three hundred leagues in extent. The reigning dynasty according to the Pali texts belonged to the Yuddhiṭṭhila *gotra*, i.e., the family of Yuddhisṭhira.⁸ The capital was Indapatta or Indapattana, i.e., Indraprastha or Indrapat near modern Delhi. It extended over seven leagues.⁹ We hear also of another city called Hatthinīpura,¹⁰ doubtless, the Hāstināpura of the epic, and a number of *nigamas* or smaller towns and villages besides

¹ *Seapna-rāsarodatto*, Act VI, p. 129.

² *JASB*, 1914, p. 321.

³ *Jātaka*, No. 353; *Carmichael Lec.*, 1918, p. 63.

⁴ II. 30. 10-11.

*Vatsabhūmīnā Kaunteya vijigye balarān balāt
Bhargōmadhipaṇchaiva Nishādādhipatīm tathā.*

"The mighty son of Kunti (i.e. Bhīmaśeṇa) conquered by force the Vatsa country and the lord of the Bhargas and then the chieftain of the Nishādās"

⁵ 29. 73. *Pratardanasya putrau dāu*

Vatsa-Bhargau babhūvatuh

"Pratardana had two sons, Vatsa and Bharga."

⁶ *DPPN*, II. 345

⁷ No. 537.

⁸ *Dharmakīrti Jātaka*, No. 413; *Dasa Brāhmaṇa Jātaka*, No. 495.

⁹ *Jātaka Nos.* 537, 545.

¹⁰ *The Buddhist Conception of Spirits*: *DPPN*, II, 1319.

the capital, such as Thullakoṭṭhita, Kammāssadamma, Kuṇḍi and Vāraṇāvata.¹

The *Jātakas* mention the Kuru kings and princes styled Dhanañjaya Koravya,² Koravya,³ and Sutasoma.⁴ We cannot, however, vouch for their historical existence in the absence of further evidence.

The Jaina *Uttarādhyayana Sūtra* mentions a king named Ishukāra ruling at the town called Ishukāra in the Kuru country.⁵ It seems probable that after the removal of the elder branch of the royal family to Kauśāmbī and the decline of the Ābhipratāriṇas, the Kuru realm was parcelled out into small states of which Indapatta and Ishukāra were apparently the most important. "Kings" are mentioned as late as the time of the Buddha when one of them paid a visit to Raṭṭhapāla, son of a Kuru magnate, who had become a disciple of the Śākya Sage. Later on, the little principalities gave place to a *Sangha* possibly, a republican confederation.⁷

Pañchāla, as already stated, comprised Rohilkhand and a part of the Central Doāb. The *Mahābhārata*, the *Jātakas* and the *Divyāvadāna*⁸ refer to the division of this country into two parts, viz, Uttara or Northern Pañchāla and Dakshina or Southern Pañchāla. The Bhāgīrathī (Ganges) formed the dividing line.⁹ According to the

¹ The epic (Mbh. V. 31, 19; 72, 15 etc.) has a reference to four villages, viz., Avisthala, Vrikasthala, Mākandī, Vāraṇāvata.

² *Kurudharmā Jātaka*, No. 276; *Dhūmakāri Jātaka*, No. 413; *Sambhara Jātaka*, No. 515; *Vidhura Paṇḍita Jātaka*, No. 545. Dhanañjaya is, as is well-known, a name of Arjuna.

³ *Dasa Brāhminya Jātaka*, No. 495; *Mahā-Sutasoma Jātaka*, No. 537.

⁴ *Mahā-Sutasoma Jātaka*. Cf. the *Mahābhārata*, I. 93. 75 where Sutasoma appears as the name of a son of Bhīma.

⁵ S. B. E., XLV. 62.

⁶ DPPN, II. 706 f.

⁷ *Arthśāstra*, 1919, 378.

⁸ P. 436.

⁹ *Mbh.*, I. 138. 70. For divisions in Vedic times see 70 f. ante.

Great Epic, Northern Pañchāla had its capital at Ahichchhatra or Chhatravati, the modern Rāmānagar near Aonla in the Bareilly District, while Southern Pañchāla had its capital at Kāmpilya, and stretched from the Ganges to the Chambal.¹ A great struggle raged in ancient times between the Kurus and the Pañchālas for the possession of Northern (Uttara) Pañchāla. Sometimes Uttara Pañchāla was included in Kururāṭṭha (-rāshṭra)² and had its capital at Hāstinapura,³ at other times it formed a part of Kāmpilla-rāṭṭha (Kāmpilya-rāshṭra).⁴ Sometimes kings of Kāmpilya-rāshṭra held court at Uttara Pañchāla-nagara, at other times kings of Uttara Pañchāla-rāshṭra held court at Kāmpilya.⁵

The history of Pañchāla from the death of Pravāhaṇa Jaivala or Jaivali to the time of Bimbisāra of Magadha is obscure. The only king who may perhaps be referred to this period is Durmukha (Dummukha), the contemporary of Nimi,⁶ who is probably to be identified with the penultimate sovereign of Mithilā.⁷ In the *Kumbhakāra Jātaka* it is stated that Durmukha's kingdom was styled Uttara Pañchāla-rāṭṭha (-rāshṭra); his capital was not Ahichchhatra but Kāmpilla (Kāmpilya)-nagara. He is represented as a contemporary of Karaṇḍu, king of Kālīṅga, Naggaji (Nagnajit), king of Gandhāra, and Nimi, king of Videha. The *Aitareya Brahmana*⁸ credits him with extensive conquests and names Bṛihaduktha as his priest :—

¹ *Mbh.*, I. 138. 73-74.

² *Sumanassa Jātaka*, No. 505; *Mahābhārata*, I. 133.

³ *Dīpāvadāna*, p. 435.

⁴ *Brahmadatta Jātaka*, No. 323; *Jayaddiya Jātaka*, No. 513 and *Gaṇḍatindu Jātaka*, No. 590.

⁵ *Kumbhakāra Jātaka*, No. 408.

⁶ *Jātaka*, No. 408.

⁷ *Jātaka*, No. 541.

⁸ VIII. 23.

“*Etam ha vā Aindraṃ Mahābhishekaṃ Bṛihaduktha Rishir Durmukhāya Pañchālāya provacha tasmādu Durmukhaḥ Pañchālo Rājā san vidyayā samantaṃ sarvataḥ pṛithivīm jayan pariyāya.*”

“This great anointing of Indra Bṛihaduktha, the seer, proclaimed to Durmukha, the Pañchāla. Therefore, Durmukha Pañchāla, being a king, by this knowledge, went round the earth completely, conquering on every side.”¹

A great Pañchāla king named Chulani Brahmadata is mentioned in the *Mahā-Ummagga Jātaka*,² the *Uttarādhyayana Sūtra*,³ the *Svapna-vāsavadattā*⁴ and the *Rāmāyana*.⁵ In the last-mentioned work he is said to have married the daughters (*kanyāḥ*) of Kuśanābha who were made hump-backed (*kubja*) by the Wind-god. In the *Jātaka*, Kevatta, the minister of Brahmadata, is said to have formed a plan for making Chulani chief king of all India, and the king himself is represented as having laid siege to Mithilā. In the *Uttarādhyayana* Brahmadata is styled a universal monarch. The story of this king is, however, essentially legendary, and little reliance can be placed on it. The Rāmāyaṇic legend regarding the king is only important as showing the connection of the early Pañchālas with the foundation of the famous city of Kanyākubja (Kanauj) whose name (city of the hump-backed maiden) is accounted for by the curse to which the story refers.⁶

¹ Keith, *Rig-Veda Brāhmaṇas*, Harvard Oriental Series, Vol. 25.

² 546.

³ S. B. E., XLV. 57-61.

⁴ Act V.

⁵ I. 32.

⁶ Cf. Watters, *Yuan Chwang*, I. 341-42. The point seems to be missed by Ratilal Mehta, *Pre-Buddhist India*, 43 n. The name Kanyākubja or Kānyakubja is already met with in the *Mahābhārata*, I. 175. 3; V. 119. 4. Kānyakubji occurs in the *Mahābhāshya* IV. 1. 2. (233), along with Ahichchatri. Kāṇṇakujja appears in Pāli texts (DPPN, I. 498).

The *Uttar-ādhyayana Sūtra* mentions a king of Kāmpilya named Sañjaya who gave up his kingly power and adopted the faith of the Jinas.¹ We do not know what happened after Sañjaya renounced his throne. But there is reason to believe that the Pañchālas, like the Videhas, Mallas and Kurus, established a *Saṅgha* form of government of the *Rāja-śabd-opajīvin* type.²

Matsya was the extensive territory between the hills near the Chambal and the forests that skirted the Sarasvatī, of which the centre was Virāṭa-nagara or Bairāt in the modern Jaipur State. The early history of the kingdom has already been related. Its vicissitudes during the period which immediately preceded the reign of Bimbisāra of Magadha are not known.³ It is not included by the *Kauṭīliya Arthaśāstra* among those states which had a *Saṅgha* or non-monarchical form of government. The probability is that the monarchical constitution endured till the loss of its independence. It was probably at one time annexed to the neighbouring kingdom of Chedi. The *Mahābhārata*⁴ refers to a king named Sahaja who reigned over the Chedis as well as the Matsyas. It was finally absorbed into the Magadha Empire. Some of the most famous edicts of Aśoka have been found at Bairāt.

A family of Matsyas settled in the Vizagapatam region in mediæval times.⁵ We are told that Jayatsena, the lord of Utkala, gave to Satyamārtanḍa of the Matsya family in marriage his daughter Prabhāvatī, and appointed him to

¹ S.B.E., XLV. 80-82.

² *Arthaśāstra*, 1919, p. 378. The Elders of this type of corporations or confederations took the title of *Rājā*. One of these *rājās* was apparently the maternal grandfather of Viśākha Pañchālīputra, a disciple of the Buddha (DPPN. II. 108).

³ 66 ff ante.

⁴ V. 74. 16; cf. VI. 47, 67; 52. 9.

⁵ Dibbida plates, *Ep. Ind.*, V. 108.

rule over the Oḍḍavādi country. After twenty-three generations came Arjuna who ruled in 1269 A.D.

The **Śūrasena** country had its capital at Mathurā which, like Kauśāmbī, stood on the Jumna. Neither the country nor its metropolis finds any mention in the Vedic literature. But Greek writers refer to the Sourasenoi and their cities Methora (Mathurā) and Cleisobora. Buddhist theologians make complaint about the absence of amenities in Mathurā. They were apparently not much interested in its kettledrums,¹ or in the *śaṭakas* (garments) and *kārshāpaṇas* (coins) about which Patañjali speaks in the *Mahābhāṣya*.² A highroad connected the city with a place called Verañjā which was linked up with Śrāvastī and the caravan-route that passed from Taxila to Benares through Soreyya, Saṅkassa (Sāṅkāśya), Kaṇṇakujja (Kanyākubja or Kanauj), and Payāga-Patiṭṭhāna (Allahabad).³

In the *Mahābhārata* and the *Purāṇas* the ruling family of Mathurā is styled the **Yadu** or Yādava family. The Yādavas were divided into various septs, namely, the Vitihotras, **Sātvatas**, etc.⁴ The Sātvatas were subdivided into several branches, *e.g.*, the Daivāvṛidhas, Andhakas, Mahā-bhojas and Vṛishnis.⁵

Yadu and his tribe are repeatedly mentioned in the *Rig-Veda*. He is closely associated with Turvaśa and, in one place, with Druhyu, Anu and Pūru.⁶ This association is also implied by the epic and Purāṇic legends which state that Yadu and Turvaśu were the sons of the same parents, and Druhyu, Anu and Pūru were their step-brothers.

¹ *Gradual Sayings*, II. 78; III. 193.

² I. 2. 48 (Kielhorn I. 19).

³ *Gradual Sayings*, II. p. 66; DPPN. II. 438, 990, 1311.

⁴ *Matsya*, 43-44; *Vāyu*, 94-96.

⁵ *Vishnu*, IV. 13. 1; *Vāyu*, 96. 1-2.

⁶ I. 108. 5.

We learn from the *Rig-veda*¹ that Yadu and Turvaśa came from a distant land, and the former is brought into very special relation to the **Parśus** or Persians.² The Sātvasas or **Satvats** also appear to be mentioned in the Vedic texts. In the *Satapatha Brāhmaṇa*³ the defeat by Bharata of the Satvats and his taking away the horse which they had prepared for an *Aśvamedha* sacrifice, are referred to. The geographical position of Bharata's kingdom is clearly shown by the fact that he made offerings on the Sarasvatī, the Jumna and the Ganges.⁴ The Satvats must have been occupying some adjoining region. The epic and Purāṇic tradition which places them in the Mathurā district is thus amply confirmed. At a later time, however, a branch of the Satvats seems to have migrated farther to the south, for in the *Aitareya Brāhmaṇa*⁵ the Satvats are described as a southern people who lived beyond the Kuru-Pañchāla area, i.e., beyond the river Chambal, and were ruled by **Bhoja** kings. In

¹ I. 36. 18; VI. 45. 1.

² VIII. 6. 46, Epigraphic evidence points to a close connection between Western Asia and India from about the middle of the second millennium B. C. Rig-Vedic Gods like Sūrya (Shurias), Marut (Maruttash), Indra, Mitra, Varuṇa, the Nāsatyas, and even **Dakṣha** (*dakash*, star, CAH. I. 553) figure in the records of the Kassites and the Mitanni.

³ XIII. 5. 4. 21 *Satānikaḥ samantāsu medhyaṁ Sā'rājīto hayam
ādatta gojñam Kāṣīnam Bharataḥ Satvatāmiva.*

The *Mbh.* vii 66. 7 (*mā satteḍni vijijahi*) seems to miss the import of the Brāhmaṇic *gāthā*.

⁴ *Sat. Br.* XIII. 5. 4. 11. *Ait. Br.* VIII. 23; *Mbh.* VII. 66. 8.

*Ashṭāsaptatiṁ Bharato Dauḥshantir Yamunāmanu
Gaṅgāyām Vṛitraghne' badhnāt pañchapañchāśataṁ hayān
Mahākarma (variant mahadadya) Bharatasya na pūrve nāpare fanāh
divyaṁ martya iva hastyābhyām (variant bāhubhyām)
nodāpuḥ pañcha mānatā (iti).*

*So śvamedhaśateneshṭvā Yamunāmanu ciryavān
triśatāśvān Sarasvatyām Gaṅgāmanu chaturśatān...*

⁵ VIII. 14. 3.

the Purāṇas also we find that a branch of the Sātvaś was styled Bhoja¹ :—

“*Bhājina-Bhājamāna-dīvy-Āndhaka-Devāvrīdha- Mahā-bhoja-Vṛishṇi-samjñah- Sātvaśasya putrā babhūvuh..... Mahābhojastvati dharmātmā tasyānvaye Bhoja-Mārtikāvātā babhūvuh.*”²

It is further stated that several southern states, Māhishmatī, **Vidarbha**, etc., were founded by princes of Yādu lineage.³ Not only the Bhojas, but the Devāvrīdha branch of the Sātvaś finds mention in the Vedic literature. Babhru Daivāvrīdha⁴ is mentioned in the *Aitareya Brāhmaṇa*⁵ as a contemporary of Bhīma, king of Vidarbha, and of Nagnajit, king of Gandhāra. The Andhakas and **Vṛishṇis** are referred to in the *Ashṭādhyāyī* of Pāṇini.⁶ In the *Kauṭīliya Arthaśāstra*⁷ the Vṛishṇis are described as a *Saṅgha*, i. e., a republican corporation. The *Mahābhārata*, too, refers to the Vṛishṇis, Andhakas and other associate tribes as a *Saṅgha*,⁸ and Vāsudeva, the Vṛishṇi prince, as *Saṅgha-mukhya* (Elder or Seigneur of the confederacy). The name of the Vṛishṇi corporation (*gaṇa*) has also been preserved by a unique coin.⁹ It is stated in the *Mahābhārata* and the *Purāṇas* that Kāṁsa, like Peisistratus and others of Greek history, tried to make himself tyrant at Mathurā by overpowering the Yādavas, and that Kṛishṇa-Vāsudeva, a scion

¹ *Vishṇu* IV. 13. 1-6. In *Mbh.* VIII. 7. 8 the Sātvaś-Bhojas are located in Anarta(Gujrāt).

² *Mat.*, 43. 10-29; 41. 33; *Vāyu*, 94. 26; 95. 35.

³ *Vāyu*, 96. 15; *Vishṇu*, 13. 3-5.

⁴ VII. 34.

⁵ IV. 1. 114; VI. 2. 34.

⁶ P. 12.

⁷ XII. 81. 25.

⁸ Majumdar, *Corporate Life in Ancient India*, p. 119; Allao, *CCAI*, pp. civf. 281.

of the Vṛishṇi family, killed him. The slaying of Kāṁsa by Kṛishṇa is referred to by Patañjali and the *Ghata Jātaka*.¹ The latter work confirms the Hindu tradition about the association of Kṛishṇa-Vāsudeva's family with Mathurā (Uttara Madhurā).²

¹ No. 454.

² The city is so called to distinguish it from Madura in South India. The question of the historical existence of Kṛishṇa Vāsudeva has been discussed in my *Early History of the Vaishṇava Sect*, 1st ed., pp. 26-35; 2nd ed., pp. 51 ff. and my *Political History of Ancient India*, 1st ed., 1923, p. 312.

Several scholars reject the identification of Kṛishṇa of the *Mahābhārata* and the *Purāṇas* with the historical Kṛishṇa of the *Chhāndogya Upanishad* (III. 17). But we should remember that—

(a) Both the Kṛishṇas have the metronymic *Devakiputra*, son of Devaki, which is rare in early times.

(b) The teacher of the Upanishadic Kṛishṇa belonged to a family (Āṅgīrasa) closely associated with the Bhojas (*Ṛig-Veda*. III. 53. 7), the kindreds of the Epic Kṛishṇa (*Mbh.*, II. 14. 32-34).

(c) The Upanishadic Kṛishṇa and his *Guru* Ghora Āṅgīrasa were worshippers of *Sūrya* (the Sun-god). We are told in the *Sāntiparva* (335. 19) that the *Sātrata-vidhi* taught by the Epic Kṛishṇa was *prāk-Sūrya-mukha-niḥṣṛita*.

(d) An Āṅgīrasa was the *Guru* of the Upanishadic Kṛishṇa. *Āṅgīrasī Śruti* is quoted as "*Śrutināmuttamā Śrutiḥ*" by the Epic Kṛishṇa (*Mbh.*, VIII. 69. 85).

(e) The Upanishadic Kṛishṇa is taught the worship of the Sun, the noblest of all rights (*jyotiḥ-uttamamiti*), high above all darkness (*tamasaspari*). This has its parallel in the *Gītā* (XIII. 18—*jyotiḥmāpi tajjyotiḥ tamasaḥ param uchyaṭe*);

(f) The Upanishadic Kṛishṇa is taught to value, not any material reward (*dakṣiṇā*), but rather the virtues of *tapodānam ājīvaṁ ahiṁsā satyavachanam*. The *Gītā* also eulogises action performed not for the material fruit thereof. Stress is laid in *Gītā* XVI. 1-2 on the virtues enumerated in the Upanishads.

The *Purāṇas* no doubt represent Sāndīpani, and not Ghora, as the great teacher of Kṛishṇa. But it has to be remembered that according to the *Vishṇu Purāṇa* (V. 21. 19) Kṛishṇa went to the sage Sāndīpani to learn lessons in the science of arms (*astrasikṣhā*) :

Tataḥ Sāndīpaniṁ Kāśyam Atantipuravāsinaṁ

astrārtham jagmaturtīraḥ Baladeva-Janārdanaḥ.

The *Harivaṁśa*, too, informs us (*Vishṇupurāṇa*, 33, 4 ff.) that the residence of Kṛishṇa, who was already a *śrutidhara*, with his *Guru* Sāndīpani was due to his desire of receiving lessons in the science of the bow (*dhanurvedachikīrṣhārtham*). The *Veda* that he learnt from this teacher is not termed *akhīla Veda*, or *Trayi*, but simply *sāṅga-Vedaṁ*, the *Veda* with its auxiliary treatises. The only *Veda* that is expressly mentioned is the *Dhanurveda* (and not the *Trayi*) together with its four divisions (*chaturpāda*), etc. The compilers of the *Bhāgavata* and *Brahma Vaivarta Purāṇas* (*Bhāg.* X. 45. 31 ff.; *BV, Janmakhanda*, 101-102) introduce

The final overthrow of the Vrishnis is ascribed to their irreverent conduct towards Brāhmaṇas.¹ It is interesting to note that the Vrishnis and the Andhakas are branded as *Vrātyas*, i.e., deviators from orthodoxy in the *Drona parva* of the *Mahābhārata*.² It is a remarkable fact that the Vrishni-Andhakas and other *Vrātya* clans, e.g., the Lichchhavis and Mallas, are found in historical times on the southern and eastern fringe of the "*Dhruvā Madhyamā diś*" occupied by the Kuru-Pañchālas and two other folks. It is not improbable that they represent an earlier swarm of Aryans who were pushed southwards and eastwards by the Pūru-Bharatas, the progenitors of the Kuru Pañchālas. It may be remembered that the *Satapatha Brāhmaṇa* actually refers to the defeat by Bharata of the Satvats—the progenitors of the Vrishni-Andhakas. And the Great Epic refers to the **exodus of the Yādavas from Mathurā** owing to pressure from the Paurava line of Magadha, and probably also from the Kurus.³

The Buddhist texts refer to Avantiputta, king of the Sūrasenas, in the time of Mahā-Kachchāna,⁴ one of the

details about the study of all the *Vedas*, *Upanishads*, treatises on law, philosophy, polity, etc., which are not found in the relevant passage of the *Vishnu Purāṇa*, which, according to critics like Bankim Chandra Chatterjādhyāya, represents an earlier and more reliable tradition. Residence with Sāndipani, therefore, does not conflict with the view that Kṛṣṇa accepted the discipleship of Ghora for purposes of religious and philosophical studies (see *EHVS*, 2nd ed., pp. 76-74). Sāndipani already knew him to be a *Śrutidhara* (versed in the *Śruti* or the *Vedas*; *Hari-vaṃśa*, *Vishnupurāṇa*, 33, 6).

Real discrepancies in regard to certain names are sometimes met with in Vedic and epic versions of several legends e.g., the story of Sanakṣepa. But even these are not regarded as adequate grounds for doubting the identity of the leading character of the Vedic *Akhyāna* with that of the corresponding epic tale.

¹ *Mahābhārata*, *Maushala parva*, I. 15-22; 2. 10; *Arthashastra*, 1919 p. 12; *Jātaka* Eng. trans. IV. pp. 55-56 V. p. 138. Fauböll, IV. 87f; V. 267.

² [41. 15.

³ Cf *Bahu-Kurucharā Mathurā*, Patanjali. IV. 1. 1.; *GEI*, p. 306 n.

⁴ M. 2° 83, DPPN, II. 438.

chief disciples of Sākyamuni, through whose agency Buddhism gained ground in the Mathurā region. The name of the king suggests relationship with the royal house of Avanti. A king named Kuvinda is mentioned in the *Kāvya-Mīmāṃsā*.¹ The Śūrasenas continued to be a notable people down to the time of Megasthenes. But at that time they must have formed an integral part of the Maurya Empire.

Assaka (*Aśmaka*) was situated on the banks of the Godāvarī.² Its capital, Potali, Potana or Podana³ is possibly to be identified with **Bodhan** in the Nizam's dominions. This accords with its position between Mūlaka (district round Paithān) and Kalinga⁴ to which Pāli texts bear witness. In the *Sona-Nanda Jātaka* we find Assaka associated with Avanti. This may suggest that Assaka included at that time Mūlaka and some neighbouring districts and thus its territory approached the southern frontier of Avanti.⁵

In the *Vāyu Purāṇa*⁶ Aśmaka and Mūlaka appear as scions of the Ikshvāku family, and the *Mahābhārata* speaks of the royal sage Aśmaka (*Aśmako nama rājarshi*) as having founded the city of Podana. This probably indicates that the Aśmaka and Mūlaka kingdoms were believed to have been founded by Ikshvāku chiefs, just

¹ 3rd ed., p. 50. He prohibited the use of harsh conjunct consonants.

² *Sutta Nipāta*, 977.

³ *Chulla-Kālinga Jātaka*, No. 301 ; D. 2. 235; Law, *Heaven and Hell in Buddhist Perspective*, 74 ; *Mbh.* I. 177. 47. As pointed out by Dr. Sukthankar the older mss. give the name as Potana or Podana and not Paudanya. This agrees with the evidence of the *Mahāgovinda Suttanta* (*Assakānañcha Potanam*) and the *Parīśiṣṭa parva* (I. 92)—*nagare Potanābhidhe*.

⁴ *Sutta Nipāta*, 977 ; *Jātaka* No. 301.

⁵ Cf. Bhandarkar, *Carm. Lec.*, 1918, pp. 53-54. It appears from the *Mahāgovinda Suttanta* that at one time Avanti extended southwards as far as the Narmadā valley and included the city of Māhiśmati which stood on the banks of the famous river.

⁶ 88. 177-178 ; *Mbh.* I. 177. 47.

as Vidarbha and Daṇḍaka were founded by princes of the Yadu (Bhoja) family. The *Mahāgovinda Suttanta* mentions Brahmadatta, king of the Assakas, as a contemporary of Sattabhu, king of Kalinga, Vessabhu, king of Avanti, Bharata, king of Sovira, Reṇu, king of Videha, Dhataratṭha, king of Aṅga and Dhataratṭha, king of Kāśi.¹

We learn from the *Assaka Jātaka*² that at one time the city of Potali was included in the kingdom of Kāśi, and that its prince, Assaka, was presumably a vassal of the Kāśi monarch. The *Chulla Kālinga Jātaka* mentions a king of Assaka named Aruṇa and his minister Nandisena, and refers to a victory which they won over the king of Kalinga.

Avanti roughly corresponds to the Ujjain region, together with a part of the Narmadā valley from Mādhātā to Maheshwar, and certain adjoining districts. Late Jaina writers include within its boundaries Tumbavana or Tumain in the Guna district of the Gwalior state about 50 miles to the north-west of Eran.³ The *Janapada* was divided into two parts by the Vindhya; the northern part drained by the Siprā and other streams had its capital at Ujjain and the southern part washed by the Narmadā had its centre at Māhissatī or

¹ *Dialogues of the Buddha*, Part II, p. 270. The last-mentioned prince is known to the *Sat. Br.*, XIII. 5. 4. 22.

² No. 207.

³ *Iha Iva Jambudīpe' pāḍa Bhartārtha vibhāṣanam*

Avantirita deśa 'sti saṅgadeśiya riddhibhikṣu
tatra Tumbavanamīti vidyate sannivesanam.

Paritishṭaparvan, XII. 2-3

Māhishmatī¹ usually identified with the rocky island of Māndhātā.²

Buddhist and Jain writers mention several other cities of Avanti, viz., Kuraraghara ("osprey's haunt"), Makkarakaṭa, and Sudarśanapura.³ The *Mahāgovinda Suttanta* mentions Māhissatī as the capital of the Avantis, and refers to their king Vessabhu. The *Mahābhārata*, however, distinguishes between the kingdoms of Avanti and Māhishmatī, but locates Vinda and Anuvinda of Avanti near the Narmadā.⁴

The *Purāṇas* attribute the foundation of Māhishmatī, Avanti, and Vidarbha to scions of the Yadu family. The *Aitareya Brāhmaṇa* also associates the Satvats and the Bhojas, branches of the Yadu family according to the *Purāṇas*, with the southern realms.⁵

The *Purāṇas* style the first dynasty of Māhishmatī as Haihaya.⁶ This family is already known to the *Kauṭīliya Arthaśāstra*⁷ and figures in the *Shoḍaśa-rājika* and other episodes of the epic. The Haihayas are said to have overthrown the Nāgas who must have been the aboriginal inhabitants of the Narmadā region.⁸ The *Matsya Purāṇa*

¹ In J. V. 133 (DPPN, I. 1050) Avanti is placed in Dakṣiṇāpatha. This is hardly reconcilable with the view that only the southern part is meant by the expression *Avanti Dakṣiṇāpatha* (Bhandarkar, *Corm. Lec.* 54).

² Pargitor in Mark P.; Fleet in JRAS, 1910, 444f. There is one difficulty in the way of accepting this identification. Māndhātā lay to the south of the Pāriyātra Mts. (W. Vindhya), whereas Māhishmatī lay between the Vindhya and the Riksha—to the north of the Vindhya and to the south of the Riksha, according to the commentator Nilakaṇṭha (*Harivamśa*, II. 38. 7-19). For identification with Mahesvara, once the residence of the Holkar family, see *Ind. Ant.*, 1875. 346ff. For Māndhātā, see *ibid.*, 1876, 53.

³ Lüders Ins. No. 469; *Gradual Sayings*, V. 31; Law, *Ancient Mid-Indian Ksatriya Tribes*, p. 158; DPPN, I. 193; *Kathākośa*, 18.

⁴ *Narmadā-māhātmya*, *Mbh.*, II. 31.10.

⁵ *Matsya*, 43-44; *Vāyu*, 95-96; *Āt.* Br., VIII. 14.

⁶ *Matsya*, 43, 8-29; *Vāyu*, 94, 5-26.

⁷ *Arthaśāstra*, p. 11; *Mbh.* vii. 68. 6 etc.; *Saundara Nanda*, VIII. 45.

⁸ Cf. Nāgpur; and *Ind. Ant.*, 1884, 85; *Bomb. Gaz.*, I. 2.313, etc.

mentions five branches of the Haihayas, namely Vītihotras Bhojas, Avantis, Kuṇḍikeras or Tuṇḍikeras and the Tāla-jaṅghas.¹ When the Vītihotras and Avantis (or the Vītihotras in Avanti) passed away, an *amātya*, minister or governor, named Pulika (Puṇika), is said to have killed his master and anointed his own son Pradyota in the very sight of the *Kshatriyas*.² In the fourth century B.C., Avanti formed an integral part of the Magadhan Empire.

The kingdom of **Gandhāra** included within its boundaries the vale of Kāśmīra and the ancient metropolis of Takshaśilā, which lay 2,000 leagues from Benares,³ but nevertheless attracted students and enquirers from the most distant provinces.

The Purāṇas represent the Gandhāra princes as the descendants of Druhyu.⁴ This king and his people are mentioned several times in the *Rig-Veda* and apparently belonged to the north-west,⁵ a fact that accords with the Purāṇic tradition. Mention has already been made of the early king, Nagnajit who is reported to have been a contemporary of Nimi, king of Videha, Durmukha, king of Pañchāla, Bhīma, king of Vidarbha,⁶ and "Karakandū,"

¹ 43. 48-49.

² We need not infer from this statement that the family of Puṇika sprang from one of the lower orders of society (e.g., cowherds). The point in the Purāṇic account is that the dynastic change was brought about by an *amātya*, a civil functionary (not a *senāpati* like Pushyamitra), and that the army (*Kshatriyas*) looked on, i.e., treated the matter with indifference or silent approval. In the time of Megasthenes soldiers (*kshatriya*, *khattiya-kula*) and councillors (*amātyas*, *amachcha-kula*) were distinct orders of society (cf. also Fick, Ch. VI). The Tibetans style Pradyota's father Anantanemi. *Essay on Guṇādhyā*, p. 173.

³ *Jātaka*, No. 406; *Talapatta Jātaka*, No. 96; *Susīma Jātaka*, No. 163.

⁴ *Matsya*, 48.6; *Vāyu*, 99.9.

⁵ *Vedic Index*, I. 385.

⁶ *Kumbhakāra Jātaka*; *Ait. Br.*, VII. 34; *Sat. Br.* VIII. 1. 4. 10; *Uttarā-dhyayana Sūtra*. A Nagnajit also appears in the *Mahābhārata* as the Gandhārian contemporary of Kṛishṇa (V. 48. 75). But the same epic mentions Śakuni as the King of Gandhāra in the time of Kṛishṇa and the Pāṇḍavas.

king of Kalinga. Jaina writers tell us that those princes adopted the faith of the Jainas.¹ As Pārśva (777 B.C.?) was probably the first historical Jina, Nagnajit, if he really became a convert to his doctrines, should have to be placed between 777 B.C. and *cir.* 544 B.C., the date of Pukkusāti, the Gandhārian contemporary of Bimbisāra. The conversion to Jainism, however, does not accord with the story related in the *Jātaka* about his own elevation and that of his confrères to the status of *Pachcheka Buddhas*, or with the interest which the king or his son Svarjit² evinced in Brāhmaṇic ritual. It is, however, to be noted that the views of the family in such matters were not treated with respect. The rival claims of different sects need not be taken too seriously. The only fact that emerges is that tradition knew the family to be interested in religious matters and holding views that did not strictly conform to traditional Brāhmaṇism.

In the middle of the sixth century B.C. the throne of Gandhāra was occupied by Pukkusāti (Pushkarasārin) who is said to have sent an embassy and a letter to king Bimbisāra of Magadha, and waged war on Pradyota of Avanti who was defeated.³ He is also said to have been threatened in his own kingdom by the Pāṇḍavas who occupied a part of the Pañjāb as late as the time of Ptolemy. In the latter half of the sixth century B.C. Gandhāra was conquered by the king of Persia. In the Bahistān inscription of Darius, *cir.* 520-518 B.C., the Gandhārians (Gadara) appear among the subject peoples of the Achaemenidan or Achaemenian Empire.⁴

¹ SBE., XLV. 87.

² *Sat. Br.*, VIII. 1. 4. 10. *Vedic Index*, I. 432.

³ *Buddhist India*, p. 28; *DDPN*, II. 215; *Essay on Guṇāḍhya*, p. 176.

⁴ See "Ancient Persian Lexicon and the Texts of the Achaemenidan Inscriptions" by Herbert Cushing Tolman, *Vanderbilt Oriental Series*, Vol. VI; *Old Persian Inscriptions*, by Sukumar Sen; *Camb. Hist. Ind.* I. 334, 338.

Kamboja is constantly associated with Gandhāra in literature and inscriptions.¹ Like Gandhāra it is included in the *Uttarāpatha*, i.e., the Far North of India.² It should, therefore, be clearly distinguished from "Kambuja" in the Trans-Gangetic Peninsula (i.e., Cambodia),³ and must be located in some part of North-West Indo-Pakistan close to Gandhāra. The *Mahābhārata* connects the Kambojas with a place called Rājapura.⁴—"Karna Rājapuram gatvā Kāmbojā nirjitā-stayā."⁵ The association of the Kambojas with the Gandhāras enables us to identify this Rājapura with the territory of that name mentioned by Yuan Chwang⁶ which lay to the south or south-east

¹ *Mbh.*, XII. 207. 43; *Anguttara N.*, P. T. S., I. 213; 4. 252, 256, 261; *Rock Edict V of Asoka*. Quite in keeping with the association with Gandhāra, famous for its good wool (*Rig. V. 1. 136. 7*), is the love of Kambojas for blankets (*Kambala*) to which Yaska (II. 2) bears testimony.

² *Cf. Mbh.*, XII. 207. 43. *Rājatarāngiṇī*, IV. 163-165. The chronicle does not place Kamboja to the north of Kashmir. It simply places the territory in the *Uttarāpatha*, and clearly distinguishes it from the land of the Tukhāras, apparently lying further to the north.

³ For the Hindu colony of "Kambuja" see Eliot, *Hinduism and Buddhism*, III, pp. 100 ff.; B. R. Chatterji, *Indian Cultural Influence in Cambodia*; R. C. Majumdar, *Kambujadeta* (Meyer Lectures).

⁴ *Mbh.*, VII. 4. 5.

⁵ "Karna having gone to (gatvā) Rājapura" vanquished the Kambojas. The passage can hardly imply that Karna marched to Kamboja "via Rājapura." It is also futile to suggest that Rājapura had anything to do with Rājagriha in Bactria (as is done by a writer in the *Proceedings and Transactions of the Sixth Oriental Conference*, Patna, p. 109). The *Ram. I. 6. 22*; the *Mbh.*, VII. 119. 14. 26, and the *Mudrārākhana*, II, clearly distinguishes Kamboja from Bāhlika (Bactria).

⁶ Watters, *Yuan Chwang*, Vol. I, p. 294. Cunningham (AGI, 1924, p. 148) identifies Rājapura with the chiefship of Rajaori to the south of Kashmir. The fact that the *Mahābhārata* (II. 27) makes separate mention of Kamboja and Abhisāra (with which the Rajaori region is identified) need not mean that the two were absolutely distinct entities in all ages. Does not the *Great Epic* (II. 70. 24-25) distinguish between Suhma and Tamralipti, and does not the *Dasa-kumara-charita* with equal emphasis place Dāmalīpta in Suhma? The truth is that Rajaori formed only a part of Kamboja which included other areas as well. The ruling family of Rajaori (Rajaori) in later times were the Khaśas (Stein in JASB, 1899, Extra No. 2, 26).

of Punch. The western boundaries of Kamboja must have reached Kāfiristān. Elphinstone found in that district tribes like the 'Caumojee,' 'Camoze,' and 'Camoje' whose names remind us of the Kambojas.¹

Kamboja may have been a home of Brāhmaṇic learning in the later Vedic period. The *Vamśa Brāhmaṇa* actually mentions a teacher named Kāmboja Aupamanyava.² The presence of Āryas (Ayyo) in Kamboja is recognised in the *Majjhima Nikāya*.³ But already in the time of Yāska the Kambojas had come to be regarded as a people distinct from the Aryans of the interior of India, speaking a different dialect.⁴ We have further changes in later ages. And in *Bhūridatta Jātaka*⁵ the Kambojas are credited with savage (Non-Aryan) customs :

ete hi dhammā anariyarūpā

*Kambojakānam vitathā bahunnan ti.*⁶

These are your savage customs which I hate,

*Such as Kamboja hordes might emulate.*⁷

This description of the Kambojas agrees wonderfully with Yuan Chwang's account of Rājapura and the adjoining countries. "From Lampa to Rājapura the inhabitants are coarse and plain in personal appearance, of rude violent dispositions...they do not belong to India proper,

¹ Elphinstone, *An Account of the Kingdom of Kabul*, Vol. II, pp. 375-377; *Bomb. Gaz.* I. 1, 498n; *JRAS*, 1843, 140; *JASB*, 1874, 260n; Wilson, *Vishnu P.*, III. 292. With the expression *assānam āyatanam*, 'land of horses,' used by Pāli texts in reference to the Kambojas (*DPPN*, I, 526, cf. *Mbh.* vi. 90, 3) may be compared the names *Aspasioi* and *Assakuoī* given by classical writers to the sturdy tribes living in the Alishang and Swat valleys in the days of Alexander (*Camb. Hist. Ind.* I. 352n).

² *Vedic Index*, I. 127, 138; *Yāska*, II. 2.

³ II. 149.

⁴ II. 2; *JRAS*, 1911, 801f.

⁵ No. 543.

⁶ *Jātaka*, VI. 208.

⁷ Cowell's *Jātaka*, VI. 110.

but are inferior peoples of frontier, (i.e., barbarian) stocks."¹

The Kambojas in the Epic period had their metropolis probably at Rājapura. Dvārakā, mentioned by Rhys Davids as the capital in the early Buddhist period, was not really situated in this country, though it was connected with it by a road.² A real city of the Kambojas was apparently Nandi-nagara mentioned in Lüders' Inscriptions Nos. 176 and 472.

The Vedic texts do not mention any king of Kamboja. But, as has already been pointed out, they refer to a teacher named Kamboja Aupamanyava who was probably connected with this territory. In the *Mahābhārata* the Kambojas are represented as living under a monarchical constitution.³ The Epic makes mention of their kings Chandravarman and Sudakṣiṇa. In later times the monarchy gave place to a *Saṅgha* form of government. The *Kauṭīliya Arthaśāstra*⁴ speaks of the Kambojas as a "*vārtā-śāstr-opajīvin*" *Saṅgha*, that is to say, a confederation of agriculturists, herdsmen, traders and **warriors**. Corporations of Kambojas (*Kambojānāṇcha ye gaṇāh*) are also mentioned in the *Mahābhārata*.⁵

¹ Watters I. 284; for the Kambojas, see also S. Lévi : "*Pré-Aryen et Pré-Dravidien dans l'Inde*," JA, 1923.

² DPPN, I. 526; cf. Law : "*The Buddhist Conception of Spirits*," pp. 80-83.

³ Cf. I. 67. 32; II. 4. 22; V. 165. 1-3; VII. 90. 59. etc.

⁴ P. 378.

⁵ VII. 89. 38.

SECTION II. AN EPIC ACCOUNT OF THE MAHĀJANAPADAS

An interesting account of the characteristics of the peoples of most of the *Mahājanapadas* described above is to be found in the *Karna parva* of the *Mahābhārata*.¹

The Kurus, Pañchālas, Matsyas, Kosalas, Kāśis, Magadhas, Chedis and Śūrasenas receive praise. Patriots hailing from Aṅga include their country in this list :

*Kuravaḥ saha Pañchālāḥ Sālvā Matsyāḥ sa-Naimishāḥ²
Kosalāḥ Kāśayo' ṅgāścha Kaliṅgā Māgadhistathā
Chedayaścha mahābhāgā dharmam jñanti śāśvatam
brāhmaṇ Pañchālāḥ Kauraveyāstu dharmam
Satyam Matsyāḥ Śūrasenāścha yajñam.*

“ The Kauravas with the Pañchālas, the Sālvās, the Matsyas, the Naimishas, the Kosalas, the Kāśis, the Aṅgas the Kaliṅgas, the Magadhas, and the Chedis who are all highly blessed, know what the eternal Law of Righteousness is. The Pañchālas observe the Vedic code, the Kauravas the law of right conduct, the Matsyas truth, and the Śūrasenas sacrificial rites.”

The Magadhas comprehend hints, the Kosalas understand from what they see,—the Kurus and Pañchālas gather the sense from half-expressed words, while the Sālvās need full instruction.

*Ṇgitajñāścha Magadhāḥ prekshitajñāścha Kośalāḥ.
arddhoktāḥ Kuru-Pañchālāḥ Sālvāḥ kṛitsnānūsāsanāḥ.*

¹ *Mahābhārata*, VIII. 40. 29; 45. 14-16; 28; 34; 40.

² The Naimishas occupied Nimsār, 20 miles from Sitāpur, on the left bank of the Gumti river (Ayyar, *Origin and Early History of Saivism in South India*, 91).

The Aṅgas had their detractors and come in for a good deal of condemnation along with the Madras and the Gandhāras :

*Āturāṇām parityāgaḥ sadāra-suta-vikrayaḥ
Aṅgeshu vartate Karna yeshām adhipatir bhavān.*

“ The abandonment of the afflicted and the sale of wives and children are, O Karna, prevalent among the Aṅgas whose overlord thou art.”

*Madrakeshu cha saṁsṛiṣṭam
śaucham Gāndhārakeshu cha,
rāja-yājaka-yājye cha
nashṭam dattam havir bhavet.*

“ Amongst the Madrakas all acts of friendship are lost as purity among the Gāndhārakas, and the libations poured in a sacrifice in which the king is himself the sacrificer and priest.”

The verses quoted above give a fair idea of the attitude, mainly of poets of the western part of the *Madhyadeśa* towards most of the *Mahājanapadas* of Northern India.

SECTION III. THE FALL OF KĀŚI AND THE ASCENDANCY OF KOSALA

Kośala nāma muditaḥ sphīto janapado mahān
—*Rāmāyaṇa*.

The flourishing period of the sixteen *Mahājanapadas* ended in the sixth and fifth centuries B.C. The history of the succeeding age is the story of the absorption of these states into a number of powerful kingdoms, and ultimately into one empire, namely, the empire of Magadha.

Kāśi was probably one of the first to fall. The *Mahāvagga* and the *Jātakas* refer to bitter conflicts between this kingdom and its neighbours, specially Kosala. The facts of the struggle are obscure, being wrapped up in legendary matter from which it is impossible to disentangle them. The Kāśis seem to have been successful at first, but the Kosalas were the gainers in the end.

In the *Mahāvagga* ¹ and the *Kosambi Jātaka* ² it is stated that Brahmadatta, king of Kāśi, robbed Dīghati, king of Kosala, of his realm, and put him to death. In the *Kunāla Jātaka* ³ we are told that Brahmadatta, king of Kāśi, owing to his having an army, seized on the country of Kosala, slew its king, and carried off his chief queen to Benares, and there made her his consort. The *Brahmachatta* ⁴ and *Sona-Nanda Jātakas* ⁵ also refer to the victories of Kāśi monarchs over Kosala.

¹ S.B.E., XVII, 294-99.

² No. 423.

³ No. 536.

⁴ No. 836.

⁵ No. 532.

Success, however, did not remain long with the Kāśis.¹ In the *Mahāsīlava Jātaka*² king Mahāsīlava of Kāśi is said to have been deprived of his realm by the ruler of Kosala. In the *Ghata*³ and *Ekarāja Jātakas*⁴ Vaṅka and Dabbasena, sovereigns of Kosala, are said to have won for their country a decided preponderance over Kāśi. The final conquest of the latter kingdom was probably the work of Kaṁsa, as the epithet *Barānasiggaho*, i.e., "seizer of Benares" or Kāśi is a standing addition to his name.⁵ The interval of time between Kaṁsa's conquest of Kāśi and the rise of Buddhism could not have been very long because the memory of Kāśi as an independent kingdom was still fresh in the minds of the people in the Buddha's time and even later when the *Aṅuttara Nikāya* was composed.

In the time of Mahākosala (about the middle of the sixth century B.C.) Kāśi formed an integral part of the Kosalan monarchy. When Mahākosala married his daughter, the lady Kosalādevi, to king Bimbisāra of Magadha, he gave a village of Kāśi producing a revenue of a hundred thousand for bath and perfume money.⁶

In the time of Mahākosala's son and successor, Pasenadi or Prasenajit, Kāśi still formed a part of the Kosalan empire. In the *Lohichcha Sutta*⁷ Buddha asks a person named Lohichcha the following questions: "Now what think you Lohichcha? Is not king Pasenadi of Kosala in possession of Kāśi and Kosala?" Lohichcha

¹ Cf. *Jātaka* No. 100.

² No. 51.

³ No. 355.

⁴ No. 303.

⁵ The *Seyya Jātaka*, No. 282; the *Tesakuna Jātaka*, No. 521; *Buddhist India*, p. 25.

⁶ *Harita Māta Jātaka*, No. 239; *Vaḍḍhaki Sūkara Jātaka*, No. 283.

⁷ *Dialogues of the Buddha*, Part I, 288-97.

replies, "Yes, that is so, Gotama."¹ We learn from the *Mahāvagga*² that a brother of Pasenadi acted as the viceroy of Kāśī.

The *Samyukta Nikāya*³ speaks of Pasenadi as the head of a group of five *Rājās*. One these was probably his brother, the viceroy of Kāśī. Among the remaining princes and chiefs we should perhaps include the *rājanya* Pāyāsi of Setavyā mentioned in the *Pāyāsi Suttanta*⁴ and the ruler of the Kālamas of Kesaputta.⁵

Another *Rājā* of the group was apparently the Śākya chief of Kapilavāstu. His political subordination to the Kosalan monarchs appears from several texts.⁶ The ruler of Devadaha may have ranked as another notable vassal of Kosala.⁷

It was probably during the reign of Mahākosala, that Bimbisāra was anointed king of Magadha. With the coronation of this famous ruler ends the period with which this part of the work deals.

¹ Cf. *Gradual Sayings*, V, 40. "As far as the Kāśī-Kosalans extend, as far as the rule of Pasenadi, the Kosalan *rājā*, extends, therein Pasenadi, the Kosalan *Rājā*, is reckoned chief."

² S.B.E., XVII, 195.

³ *The Book of the Kindred Sayings*, translated by Mrs. Rhys Davids, I., p. 109.

⁴ Cf. *Mūlinda*, IV, 4, 14; the *Vimāna-vatthu* commentary; Law, *Heaven and Hell*, 79, 83. Pāyāsi occurs as the name of a village in a Sabet Mahet Inscription. It has been identified with a village close to the findspot of the record (Ray, DHNI, I, p. 521).

⁵ *Indian Culture*, II, 606; *Aṅguttara*, I, 168.

⁶ See *Supra*, p. 90.

⁷ Kapilavāstu, Devadaha and Koliya are sometimes mentioned as three distinct states (DPPN, I, 102n). The subordination of the Sakya to the King of Kosala necessarily implies the latter's control over Devadaha which was in part, at any rate, a Śākyan city.

SECTION IV. KINGSHIP.

We have endeavoured to give in outline the story of the political vicissitudes through which Northern India and a considerable portion of the Deccan passed from the accession of Parikshit to the coronation of Bimbisāra. We shall now attempt a brief survey of some of the institutions of the age without which no political history is complete. We have seen that during the major part of the period under review the prevailing form of government was monarchical. The later Vedic texts and auxiliary treatises give us a few details about the rank and power of the rulers in the different parts of India, their social status, the methods of their selection and consecration, the chief members of their household, the civil and military services, the limitations of royal authority and popular participation in affairs of the state. Even when all scraps of information are pieced together, the picture is dim. The facts gleaned from Vedic sources which alone can, with confidence, be referred to the period before 500 B.C. have to be elucidated or supplemented by post-Vedic data embodying traditions about the heroic age that preceded the rise and growth of the Magadhan Empire.

The various **kinds of rulership** prevalent in different parts of India are thus described in the *Aitareya Brāhmaṇa* : ¹

" *Etasyām Prāchyām diśi ye ke cha Prāchyānām
rājānaḥ Sāmraṣṭyāyaiva te'bhishichyante Samrāt-
ityenān-abhishiktānāchakshata etāmeva Devānām vihitimanu.*

Etasyām Dakṣiṇāyām diśi ye ke cha Satvatām Rājāno Bhaujyāyaiva te'bhishichyante Bhoj-ityenān-abhishiktān-āchakshata etāmeva Devānām vihitimanu.

Etasyām Pratiçhyām diśi ye ke cha Nīchyānām Rājāno ye'pāchyānām Svārājyāyaiva te'bhishichyante Svarāt-ityenān-abhishiktānāchakshata etāmeva Devānām vihitimanu.

Etasyām Udīchyām diśi ye ke cha pareṇa Himavantam Janapadā Uttara-Kurapa Uttara-Madrā iti Vairājyāyaiva te'bhishichyante Virāt-ityenān-abhishiktānāchakshata etāmeva Devānām vihitimanu.

Etasyām dhruvāyām Madhyamāyām pratishṭhāyām diśi ye ke cha Kuru-Pañchālānām Rājānaḥ sa Vaś-Ośīnarānām Rājyāyaiva te'bhishichyante Rāj-ityenān-abhishiktānāchakshata etāmeva Devānām vihitimanu."

"In this eastern quarter, whatever kings there are of the eastern peoples, they are anointed for overlordship (*Sāmrājya*); 'O Overlord' they style them when anointed in accordance with the action of the gods. In the southern quarter whatever kings there are of the Satvats, they are anointed for paramount rule (*Bhaujya*); 'O Paramount Ruler' they style them when anointed in accordance with the action of the gods. In this western quarter, whatever kings there are of the southern and western peoples, they are anointed for self-rule (*Svārājya*); 'O Self-Ruler' they style them when anointed in accordance with the action of the gods. In this northern quarter, the lands of the Uttara-Kurns and the Uttara-Madrās, beyond the Himavat, their (kings?) are anointed for sovereignty (*Vairājya*); 'O Sovereign' they style them when anointed in accordance with the action of the gods. In this firm middle established quarter, whatever kings there are of the Kuru-Pañchālas with the Vaśas and Uśīnaras, they are anointed for kingship; 'king' they style them when anointed in accordance with the action of the gods."¹

¹ *Rig-Veda Brāhmaṇas*, translated by Keith, Harvard Oriental Series, Vol. 25.

Several scholars assert that *Vairājya* means a kingless state. But in the *Aitareya Brāhmaṇa*¹ a king consecrated with Indra's great unction is called *Virāt* and worthy of *Vairājya*. When a king consecrated with the *Punarbhisheka* (renewed anointment) ascends his *Āsandī* or throne, he prays for attaining *Vairājya* as well as other kinds of royal dignity. Sāyana takes the word *Vairājyam* to mean pre-eminence among kings, *itarebhyo bhupatibhyo vaiśishtyam*. This is virtually the sense of the word that Dr. Keith accepts in his translation.

The *Śukranīti*,² too, understands *Virāt* to denote a superior kind of monarch. In the *Mahābhārata* Kṛishna is lauded as *Samrāt*, *Virāt*, *Svarāt* and *Sura-rāja*.³ If the Uttara-Kurus and the Uttara-Madras are to be regarded as republican, it is not because of the use of the term *Vairājya*, but because in their case it is not the *rājan* but the *janapada* which is said to be anointed for sovereignty. It should, however, be remembered that already in the Brāhmaṇa period Uttara-Kuru has become a *devakshetra* which the arms of a mortal could not reach.⁴

It is not easy to decide whether all the terms *Sām-rājya*, *Bhaujya*, *Scārājya*, *Vairājya* and *Rājya* referred to essentially different forms of royal authority in the Brāhmaṇic period. But two terms at least, namely, *Sām-rājya* and *Rājya* are clearly distinguished from each other by the *Satapatha Brāhmaṇa*.⁵

¹ VIII. 17.

² B. K. Sarkar's Translation, p. 24; Kaṇṭilya (VIII.2), however, takes *Vairājya* to mean a system of government which comes into existence by forcible seizure of a country from the legitimate ruler for purposes of exploitation.

³ XII. 49. 11; cf. 68.34.

⁴ *At. Br.* viii. 29. The existence of *Ganas* and of *Ganajyeshthas* are hinted at *Rig.* V. I. 23, 8; II. 23, 1; X. 84, 12; 112, 9; *Sat. Br.* XIII. 2. 8. 4. etc.

⁵ V. 1. 1. 12-13; cf. *Kātyāyana Śrauta Sūtra*, XV. 1. 1, 2.

*Rājā vai Rājasūyeneshṭvā bhavati, Samrāj Vājapeyen-
āvarām hi Rājyaṁ param Sāmrājyam. Kāmayeta vai Rājā
Samrāj bhavitum āvarām hi rājyaṁ param Sāmrājyam. Na
Samrāt kāmayeta Rājā bhavitum āvarām hi rājyaṁ param
Sāmrājyam.*

"By offering the *Rājasūya* he becomes *Rājā* and by the *Vājapeya* he becomes *Samrāj*, and the office of *Rājan* is the lower and that of *Samrāj*, the higher; a *Rājan* might indeed wish to become *Samrāj*, for the office of *Rājan* is the lower and that of *Samrāj* the higher; but the *Samrāj* would not wish to become a *Rājā* for the office of *Rājan* is the lower, and that of *Samrāj* the higher."

In the *Rig-Veda*,¹ and later on in the *Purāṇas*, *Bhoja* appears as a proper name. But the *Brāhmaṇas* regard it as a royal designation, applicable to the consecrated monarchs of the southern region.² The word *Cæsar* furnishes a parallel. Originally the name of a Roman dictator and of members of his family, it is used, in later ages, as a title by Roman and German Emperors. As to *Svārājya* it is sometimes taken to mean uncontrolled dominion, and is opposed to *Rājya*.³

The king was usually, though not always, a *Kshatriyā*. The *Brāhmaṇas* were considered to be unsuited for kingship. Thus we read in the *Śatapatha Brāhmaṇa*—"To the king (*Rājan*) doubtless belongs the *Rājasūya*; for by offering the *Rājasūya* he becomes king, and unsuited for kingship is the *Brāhmaṇa*."⁴

¹ III. 53. 7.

² 'Bhoja' may have reference to the king or chieftain as ruler, protector or devourer of his people (*Viśāmatā*). It appears as an official designation in several inscriptions of Southern India (*Ind. Ant.* 1876, 177; 1877, 25-28). In *Mbh.* I. 84. 22, it is applied to a ruler and his family who are deprived of many of the attributes of sovereignty (*arājā Bhojaśabdam teṣāṁ tatra prāpsyasi sāncayaḥ*).

³ *Kāthaka Samhitā*, XIV. 5; *Maitrāyaṇi Samhitā*, I. II, 5, etc., *Vedic Index*, II. 221.

⁴ V. I. 1. 12; *SBE*, XLI; *Eggeling Sat. Br.*, Part III, p. 4.

Rājña eva rājasūyam. Rājā vai rājasūyeneshlvā bhavati na vai Brāhmaṇo rājyāyālam avaram vai rājasūyam param Vājapeyam.

A Brāhmaṇa king is, however, contemplated in a passage of the *Aitareya Brāhmaṇa*.¹ We have references to Śūdra, Āyogava and even non-Aryan kings in other Vedic texts. King Jānaśruti Pautrāyaṇa is branded a Śūdra in the *Chhāndogya Upanishad*.² King Marutta Āvikshita is styled "Āyogava" in the *Śatapatha Brāhmaṇa*.³ *Āyogava* denotes, in legal codes, a member of a mixed caste, a descendant of a Śūdra by a Vaiśya wife.⁴ *Nishāda sthapatis* (kings or chieftains) figure in a *Śrauta sūtra* and the *Rāmāyaṇa*. In the *Jaiminiya Upanishad Brāhmaṇa* it is stated that even an *anārya* "obtains," *prāpnoti*, kings.⁵ This points either to non-Aryan kings or to the admission of *anāryas* into the dominions of Aryan rulers. The *Jātakas* and the Great Epic refer to kings of various castes including Brāhmaṇas.⁶

Kingship was sometimes **hereditary**, as is indeed shown by several cases where the descent can be traced. Mention may be made in this connection of the *Pārikshitās* and the kings of Janaka's line; hereditary kingship is also suggested by the expression *Daśapurushamrājya*—a kingdom of ten generations—occurring in the *Śatapatha Brāhmaṇa*.⁷ But elective monarchy was not unknown.⁸

¹ VIII. 23 (story of Atyarāti's offer to Vāsishṭha Sātyahavya).

² IV. 2. 1-5. Apparently Śūdra kings were not unknown in the age.

³ XIII. 5. 4. 6.

⁴ *Manu-Saṁhitā*, X. 12.

⁵ *Vedic Index*, I. 454; *Rām*, II. 50, 32; 84. 1. *Jaim. Up. Br.* 1. 4. 5.

⁶ Cf. *Jātakas*, 75, 432, *Mbh.* I. 100, 49f; 158, 70.

⁷ XII. 9. 3. 1-3; cf. also the reference to the birth of an heir to the throne (*At. Br.* VIII. 9 and to the king as *Rājpitā*, VIII. 17).

⁸ Reference may be made in this connection to the passages of the *Aitareya Brāhmaṇa* (e.g., VIII. 12) describing the choice and consecration of divine rulers (Ghoshal, *A History of Hindu Political Theories*, 1927, p. 26), and notices of royal election in post-Vedic texts looking back to an early period, e.g., *Mbh.*, I. 04.

The selection was made sometimes by the people and occasionally by the ministers. The choice was ordinarily limited to the members of the royal family only, as is shown by the legend in Yāska¹ of the Kuru brothers Devāpi and Samtanu, and the story in the *Samvara Jātaka*² of the Kāśī princes Uposatha and Samvara. In the *Jātaka* the councillors ask a reigning king, "When you are dead, my lord, to whom shall we give the white umbrella?" "Friends," said the monarch, "all my sons have a right to the white umbrella. But you may give it to him that pleases your mind."

At times the **popular choice** fell on persons who did not belong to the ruling dynasty. Such may have been the case when the Śrīñjayas expelled their hereditary ruler together with the *Sthapati*.³ Clear instances of popular preference for individuals outside the royal family are furnished by the *Jātakas*. The *Pādañjali Jātaka*,⁴ for instance, tells us that when a certain king of Benares died, his son, Pādañjali by name, an idle lazy loafer, was set aside, and the minister in charge of things spiritual and temporal was raised to the throne. The *Sachchamkira Jātaka*,⁵ relates a story how nobles, Brāhmanas and all classes slew their king and anointed a private citizen. Sometimes the candidate comes from a place outside the realm. The *Darīmukha*⁶ and *Sonaka Jātakas*⁷ tell

49-*rājate tam prajāḥ sareṇa dharmajña iti varire*. The expression king-maker (*rāja-karīṇi*, *Āit. Br.* VIII. 17; *Sat. Br.* III. 4. 1. 7) points to the important part played by officials including headmen of villages in the choice of the ruler. Both in the Vedic texts (*Āit. Br.* VIII. 12) and the epic emphasis is laid on the possession of moral qualities. The leader on whom the choice falls is *ojishṭha*, *balishṭha*, *sahishṭha*, *sattamaḥ*, *pārayishṭatama*, *dharmajña*. In the fourth century B. C. physical beauty carried the palm in one territory (Kathala in the Punjab according to Onesikritos).

¹ *Nirukta* II. 10; *Ved. Ind.* II, 211.

² No. 462.

³ *Sat. Br.* XII. 9. 3. 1 ff.

⁴ No. 247.

⁵ No. 78.

⁶ No. 378; cf. No. 401.

⁷ No. 529.

us how on failure of heir at Benares a prince of Magadha was elected king.

The monarch during the Brāhmaṇa period was usually allowed to have **four queens**, viz., the *Mahishī*, the *Parivṛiktī*, the *Vāvātā* and the *Pālāgalī*. The *Mahishī*, was the chief wife, being the first one married according to the *Śatapatha Brāhmaṇa*.¹ The *Parivṛiktī* was the neglected or discarded wife, probably one that had no son. The *Vāvātā* is the favourite, while the *Pālāgalī* was the daughter of the last of the court officials.² The *Aitareya Brāhmaṇa*,³ however, refers to the "hundred" wives of king Hariśchandra. In the *Jātaka* period several kings kept a bigger harem. We are told in the *Kusa Jātaka*⁴ that king Okkāko (Ikshvāku) had sixteen thousand ladies in his harem among whom Silavatī was the chief (*aggamahī*). The king of Benares according to the *Dasaratha Jātaka*,⁵ had the same number of wives. In the *Suruchi Jātaka*,⁶ a king of Mithilā says, "Ours is a great kingdom, the city of Mithilā covers seven leagues, the measure of the whole kingdom is 300 leagues. Such a king should have sixteen thousand women at the least." Sixteen thousand appears to have been a stock phrase. The number is evidently exaggerated. But it indicates that the kings of the *Jātaka* period were extreme polygamists who frequently exceeded the Brāhmaṇic number of four or even a hundred queens.

The king was consecrated after his succession or election with an elaborate **ritual** which is described in several *Brāhmaṇas*, and for which the appropriate formulas (*mantras*) are given in the Vedic *Samhitās*. Those

¹ VI. 5. 3 1. *Ved. Ind.*, I 478.

² Weber and Pischel in *Vedic Index*, I, 478.

³ VII. 18.

⁴ No. 531.

⁵ No. 461. The *Rāmāyaṇa* (II. 34. 13) allows this king only 750 ladies besides the chief consorts.

⁶ No. 482.

who aided in the consecration of the king were called *Rājakartri* or *Rājakrit*, i.e., "king-maker." In the *Śatapatha Brāhmaṇa*¹ the persons meant and specified are the *Sūta* (minstrel, chronicler or charioteer), and the *Grāmaṇī*, leader of the host or of the village.² Prof. Rādhākumud Mookerji observes:³ "It is apparent from the lists of persons aiding in the royal coronation that both official and non-official or popular elements were represented in the function." The principal ceremonies or sacrifices of royal inauguration were the *Vājapeya*, the *Rājasūya*, the *Punar-abhisheka* and the *Aindra Mahābhisheka*.

The *Vājapeya* (lit. "the drink of strength") bestowed on the performer a superior kind of kingship called "*Sāmrājya*," while the *Rājasūya* or royal inauguration merely conferred the ordinary monarchical dignity.⁴ The *Punar-abhisheka*, or renewed consecration, made the king-elect eligible for all sorts of royal dignity, viz., *Rājya*, *Sāmrājya*, *Bhaujya*, *Śvārājya*, *Vairājya*, *Pārameshṭhya*, *Māhārājya*, *Adhipatya*, *Śvāśya* and *Ātishṭhatva*.⁵ The object of the *Aindra Mahābhisheka* (the great anointing of the king of the celestials) is thus described :

"*Sa ya ichchhed evameit Kshatriyam ayaṁ sarvā jītir-jayetāyaṁ sarvāmlokaṁ vindetāyaṁ sarveshām Rājñām Śraishṭhyam, Ātishṭhām, Paramatām gachchhetu, Sam-*

¹ III. 4. 1. 7; XIII. 2. 2. 18.

² The post of *Grāmaṇī* seems to have been ordinarily held by a *Vaiśya* (*Vedic Index*, I. 247; II. 334; *Comb. Hist.* 131; *Sat. Br. V.* 3. 1. 6.)

³ *The Fundamental Unity of India*, p. 83.

⁴ *Rājya*, cf. *Sat. Br.*, V. I. 1, 12-13; some texts while agreeing that the *Vājapeya* is a *Samrājya* says that the *Rājasūya* is a *Varuṇa-sāya*, consecrated to the universal sway wielded by *Varuṇa*. *Tait. Saṁ.* (V. 6, 2. 1) and *Br.* (II. 7. 6. 1); *Sat. Br.* V. 4. 3. 2; Keith, *The Religion and Philosophy of the Veda and Upanishads*, 340; *Mahābhārata*, Bk. II. 12. 11-13 etc.

⁵ *Āit. Br.* VIII. 6. For the meaning of these terms see Keith's translation quoted below. Keith's rendering of some of the expressions, e.g., *Bhaujya* and *Vairājya*, is, however, hardly satisfactory.

*rājyaṁ, Bhaujyaṁ, Svārājyaṁ, Vairājyaṁ, Pāramesh-
thyaṁ, Rājyaṁ, Māhārājyaṁ, Ādhipatyāṁ, ayaṁ samanta-
paryāyi syāt Sārcabhaumaḥ sārvaṃyusha ā'ntādā parārddhāt
prithivyai samudraparyantāyā Ekarāḥ iti tametena Aindreṇa
Mahābhishekeṇa kshatriyaṁ śāpayitvā'bhishiñchet.*¹

"If he who knows thus should desire of a *kshatriya*, 'May he win all victories, find all the worlds, attain the superiority, pre-eminence and supremacy over all kings and overlordship, paramount rule, self-rule, sovereignty, supreme authority, kingship great kingship and suzerainty, may he be all-encompassing, possessed of all the earth, possessed of all life, from the one end up to the further side of the earth bounded by the ocean, sole ruler;' he should anoint him with the great anointing of Indra, after adjuring him"²

The **Vājapeya** rites³ include a race of 17 chariots, in which the sacrificer is allowed to carry off the palm, and from which, according to Eggeling, the ceremony perhaps derives its name. Professor Hillebrandt would claim for this feature of the sacrifice the character of a relic of an old national festival, a kind of Indian Olympic games. After the chariot race the next interesting item is the mounting of a pole, having a wheaten ring or wheel⁴ on the top, by the sacrificer and his wife, from which homage is made to the mother earth. The *Śatapatha Brāhmaṇa* says, "Truly he who gains a seat in the air gains a seat above others."⁵ The royal sacrificer having descended from the pole, is offered a throne-seat

¹ *Ait. Br.* VIII. 15.

² Keith, *HOS*, Vol. 25.

³ *Sat. Br.* V. 1. 1. 6. ॥; *S.B.E.*, xli; *Vedic Index*, II. 281; Keith, *Black-pajus*, cviii-cxi; BPVU, 330f.

⁴ *Gaudhūman chashālam*, "a wheaten headpiece (Eggeling)" "a wheel-shaped garland of meal" (*S. B. E.*, xli 31; Keith *R. P. V. U.*, 330; *Sat. Br.* V. 2. 1. 6).

⁵ *Sat. Br.*, V. 2, 1. 21.

with a goatskin spread thereon and addressed by the *Adhvaryu* (priest) in the following words: "Thou art the ruler, the ruling lord (*yantri*, *yamana*)—thou art firm and steadfast (*dhruva*, *dharuṇa*)—(here I seat) thee for the tilling, for peaceful dwelling (*kshema*), for wealth (*rayi*), for prosperity (*posha*), i.e., for the welfare of the people, the common weal."¹

The **Rājasūya** consisted of a long succession of sacrificial performances which began on the first day of *Phālguna* and spread over a period of upwards of two years.² The rite is described at great length in the *Satapatha Brāhmaṇa*.³ Besides much mere priestly elaboration, the ritual contains traces of popular ceremonial. The popular features are chiefly these:—

(1) The *Ratninām havīṁshi*⁴ or presents to the divinities of the bejewelled ones (or those possessed of the jewel offering), viz., the chief queen and court officials;

(2) The *Abhishechanīya*⁵ or besprinkling ceremony;

(3) The *dig vyāsthāpana*⁶ or the king's symbolical walking towards the various quarters as an indication of his universal rule;

(4) Treading upon a tiger skin,⁷ thus gaining the strength and the pre-eminence of the tiger;

(5) Narration by the *hotri* priest of the story (*ākhyāna*) of Śunaḥśepa.⁸

¹ *Sat. Br.*, V. 2. 1. 25; *The Fundamental Unity of India*, p. 80.

² Keith, *Black Yajus*, pp. cxi-cxiii, *RPVU*, 341; *Vedic Index*, II. 219; *SBE.*, xli, p. xxvi.

³ V. 2.3. 9 (*et seq.*) *S. B. E.*, xli, 42-113.

⁴ *Sat. Br.* V. 3. 1. M. Louis Renou says—"les offrandes ne sont pas faites aux *ratnin* mais aux divinités dans les maisons de chaque *ratnin*."

⁵ *Sat. Br.* V. 3. 3-4

⁶ *Sat. Br.* V. 4. 1. 3; Keith, *Black Yajus*, *op. cit.*,

⁷ *Sat. Br.* V. 4. 1. 11.

⁸ *At. Br.* vii, 13 ff; Keith, *RPVU*, 341n.

(6) A mimic cow raid against a relative¹; or a sham fight with a member of the ruling aristocracy (*rājanya*);²

(7) Enthronement;³

(8) A game of dice in which the king is made to be the victor;⁴

The recipients of the sacrificial honours called "*Ratni-nām havīṣhī*" were the divinities in the houses of the **Ratnins**, i.e., of the chief members of the royal household and of the king's civil and military service, viz.—

1. The *Senānī* (Commander of the army).⁵
2. The *Purohita* (Royal Chaplain).
3. The *Mahishī* (Chief Queen).
4. The *Sāta* (Charioteer and Bard).⁶
5. The *Grāmaṇī* (Leader of the Host or Village Headman).⁷
6. The *Kṣhattṛi* (Chamberlain)—forerunner of the *Antarvamsika* or Superintendent of the Seraglio of later times.⁸
7. The *Samgrahitṛi* (Treasurer)—forerunner of the *Sannidhātṛi* of the *Arthasāstra*.
8. The *Bhāgadugha* (Collector of the Royal Share, i.e., Taxes)—forerunner of the *Samāharṭṛi*.
9. The *Akshāvāpa* (Keeper of the Dice).⁹

¹ RPVU, 342; cf. *Sat. Br.* V. 4. 3. 3. *et seq.*

² Cf. *Taittirīya Saṁhitā*, I. 8. 15 with commentary; *Vedic Index* II. 219. SBE; xii, 100, n. 1.

³ *Sat. Br.* V. 4. 4. 1.

⁴ *Sat. Br.* V. 4. 4. 6; Keith, *Religion and Philosophy of the Veda*, etc., p. 342.

⁵ Cf. *Senāpālī* in *Āit. Br.* viii. 23.

⁶ The importance of this office is shown by the cases of *Samantra* and of *Sañjaya* who is called a *Mahāmātra* (*Mbh.* XV. 18. 4).

⁷ Cf. the *Adhikṛita*s appointed for *grāmas* or villages by the paramount ruler (*Samrāt*) mentioned in the *Prāna Upaniṣad* (III. 4).

⁸ Vidura was the *Kṣhattṛi* (*Mbh.* I. 200, 17; II. 66 l., etc.) at the Kuru Court. For the views of different commentators see *Vedic Index*, I. 231.

⁹ Cf. the position of *Rākṣa* (*Yudhiṣṭhira*) at the *Matsya* Court.

10. The *Go-vikartana* (lit. Cutter-up of Cattle, i. e., the King's Companion in the Chase).

11. The *Pālāgala* (Courier)—forerunner of the *Dūta* (*Śāsanahara*, etc.).¹

The most essential part of the *Rājasūya* was the **Abhisheka** or besprinkling. It began with offerings to the deities Savitā Satyaprasava, Agni Grihapati, Soma Vanaspati, Brihaspati Vāk, Indra Jyeshtha, Rudra Paśupati, Mitra Satya and Varuṇa Dharmapati. The consecration water (*Abhishechanīyā Āpaḥ*) was made up of seventeen kinds of liquid including the water from the river Sarasvatī, sea-water, and water from a whirlpool, a pond, a well and dew. The sprinkling was performed by a Brāhmaṇa priest, kinsman or brother of the king-elect, a friendly *Rājanaya* and a *Vaiśya*.

The two most important kinds of *Abhisheka* were the *Punar-abhisheka* and the *Aindra Mahābhisheka*.

The **Punar-abhisheka** or Renewed Anointment is described in the *Aitareya Brāhmaṇa*.² It was intended for Kshatriya conquering monarchs. The first interesting part of the ceremony was the king's ascent to the throne or *Āsandī* which was made of *udumbara* wood with the exception of the interwoven part (*vivayana*) which consisted of *muñja* grass. Then came the besprinkling. Among other things the priest said: "Do thou become here the

¹ Curiously enough, this list of the *ratnins* does not include the *Śthapati*, probably a local ruler, vassal chief, or governor who is, however, mentioned in *Sat. Br. V. 4. 4. 17*, in connection with the concluding ceremonies of the *rājasūya*. The sacrificial sword (*śphya*) given by the priest to the king is passed on successively to the king's brother, the *sūta* or the *sthapati*, the *grāmaṇi* and finally to a tribesman (*rajāta*). The post of *sthapati*, was held by *Uparikas* or governors of *Bhuktis* (provinces) in the Gupta period (Fleet, CII, p. 120). Slightly different lists of *ratnins* are found in the *Taittirīya* texts. A group of eight *śiras* gods mention in the *Pañchasiṃhā Brāhmaṇa* (Comb. Hist. Ind. I, 131). In *Sat. Br. XIII. 5. 4. 6*, we have reference to the *Parīśeshtri*, the *Kshatri* and the *Sabhāśads* in connection with a performance of the horse-sacrifice.

² VIII. 5-11.

overking of kings; the great of the great people, the supreme ruler of the people (or the peasantry)."¹ *Rājñām tvam Adhirāja bhaveha; Mahāntām tvā mahīnām Samrājām charshaṇīnām.*"² The king was next required to get down from the throne and make obeisance to the holy power (Brahman); "*Brahmaṇa eva tat Kshatram vaśam eti tad yatra vai Brahmaṇaḥ Kshatram vaśam eti tad rāshṭram samṛiddham tad vīravadhāsmīn vīro jāyate,*" "*verily thus the lordly power (Kshatra) falls under the influence of the holy power (Brahman). When the lordly power falls under the influence of the holy power, that kingdom is prosperous, rich in heroes; in it a hero or heir (vīra) is born.*"⁴ Here there is provision for the prevention of royal absolutism.

Janamejaya, the son of Parikshit, was evidently consecrated with the *Punar-abhisheka*.⁵

The **Aindra Mahābhisheka**⁶ or Indra's great unction consisted of five important ceremonies. In the first place, an **Oath** is administered by the priest to the king-elect: "*From the night of thy birth to that of thy death for the space between these two, thy sacrifice and thy gifts, thy place, thy good deeds, thy life and thine offspring let me take, if thou play me false.*"⁷ Next follows the *Ārohana* or enthronement. When the king is seated on the throne we have the *Utkrośana*⁸ or proclamation. The king-makers should say "*The Kshatriya, if not proclaimed, cannot show his strength, let us*

¹ Keith, HOS, 26 (slightly amended).

² *Ait. Br.*, VIII. 7.

³ *Ait. Br.*, VIII. 9.

⁴ Keith.

⁵ *Ait. Br.*, VIII. 11. A second coronation of the Ceylonese king Devānampiya Tissa is referred to by the chronicles (Geiger's trans. of the *Mahāvamsa*, p. xxiii).

⁶ *Ait. Br.*, viii. 12-23.

⁷ Keith; *Ait. Br.*, VIII. 15.

⁸ *Ait. Br.*, VIII. 17.

proclaim him. "Be it so" (the people reply). Him the king-makers proclaim saying :

"Him do ye proclaim, O men (*janāḥ*) as king and father of kings . . . The sovereign lord of all beings (*Viśvasya bhūtasya adhipatī*) hath been born, the eater of the folk (*Viśāmattā*) hath been born, the destroyer of enemies (*Amitrānām hantā*) hath been born, the protector of the Brāhmaṇas (*Brāhmaṇānām goptā*) hath been born, the guardian of the law (*Dharmasya goptā*) hath been born."

Here we have the important attributes of kingship. In the words *Viśvasya bhūtasya adhipatī* (supreme lord of all beings) we have a reference to the king's sovereignty and *imperium*. The expression *Viśāmattā*, devourer of the folk, alludes to his power of taxation. As *Amitrānām hantā* he exercises supreme command to weed out enemies. The epithet *Brāhmaṇānām goptā* gives expression to his special relations with the hierarchy, while the style *Dharmasya goptā* points to his duties in connection with the preservation of the laws and their proper administration for the promotion of the common weal (*yoga-kshema*).

When the king has been proclaimed there is an address with the formula, *abhimantraṇa*.¹

Varuṇa the Wise One

Hath set him down, preserving order,

. for kingship

Then comes the anointment (*abhishechana*)

The following kings are said to have been consecrated with the *Aindra Mahābhisheka*; Janamejaya Pārikshita, Śāryāta Mānava, Śātānika Sātrājita, Āmbāśṭhya, Yudhāmśraushtī Augrasainya, Viśvakarmā Bhauvana, Sudās Paijavana, Marutta Āvikshita, Aṅga Vairochana and Bharata Daughshyanti.² The first-mentioned king,

¹ *Ibid.*, VIII, 18.

² *Ibid.*, VIII, 21-23.

and probably the third, fourth, fifth and ninth also, belonged to the post-Parikshit period.¹ Durmukha Pāṇchāla and Atyarāti Jānantapī were informed of the efficacy of the rite. The first made good use of the advice. But the latter who neglected his priest, and wanted to conquer the Uttara-Kurus, whom "no mortal man could vanquish," perished at the hands of a king of the Śibis.

Closely connected with the *Aindra mahābbhisheka* was another important ceremonial called the **Aśvamedha** or horse-sacrifice. All the kings who were, according to the *Aitareya Brāhmaṇa*, actually consecrated with Indra's great function are represented as "going round the earth completely, conquering on every side, and offering the horse in sacrifice" (*samantam sarvataḥ prithivīm jayan pariṇyāśvena cha medhyeneje*). To the list of kings and princes who performed the famous rite the *Satapatha Brāhmaṇa*² adds the names of the Pārikshitas (or Pārikshitīyas) Bhīmasena, Ugrasena and Śrutasena; the Kosalan king (*Kausalya-rāja*) Para Āṭṭpāra Hairanya-nābha; the Aikshvāka king Purukutsa Daurgaha; the Pāṇchāla kings Kraivya, the superman of the Krivis (*Krivīṇām atipurusha*) and Śona Sātrāsāha; the Matsya king Dhvasan Dvaitavana, and the Śvikna king Rishabha Yājñātura. The *Āpastamba Śrauta Sūtra* says that a paramount king (*Sārcabhauma Rājā*) may perform the

¹ Satasoka defeated Dhritarashtra of Kāśi who, according to the *Mahāgoriṇḍa Suttanta* was a contemporary of Sattabha of Kaliṅga and of Brahmadaṭṭa of Asvaka. As the Deccan kingdoms are not referred to in pre-Parikshita works, it is probable that Satasoka and his contemporaries flourished after Parikshit. Āmbāshṭhya and Yudhāmhāraushṭhi were contemporaries of Parvata and Nārada who were very near in time to Nagnajit, the contemporary of Nimi, probably the penultimate king of Videha. Aṅga was probably the immediate predecessor of Dadhivāhana who, according to Jaina evidence, flourished in the 6th century B.C.

² XIII. 6. 4, 1-23.

Aśvamedha.¹ The *Aśva* or steed for a year roamed under guardianship of a hundred princes, and a hundred nobles, a hundred sons of heralds (or charioteers) and village headmen, a hundred sons of warriors and treasurers² (chamberlains?) equipped with various kinds of defensive and offensive weapons. If the year were successfully passed the steed was sacrificed. The features of the rite included panegyrics of the sacrificer along with righteous kings of yore by lute-players including a *Rājanya* who sings to the lute three songs made by himself, "such war he waged, such battle he won." There is also a "circle of tales," *Pāriplava Ākhyāna*³ which lasts by series of ten days for the whole year.

The kingship disclosed in Brāhmaṇic songs and ritual is not merely a "Patriarchal Presidency." The monarch is not merely a chief noble, the first among equals, 'President of a Council of Peers.' In a famous Atharvanic laud the *rājā* of the Kurus, is extolled as a *deva* who

¹ XX. i. 1. Variant readings (e. g. *apgasāreabhaumah*) of the relevant text seem hardly acceptable; Cf. Baudh. XV. 1. Even as late as the time of Bhavabhūti (eighth century A. D.) the *Aśvamedha* was looked upon as "the super-eminent touchstone to test the might of warriors conquering the world and an indication of the conquest of all the warriors"—*Aśvamedha itī viśvavijayinām Kṣatriyāyāmūrtiśca laḥ sarva-kṣatriya-paribhāvi mahānutharshanishkarṣaḥ* (*Uttara-Rāma-charitām*, Act IV, translated by Vinayak Śaḍashiv Patvardhan). The sacrifice seems also to have been performed in early times to atone for sinful work. There was also a Viśvākṣa adaptation of the famous rite—no animals being killed on the occasion, and the oblations prepared in accordance with the precepts of the *Āraṇyakas*. Reference may be made to the story of Uparichara Vasu in the *Sāntiparva* of the *Mahābhārata*, Ch. 335-339 (Raychaudhuri, *EHVS.*, 2nd ed., 132). Regarding the significance of the *Aśvamedha* see also D. C. Sircar's note in *Indian Culture* I, pp. 311 ff; II. 789ff.

² *Sat. Br.* XIII. 4. 2. 5. *tesyante purastādrakṣitāra upakṛtā bhavanti. Rājaputrāḥ karachināḥ śataṁ rājanyā nishāṅgināḥ śataṁ sūtagrāman-yāṁ putrā śikṣapṛṣṭināḥ śataṁ Kṣātra Saṁgrahitṛiṇāṁ putrā daṇḍināḥ śatamaśeasatāṁ nirashṭam niramanāṁ yasminnenamapiṣṭiṇya rakṣanti.*

³ S. B. E. xlv. pp. 298ff; *Pāriplava Ākhyāna* in *Sat. Br.* XIII. 4. 3. 2; Keith, *Black Yajus*, pp. cxxxii f; *RPVU*, 343 f; Hopkins, *GEI* 365, 396.

surpassed mere mortals (*martyas*). The consecrated king is the lord of all beings. He is called "*viśvāsyā bhūtasya adhipati*," and is further described as the devourer of the people—*viśāmatā*.¹ "*Rājū ta ekaṁ mukhaṁ tena mukhena viśo'tsi*."² He is surrounded by armed kinsmen and retainers.³ He can "banish a Brāhmaṇa at will, mulct and overpower a Vaiśya at will, and exact labour from or slay a Śudra at will."⁴ Further he claims the power of giving his kingdom away to anybody he liked. In the *Bṛihadāraṇyaka Upanishad* Janaka says to Yājñavalkya, "*So'ham Bhagavate Videhān dadāmi māñchāpi saha dāsyāyeti*."⁵

The king, however, was not an absolute despot in practice. His power was checked, in the first place, by the Brāhmaṇas. We have seen that the most powerful sovereigns, even those who were consecrated with the *Punarabhisheka*, had to descend from the throne and make obeisance to the 'holy power' (Brahman) that was the repository of culture and education in those days. We learn from the *Aitareya Brāhmaṇa*,⁶ and the *Kauṭiliya Arthaśāstra*⁷ that even a powerful king like Janamejaya was humbled by the Brāhmaṇas. Karālā Janaka met his doom for a crime against a Brāhmaṇa maiden. The Vṛishpis perished on account of their irreverent conduct towards Brāhmaṇas.⁸ This shows

¹ *Ait. Br.*, VIII, 17.

² *Kaush.*, Up., II, 6.

³ *Ait. Br.*, iii, 48. "Sixty-four armed warriors assembled were his (a Kuru's) sons and grandsons." When a Pañchāla king makes an offering there arise "Six thousand and three and thirty warriors clad in mail." *Śat. Br.*, XIII, 5, 4, 16; cf. 4 2, 5.

⁴ *Ait. Br.*, vii, 29.

⁵ *Bṛih. Up.*, IV, 4, 23.

⁶ VII, 27.

⁷ Ed. 1919, p. 11.

⁸ Cf. also the fate of the Vaitahavyas, *Camb. Hist. Ind.* I, 121.

that not only kings, but republican corporations (*Saṅgha*), too, had to cultivate friendly relations with the Brāhmaṇas.

The second check was supplied by the ministers individually or in council, and village headmen who aided in the consecration of the king and whom the king consulted on important occasions. In the Vedic texts the *Sūta* and the *Grāmaṇi* are styled *Rājakarṣi* or *Rājakṛit*, i.e., **King-maker**, "*Rajakṛitaḥ Sūta-Grāmaṇyaḥ*."¹ The very title indicates their importance in the body politic. They, as well as the other *Ratnins*, figure prominently in the sacrifice of royal inauguration.

The existence of a Royal Council (*Sabhā*) is clearly suggested by references to *sabhāsads* in Vedic texts, particularly in connection with king Marutta Āvikshita.² In the *Rāmāyaṇa*³ the *sabhā* is clearly a body in which the *Rājakarṣis* have a place along with the *amātyas* and the *Rājapurohita* (royal chaplain). The claim of the ministers and headmen to be consulted is recognised in Pāli texts while dealing with the period down to the time of Bimbisāra. The *Mahāvagga* says, "King Brahmadatta of Kasi, O Bhikkhus, having entered Benares, convoked his ministers and counsellors (*Amacce Pārisajje sannipātā petvā*)⁴ and said to them: 'If you should see, my good sirs, young Dīghāvu, the son of king Dīghiti of Kosala, what would you do to him?' " The *Mahā assāroha Jātaka*⁵ refers to a king who by beat of drum through the city gathered together his counsellors (*amacheha, amātya*). The *Chulla-Sutasoma Jātaka* refers to the eighty

¹ *Sat. Br.*, III. 4. 1. 7; XIII. 2. 2. 18; In *Rām.* II. 67. 2; 79. 1. the king-makers are *dvijātayah*.

² *Āit. Br.* viii. 21; *Sat. Br.* XIII. 5. 4. 6

³ II. 67. 2-4.

⁴ S.B.E., XVII 304; *Vinnyapitakam* (Oldenberg), I (1879), p. 348. C *Rām.* II, 79, *sāmātyāḥ sapariśadaḥ*.

⁵ No. 302.

thousand councillors of a king headed by his general,¹ (*Senāpati pamukhāni asitī amachcha sahāssāni*). The power of councillors (*amātyas*) to depose a prince and elect a king is recognised in the *Pādañjali*, *Saṃvara*, and *Sonaka Jātakas* respectively. There is evidence regarding special gemots of village headmen. We are told that "when Seniya Bimbisāra, the king of Magadha, was holding an assembly of the eighty thousand *Grāmikas* (Village headmen) he sent message to Soṇa Kolivisa."²

Another check was supplied by the general body of the people (*Jana*, *Mahājana*) who were distinct from the ministers and *Grāmaṇīs*, or *Grāmikas*, and who used to meet in an assembly styled **Samiti** or **Parishad** in the *Upanishads*.³ In the *Utkrośana* passage of the *Aitareya Brāhmaṇa*⁴ the people (*Janāḥ*) are clearly distinguished from the *Rājakartāraḥ* among whom, according to the *Śatapatha Brāhmaṇa*⁵ were included the *Sūta* and the *Grāmaṇī*.⁶ That the *Samiti* or *Parishad* was an assembly of the whole people, is apparent from such expressions as "*bhūyishṭhāḥ Kuru-Pañchālāssāgatā bhavitāraḥ...*"⁷, "*Pañchālānām Samitim eyāya*", "*Pañchālānām Parishadam ājagāma*," "*samaggā Śivayo hutvā*". The *Chhāndogya Upanishad*⁸ mentions the *Samiti* of the *Pañchāla* people presided over by king *Pravāhana Jaivali*, *Śvetaketurh*

¹ Cowell's *Jātaka*, V. p. 97 (No. 525); 'eighty thousand' is a stock number and should not be taken too literally.

² *Mahāvagga*, S. B. E. XVII, p. 1.

³ In the *Jaim. Up. Br.* II. II. 4. we find a reference to the *Parishad*, the *Sabhā* and the *Saṃsad*. It is not clear, if these are distinct institutions. The *sabhā* and the *samiti* are, however, distinguished in the *Atharva-Veda*.

⁴ VIII, 17; cf. *Śat. Br.* V. 33. 12.

⁵ III, 4. 1. 7; XIII. 2. 2. 18.

⁶ For *Mahājana*, see *Jātaka* (525), Vol. V. p. 187; *Jātakas* (542, 547), Vol. VI. p. 156, 489 etc; cf. *Śat. Br.* V. 3. 3. 12.

⁷ "Most of the Kuru-Pañchalas shall be assembled together." *Jaim. Up. Br.* III. 7. 6.

⁸ V 3. 1.

Āruṇeyah Pañchālānām Samitim eyāya ; tam ha Pravāhaṇo Jaivalir uvācha." The *Bṛihadāraṇyaka Upanishad*¹ uses the term *Parishad* instead of *Samiti*, "*Śvetaketur ha vā Āruṇeyah Pañchālānām Parishadamājagāma.*" The analogy of the Lichchhavi *Parishā* and of similar assemblies mentioned in Buddhist works shows that the functions of the Kuru and Pañchāla *Parishads* were not necessarily confined to philosophical discussions only. The *Jaiminīya Upanishad Brāhmaṇa*² refers to disputations (*saṁvāda*) and witnesses (*upa-draśṭṛi*) in connection with popular assemblies, and informs us that the procedure among the Kurus and the Pañchālas was different from that of Sūdras. The people took part in the ceremony of royal inauguration.³ The *Dummedha Jātaka*⁴ refers to a joint assembly of ministers, Brāhmaṇas, the gentry, and the other orders of the people.

That the people actually put a curb on royal absolutism is proved by the testimony of the *Atharva-Veda*⁵ where it is stated that concord between king and assembly was essential for the former's prosperity. We have evidence that the people sometimes expelled and even executed their princes together with unpopular officials. Thus it is stated in the *Satapatha Brāhmaṇa*⁶ "Now Dush-tarītu Pauṁsāyana had been expelled from the kingdom which had come to him through ten generations, and the Sṛiṅjayas also expelled Revottaras Pātava

VI. 2. 1.

² III. 7. 6.

³ *Alt. Br.*, VIII. 17.

⁴ No. 50; cf. *Vessantara Jātaka* (No. 547), Vol. VI, pp. 490 ff. The whole Sivi people assembled to discuss a matter of public importance, to give advice to the king and to inflict punishment on a prince.

⁵ VI. 88. 3.

⁶ XII. 9. 3. 1 *et seq*; Eggeling, V. 269.

Chākra Sthapati.'"¹ The *Aitareya Brāhmaṇa*² refers to personages who were expelled from their kingdoms (*rāsh(ras)*) and who were anxious to recover them with the help of the Kshatriya consecrated with the *Punar-abhisheka*. Such persons were the Indian counterparts of the French "emigrants" who sought to reclaim revolutionary France with the help of the troops of the Hapsburgs and the Hohenzollerns.³ We learn from the *Vessantara Jātaka*⁴ that the king of the Śivis (Śibis) was compelled to banish prince Vessantara in obedience to "the people's sentence" (*Sivīnam vachanatthena samhā ratthā nirajjati*).

The king was told :

"*Sache tvaṃ na karissasi Sivīnam vachanam idam
maññe taṃ saha puttena Sivīhatthe karissare ti*"

The bidding of the Sivi folk if you refuse to do

The people then will act, methinks, against your son

and you.

The king replied :

"*Eso che Sivīnam chhando chhandam na panudāmase*"

Behold the people's will, and I that will do not gainsay.

The *Padakusalamānava Jātaka*⁵ tells a story how the town and the countryfolk of a kingdom assembled (*jānapadā negamā cha samāgatā*), beat the king and priest to death as they became a source, not of weal, but of woe (lit. fear, *yato khemaṃ tato bhayaṃ*), and anointed a good man as king. A similar story is told in the *Sachchamkira Jātaka*.⁶ We are told in the *Khaṇḍahāla Jātaka*⁷ that

¹ For the designation 'Sthapati', see *ante*, p. 167.

² VIII. 10.

³ Cf. Lodge, *Modern Europe*, p. 517.

⁴ No. 547; Text VI. 490-502. The Śibis are known to *Alt. Br.* viii, 23.

⁵ No. 432.

⁶ No. 73.

⁷ No. 512.

the people of one kingdom killed the minister, deposed the king, made him an outcaste and anointed a prince as king. The ex-king was not allowed to enter into the capital city. Fick¹ points out that in the *Talapatta Jātaka* a king of Takshaṣilā says that he has no power over the subjects of his kingdom. This is in striking contrast with the utterance of Janaka quoted above.² Evidently the Royal power had declined appreciably, at least in some of the north-western *Janapadas*, since the days of Janaka.³

¹ *The Social Organisation in North-East India*, trans. by Dr. S. K. Maitra, pp. 113-114. Dr. D. R. Bhandarkar follows him in *Carmichael Lectures*, 1918, 134f.

² P. 172, "*Bhagavate Videhān dadāmi*".

³ Note the references to elected kings (e. g. amongst the Kathaioi) and autonomous folks by the historians of Alexander in the fourth century B.C. The Ambashthas had a strong monarchy in the Brāhmaṇa period (*Ait. Br.* viii 21). In the days of Alexander (*Inn. Alex.* 252) the constitution was democratic.

PART II

172

Political History of Ancient India

PART II

From the Coronation of Bimbisāra to the Extinction of the
Gupta Dynasty

CHAPTER I. INTRODUCTION.

SECTION I. FOREWORD.

The following pages deal with the political history of India from the time of Bimbisāra to that of the Guptas. For this period we are fortunately in possession of authentic historical materials in addition to literary tradition to which reference has already been made in the first part of the book. These materials are derived principally from the following sources: inscriptions, coins, accounts left by foreign observers and works of Indian authors of known date and authenticity.

Inscriptions engraved on stone and copper undoubtedly form the most copious and important source. Hardly less important are the coins which constitute almost the sole evidence of the history of certain dynasties and republican communities of the second and first centuries B. C. Foreign accounts, especially the records of Greek diplomats and navigators and of Chinese annalists and pilgrims, are especially valuable in connection with the vexed question of Indian chronology. Works of Indian writers of known epochs, that illumine the darkness of our period, and afford interesting glimpses of political history, are extremely rare and comprise the *Mahābhāshya* (Great Commentary) of Patañjali, the

Kalpanāmaṇḍitikā of Kumāralāta, the *Life of Vasubandhu* by Paramārtha and the *Harsha-charita* (Deeds of Harsha) by Bāṇabhaṭṭa.

For the history of the period from Bimbisāra to Aśoka the writer of these pages cannot in some respects claim much originality. The subject has been treated by Rhys Davids and Smith, and a flood of new light has been thrown on particular dynasties by Geiger, Bhandarkar, Rapson, Jayaswal, Malalasekera, Jackson, Herzfeld, Hultsch and others. Use has in some cases been made of the information contained in their works, and it has been supplemented with fresh data gathered mainly from epical, Jaina, Buddhist and classical sources. As instances it may be pointed out that attention to the name Haryanka, given to the Bimbisārid family by Aśvaghoṣa, was first drawn in these pages. The tradition recorded in the *Harsha-charita* and Jaina works regarding the tragic end of Śiśunāga's line and origin of the Nandas has been collated with the evidence of the Graeco-Latin writers. Epic data have been used largely to illustrate the dawn of Magadban ascendancy, locate tribes like the Kambojas and the Pulindas who figure in the Aśokan edicts, and to explain expressions like *stryadhaksha*, *viḥarayātrā*, *anusamyāna* etc. Old materials have also been presented in many cases in a new shape, and the author's conclusions are often different from those of former writers.

In the chapter on the Later Mauryas the author has examined the causes of the dismemberment of the Maurya Empire, and drawn pointed attention to the Gārgi Saṁhita, the Hon Hanshu, etc. and has tried to demonstrate the unsoundness of the current theory that "the fall of the Maurya authority was due in large measure to a reaction promoted by the Brāhman."¹

¹ The Chapter on the Later Mauryas was published in the JASB, 1920 (No. 18, pp. 305 ff.).

The treatment of the history of the Early Post-Mauryan and Scythian periods, though not entirely original, is different in many respects from that of previous authors. It has not been possible to accept the current views with regard to the lineage of Pushyamitra and the history and chronology of several dynasties, notably of the Early śātavāhanas, the Greeks of Śākala, and the Śaka-Pahlavas of the *Uttarāpatha* or North-West India. As early as 1923 the writer of these pages assigned to the Nāgas of the Jumna valley and Eastern Malwa and the Bhāraśivas their proper place in the history of the post-Kushan period, a fact which has been ignored in some wellknown publications.

In the account of the Gupta period use has been made of the mass of fresh materials accumulated since the publication of the works of Bühler, Fleet, Smith and Allan. The notices of the most famous ruling family of the age in early epigraphs and literature, which are sometimes overlooked, have received due attention, its relations with southern dynasties like the Vākaṭakas have been discussed, and an attempt has been made to present a connected history of the so-called 'Later Guptas.'¹

¹ The Chapter on the so-called Later Guptas was published in the *JASB.*, 1920 (No. 19, pp. 313 ff),

SECTION II. LOCAL AUTONOMY AND IMPERIAL UNITY.

The chief interest of the political history of the post-Bimbisārian Age lies in the interplay of two opposing forces, one centrifugal, the other centripetal, *viz.*, the love of local (*Jānapada*) autonomy and the aspiration for imperial unity. The former ideal is best expressed in the words of Manu—*sarvaṃ paravaśaṃ duḥkham, sarvaṃ ātmavaśaṃ sukham*,¹ "subjection to others is full of misery, subjection to self leads to happiness." The predilection for local self-rule was in part fostered by geographical conditions. The intersection of the land of India by deep rivers and winding chains of mountains flanked by dreary deserts or impenetrable forests, developed a spirit of isolation and cleft the country asunder into small political units whose divergences were accentuated by the infinite variety of local conditions. But the vast riparian plain of the north and the extensive plateau in the interior of the Deccan Peninsula, decked with green by the life-giving streams that flow from the majestic heights of the Himālayas and the Western Ghats, fostered an opposite tendency—an inclination towards union and coalescence. The sands which choked the Sarasvatī, the floods that swelled the Lauhītya, the dangers that lurked in the Mahātavī proved no effective bar to unity. The five hills of Girivraja could not permanently withstand the conquering heroes who were charged with an imperial mission. The head of the Vindhya bent in reverence before the sage who was bringing the culture of the Ganges valley to the banks of the Godāvarī and the Tāmraparṇī.

The desire for union under one political authority became manifest as early as the Brāhmaṇa period and found expression in passages like the following:—

“May he (the king) be all-encompassing, possessed of all the earth, possessed of all life, from the one end up to the further side of the earth bounded by the ocean, sole ruler (*ekarāt*).”

The ideal persists throughout our period and inspired poets and political philosophers who spoke of the thousand *yojanas* (leagues) of land that stretch from the Himālayas to the sea as the proper domain of a single universal emperor (*chakravarti-kshetra*) and eulogised monarchs who protected the earth decked with the Ganges, as with a pearl necklace, adorned with the Himavat and the Vindhya, as with two earrings, and robed with a swinging girdle in the shape of the rocking oceans.

The imperial ideal had to contend with the centrifugal tendencies of *Jānapada* (provincial and tribal) autonomy. The two forces operated in successive epochs almost with the regularity of the swing of the pendulum. The aspiration for a unity that transcended local boundaries owed its success not a little to the presence of another factor in Indian politics—the danger threatening from foreign invaders. It was only when the “earth was harassed by the barbarians” (*Mlechchhairudvejyamānā*) that she sought refuge in the strong arms of Chandra Gupta Maurya, the first great historical emperor of India—whose dominions undoubtedly overstepped the limits of *Āryāvarta*. Among the early empire-builders of the south was a prince who rid his country of the Scythians, Greeks and Parthians (*Saka-Yavana-Pahlava-nishūdana*). And the rulers who revived the imperial glory of the Gangetic Provinces in the fourth and fifth centuries A.D., were warriors who humbled the pride of the Scythian “Son of Heaven” and

braved the wrath of the Saka king in his own city. According to sacred legends Vishnu in the shape of a Boar had rescued the earth in the aeon of universal destruction. It is significant that the worship of the Boar Incarnation became widely popular in the Gupta-Chalukya period. The poet Viśakhadatta actually identifies the man in whose arms the earth found refuge when harassed by the *Mlechchhas*, who "shook the yoke of servitude from the neck" of his country, with the *Vārāhītanu* (Boar form) of the Self-Existent Being. Powerful emperors both in the north and the south recalled the feats of the Great Boar and the mightiest ruler of a dynasty that kept the Arabs at bay for centuries actually took the title of *Ādivarāha* or the Primeval Boar. The Boar Incarnation then symbolized the successful struggle of Indians against the devastating floods issuing from the regions outside their borders that threatened to overwhelm their country and civilisation in a common ruin.

CHAPTER II

THE RISE OF MAGADHA

*Sarvamūrdhābhishiktānāmesha mūrdhni jvalishyati
prabhāharo' yaṁ sarveshām jyotishāmicā bhāskararah
enamāsādyā rājānaḥ samriddha-balavāhanā
vināśamupayāsyanti śalabhā iva pāvakaṁ.*

—*Mahābharata*.¹

SECTION I. GENERAL CHARACTER OF THE PERIOD C. 544 B. C. to 324 B. C.

The most remarkable feature of the age that commenced with the coronation of Bimbisāra c. 545—44 B.C.,² and ended with the retirement of Alexander from India and the accession of Chandra Gupta Maurya (324 B. C.), is the rise of a New Monarchy in the Eastern part of the Indo-Pakistan sub-continent which is already heralded by a *Brāhmaṇa* passage cited above³:

“In this eastern quarter (*prāchyām diśi*), whatever kings there are of the eastern peoples, they are anointed for supreme kingship (*Sāmrājya*); ‘O supreme king (*Samrāt*) they style them when anointed.”

The eastern peoples, *prāchyas*, are not enumerated in the same manner as those of the southern, the northern and the central regions. But it may be safely assumed that the name used in the *Aitareya Brāhmaṇa* stands for the *Prasii* of the Graeco-Roman writers. The most famous nations of the east in the *Brāhmaṇa-Upanishad* period were the *Kāśis*, the *Kosalas* and the *Videhas*. But a new star was

¹ II. 19 10-11.

² See below, Section VII.

³ Pp. 166-7

soon in the ascendant. Under the vigorous kings of the race of Bimbisāra and Nanda Magadha played the same part in ancient Indian politics as Wessex did in pre-Norman England and Prussia in Hohenzollern Germany. Several circumstances contributed to the pre-eminence of the new aspirant for imperial power—its position of vantage between the upper and lower parts of the vast riparian plain of Northern India, the possession of an almost unassailable stronghold amidst five hills, and another at and near the confluence of several rivers, the arteries of commerce and navigation in those days, a superbly rich and fruitful soil, and resources including a powerful elephant corps which greatly impressed the classical writers and writers in polity.

But strategic position and material wealth cannot suffice to raise a nation to greatness. As Burke says, it is the quality and spirit of the people 'that give all their life and efficacy to them'. As in several Atlantic lands, so in Magadha, we have a fusion of folks and cultures. Kīkaṣas mixed here with enterprising clans coming from upper India as Celts did with Latins and Teutons in Mediæval France and some adjoining territories. It is not difficult to find out two strands in the cultural—no less than the racial—texture of the population. The same nation that produced relentless fighters and, 'exterminators of kings' and clans like Jarā-sandha of epic legend, Ajātaśatru, Mahāpadma, Chanḍāsoka (the ruthless conqueror of Kalinga) and perhaps Samudra Gupta, hearkened at the same time to the devout teachings of Madhyama Prātibodhīputra, Varddhamāna Mahāvīra, and Gautama Buddha, and played a conspicuous part in the propagation of a world religion as it did in the establishment of an empire embracing nearly the whole of India. The birth of Ajātaśatru and the enlightenment of the Buddha took place in the same country and the same age, and they met in Rājagriha as Charles V and

Martin Luther did at Worms. The symbol of aggressive imperialism stood face to face with the preacher of piety and morality, leader of a movement that was destined to convulse a continent. The two ideologies did not long remain apart. They were harmonised and the magician who worked the miracle was Dharm-āśoka who combined in himself the imperial tradition of his forbears as well as the spiritual fervour of the sage of the Śākya.

A characteristic of the people of Magadha was an elasticity of social behaviour which was absent in the system which developed on the banks of the Sarasvatī and the Drishadvatī. In their country Brāhmaṇas could associate with *Vrātyas*, the *Rājanya* could admit the *Sūdra* girl to the harem, the *Vaiśya* and even the *Yavana* could be promoted to gubernatorial office, hereditary rulers of aristocratic lineage could be expelled to make room for the offspring of a *nagara-sobhinī*, and the "royal throne of kings" was not beyond the reach of a barber.

Magadhan rulers and chancellors like Vassakāra (Varshakāra) and Kauṭilya, were not over-scrupulous in their methods. Tradition credits some of them with the use of Machiavellian diplomacy in disintegrating kingdoms and republics, and invention of engines of destruction which worked with deadly effect. But they had the sagacity to evolve an administrative system in which princes royal, ministers of state as well as leading men of villages had their due share. Foreign diplomats and pilgrims in the fourth century B. C., as well as the fifth and seventh centuries A. D. speak of their sense of justice, their hospitals, charitable institutions and public works. They believed in ceaseless endeavour with the object of realising the dream of a united Jambudvīpa (Greater India) integrated by political as well as spiritual ties. In the *Māgadha* bards, the rulers of Girivraja and Pāṭaliputra had a body of devoted men who could rouse popular

enthusiasm in a cause in which they believed. These singers and chroniclers have left a legacy which is invaluable to the student of ancient history.

The rise of Magadha synchronised with, and may have been a contributory cause of, an exodus of people from the *Madhya-deśa* to the outlying parts of India, notably the west and the south. The displacement of the Yādavas in antiquity is vouched for by epic tradition. It is well-known that the Vṛishnis and cognate clans of Dvārakā in Kāthiāwār and several peoples of the Deccan claimed Yādu lineage. It was in the period under review that the Far South of India comes definitely within the geographical horizon of the grammarians and foreign diplomats some of whom graced the *Durbar* of Magadhan kings. *Sapta-Sindhu* had at last developed into *Jam udvīpa*. And the time was not distant when a notable attempt would be made to impress the stamp of unity on it in the domain of culture and politics.

In making their prowess felt throughout the vast sub-continent of India the great men of Magadha had at first to face three problems, *viz.*, those presented by the republics mainly on their northern frontier, the monarchies that grew up on the Rāptī, the Jumna and the Chambal and the foreign impact that made itself felt in the Punjab and Sind. We turn first to the republics.

SECTION II. REPUBLICS IN THE AGE OF BIMBISARA.

It was Rhys Davids who first drew pointed attention to the survival, side by side with the monarchies, of a number of small aristocratic republics in the age of the Buddha and of Bimbisāra.¹ The most important amongst these states were the **Vrijians** of North Bihār and the **Mallas** of Kusinārā (Kusinagara) and Pāvā. An account of both these peoples has already been given.² Among the smaller republics we find mention of the Śākya of Kapilavastu, the Koliyas of Devadaha and Rāmagāma, the Bhaggas (Bhargas) of Sumsumāra Hill, the Bulis of Allakappa, the Kālāmas of Kesaputta, and the Moriyas of Pippalivana.

The Śākya were settled in the territory bordered on the north by the Himālayas, on the east by the river Rohiṇī,³ and on the west and south by the Rāptī.⁴ Their capital, Kapilavastu, stood close to the western bank of the Rohiṇī, some eight miles to the west of the famous Lumbinīvana,⁵ the place of the Buddha's nativity, the site of which is marked by the Rummindeī pillar of one of the greatest of his followers.⁶ The city is possibly mentioned in the *Tīrthayātrā* section of the *Mahābhārata*⁷ under the name of *Kapilāvata*. It was connected by roads with the capitals of the Kosalas and

¹ *Buddhist India*, p. 1.

² *Supra* pp. 118ff, 126ff.

³ A tributary of the Rāptī (Oldenberg, *Buddha*, p. 96). Cunningham (AGI, new ed. 476) identifies it with the Kobāna.

⁴ *Rapean Ancient India*, p. 161; Oldenberg, *Buddha*, pp. 95-96.

⁵ AGI (new ed) 476.

⁶ Kapilavastu is sometimes identified with Piprāwā in the north of the Baett district, or Tilaura Kot and neighbouring ruins in the Tarāi about 10 miles to the N.W. of Piprāwā. (Smith, *EHI*, third ed., p. 169.)

⁷ III. 84. 31.

the Vrijikas, and through them with the other great cities of the age. The Sākya had a town called Devadaha which they appear to have shared with their eastern neighbours, the Koliyas. They acknowledged the suzerainty of the king of Kosala and, like him, claimed to belong to the solar (*Āditya*) race and Ikshvāku family.

The **Koliyas** claim to have been cadets from the royal house of Benares. Tradition connects them with the cities of Rāmagāma and Devadaha.¹ The river Rohiṇi separated their capital from that of the Sākya, and helped to irrigate the fields of both the clans.² "Once upon a time in the month of *Jetṭhamūla* when the crops began to flag and droop, the labourers from amongst both the peoples assembled together." Then followed a scramble for water. Bloodshed was averted by the mediation of the Buddha.³ From the mutual recriminations in which they indulged, we learn that the Sākya had the custom of marrying their own sisters. Cunningham places the Koliya country between the Kohāna and Aumi (Anomā) rivers. The Anomā seems to have formed the dividing line between the Koliyas on the one hand and the Mallas and Moriyas on the other.

The **Bhaggas** (Bhargas) are known to the *Aitareya Brāhmaṇa*⁴ and the *Aṣṭādhyāyī* of Pāṇini.⁵ The former work refers to the Bhārgāyaṇa prince Kairiśi Suvan. In the latter half of the sixth century B.C., the Bhagga state was a dependency of the Vatsa kingdom; for we learn from the preface to the *Dhonasākha Jātaka*,⁶ that prince Bodhi, the son of Udayana, king of the Vatsas, dwelt

¹ DFPN, I. 680f. The Koliya capital stood close to the eastern bank of the Rohiṇi.

² The *Kuṇḍala Jātaka* (introductory portion).

³ DFPN, I. 690, Conn. AGI (new) 477; 491 ff.

⁴ VIII. 28.

⁵ IV. 4. III, 177.

⁶ No. 363.

in Sumsumāragiri and built a palace called *Kokanada*. The *Mahābhārata* and the *Harivaṃśa* also testify to the close connection between the Vatsas and the Bhargas (Bhaggas) and their proximity to the Nishādas. The testimony of the epic and the *Apadāna* seems to locate them in the Vindhyan region between the Jumna and the Son.¹

Regarding the **Bulis** and the **Kālāmas** we know very little. The *Dhammapada commentary*² refers to the Buli territory as the kingdom of Allakappa, and says that it was only ten leagues in extent. From the story of its king's intimate relationship with king Veṭṭhadīpa it may be presumed that Allakappa lay not far from Veṭṭhadīpa, the home of a famous Brāhmaṇa in the early days of Buddhism, who made a cairn over the remains of the Buddha in his native land.³ The Kālāmas were the clan of the philosopher Ālāra, a teacher of Gautama before he attained to *Sambodhi*.⁴ The name of their *nigama* (town) Kesaputta, reminds us of the Keśins, a people mentioned in the *Satapatha Brāhmaṇa*⁵ and probably also in the *Aṣṭādhyāyī* of Pāṇini,⁶ and connected with the Pañchālas and Dālhyas who appear in the *Rig-Veda*,⁷ as settled on the banks of the Gomatī. Kesaputta itself seems to have been annexed to Kosala,⁸ and no doubt acknowledged the suzerainty of the king of that powerful state.

¹ *Mbh.*, II, 30, 10-11; *Hariv.*, 29, 73, DPPN, II, 346; *Supra* p. 133.

² Harvard Oriental Series, 28, p. 247.

³ Majumdar Sāstri connects Veṭṭhadīpa with Kasia (AGI, 1924, 714); cf. Fleet in JRAS, 1906, p. 900n; Hoey suggests that Veṭṭhadīpa is Bettiah in the Champaran District of Bihar.

⁴ *Buddhacarita*, XII, 2.

⁵ *Ved. Ind.*, Vol. I, p. 186.

VI, 4, 166.

⁷ V, 61.

⁸ The *Āṅguttara* (P. T. 8, I, 186; Nipāta III, 65).

The **Moriyas** (Mauryas) were the same clan which gave Magadha its greatest dynasty.¹ They are sometimes spoken of as of Śākya origin, but the evidence is late. Earlier evidence distinguishes between these two clans.² The name is derived, according to one tradition, from *mora* (*mayūra*) or peacock. The place where they settled down is said to have always resounded with the cries of these birds. Pipphalivana, the Moriya capital, is apparently identical with the Nyagrodhavana or Banyan Grove, mentioned by Hiuen Tsang, where stood the famous Embers Tope.³ Fa Hien tells us that the Tope lay four *yojanas* to the east of the river Anomā, and twelve *yojanas* (probably some 54 miles) to the west of Kusinārā.⁴

It will perhaps not be quite out of place to say here a few words about the internal **organisation** of the republics. Space, however, forbids a detailed treatment of the subject. They fall mainly into two classes, *viz.*, those that were constituted by the whole or a section of a single clan (*kula*) *e.g.*, the Śākyas, the Koliyas, the Mallas of Kusinārā, the Mallas of Pāvā etc., and those that comprised several clans like the Vrijis (Vajjis) and the Yādavas. The distinguishing feature of a state of this type is the absence of *one* single hereditary monarch who exercised *full* control over it. The *Basileus*, if he survived at all, must have done so as a mere magistracy or as a dignified

¹ "Then did the Brāhmaṇa Cānakka anoint a glorious youth, known by the name Candagutta, as king over all Jambudīpa, born of a noble clan, the Moriayas." Geiger, *Mahāvamsa*, p. 27; DPPN, II, 673.

² *Mahāparinibbāna Sutta*.

³ Rhys Davids, *Buddhist Suttas*, p. 135; Watters, *Yuan Chwang*, II, pp. 23-24; Cunningham, *AGI*, new ed., pp. 491f, 496f.

⁴ *AGI* (new) 491, Legge, *Fa Hien*, p. 79; Watters, I, 141; cf. JRS., 1903. As Kasja (Kusinārā, Kuśinagara) lay 35 miles to the east of Gorakhpur (*AGI*, 493), the Moriya city could not have been situated very far from the last-mentioned town. The Moriayas seem also to have been close neighbours of the Koliyas beyond the Anomā and the Mallas of Anupiyā on the banks of that river.

part of the constitution.¹ The efficient part comprised a president (chief, *gaṇapati*, *gaṇajyestha*, *gaṇarāja*, *saṅgha-mukhya*) and a council of archons taken from the ruling class. Such a president was Cheṭaka of Vaiśālī and Akoup-his of Nysa in later times, the terrestrial counterpart of Indra, in his capacity as the *Jyeshtha* of the Marud-*gaṇa*.² According to a Jaina tradition the number of members of the supreme executive in charge of foreign and military affairs was in some states nine.³ There were functionaries like *uparājās* and *senāpatīs* who exercised judicial and military functions. All these Elders possibly answer to the *Mahallakas* of Pāli texts and *Mahattaras* of the *Vāyu Purāṇa*,⁴ whom it was the duty of the citizens to respect and support.

Some of the clans possibly had an elaborate system of judicial procedure with a gradation of officers. Others, notably the Koliyas, had a police force which earned notoriety for extortion and violence.⁵ Reverence for tradition, especially for traditional religion with its shrines and ministers, was a feature that recalls the part that ancestral religion played in ancient Babylonia and modern Nippon.

Perhaps the most important institution of the free republics was the *Parishā*, the popular assembly, where young and old held frequent meetings, made their decisions and carried them out in concord. Kettledrums⁶ were used by an officer (styled *sabhāpala* in the epic) to

¹ Cf. the case of Ugrasena among the Yādavas.

² *Rig-veda* I. 23. 8; cf. II. 23. 1.

³ *Nava Mallai*, *Nava Lechchhai* etc. *supra* p. 125. In Nysa the governing body consisted of 300 members. The number of "leading men of cities and provinces" entrusted by the Kshudrakas with power to conclude a treaty is not definitely stated.


⁴ *Vāyu*, 96. 35.


⁵ *DPPN*, I. 696.

⁶ *Këndred Sayings* II. 178 (reference to kettledrum of the Dasārhas; cf. *Mbh.*, I. 220. 11).

bring the people to the Mote Hall, called *Santhāgāra* in the Pali texts. The procedure is perhaps analogous to that followed in the Kuru-Pañchāla assembly mentioned in the *Jaiminiya Upanishad Brāhmaṇa*, in a palaver in Sakra's heaven described in the *Mahāgovinda Suttanta*, or in formal gatherings of the Chapters of the Buddhist Order referred to in the *Vinaya* texts. Members "are seated in a specified order. After the president has laid the proposed business before the assembly, others speak upon it, and recorders take charge of the unanimous decision arrived at."¹ If there is any disputation (*saṃcāda*) the matter is referred to a committee of arbitrators. It is possible that technical expressions like *āsana-prajñāpaka* (seat-betokener), *ñatti* (*jñapti*, motion), *śalākā-gāhāpaka* (ballot-collector), *gaṇa-pūraka* (whip), *ubbāhikā* (referendum) found in the Rules of the Order, were adopted from those in use in the assemblies of the free tribes or clans.

¹ *Jaim. Up. Br.* III 7, 55. *Comb. Hist. Ind.* I, 176; cf., *Carm. Lec.* 1918, 189E.





SECTION III. THE MINOR PRINCIPALITIES AND THE GREAT MONARCHIES

An important feature of Indian history throughout the ages is the presence of numerous petty *Rājās* holding their courts either in some forest region, mountain fastness, or desert tract away from the main currents of political life, or in a riparian or maritime district, each separated from his neighbour by a range of hills, a stream, a forest or an expanse of sandy waste. It is impossible to enumerate all such tiny states that flourished and decayed in the days of Bimbisāra. But a few deserve notice. Among these were Gandhāra ruled by Pauskarakasārin or Pukkusāti, a remote predecessor of Āmbhi, Mādra governed by the father of Khemā, a queen of Bimbisāra, Roruka (in Sauvīra or the Lower Indus Valley) under the domination of Rudrāyana,¹ Śurasena ruled by Avantīputta (either a successor of, or identical with, Subāhu), and Aṅga under the sway of Driḍhavarman and Brahmaddatta.

It is difficult to say anything about the ethnic affiliation of these rulers. The form of the names indicates that they were either Aryans themselves or had come under the influence of Aryan culture. But there were certain principalities which were definitely styled Nishāda in the epic, and Ālavaka, (forest-folk of Yaksha-infested land) in the Pāli texts and were doubtless of non-Aryan origin.

One of these, the realm of **Ālavaka**,² demands some notice as the relic of a past that was fast disappearing. This little state was situated near the Ganges and was probably identical with the Chanchu territory visited by Yuan

¹ *Dīrghacādāna*, p. 545.

² *Sutta Nipata* S. B. E., X, II, 29-30.

Chwang (Hiuen Tsang). Cunningham and Smith identify it with the Gbāzipur region.¹ The name is derived from the capital Ālavī² (Sanskrit *Aṭavī*, cf. *Ātavika*) or Ālabhiyā³ which stood close to a large forest that doubtless suggested the particular nomenclature.⁴ In the *Abhidhānappadīpikā* Ālavī finds a place in a list of twenty famous cities: Bārāṇasī, Sāvattihī, Vesālī, Mithilā, Ālavī, Kosambhī, Ujjenī, Takkasilā, Champā, Sāgala, Sumsumāragira, Rājagaha, Kapilavatthu, Sāketa, Indapaṭṭa, Ukkatṭha,⁵ Pāṭaliputtaka, Jettuttara,⁶ Saṃkassa⁷ and Kusinārā. The *Chullavagga*⁸ mentions the Aggālave shrine at Ālavī which the Buddha honoured by his visits, as it lay on the way between the capitals of Kosala and Magadha. In the *Uvāsaga-dasāo* the king of Ālabhiyā is named *Jiyasattū* (Jita-śātru, conqueror of enemies). But *Jiyasattū* seems to have been a common designation of kings⁹ like the epithet *Devānampiya* of a later age.¹⁰ The name is given also to the rulers of Sāvattihī, Kampilla, Mithilā, **Champā**, Vāṇiyagāma, Bārāṇasī and Polasapura,

¹ Watters, *Yuan Chwang*, II, pp. 61, 310.

² *Sutta Nipāta : The Book of the Kindred Sayings*, Vol. I, p. 275.

³ *Uvāsaga-dasāo* II, p. 103; Appendix, pp. 51-53.

⁴ Cf. *The Book of the Kindred Sayings*, Vol. I, p. 160. The derivation of the name of the country from *aṭavī* was suggested by Hoernle who also pointed out the reference in the *Abhidhānappadīpikā*. Cf. also the references to forest peoples and kingdoms in the inscriptions of Aśoka and Samudra Gupta.

⁵ A town in the Kingdom of Kosala (*Dialogues of the Buddha*, I, 108).

⁶ Near Chitor (N. L. Dey).

⁷ Sanskrit Sāṅkāsya or Kapitthikā which is identified by Cunningham with Sankisa on the Ikshumati river, in the Farukhabad District, U. P. (Cunn, AGI, new ed. pp. 422f., 706).

⁸ VI, 17; cf. also *Gradual Sayings*. IV, 147; DPPN, I, 295.

⁹ Cf. *Amitrānāḥ hantā* of the *Ait. Br.* The Essay on Guṇādhyā (189) mentions Hatthālavaka as the king of Ālavī.

¹⁰ In Babylon, however, the style "favourite of the gods" is found as early as the age of Hammurabi (*Camb. And. Hist.*, I, p. 511; *I. C.*, April-June, 1946, p. 241).

who were all contemporaries of Mahāvīra.¹ Buddhist writers refer to other "Yakkha" principalities besides Ālavaka.²

The most important factors in the political history of the period were, however, neither the republics nor the forest principalities but the **four Great Kingdoms** of Kosala, Vatsa, Avanti and Magadha.

In **Kosala** king Mahākosala had been succeeded by his son Pasenadi or Prasenajit. As already stated, the Kosalan monarchy had spread its tentacles over a vast area extending perhaps from the Gumti to the Little Gaṇḍak and from the Nepalese Tarāi to the Ganges, possibly even to the eastern part of the Kaimur range. It counted amongst its vassals several *rājās*,³ including, doubtless, the rulers of the Kāśis, the Śākyas and the Kālāmas. Among its officials were two Mallas, Bandhula and his nephew Dīrgha Chārāyaṇa,⁴ who must have helped their sovereign to secure influence in the tiny state beyond the Little Gaṇḍak from which they came. "Nine Mallakis" appear as allies of the rulers of Kāśi-Kosala in Jaina texts. Friendship with the "Visālikā Licchabhavī" and with Seniya Bimbisāra,⁵ the master of Mgadha, must have favoured peaceful penetration in the east and left the king free to organise his kingdom and dealing drastically with robbers and savages who menaced the road from

¹ Cf. Hoernle, *Ucāsaga-dasāo*, II, pp. 6, 64, 100, 103, 106, 118, 166. In the *Ārya Mañjuśrī Mūla Kalpa* (ed. G. Śāstri, p. 645), a king of Gauḍa is styled "Jitadatra". It is absurd to suggest, as does Hoernle (p. 103 n), that Jiyasattū, Prasenajit and Cheḍaga were identical. Cf. *Indian Culture*, II, 806.

² Cf. *Sutta Nipāta*, S.B.E., Vol. X, ii, p. 45.

³ For the identification of the *Rājās*, see Part I ante, 155f.

⁴ *Majjhima N.* II, p. 118. He is probably identical with the person of that name mentioned in the *Kauṭīliya Arthśāstra* and inscriptions (*nīlīvijita Chārāyanah*, *Ep. Ind.* III, 210) as a writer on polity, and by Vātsyāyana as an authority on Erotics.

⁵ *Majjhima N.* II, p. 101.

Sāketa to Sāvattthī, and interfered with the peaceful life of the monks.

The character of such a man, one of the leading figures of the age, who had received his education at Taxila, and became a friend of the Buddha, deserves study and we have an admirable exposition by Mrs. Rhys Davids. "He is shown combining like so many of his class all the world over, a proneness to affairs of sex with the virtues and affection of good 'family man', indulgence at the table with an equally natural wish to keep in good physical form, a sense of honour and honesty, shown in his disgust at legal cheating, with a greed for acquiring wealth and war indemnities, and a fussiness over lost property, a magnanimity towards a conquered foe with a callousness over sacrificial slaughter and the punishment of criminals. Characteristic also are both his superstitious nervousness over the sinister significance of dreams due, in reality, to disordered appetites, and also his shrewd politic care to be on good terms with all religious orders, whether he had testimonials to their genuineness or not."²

The family life of the king had its bearing on affairs of the state. He married a Magadhan princess which fact must have cemented his friendship with Bimbisāra, who got a Kosalan wife in return. Another queen of Pasenadi (Prasenajit) was the famous Vāsabhakkhattiyā, daughter of Mahānāman, the Śākyan, by a slave girl.³ The issues of this marriage were a son, Viḍūḍabha (Viduratha), who rose to be his father's *senāpati* (general)⁴ and

¹ *Mahāvagga*, SBE, XIII, pp. 220, 261. Among the marauders was the notorious Aṅgulimāla.

² *Sage and king in Kosala-Saṃyutta*, Bhandarkar Commemoration Volume, p. 134.

³ DPPN, II. 171; 857.

⁴ For the employment of prince as *Senāpati*, see Kauṭilya (Mysore edition), 1919, p. 34; cf. 346.

afterwards his successor,¹ and a daughter Vajirā or Vajiri Kumārī² who became the queen of Ajātaśatru, the successor of Bimbisāra on the throne of Magadha. The careers of the prince and the princess are bound up with memorable events, viz., the war of the Kosalan king with Ajātaśatru, the loss of his throne as a result of his son's revolt, and the terrible vengeance that the latter wreaked on the Sākyaas for sending the offspring of a slave woman to the Kosalan harem to become the mother of the prince.

When the Magadhan war brought disaster to the king's arms he married Mallikā, daughter of the chief of garland-makers, who sweetened his days till her death, and made herself famous by her benefactions. Among these was a garden, the Mallikārama, which was set apart for religious discussions.³ She leaned towards the Buddha and his order, though her husband, with great insight, extended his patronage to Brāhmaṇas as well.⁴ Mallikā and Sumanā, the king's sister,⁵ remind one of Kāruvākī and Rājyaśrī, famous for their charity and interest in Buddhist teaching in the days of Aśoka and Harsha respectively.

The internal organisation of the kingdom of Kosala presents some interesting features. There was a body of ministers at the centre, but they had little control over the

¹ Viḍūḍabha's name is generally omitted in Purāṇic manuscripts. The Purāṇas, however, mention a king named Suratha. Pargiter points out (*D. K. A.*, 12, n 63) that one manuscript of the *Vishṇu Purāṇa* gives the name *Viduratha* instead of Suratha. But that prince is represented as the great-grandson of Prasenañjit. Similarly, the Purāṇas represent Udāyin as the grandson of Ajātaśatru. These instances emphasize the need for a critical handling of the Purāṇic lists.

² *Majjhima*. II, p. 110.

³ DPPN. II. 455-7. A more famous place, Jetavana, is said to derive its name from a son of Prasenañjit.

⁴ *Dialogues of the Buddha*, I. pp. 108, 288. For Pasenadi's benefactions to the Buddha and his followers see *Gagga Jātaka*, no. 155. For preparations for a great sacrifice, see *Kindred saying*. I. 102.

⁵ DPPN. II, 168 ff, 172, 1245.

king's whims. Those specifically mentioned by tradition were Mṛigadhara,¹ Ugga, Siri-Vaḍḍha, Kāla and Junha. The generals included the Crown Prince and some Malla chiefs. Police duties on roads were performed by soldiers. Portions of the royal domain were granted to Brāhmaṇas like Pokkharasādī, with power over them as if they were kings. The weakness of the system soon became apparent, and led to the downfall of the king. Ministers, who were lavish in their charity, were preferred to those who approved of a more economical policy, and one of the favourites is said to have actually been allowed to rule over the kingdom for seven days. The large powers granted to *Brāhmaṇa* donees must have promoted centrifugal tendencies, while the infidelity of some of the generals including the Crown Prince, and the cruel treatment by the latter, when he became king, of vassal clansmen contributed to the eventual downfall of the monarchy.

In the **Vatsa** kingdom which, probably at this time, extended along the southern frontier of Kosala, king Satānika Parantapa was succeeded by his son Udayana who rivals Śrī Rāmachandra, Nala and the Pāṇḍavas in being the hero of many romantic legends.² The commentary on the *Dhammapada* gives the story of the way in which Vāsuladattā or Vāsavadattā, the daughter of Pradyota, king of Avanti, became his queen. It also mentions two other consorts of the

¹ Hecule, *Urāsaga-dasdo*. II. Appendix. p. 36. DPPN. I, 332, 372, 360; II, 1146.

² For a detailed account of the legends, see "Essay on Guṇāḍhya and the Brihathkathā," by Prof. Félix Lacote, translated by Rev. A. M. Tabard. See also *Annals of the Bhandarkar Institute*, 1920-21; Gune, "Pradyota, Udayana, and Sreṇika—A Jaina Legend"; J. Sen, "The Riddle of the Pradyota Dynasty" (I. H. Q., 1920, pp. 578-700); Nariman, Jackson and Ogden, *Priyadarśikā*, lxii ff.; Aiyangar Com. Vol., 332 ff.; Mahabharata, DPPN. I, 379-80; II, 318, 869.

Vatsa king, viz., Māgandiyā,¹ daughter of a Kuru Brāhmaṇa, and Sāmāvatī, the adopted child of the treasurer Ghosaka. The *Milindapañho* refers to a peasant woman named Gopāla-mātā who also became his wife.² The *Swapna-Vāsavadatta* attributed to Bhāsa, and some other works, mention another queen named Padmāvatī who is represented as sister to king Darśaka of Magadha. The *Priyadarśikā* speaks of Udayana's marriage with Āraṇyakā, the daughter of Dṛiḍhavarman, king of Aṅga. The *Ratnāvalī* tells the story of the love of the king of Vatsa and of Sāgarikā, an attendant of his chief queen Vāsavadattā. Stories about Udayana were widely current in Avanti in the time of Kālidāsa as we learn from the *Meghadūta*: "*prāpy-Āvantim Udayana-kothā-kovida grāmaṣṭiddhān*." The *Jātakas* throw some side-light on the character of this king. In the preface to the *Mātanga Jātaka* it is related that in a fit of drunken rage he had Piṇḍola Bhāradvāja tortured by having a nest of ants tied to him. The *Kathā-sarit-sāgara* of Somadeva, a writer of the eleventh century A.D., contains a long account of Udayana's *Digvijaya*.³ The *Priyadarśikā* of Śrī Harsha⁴ speaks of the king's victory over the lord of Kalinga, and the restoration of his father-in-law Dṛiḍhavarman to the throne of Aṅga. It is difficult to disentangle the kernel of historical truth from the husk of popular fables. It seems that Udayana was a great king who really made some conquests, and contracted matrimonial alliances with the royal houses of Avanti, Aṅga and Magadha. But his career was meteoric. He left no worthy successor. Bodhi, his son by the chief queen, preferred a quiet life amidst the sylvan surroundings of

¹ Cf. Anupamā, *Dīpāvadāna*, 36.

² IV. 9. 26; DPPN, I. 379-80.

³ Towney's Translation, Vol. I, pp. 148 ff.

⁴ Act IV.

Suinsumaragiri to the troubles of imperial adventure. The kingdom, harassed by various wars, was at last overcome by its ambitious neighbour on the south-west, viz., Avanti, and was governed by a prince of the royal line of Ujjain.¹

The throne of **Avanti** was, in the days of Udayana, occupied by Chaṇḍa Pradyota Mahāsena whose daughter, Vasavadattā, became the chief queen of the lord of the Vatsas. Regarding the character of Pradyota the *Mahāvagga* says that he was cruel.² The *Purāṇas* observe that he was "*nayavarjita*", i.e., destitute of good policy and add that "he will indeed have the neighbouring kings subject to him—*sa vai pranata-sāmantah*". He had at one time made the Vatsa king a captive and had a close relation on the throne of Mathurā. The terror that he struck among his neighbours is apparent from a statement of the *Majjhima Nikāya*³ that Ajātaśatru, son of Bimbisāra, fortified Rājagriha because he was afraid of an invasion of his territories by Pradyota. He also waged war on Pushkarasarin, the king of Taxila.⁴

¹ Cf. story of Maṇiprabha from *Āraṇyaka-Kathānakas*. Jacobi *pariśiṣṭa-paracan*, 2nd ed. xi, Tawney, *Kathā-pariśiṣṭa-sāgara*, II. p. 481. According to the *Āraṇyaka-Kathānakas* IV, reproduced by Dharmadharma in his *Kohāvali*, Maṇiprabha, great-grandson of Pradyota, ruled at Kausāmbī, while his brother Avantiseṇa exercised sway at Ujjain (Avanti).

² S.B.E., XVII, p. 187.

³ III. 7.

⁴ Pradyota was unsuccessful in this war and was only saved from disaster by the outbreak of hostilities between Pushkarasarin and the Pāṇḍavas (*Essay on Guṇādhya*, 176).

SECTION IV. MAGADHA CRESCENT—BIMBISĀRA

According to Jaina legend Pradyota went forth to attack Rājagṛīha even during the lifetime of Bimbisāra.¹ The last-mentioned prince, the real founder of Magadhan imperial power in the historic period, was the son of a petty chief of South Bihār, whose very name seems to have been forgotten. Tradition tried to fill the lacuna possibly by an imaginary nomenclature.² An early authority describes the family to which the prince belonged as the *Haryāṅka-kula*. As we have already seen,³ there is no reason to discard this evidence in favour of the later tradition of the *Purāṇas*. Young Bimbisāra, who also bore the name or epithet of Seṇiya (Śreṇika), is said to have been anointed king by his own father when he was only fifteen years old.⁴ The momentous event cannot fail to recall a solemn ceremony that took place some nine hundred years later when another king of Magadha clasped his favourite son in arms in the presence of the princes royal and ministers, in council assembled, and exclaimed, "Protect the entire land".

The new ruler had a clear perception of the political situation of his time. The military power of the Vṛjji Confederation was growing in the North. Aggressive monarchies under ambitious rulers were following a policy of expansion from their bases in Śrāvastī, and Ujjain. The cruel and unscrupulous ruler of the

¹ He was foiled by the cunning of Prince Abhaya (*Annals of the Bhandarkar Institute*, 1920-21, 3; cf. *DPPN*, I, 123).

² Among the names given by various late writers we find the following: Bhāṭiyo (Bhaṭṭiya, Bodhisa), Mahāpadma, Hemajit, Kshemajit, Kshetrojā or Kshetrāja.

³ *Supra*, p. 115ff.

⁴ *Mahāvamśa* (Geiger's trans.), p. 12.

last-mentioned city engaged in hostilities with Pushkara-sārin of Taxila. The king of Taxila harassed by numerous enemies including the mysterious Pāṇḍavas who are known to have been in possession of Śākala (in the Punjab) in the days of Ptolemy, turned to the king of Magadha for help. Though ready to oblige his Gandhārian friend by receiving an embassy, Bimbisāra, who had to liquidate the long-standing feud with his eastern neighbour across the Champā, was in no mood to alienate Pradyota or any of the other military chiefs of the age.

When the king of Avanti was suffering from jaundice he sent the physician Jīvaka. He also pursued a policy of dynastic marriages like the Hapsburgs and Bourbons of Europe and contracted alliances with the ruling families of Madra,¹ Kosala² and Vaiśālī. These measures were of great importance. They not only appeased the most formidable militarists of the age, but eventually paved the way for the expansion of the kingdom both westward and northward. Bimbisāra's Kosalan wife brought a Kāśī village producing a revenue of a hundred thousand for bath and perfume money.³ The Vaiśālīan connection produced momentous consequences in the next reign.

¹ Khemā, the princess of Śākala (Madra) is said to have been the chief consort of Bimbisāra. Was she connected with the Pāṇḍavas who are found in Śākala as late as the age of Ptolemy?

² According to the *Dhammapada Commentary* (Harvard, 29, 60; 30, 225) Bimbisāra and Pasenadi were connected by marriage, each having married a sister of the other.

³ *Jātaka*, Nos. 239, 269, 402. According to the *Thusa Jātaka* (333) and the *Mūshika Jātaka* (373) the Kosalan princess was the mother of Ajātasatru. The preface to the *Jātakas* says, "At the time of his (Ajātasatru's) conception there arose in his mother, the daughter of the king of Kosala, a chronic longing to drink blood from the right knee of king Bimbisāra". In the *Saṃyukta Nikāya* (*Book of Kindred Sayings*, 110) Pasenadi of Kosala calls Ajātasatru his nephew. In Vol. I, page 38a of the *Book of the Kindred Sayings*, however, Maddā (Madra) appears as the name of Ajātasatru's mother. A Tibetan writer, calls her Vāsavi (DPPN, I, 34.). The Jaina writers represent Chellapā, daughter of Chetaka of Vaiśālī as the mother of Kūpika-Ajātasatru. The *Nikāyas* call Ajātasatru Vedahiputtia

The shrewd policy of Bimbisāra enabled him to devote his undivided attention to the struggle with Aṅga which he annexed after defeating Brahmadatta.¹ The annexation of Aṅga by Bimbisāra is proved by the evidence of the *Mahāvagga*² and that of the *Soṇadaṇḍa Sutta* of the *Dīgha Nikāya* in which it is stated that the revenues of the town of Champā have been bestowed by King Bimbisāra on the Brāhmaṇa Soṇadaṇḍa. We learn from Jaina sources that Aṅga was governed as a separate province under the Magadhan Crown Prince with Champā as its capital.³ The king himself resided in Rājagriha-Girivraja.⁴ Thus by war and policy Bimbisāra added Aṅga and a part of Kāśī to the Magadhan dominions, and launched Magadha to that career of conquest and aggrandisement which only ended when Aśoka sheathed his sword after the conquest of Kāliṅga. We learn from the *Mahāvagga* that Bimbisāra's dominions embraced 80,000⁵ townships.

The victories of Bimbisāra's reign were probably due in large measure to the vigour and efficiency of his administration. He exercised a rigid control over his

(Vaidēhiputra), i.e., son of the Videhan princess. This is taken to confirm the Jaina tradition because Vaidāli was in Videha. Buddhaghosha, however, resolves "Vedehi" into *Veda-ihā*, *Vedena ihā* or intellectual effort (BKS, Vol. I, 109a) and seems to suggest that "Vedehiputta" simply means "Son of the accomplished princess". We should moreover remember that the Kosalan monarch Para Aṅgira, had the epithet *Vaidēha* and the name Kausalyā was applied to several Kāśī princesses in the epic. The appellation Vaidēhiputra, therefore, does not necessarily disprove the Kosalan parentage of the mother of Aśoka's father. According to one authority "Chellā" (Chellānā) was styled "Vaidēhi" "as she was brought from Videha" (AIU, II, 29).

¹ JASB, 1914, p. 321.

² SBE, XVII, p. 1.

³ Hemchandra, the author of the *Parīkṣitaparvan* VII, 22; cf. also the *Bhagavati Sūtra* and the *Nirayāsa Sūtra* (ed. Warren, p. 3). King (rājā) Kuṇḍiya, son of King Seniya by Chellānādevī, ruled in Champā-nagari in Bhārata-varāha, which is in Jambudvīpa.

⁴ *Sutta Nipāta*, SBE, X, ii, 67.

⁵ Apparently a stock number.

High Officers,¹ dismissing those who advised him badly and rewarding those whose advice he approved of. The result of the 'purge' was the emergence of the type of official represented by Vassakāra and Sunītba. The High Officers (*Rājabhāṭa*) were divided into several classes, viz., (1) *Sabbatthaka* (the officer in charge of general affairs), (2) *Senā-nāyaka Mahāmattas* (generals), and (3) *Vohārika Mahāmattas* (judges).² The *Vinaya* texts afford us a glimpse of the activities of these *Mahāmātras*, and the rough and ready justice meted out to criminals. Thus we have reference not only to imprisonment in jails (*kārā*), but also to punishment by scourging (*kaṣā*), branding, beheading, tearing out the tongue, breaking ribs, etc. There seems to have been a fourth class of *mahāmātras* who were responsible like the village syndics and headmen (*grāma-bhojaka* or *grāma-kuṭa*) for the levy of the tithe on produce.³

In provincial administration a considerable degree of autonomy was allowed. We hear not only of a sub-king at Champā, but of *maṇḍalika rājās*⁴ corresponding perhaps to the earls and counts of mediaeval European polity. But Bimbisāra, like William the Conqueror, sought to check the centrifugal tendencies of the system by a great gemote of village headmen (*grāmikas*) who are said to have assembled from the 80,000 townships of the realm.

Measures were taken for the improvement of communications and the foundation of a new royal residence. Yuan Chwang (Hiuen Tsang) refers to Bimbisāra's road and causeway, and says that when Kuśāgrapura

¹ *Chullavagga* of the *Vinayapitaka*, VII. 3. 5. See also *Vinaya*, I. 73; 74f. 207, 240.

² Another judicial officer mentioned in Pali texts (*Kindred Sayings*, II. 172) is the *Vinichchay-āmachcha*.

³ *Camb. Hist.*, I. 199.

⁴ *DPPN*, II. 896.

(old Rājagriha) was afflicted by fires, the king went to the cemetery and built a new city. Fa Hien, however, gives the credit for the foundation of New Rājagriha to Ajātaśatru. The patronage of Jivaka shows that medical arrangements were not neglected.

In one respect Bimbisāra was unfortunate. Like Prasenajit he was possibly the victim of the malevolence of the Crown Prince whom he had appointed to the vice-royalty of Champā,¹ and had perhaps even admitted to royalty, following the precedent of his own father.² The ungrateful son, who is variously called Ajātaśatru, Kūṇika and Aśokachanda³ is said to have put his father to death. The crime seriously affected the relations of Magadha with Kosala. Dr. Smith regards the story of the murder as 'the product of *odium theologicum*,' and shows excessive scepticism in regard to the evidence of the Pāli canon and chronicles. But the general credibility of these works has been maintained by scholars like Rhys Davids and Geiger whose conclusions seem to be confirmed directly or indirectly by the testimony of independent classical and Jaina writers.⁴

¹ *Bhagavati Sūtra*, *Nirayāvali Sūtra*, *Parisiṣṭaparacan* IV, 1-9; VI 23, and the *Kathākośa*, p. 178.

² *Chullavagga*, VII. 3. 5. Bimbisāra seems to have sought the assistance of other sons, too, in the work of government. One of these, Abbaya (son of Padmāvati of Ujjain or of Nandā helped his father to foil the machinations of Pradyota. Other children, recorded by tradition were Vimala Koṇḍāṇḍa by Ambapālī, Halla and Vekalla by Chellānā, Kāla, Silavat, Jayasena and a girl Chundi by other wives.

³ *Kathākośa*. The *Aupapātiya sūtra* styles him *Devānūpiya* (IA, 1881 108) a title possibly identical with *Devānūpiya* of inscriptions of the third century B. C.

⁴ Cf. the Jaina attempt to whitewash Kūṇika from the stain of intentional parricide (Jacobi referring to the *Nirayāvali Sūtra* in his *Kalpa Sūtra* of Bhadravāhu, 1879, p. 5).

SECTION V. MAGADHA MILITANT—

✓ KŪNIKA-AJĀTAŚATRU.

Whatever may have been the mode by which he acquired the throne, Kūnika-Ajātsātru proved to be an energetic ruler. The defences of the realm were strengthened by fortifications at Rājagriha and the foundation of a new stronghold at Pāṭaligrama near the junction of the Śon and the Ganges. Like Frederick II of Prussia he carried out the policy of a father with whom his relations were by no means cordial. His reign was the highwater mark of the power of the Haryāṅka dynasty. He not only humbled Kosala and permanently annexed Kāśi, or a part of it, but also absorbed the state of Vaiśālī. The traditional account of his **duel with Kosala** is given in Buddhist texts.¹ It is said that when Ajātsātru murdered Bimbisāra, his father, the queen Kosalā Devī died of love for him. Even after her death the Magadhan King continued to enjoy the revenues of the Kāśi village which had been given to the lady for bath money. But Prasenajit, the sovereign of Kosala, determined that no parricide should have a village which was his by right of inheritance. War followed, sometimes the Kosalan monarch got the best of it, and sometimes the rival king. On one occasion Prasenajit fled away in defeat to his capital Śrāvastī; on another occasion he took Ajātsātru prisoner but spared his life as he was his nephew. He confiscated the army of the captive prince but sought to appease him by the offer of the hands of his daughter Vajirā. The princess was dismissed with the

¹ *The Book of the Kindred Sayings*, I. pp. 109.-110. *The Saṃyutta Nikāya* and the *Haritamāta*, *Vaḍḍhaki-Sūvara*, *Kummā Sapiṇḍa Tachchha Sūvara* and the *Bhaddasāla Jātakas*.

Kāśī village in question, for her bath money. Her father could not enjoy the fruits of peace for more than three years.¹ During his absence in a country town, Dīgha Chārāyaṇa, the Commander-in-Chief, raised prince Viḍūḍabha to the throne.² The ex-king set out for Rājagṛīha, resolved to take Ajātaśatru with him and capture Viḍūḍabha. But he died from exposure outside the gates of the Magadhan metropolis.

The traditional account of the **war with Vaiśālī** is preserved in part by Jaina writers. King Seniya Bimbisāra is said to have given his famous elephant *Seyanaga* (*Sechanaka*, the sprinkler), together with a large necklace of eighteen strings of jewels, to his younger sons Halla and Vehalla born from his wife Chellana, the daughter of Rājā Cheṭaka of Vaiśālī. His eldest son Kūṇiya (Ajātaśatru), after usurping his father's throne, on the instigation of his wife Paūmāvai (Padmāvati),³ demanded from his younger brothers the return of both gifts. On the latter refusing to give them up and flying with them to their grandfather Cheṭaka in Vaiśālī, Kūṇiya, having failed peacefully to obtain the extradition of the fugitives, commenced war with Cheṭaka.⁴ According to Buddhaghosha's commentary the *Sumaṅgala-vilāsini*,⁵ the cause of the war was a breach of trust on the part of the Lichchhavis in connection with a mine of precious gems or some fragrant

¹ DPPN, II, 172.

² *Bhaddasāla Jātaka*.

³ The appellation Padmāvati is of so frequent occurrence in connection with Magadhan royalty that it seems to be an epithet rather than a personal name. The mother of prince Abhaya, a queen of Ajātaśatru, and a sister of Darśaka, all have this name according to tradition. Cf. the name Padmīni applied to the most commendable type of women in treatises on Erotics. It is also not improbable that the name belongs to the domain of mythology,

⁴ *Ucāsaga-dasāo*, II. Appendix, p. 7; cf. Tawney, *Kathākośa*, pp. 176 ff.

⁵ Burmese-Edition, Part II, p. 99. See now B. C. Law, *Buddhistic Studies*, p. 199; DPPN, II, 781.

material near a port on the Ganges over which a condominium was exercised by Ajātaśatru and his northern neighbours.

The preliminaries to the struggle between Magadha and Vaiśālī are described in several Pāli texts.¹ In the *Mahāvagga* it is related that Sunīd(t)ha and Vassakāra, two ministers of Magadha, were building a fort at Pāṭaligrāma in order to repel the Vajjis (Vrijis). The *Mahāparinibbāna Suttanta* says: "The Blessed One was once dwelling in Rājagaha on the hill called the Vulture's Peak. Now at that time Ajātasattu Vedehiputta, the king of Magadha, was desirous of attacking the Vajjians; and he said to himself, 'I will root out these Vajjians, mighty and powerful though they be, I will destroy these Vajjians, I will bring these Vajjians to utter ruin'".

"So he spake to the Brāhmaṇa Vassakāra, the prime minister of Magadha, and said, 'Come now, Brāhmaṇa, do you go to the Blessed One, and...tell him that Ajātasattu... has resolved, 'I will root out these Vajjians'. Vassakāra hearkened to the words of the king...' (and delivered to the Buddha the message even as the king had commanded).

In the *Nirayāvalī Sūtra* (*Nirayāvaliyā-Sutta*) it is related that when Kūpika (Ajātaśatru) prepared to attack Chetaka of Vaiśālī the latter called together the eighteen *Gaṇarājas*² of Kāśī and Kosala, together with the Lichchavis and Mallakis, and asked them whether they would satisfy Kūpika's demands, or go to war with him. The good relations subsisting between Kosala and Vaiśālī are referred to in the *Majjhima Nikāya*.³ There is thus no reason to doubt the authenticity of the Jaina statement regarding the alliance between Kāśī-Kosala on the one

¹ SBE, XI, pp. 1-5; XVII. 101, *Gradual Sayings* IV. 14. etc.

² Chiefs of republican clans. Cf. 125 ante.

³ Vol. II, p. 101.

band and Vaiśālī on the other. It seems that all the enemies of Ajātaśatru including the rulers of Kāśī-Kosala and Vaiśālī offered a combined resistance. The Kosalan war and the Vajjian war were probably not isolated events but parts of a common movement directed against the establishment of the hegemony of Magadha. The flames fused together into one big conflagration.¹ We are reminded of the tussle of the Samnites, Etruscans and Gauls with the rising power of Rome.

In the war with Vaiśālī Kūpiya-Ajātaśatru is said to have made use of the *Mahāsilākaṇṭaka* and *ra(t)hamusala*. The first seems to have been some engine of war of the nature of catapult which threw big stones. The second was a chariot to which a mace was attached and which, running about, effected a great execution of men.² The *ra(t)hamusala* may be compared to the tanks used in the great world wars.

The war is said to have synchronised with the death of Gosāla Maṅkhaliputta, the great teacher of the Ājīvika sect. Sixteen years later at the time of Mahāvīra's death the anti-Magadhan confederacy is said to have been still in existence. We learn from the *Kalpa Sūtra* that on the death of Mahāvīra the confederate kings mentioned in the *Nirayāvalī Sūtra* instituted a festival to be held in memory of that event.³ The struggle between the Magadhan king and the powers arrayed against him thus seems to have been protracted for more than sixteen years. The

¹ We are told that even Pradyota of Avanti made preparations to avenge the death of his friend Bimbisāra (DPPN, I, 34).

² *Ucāsaga-dasāo*, Vol. II, Appendix, p. 60 : *Kathākośa*, p. 179.

³ S.B.E., xxii, 266 (para. 128). As pointed out by Jacobi (*The Kalpasūtra* of Bhadravāhu, 6 ff.) the traditional date of Mahāvīra's Nirvāṇa is 470 years before Vikrama (58 B. C.) according to the *Svetambaras*, and 605 according to the *Digambaras*. It is suggested that Vikrama of the Digambaras is intended for Śalivahana (78 A. D.). A different tradition is, however, recorded by Hemachandra who says that 155 years after the liberation of Mahāvīra Chandragupta became king :—

Aṭṭhakathā gives an account of the Machiavellian tactics¹ adopted by Magadha statesmen headed by Vassakāra to sow the seeds of dissension among the Vaiśālīans and thus bring about their downfall.²

The absorption of Vaiśālī and a part at least of Kāśī as a result of the Kosalan and Vajjian wars probably brought the aspiring ruler of Magadha face to face with the equally ambitious sovereign of Avanti. We have already referred to a statement of the *Majjhima Nikāya* that on one occasion

*evam cha śrī Mahāvīra mukter varṣaśate gate
pañcchapañchāśadadhike Chandragupto'bhavan nripah
Sthavirāvalcharita, Parīśiṣṭaparva, VIII. 339.*

As Chandragupta's accession apparently took place between 390 and 312 B.C., the tradition recorded in Hemchandra's *Parīśiṣṭaparva* would place the date of Mahāvīra's death between 481 and 467 B.C. But early Buddhist texts (*Dialogues*, III, pp. 111, 203 *Majjhima*, II, 243) make the famous Jaina teacher predecease the Buddha, and the latest date assigned by reliable tradition to the *Parinirvāṇa* of the Śākya sage is 486 B.C. (Cantonese tradition, Smith, EHI. 4th ed., 49). According to Ceylonese writers, Śākyamuni entered into *nirvāṇa* in the eighth year of Ajātaśatru (*Ajātasattuno vasse aṭṭhame muni nibbuta, Mahāvamsa*, Ch. II). This would place the accession of the son of Bimbisāra in 493 B.C., if the Cantonese date for the *nirvāṇa* of the Buddha is accepted. Jaina writers put the interval between Kūṣika's accession and the death of their master at 16 and 'x' years. According to Buddhist chroniclers the interval would be less than 8 years as Mahāvīra predeceased the Buddha. The divergent data of the Jaina and Buddhist texts can only be reconciled if we assume that the former take as their starting point the date of the accession of Kūṣika as the *rājā* of Champā, while the Buddhists begin their calculation from a later date when Ajātaśatru mounted the throne of Rājagṛha. According to Buddhist tradition Vassakāra's visit to the Buddha in connection with the Vrijian incident took place a year before the *parinirvāṇa*. The destruction of the Vrijī power took place some three years later on (DPPN, I. 33-34) i.e. c. 484 B.C. Too much reliance cannot, however, be placed on the traditional chronology.

¹ Diplomacy (*upaśāpana*) and disunion (*mīthubheda*), DPPN, II. 846; JRAS, 1931. Cf. *Gradual Sayings*, IV. 12. "The Vajjians cannot be overcome in battle, but only by cunning, by breaking up their alliance."

² Cf. *Modern Review*, July, 1919, pp. 55-56. According to the *Ārya Mañjuśrī-Mūla-Kalpa* (Vol. I, ed. Ganapati Śāstri pp. 603 ff) the dominions of Ajātaśatru embraced, besides Magadha, Aśga, Vārāṇasī (Benares), and Vaiśālī in the north. In the opinion of Dr. Jayaswal the Parkham statue is a contemporary portrait of king Ajātaśatru. But Kūṣika of Parkham (Lüders List No. 150) is obviously not a king.

Ajātaśatru was fortifying his capital because he was afraid of an invasion of his dominions by Pradyota. We do not know whether the attack was ever made. Ajātaśatru does not appear to have succeeded in humbling Avanti. The conquest of that kingdom was reserved for his successors.

It was during the reign of Ajātaśatru that both Mahāvīra and Gautama, the great teachers of Jainism and Buddhism respectively, are said to have entered *nirvāṇa*. Shortly after the death of Gautama a Council is said to have been held by the monks of his Order for the recitation and collection of the Doctrine.

SECTION VI. AJĀTAŚATRU'S SUCCESSORS—THE TRANSFER OF CAPITAL AND THE FALL OF AVANTI

Ajātaśatru was succeeded according to the *Purāṇas* by Darśaka. Geiger considers the insertion of Darśaka after Ajātaśatru to be an error, because the Pāli Canon indubitably asserts that Udāyi-bhadda was the son of Ajātaśatru and probably also his successor. Jaina tradition recorded in the *Kathakośa*¹ and the *Parīśiṣṭaparvan*² also represents Udaya or Udāyin as the son of Kūṇika by his wife Padmāvati,³ and his immediate successor.

Though the existence of Darśaka, as a ruler of Magadha and a contemporary of Udayana, is rendered probable by references in the *Svapna-Vāsavadatta* attributed to Bhāsa, yet in the face of Buddhist and Jaina evidence it cannot be confidently asserted that he was the immediate successor of Ajātaśatru on the imperial throne of Magadha. He may have been one of the *maṇḍalika rājās* like the father of Viśākha Pāñchālputra. His inclusion among Magadhan suzerains is possibly paralleled by that of Śuddhodana in the main list of the Ikshvākuids. Certain writers identify him with Nāga-Dāsaka who is represented by the Ceylonese Chornicles as the last king of Bimbisāra's line.⁴ The *Divyāvadāna*,⁵ however,

¹ P. 177.

² P. 42.

³ Buddhist writers represent Vajirā, daughter of Prasenajit, as the mother of Udāyi.

⁴ E. g., Dr. D. R. Bhandarkar. In this connection mention was made, in earlier editions, of a passage in the *Si-yu-ki*, (Beal's Trans. II, p. 102) : "To the south-west of the old *Saṅghārāma* about 100 li is the *Saṅghārāma* of Ti-lo-shi-kia...It was built by the last descendant of Bimbisāra rāja." The name of the second *Saṅghārāma* was sought to be connected with that of Darśaka who was here represented as the last descendant of Bimbisāra. But I now think that the connection of the monastery with the name of Darśaka is extremely doubtful. See Watters II, p. 106f.

⁵ P. 369.

omits this name altogether from the list of the Bimbisārids. There was thus no unanimity even among Buddhists about the lineage and position of the king.

Udyāin : Before his accession to the throne Udāyin or Udāyi-bhadda, the son of Ajātaśatru, seems to have acted as his father's Viceroy at Champā.¹ The *Parīśiṣṭa-parvan* informs us that he founded a new capital on the banks of the Ganges which came to be known as Pāṭaliputra.² This part of the Jaina tradition is confirmed by the testimony of the *Gārgī Saṃhitā*³ and the *Vāyu Purāṇa* according to which Udāyin built the city of Kusumapura (Pāṭaliputra) in the fourth year of his reign. The choice of the place was probably due to its position in the centre of the realm which now included North Bihār. Moreover, its situation at the confluence of two large rivers, the Ganges and the Son and close to other streams, was important from the commercial as well as the strategic point of view. In this connection it is interesting to note that the *Kauṭīliya Arthaśāstra* recommends a site at the confluence of rivers for the capital of a kingdom.

The *Parīśiṣṭa-parvan*⁴ refers to the king of Avanti as the enemy of Udāyin. This does not seem to be improbable in view of the fact that his father had to fortify his capital in expectation of an attack about to be made by Pradyota, ruler of that country. The fall of Aṅga and Vaiśālī and the discomfiture of Kosala had left Avanti the only important rival of Magadha. This last kingdom had absorbed all the monarchies and republics of Eastern India. On the other hand, if the *Kathā-sarit-sāgara* and the *Āvaśyaka kathānakas*⁵ are to be believed, the kingdom

¹ Jacobi, *Parīśiṣṭa-parvan*, p. 42.

² VI. 34; 175-180.

³ Kern, *Bṛīhat Saṃhitā*, 36.

⁴ Pp. 45-46, Text VI, 191. *Abhūdusahanonityam Avantiśo' py-Udāyinaḥ.*
See *Supra* sec. III, p. 204.

of Kauśāmbī was at this time annexed to the realm of Pālaka of Avanti, the son of Pradyota and was governed by a prince belonging to his family. The two kingdoms, Magadha and Avanti, were brought face to face with each other. The war of nerves between the two for ascendancy probably began, as we have seen, in the reign of Ajātaśatru. It must have continued during the reign of Udāyin. The issue was finally decided in the time of Siśunāga, or of Nanda as Jaina tradition seems to suggest.²

Udāyin's successors in the *Purāṇas* are Nandivardhana and Mahānandin. According to the Jainas he left no heir.³ The Ceylonese chroniclers place after Udāyi the kings named Anuruddha, Muṇḍa and Nāga Dāsaka. This tradition is partially confirmed by the

¹ For a traditional account of the conflict between Udāyin and the king of Avanti, see IHQ, 1929, 399.

In the opinion of Dr. Jayaswal one of the famous "Patna Statues" which at the time of the controversy, stood in the Bārhat Gallery of the Indian Museum (*Ind. Ant.*, 1919, pp. 29ff.), is a portrait of Udāyin. According to him the statue bears the following words:

Bhage ACHO chhonidhiṣe.

He identifies ACHO with king Aja mentioned in the *Bhāgavata* list of Siśunāga kings, and with Udāyin of the *Matsya*, *Vāyu* and *Brahmāṇḍa* lists. Dr. Jayaswal's reading and interpretation of the inscription have not, however, been accepted by several scholars including Dr. Barnett, Mr. Chanda and Dr. R. C. Majumdar. Dr. Smith, however, while unwilling to dogmatize, was of opinion that the statue was pre-Maurya. In the third edition of his *Asoka* he considers Dr. Jayaswal's theory as probable. The characters of the short inscription on the statue are so difficult to read that it is well-nigh impossible to come to a final decision. For the present the problem must be regarded as not yet definitely solved. Cunningham described the statue as that of a *Yaksha*. According to him the figure bore the words "Yakhe Achusanigika. Mr. Chanda's reading is: *Bha(?) ga Achachha nibika* (the owner of inexhaustible capital, i.e., Vaiśravaṇa). See *Indian Antiquary*, March, 1919. Dr. Majumdar reads: *Gate (Yakhe?) Lechchhai (v) 40. 4* (*Ind. Ant.*, 1919).

² *Ind. Ant.*, II, 362.

³ *Parīkṣitaparvan*, VI, 236.

Āṅguttara Nikāya which alludes to Muṇḍa,¹ King of Pāṭaliputra. The *Divyāvadāna*, too, mentions Muṇḍa but omits the names of Anuruddha and Nāga-Dāsaka. The *Āṅguttara Nikāya* by mentioning Pāṭaliputra as the capital of Muṇḍa indirectly confirms the tradition regarding the transfer of the Magadhan metropolis from Rājagriha to Kusumapura or Pāṭaliputra before his reign.

The great Ceylonese chronicle avers that all the kings from Ajātaśatru to Nāga-Dāsaka were parricides.² The citizens drove out the family in anger and raised an *amātya* (official) to the throne.

Susunāga or Śisunāga, the new king³ seems to have been acting as the Magadhan Viceroy at Benares. The employment of *amātyas* as provincial governors or district officers need not cause surprise. The custom continued as late as the time of Gautamīputra Śātakarṇi and Itudradāman I. The *Purāṇas* tell us that "placing his son at Benares he will repair to (the stronghold of) Girivraja". He had a second royal residence at Vaiśālī which ultimately became his capital.⁴ "That monarch (Śisunāga), not unmindful of his mother's origin,⁵ re-established the city of Vesālī (Vaiśālī) and fixed in it the royal residence. From that

¹ *Āṅg.* III, 57. "The venerable Nārada dwell near Pāṭaliputta in the Cook's Park. Now at that time Bhaddā, the dear and beloved queen of king Muṇḍa died." The king's grief was intense. The queen's body was placed in an oil vessel made of iron. A treasurer, Piyaka, is also mentioned. (*Gradual sayings*, III, 46).

² The violent death of Kūpika (Ajātaśatru) is known to Jain tradition (Jacobi, *Parīśiṣṭoparaṇa*, 2nd ed. p. xiii).

³ The question of the relative merits of Purāṇic and Ceylonese accounts of this king and his place in early Magadhan lists of kings have been discussed in Part I, pp. *supra*. 115 ff.

⁴ SBE, XI, p. xvi. If the *Drātrīmat puttālikā* is to be believed Vesālī (Vaiśālī) continued to be a secondary capital till the time of the Nandas.

⁵ Śisunāga, according to the *Mahāvamsa* (Turnour's *Mahāvamsa* xxviii), was the son of a Licchavi rāja of Vaiśālī. He was conceived by a *nagara-tobhini* and brought up by an officer of State.

time Rājagaha (Rājagṛiha-Girivraja) lost her rank of royal city which she never afterwards recovered".

The most important achievement of Śiśunāga seems to have been the destruction of the 'glory' of the **Pradyota dynasty of Avanti**. Pradyota the first king of the line, had been succeeded, according to tradition, by his sons Gopāla and Pālaka after whom came Viśākha and Āryaka. The name of Gopāla is omitted in the *Purāṇas* with the possible exception of the *k* Vishṇu manuscript, where it finds mention instead of Pālaka.¹ The accession of the latter synchronised, according to Jaina accounts, with the passing away of Mahāvīra. He is reputed to have been a tyrant. Viśākha-bhūpa (*i.e.*, king Viśākha-called Viśākha-yūpa in most *Purāṇic* texts) may have been a son of Pālaka.² The absence of any reference to this prince in non-*Purāṇic* accounts that have hitherto been available, may suggest that he ruled in some outlying district (Mābishmatī), or was set aside in favour of Āryaka who occupied the throne, as a result of a popular outbreak, almost immediately after the fall of Pālaka. The *Purāṇas* place after Āryaka or Ajaka a king named Nandivardhana, or Vartivardhana, and add that Śiśunāga will destroy the prestige of the Pradyotas and be king. Dr. Jayaswal identifies Ajaka and Nandivardhana of the Avanti list with Aja-Udāyin and Nandivardhana of the *Purāṇic* list of Śaiśunāga kings. Dr. D. R. Bhandarkar, on the other hand, says that Āryaka or Ajaka was the

¹ Essay on Guṇādhyaya, 116; Gopāla and Pālaka find mention in the *Bṛihat Kathā*, *Scopra-Vāsavadattā*, *Pratijñā-Yaugandharayana*, *Mṛichekhakaṭika* etc. A prince named Kumārasena is known to the *Harsha-charita*. According to the Nepalese *Bṛihat Kathā* (cf. *Kathā-sarit-sāgara* XIX, 67) Gopāla succeeds Mahāsena (Pradyota) but abdicates in favour of his brother Pālaka. Pālaka renounces the crown in favour of Avantivardhana, son of Gopāla. In the *Jvālyaka Kathānakas* (*Paridīpita*) parvan, 2nd ed. xii) Avantisena is mentioned as a grandson of Pālaka.

² DKA., 19 n29. The *Kalbi Purāṇa* (I. 3. 32f.) mentions a king named Viśākha-yūpa who ruled at Māhīmatī near the southern frontier of ancient Avanti.

son of Gopāla, the elder brother of Pālaka.¹ 'Nandivardhana' and 'Vartivardhana' are apparently corruptions of Avantivardhana, the name of a son of Pālaka according to the *Kathā-sarit-sāgara*,² of Gopāla according to the Nepalese *Bṛihat-kathā*,³ or possibly identical with Avantisena, a grandson of Pālaka according to the *Āvaśyaka Kathānakas*.⁴ The Pradyota dynasty must have been humbled by Śiśunāga in the time of king Avantivardhana. The Magadban victory was doubtless facilitated by the revolution that placed Āryaka, a ruler about whose origin there is hardly any unanimity, on the throne of Ujjain.

Śiśunāga⁵ was succeeded according to the *Purāṇas* by his son **Kākavarṇa**, and according to the Ceylonese chronicles by his son **Kālāśoka**. Jacobi, Geiger and Bhandarkar agree that Kālāśoka, "the black Aśoka" and Kākavarṇa, "the crow-coloured" are one and the same

¹ *Carm. Lee*, 1918, 64f. But J. Sen rightly points out (*IIIQ*, 1930, 690) that in the *Mṛichekhakaṭika* Āryaka is represented as a cow-boy who was raised to the throne after the overthrow of the tyrant Pālaka.


² Tawney's translation, II, 485 Cf. *Camb. Hist. Ind.*, I, 311.

³ *Essay on Guṇāḍhya*, 115.

⁴ *Parīśiṣṭa pāraṇa*, 2nd ed. p. xli.

TRADITIONAL GENEALOGY OF THE PRADYOTAS

Prōṭika (Anantanemi)



⁵ The *Kācya Mimāṃsā* (3rd ed., p. 60) contains an interesting notice of this king and says that he prohibited the use of cerebials in his harem.

individual. The conclusion accords with the evidence of the *Aśokāvadāna* which places Kākavarṇin after Muṇḍa, and does not mention Kālāśoka.¹ The new king already served his apprenticeship in the art of government possibly at Benares and in the district of Gayā. The two most important events of his reign are the meeting of the second Buddhist Council at Vaiśālī, and the final transfer of the capital to Pāṭaliputra.

Bāṇa in his *Harsha-charita*² gives a curious legend concerning his death. It is stated that Kākavarṇa Śaiśunāgi had a dagger thrust into his throat in the vicinity of his city. The story about the tragic fate of this king is, as we shall see later on, confirmed by Greek evidence.

The traditional **successors of Kālāśoka** were his ten sons who are supposed to have ruled simultaneously. Their names according to the *Mahābodhivaṃsa* were Bhadrāsena, Koraṇḍavarṇa, Maṅgura, Sarvañjaba, Jālika, Ubhaka, Sañjaya, Koravya, Nandivardhana and Pañchamaka.³

Only one of these names, viz., that of **Nandivardhana** occurs in the Purāṇic lists.⁴ This prince attracted some attention in recent years. His name was read on a Patna statue⁵ and in the famous Hāthigumpā inscription of Khāravela. He was sought to be identified with Nandarrāja of Khāravela's record on the strength of Kshemen-dra's reference to *Pūrvananda* (Nanda the Elder) who,

¹ *Divyāvadāna*, 369; Geiger, *Mahāvamsa*, p. xli.

² K. P. Parab, 4th ed. 1918, p. 199.

³ The *Divyāvadāna* (p. 369) gives a different list of the successors of Kākavarṇin: Sabālin, Tulakuchi, Mahāmaṇḍala and Prasenañjit. After Prasenañjit the crown went to Nanda.

⁴ Bhandarkar, *Carm. Lec.*, 1918, 83.

⁵ Dr. Jayaswal opined that the headless "Patna statue" which stood, at the time when he wrote, in the Bhārhut Gallery of the Indian Museum, was a portrait of this king. According to him the inscription on the statue runs as follows:—

Sapa (or Sara) khate Vaṣa Nandī.

we are told, should be distinguished from the *Navanandāh* or New (Later) Nandas, and taken to answer to a ruler of the group represented by Nandivardhana and Mahānandin of the *Purāṇas*.¹ In the works of Kshemendra and Somadeva, however, Pūṛavananda (*singular*) is distinguished, not from the *Navanandāh*, but from Yogananda (Pseudo-Nanda), the re-animated corpse of

He regarded *Vaṭa Nāṁdi* as an abbreviation of Vartivardhana (the name of Nandivardhana in the *Vāyu* list) and Nandivardhana. Mr. R. D. Banerji in the June number of the *Journal of the Bihar and Orissa Research Society*, 1919, said that there cannot be two opinions about the reading *Vaṭa Nāṁdi*. Mr. Chanda, however, regarded the statue in question as an image of a *Yaksha* and read the inscription which it bore as follows :—

Yaksha sa (?) vaṭa nāṁdi.

Dr. Majumdar said that the inscription might be read as follows :—

Yakhe saṁ vajinām 70.

He placed the inscription in the second century A. D., and supported the *Yaksha* theory propounded by Cunningham and upheld by Mr. Chanda. He did not agree with those scholars who concluded that the statue was a portrait of a Śaiśunāga sovereign simply because there were some letters in the inscription under discussion which might be construed as a name of a Śaiśunāga king. Referring to Dr. Jayaswal's suggestion that the form *Vaṭa Nāṁdi* was composed of two variant proper names (Vartivardhana and Nandivardhana)—he said that Chandragupta II was also known as Devagupta, and Vighrahapāla had a second name Śūrapāla; but who had ever heard of compound names like Chandra-Deva, or Deva-Chandra, and Śūra-Vighraha or Vighraha-Śūra? (*Ind. Ant.*, 1919).

Mahāmahopādhyāya Haraprasād Śāstri took *Vaṭa Nāṁdi* to mean *Vrātya Nāṁdi* and said that the statue had most of the articles of dress as given by Kātyāyana to the *Vrātya Kshatriyas*. In the *Purāṇas* the Śiśunāga kings are mentioned as *Kshattrabandhus*, i.e., *Vrātya Kshatriyas*. The Mahāmahopādhyāya thus inclined to the view of Dr. Jayaswal that the statue in question was a portrait of a Śaiśunāga king (*JBORS.*, December, 1919).

Mr. Orinendu Coomar Gangoly, on the other hand, regarded the statue as a *Yaksha* image, and drew our attention to the catalogue of *Yakshas* in the *Mahāmāyūrī* and the passage "*Nāṁdi cha Vardhanas chaiva nagare Nandivardhane*" (*Modern Review*, October, 1919). Dr. Barnett was also not satisfied that the four syllables which might be read as *Vaṭa Nāṁdi* mentioned the name of a Śaiśunāga king. Dr. Smith, however, in the third edition of his *Asoka* admitted the possibility of Dr. Jayaswal's contention. We regard the problem as still unsolved. The data at our disposal are too scanty to warrant the conclusion that the inscription on the "Patna statue" mentions a Śaiśunāga king. The script seems to be late.

¹ Jayaswal (supported by R. D. Banerji); *The Oxford History of India*, Additions and Corrections; *JBORS*, 1918, 91.

king Nanda.¹ The *Purāṇic* as well as the Ceylonese, chroniclers know of the existence of only *one* Nanda line and agree with Jaina tradition in taking *nava* to mean *nine* (and not *new*).² They represent Nandivardhana as a king of the Śaiśunāga line—a dynasty which is sharply distinguished from the Nandas. The *Purāṇas* contain nothing to show that Nandivardhana had anything to do with Kalinga.³ On the contrary, we are distinctly told that when the Śaiśunāgas and their predecessors were reigning in Magadha 32 kings ruled in Kalinga synchronously. “It is not Nandivardhana but Mahāpadma Nanda who is said to have brought ‘all under his sole sway’ and ‘uprooted all *Kshatriyas*.’ So we should identify Nandārāja of the Hāthigumphā inscription who held possession of Kalinga either with the all-conquering Mahāpadma Nanda or one of his sons.”

¹ Cf. *Kaṭhā-sārit-sāgara*, Durgāprasad and Parab's edition, p. 10.

² Cf. Jacobi, *Parīśishtaparva*, VIII. 3; App. p. 2; ‘*Nandavamsa*’ **Navamo** *Nandārājā*.

³ Chanda, *Memoirs of the Archaeological Survey of India*, No. I, p. 11.

SECTION VII. CHRONOLOGY OF THE HARYAṆKA- ŚAIŚUNĀGA KINGS.

There is considerable disagreement between the *Purāṇas* and the Ceylonese chronicles regarding the chronology of the kings of the Bimbisārian (or Haryaṇka) and Śaiśunāga dynasties. Even Smith and Pargiter are not disposed to accept all the dates given in the *Purāṇas*.¹ According to Ceylonese tradition Bimbisāra ruled for fifty-two years, Ajātaśatru for 32 years, Udāyī for 16 years, Anuruddha and Muṇḍa for 8 years, Nāga-Dāsaka for 24 years, Śiśunāga for 18 years, Kālāśoka for 28 years and Kālāśoka's sons for 22 years. Gautama Buddha died in the eighth year of Ajātaśatru,² i.e., in the (52+8=) 60th year (i.e., a little more than 59 years) after the accession of Bimbisāra. The event happened in 544 B.C. according to a Ceylonese reckoning, and in 486 B.C. according to a Cantonese tradition of 489 A.D., based on a 'dotted record' brought to China by Saṃgha-bhadra. The date 544 B.C. can, however, hardly be reconciled with a *gāthā* transmitted in the Ceylonese chronicles which states that Priyadarśana (Aśoka Maurya) was consecrated 218 years after the Buddha had passed into *nirvāṇa*.³ This fact and certain Chinese and Chola

¹ Pargiter (AIHT, pp. 286-7) reads the *Matsya Purāṇa* as assigning the Śiśunāgas 163 years, and further reduces the number to 145 allowing an average of about 14½ years for each reign. He places the beginning of the Śiśunāgas (among whom he includes the Bimbisārids) in B.C. 567 and rejects (287n) the traditional figures for the reigns of Bimbisāra and his son. Cf. also Bhandarkar, *Carm. Lec.*, 1918, p. 68. 'A period of 363 years for ten consecutive reigns' i.e., 36.3 years for each 'is quite preposterous.'

² *Mahāvamsa*, Ch. 2 (p. 12 of translation).

³ *Dre satāni cha vaṣṣāni etthārassa vaṣṣāni cha Sambuddhe parinibbute abhisitto Piyadassano.*

Ibid., p. xxiii. (Cf. *Dip.* 6. 1).

synchronisms led Geiger and a few other scholars to think that the era of 544 B.C. is a comparatively modern fabrication and that the true date of the death of the Buddha is 483 B.C.¹—a result closely approaching that to which the Cantonese tradition leads us. The Chola synchronisms referred to by these scholars are, however, not free from difficulties, and it has been pointed out by Geiger himself that the account in Chinese annals of an embassy which Mahānāman, king of Ceylon, sent to the emperor of China in 428 A.D., does not speak in favour of his revised chronology. The traditional date of Menander which is C. 500 A.B., works out more satisfactorily with a *Nirvāṇa* era of 544 B.C., than with an era of 483 or 486 B.C. In regard to the Maurya period, however, calculations based on the traditional Ceylonese reckoning will place the accession of Chandragupta Maurya in $544-162=382$ B.C., and the coronation of Aśoka Maurya in $544-218=326$ B.C. These results are at variance with the evidence of Greek writers and the testimony of the inscriptions of Aśoka himself. Classical writers represent Chandragupta as a contemporary of Alexander (326 B.C.) and of Seleukos (312 B.C.). Aśoka in his thirteenth Rock Edict speaks of certain Hellenistic kings as alive. As one at least of these rulers died not later than 258 B.C. (250 B.C. according to some authorities) and as rescripts on morality began to be written when Aśoka was anointed twelve years, his consecration could not have taken place after 269 B.C. (261 B.C. according to some). The date cannot be pushed back beyond 277 B.C., because his grandfather Chandragupta must have ascended the throne after 326 B.C., as he met Alexander in that year as an ordinary individual and died after a reign of 24

¹ *Ibid*, Geiger, trans. p. xxviii; JRAS, 1900, pp. 1-34.

years, and the next king Bindusāra, the father and immediate predecessor of Aśoka, ruled for at least 25 years. $326 \text{ B.C.} - 49 = 277 \text{ B.C.}$ Aśoka's coronation, therefore, took place between 277 and 261 B.C., and as the event happened, according to the old *Gāthā* recorded by the Ceylonese Chroniclers, 218 years after the *parinirvāṇa* of the Buddha, the date of the Great Decease should be placed between 495 and 479 B.C. The result accords not with the Ceylonese date 544 B.C., but with the Cantonese date 486 B.C., and Geiger's date 483 B.C., for the *parinirvāṇa*. The Chinese account of embassies which King Meghavarṇa sent to Samudra Gupta, and King Kia-Che (Kassapa) sent to China in 527 A.D., also speaks in favour of the date 486 B.C., or 483 B.C., for the Great Decease. Geiger's date, however, is not recognised by reliable tradition. The same remark applies to the date (Tuesday, 1 April, 478 B.C.) preferred by L. D. Swami Kannu Pillai.¹ The Cantonese date may, therefore, be accepted as a working hypothesis for the determination of the chronology of the *early* dynasties of Magadha. The date of Bimbisāra's accession, according to this reckoning, would fall in or about $486 + 59 = 545 \text{ B.C.}$, which is very near to the starting point of the traditional Ceylonese *Nirvāṇa* era of 544 B.C. 'The current name of an era is no proof of origins.' It is not altogether improbable that the Buddhist reckoning of Ceylon originally started from the coronation of Bimbisāra and was later on confounded with the era of the Great Decease.

In the time of Bimbisāra Gandhāra was an independent kingdom ruled by a king named Paushkarasārin (Pukkusāti). By B.C. 519 at the latest it had lost its independence and had become subject to Persia, as we

¹ *An Indian Ephemeris*, I, Pt. 1, 1922, pp. 471 ff.

learn from the inscriptions of Darius. It is thus clear that Paushkarasārin and his contemporary Bimbisāra lived before B.C. 519. This accords with the chronology which places his accession and coronation in or about B.C. 545-44.

SUGGESTED CHRONOLOGICAL TABLE

(APPROXIMATE DATES)

Event

Year B.C.

- * 565 Birth of the Buddha.
- 560 Birth of Bimbisāra.
- c. 558 Accession of Cyrus the Achaemenid.
- ~~545-44~~ Accession of Bimbisāra. Epoch of a Ceylonese Era.
- 536 The Great Renunciation (of the Buddha).
- 530 Enlightenment.
- 530-29 The Buddha's visit to Bimbisāra.
- | 527 Traditional Epoch of the era of Mahāvira's *Nirvāṇa*
- ~~522~~ Accession of Darius I.
- 493 Accession of Ajātaśatru.
- ~~486~~ Cantonese date of the *Parinirvāṇa* of the Buddha. The death of Darius I. Council of Rājagṛiha.
- 461 Accession of Udāyidhadraka.
- 457 Foundation of Pāṭaliputra (Kusumapura).
- 445 Aniruddha (Anuruddha) and Muṇḍa.
- 437 Nāga-Dāsaka (omitted in the *Divyāvadāna* and Jaina texts)
- 413 Śiśunāga.
- 395 Kālāśoka (Kākavarṇa).
- 386 Council of Vaiśālī.
- 367 Sons of Kālāśoka, and *de facto* rule of Mahāpadma Nanda.
- 345 End of the Śaiśunāga dynasty.

SECTION VIII. THE NANDAS.

The Saiśunāga dynasty was supplanted by the line of Nanda.¹ With the new family we reach a stage of East Indian history when the indubitable evidence of inscriptions becomes available to supplement the information gleaned from traditional literary sources. The famous Hāthigumphā record of Khāravela, of the second or first century B.C., twice mentions Nandā-rāja in connection with Kalinga.

*Pañchame cedāni vase Nandārāja-ti-vasa-
sata-oghātitaṃ
Tanasuliya-vāṭā panāḍi (m) nagaram
pavesa (yati).....*

“And then, in the fifth year, (Khāravela) caused the canal opened out by King Nanda three hundred years²

¹ According to Jaina tradition Nanda was proclaimed king after Udāyin's assassination, and sixty years after the Nireṣṇa of Varddhamaṇa (*Parīśiṣṭa* P. VI. 243). For Nanda history see now *Age of the Nandas and Mauryas*, pp. 9-26. N. Sastri, Raychaudhuri and others.

² This interpretation of '*tivasasata*' accords substantially with the Purāṇic tradition, regarding the interval between the Nandas and the dynasty to which Śātakarṇi, the contemporary of Khāravela in his second regnal year, belonged (137 years for the Mauryas + 112 for the 'Śuṅgas' + 45 for the Kāṇvas=294). If the expression is taken to mean 103 years (as is suggested by some scholars), Khāravela's accession must be placed 103-5=98 years after Nandārāja. His elevation to the position of Yuvārāja took place 9 years before that date i.e., 98-9=89 years after Nanda, i.e., not later than 324-89=235 B.C. Khāravela's senior partner in the royal office was on the throne at that time and he may have had his predecessor or predecessors. But we learn from Aśoka's inscriptions that Kalinga was actually governed at that time by a Maurya Kumāra, (and not by a Kalinga-adhipati or Chakravartī) under the suzerainty of Aśoka himself. Therefore, *tivasasata* should be understood to mean 300 and not 103 years. S. Konow (*Acta Orientalia*, I.22-26) takes the figure to express not the interval between Nanda and Khāravela, but a date during the reign of Nanda which was reckoned from some pre-existing era. But the use of any such era in the particular country and epoch is not proved. Khāravela himself, like Aśoka, uses regnal years. The agreement with Purāṇic tradition speaks in favour of the view adopted in these pages.

back to be brought into the capital from the Tanasuliya road."

Again, in connection with the twelfth year of Khāravela's reign, we have a reference to *Nadarāja-jīta Kaliṅga-jana-saṁ* (n) i (ve) *saṁ* (or, according to another reading, *Namda-rājanīlām Kaliṅga Jina saṁnivesaṁ*),¹ i.e., a station or encampment, or a Jaina shrine, in Kaliṅga acquired² by king Nanda.

The epigraphs, though valuable as early notices of a line known mainly from literature, are not contemporaneous. For contemporary reports we must turn to Greek writers. There is an interesting reference, in the *Cyropaedia*³ of Xenophon, who died some time after 355 B.C., to "the Indian king, a very wealthy man". This cannot fail to remind one of the Nandas whom the unanimous testimony of Sanskrit, Tamil, Ceylonese and Chinese writers describe as the possessors of enormous wealth.⁴ Clearer information about the ruling family of Magadha

Barua, *Hāthigumpha Inscription of Khāravela* (IHQ, XIV, 1938 pp. 250ff). *Sanniveśa* is explained in the dictionaries as an assemblage, station, seat, open space near a town etc. (Monier Williams). A commentator takes it to mean 'a halting place of caravans or processions'. Kuṇḍagrāma was a *sanniveśa* in Videha (SBE, XXII, *Jaina Sūtras*, pt. I, Intro.). The reference in the inscription to the conquest of a place, or removal of a sacred object from Kaliṅga by Nandarāja disposes of the view that he was a local chief (*Camb. Hist.* 538).

² Dr Barua (*op. cit.* p. 276n) objects to a Nanda conquest (or domination) of any part of Kaliṅga on the ground that the province "had remained unconquered (*acijita*) till the 7th year of Aśoka's reign". But the claim of the Maurya secretariat is on a par with Jahāngir's boast that "not one of the Sultans of lofty dignity has obtained the victory over it" (i.e., Kangra, Rogers, *Tārik*, II, 164). Kaliṅgas appear in the Purāṇas among the contemporaries of the Śaiśunāgas who were overpowered by Nānda, the *Sarta-Kaśatrāntaka*.

³ III, II, 25 (trans. by Walter Miller).

⁴ Cf. the names Mahāpadmapati and Dhana Nanda. The *Mudrārākhaṣa* refers to the Nandas as '*nāganoratilatadadrayakoṭṭīśvarāḥ*' (Act III, verse 27), and '*Artharuchi*' (Act I).

A passage of the *Kathā-sarit-sāgara* says that King Nanda possessed 990 millions of gold pieces. Tawney's Translation, Vol. I, p. 21.

Dr. Aiyangar points out that a Tamil poem contains an interesting statement regarding the wealth of the Nandas "which having accumulated first in Pāṭalī

(c. 326 B.C.) is supplied by the contemporaries of Alexander whose writings form the bases of the accounts of Curtius, Diodoros and Plutarch. Unfortunately, the classical writers do not mention the family name 'Nanda'. The reading 'Nandrum' in the place of 'Alexandrum' in the account of Justin is absolutely unjustifiable.

For a detailed account of the dynasty we have to rely on Indian tradition. Indian writers seem to be mainly interested in the Nanda age partly as marking an epoch in a social upsurge and the evolution of imperial unity, and partly as accessory to the life-sketch of Jaina patriarchs and to the *Chandragupta-kathā* of which we have fragments in the *Milindapañho*, *Mahāvamsa*, the Purāṇic chronicles, the *Bṛihat-Kathā* and its later versions together with the *Mudrā-rākshasa* and the *Arthaśāstra* compendiums.

The first Nanda was **Mahāpadma** or Mahāpadmapati¹ according to the *Purāṇas* and **Ugrasena** according to the *Mahābodhivamsa*. The *Purāṇas* describe him as a son of the last *Kshatrabandhu* (so-called Kshatriya) king of the preceding line by a *Śūdrā* mother. (*Śūdrā-garbh-odbhava*). The Jaina *Parīśiṣṭaparvan*,² on the

bid itself in the floods of the Ganges." *Beginnings of South Indian History*, p. 89. For N. Sastri's views see ANM, pp. 253ff.

According to Ceylonese tradition "The youngest brother (among the sons of Ugrasena) was called Dhana Nanda, from his being addicted to hoarding treasure. ...He collected riches to the amount of eighty *koṭis*—in a rock in the bed of the river (Ganges) having caused a great excavation to be made, he buried the treasure there...Levying taxes among other articles even on skins, gums, trees, and stones he amassed further treasures which he disposed of similarly." (Turnour, *Mahāvamsa*, p. xxxix).

Hsuen Tsang, the Chinese pilgrim, refers to "the five treasures of King Nanda's seven precious substances."

¹ 'Sovereign of an infinite host' or 'of immense wealth' according to the commentator (Wilson. *Vishnu P.* Vol. IX, 184n). A city on the Ganges, styled Mahāpadmapura, is mentioned in *Mbh.* XII. 363. 1.

P. 46. Text VI. 231-32.

other hand, represents Nanda as the son of a courtesan by a barber. The Jaina tradition is strikingly confirmed by the classical account of the pedigree of Alexander's Magadhan contemporary who was the predecessor of Chandragupta Maurya. Referring to this prince (Agrammes) Curtius says, "His **father** was in fact a **barber**, scarcely staving off hunger by his daily earnings, but who from his being not uncomely in person, had gained the affections of the queen, and was by her influence advanced to too near a place in the confidence of the reigning monarch. Afterwards, however, he treacherously murdered his sovereign, and then, under the pretence of acting as guardian to the royal children, **usurped the supreme authority**, and having put the young princes to death, begot the present king."

The barber ancestry of Agrammes, recorded by the classical writers is quite in keeping with the Jaina story of the extraction of the Nanda line. That the Magadhan contemporary of Alexander and of young Chandragupta was a Nanda king is not disputed. The real difficulty is about his identity. He could not possibly have been the first Nanda himself. The words used in reference to Agrammes, "the present king," i.e., Alexander's contemporary in Curtius' narrative, make this point clear. He (Agrammes) was *born in purple* to one who had already "*usurped supreme authority*" having secured the affections of a *queen*. That description is scarcely applicable to the founder of the dynasty who was, according to Jaina testimony, the son of an ordinary courtesan (*ganikā*) by a barber apparently without any pretensions to *supreme power in the state*.

The murdered sovereign seems to have been Kālāsoka-Kālavarṇa who had a tragic end as we learn from the

Harsha-charita. Kākavarṇa Saiśunāgi, says Bāṇa, had a dagger thrust into his throat in the vicinity of his city. The young princes referred to by Curtius were evidently the sons of Kālāśoka-Kākavarṇa. The Greek account of the rise of the family of Agrammes fits in well with the Ceylonese account of the end of the Saiśunāga line and the rise of the Nandas, but not with the Purāṇic story which represents the first Nanda as a son of the last Saiśunāga by a Sūdra woman, and makes no mention of the young princes. The name Agrammes is probably a distorted form of the Sanskrit Augrasainya, "son of Ugrasena".¹ Ugrasena is, as we have seen, the name of the first Nanda according to the *Mahābodhivaṃsa*. His son may aptly be termed Augrasainya which the Greeks corrupted into Agrammes and later on into Xandrames.²

The *Purāṇas* call Mahāpadma, the first Nanda king, the destroyer of all the Kshatriyas (*sarva Kshatrāntaka*) and the sole monarch (*ekarāt*) of the earth which was under his undisputed sway, which terms imply that he finally overthrew all the dynasties which ruled contemporaneously with the Saiśunāgas, viz., the Ikshvākus, Pañchālas, Kāśis, Haihayas, Kaliṅgas, Āśmakas, Kurus,

¹ "Augrasainya" as a royal patronymic is met with in the *Aitareya Brāhmaṇa*, viii. 21.

² The identification of Xandrames (taken to answer to Sanskrit Chandramas), the Magadhan contemporary of Alexander, with Chandragupta, proposed by certain writers, is clearly untenable. Plutarch (*Life of Alexander*, Ch. 83) clearly distinguishes between the two, and his account receives confirmation from that of Justin (Watson's tr., p. 142). Xandrames or Agrammes was the son of a usurper born after his father had become king of the Prasii, while Chandragupta was himself the founder of a new sovereignty, the first king of his line. The father of Xandrames was a barber who could claim no royal ancestry. On the other hand, Brāhmanical and Buddhist writers are unanimous in representing Chandragupta as a descendant of a race of rulers, though they differ in regard to the identity of the family and its claim to be regarded as of pure Kshatriya stock. Jaina evidence clearly suggests that the barber usurper is identical with the Nāpita-kumāra or Nāpitasā (*Paristishṭa*, VI. 231 and 244) who founded the Nanda line.

Maithilas, Sūrasenas, Vitihotras,¹ etc. The Jainas, too, allude to the wide dominion of Nanda.² The Indian account of the unification of a considerable portion of India under Nanda's sceptre is corroborated by several classical writers who speak of the most powerful peoples who dwelt beyond the 'extensive deserts' (apparently of Rājputāna and some adjoining tracts) in the time of Alexander, viz., the Prasii (*Prāchyas*) and the Gangaridae (people of the lower Ganges Valley) as being under one sovereign who had his capital at Palibothra (Pāṭaliputra).³

¹ Conquest of some of the territories occupied by the tribes and clans named here by former kings of Magadha does not necessarily mean the total extinction of the old ruling families, but merely a deprivation of their glory (*yaśaś*) and an extension of the suzerainty of the conqueror. Extirpation cannot be meant unless it is definitely asserted as in the case of Mahāpadma Nanda's conquest, or that of Samudra Gupta in Āryāvarta. It may also sometimes be implied by the appointment of a prince of the conquering family as viceroy. Allowance, however, must be made for a good deal of exaggeration. Even the Vajjians were not literally 'rooted out' by Aśśaśatru, as the most important of the constituent clans, viz., the Licchavis, survive till the Gupta Age. A branch of the Ikshvākus may have been driven southwards as they are found in the third or fourth century A.D. in the lower valley of the Kṛishṇā. The Kāśis overthrown by Nanda may have been the descendants or successors of the prince whom Śaiśunāga had placed in Benares. The Halbhayas occupied a part of the Narmadā valley. Conquest of a part of Kālīṅga by Nanda is suggested by the Hāthīgumphā record, that of Aśśmakas and part of the Godāvarī valley by the city called 'Nau Nand Dehra' (Nander, Macanliffe, *Sikh Religion*, V, p. 236). Vitihotra sovereignty had terminated before the rise of the Pradyotas of Avantī. But if the Purāṇic statement (*DKA*, 23, 69) "Contemporaneously with the aforesaid kings (Śaiśunāgas, etc.) there will be.....Vitihotras" has any value, the Śaiśunāgas may have paved the way for a restoration of some scion of the old line in Avantī. According to the evidence of the *Purāṇas* (*Vāyu* 24, 51-52) the Vitihotras were one of the five *ganas* of the Halbhayas, and the survival of the latter is well attested by epigraphic evidence. The Maithilas apparently occupied a small district to the north of the Vajjian dominions annexed by Aśśaśatru. The Pañcābāhas, Kurus, and the Sūrasenas occupied the Gangetic Doab and Mathurā and the control of their territories by the king of Magadha c. 325 B.C., accords with Greek evidence.

² *Somudrasasanebhyaśśamudromapiśriṅṇā
upāyaśśastairākṛiṣṭhā tataśś ca' kṛitā Nandaeśśi*

Parishista Parvan, VII, 81.

³ *Ino. Alex.*, 221, 291; *Megasthenes and Arrian* by McCrindle (1926) pp. 67, 141, 161.

Pliny informs us¹ that the Prasii surpass in power and glory every other people in all India, their capital being Palibothra (Pāṭaliputra), after which some call the people itself Palibothri, nay, even the whole tract of the Ganges. The author is referring probably to conditions in the time of the Mauryas, and not in that of the Nandas. But the greatness that the Prasii (i.e. the Magadhans and some other eastern peoples) attained in the Maurya Age would hardly have been possible but for the achievements of their predecessors of which we have a record by the historians of Alexander. The inclusion of the Ikshvāku territory of Kosala within Nanda's dominions seems to be implied by a passage of the *Kathā-saritsāgara*² which refers to the camp of king Nanda in Ayodhyā. Several Mysore inscriptions state that Kuntala, a province which included the southern part of the Bombay presidency and the north of Mysore, was ruled by the Nandas.³ But these are of comparatively modern date, the twelfth century, and too much cannot be built upon their statements. More important is the evidence of the Hāthigumphā inscription which mentions the constructive activity of Nandarāja in Kalinga and his conquest (or removal) of some place (or sacred object) in that country. In view of Nanda's control over parts of Kalinga, the conquest of Āśmaka and other regions lying further south does not seem to be altogether improbable. The existence on the Godāvarī of a city called "Nau Nand Dehra" (Nander)⁴ also suggests that the Nanda dominions may have embraced a considerable portion of the Deccan.

¹ *Megasthenes and Arrian* (1926), p. 141.

² Tawney's Translation, p. 31.

³ Rice, *Mysore and Coorg from the Inscriptions*, p. 3; Fleet, *Dynasties of the Kanarese Districts*, 284, n. 2.

⁴ Macauliffe's *Sikh Religion*, V, p. 236.

The *Matsya Purāṇa* assigns 88 years to the reign of the first Nanda, but 88 (*Aṣṭāśīti*) is probably a mistake for 28 (*Aṣṭāvimsatī*), as the *Vāyu* assigns only 28 years. According to Tāranāth Nanda reigned 29 years.¹ The Ceylonese accounts inform us that the Nandas ruled only for 22 years. The Purāṇic figure 28 is probably to be taken to include the period when Nanda was the *de facto* ruler of Magadha before his final usurpation of the throne.

Mahāpadma-Ugrasena was succeeded by his eight sons who were possibly kings in succession. They ruled for twelve years according to the Purāṇas. The Ceylonese Chronicles, as we have already seen, give the total length of the reign-period of all the nine Nandas as 22 years. The Purāṇas specify the name of one son of Mahāpadma, viz., Sukalpa.² The *Mahābodhivamsa* gives the following names: Paṇḍuka, Paṇḍugati, Bhūtapāla, Rāshṭrapāla, Govishāṇaka, Daśasiddhaka, Kaivarta and **Dhana**. The last king is possibly identical with the **Agrammes** or **Xandrames** of the classical writers. Agrammes is, as we have seen, probable a distortion by the Greeks of the Sanskrit patronymic *Augrasainya*.

The first Nanda left to his sons not only a big empire but also a large army and, if tradition is to be believed, a full exchequer and an efficient system of civil government. Curtius tells us that Agrammes, king of the Gangaridae and the Prasii, kept in the field for guarding the approaches to his country 20,000 cavalry and 200,000 infantry, besides 2,000 four-horsed chariots, and what was the most formidable force of all, a troop of elephants

¹ *Ind. Ant.*, 1875, p. 362.

² The name has variants. One of these is Sahalya. Dr. Barua makes the plausible suggestion that the prince in question may be identical with Sahalin of the *Dirgāradāna* (p. 369; Pargiter, *DKA*, 25 n 24; *Bauddha Dharma Kosha*, 44). The evidence of that Buddhist work in regard to the relationship between Sahalin and Kākavarṇa can, however, hardly be accepted. The work often errs in this respect. It makes Pushyamitra a lineal descendant of Aśoka (p. 433).

which, he said, ran up to the number of 3,000. Diodoros and Plutarch give similar accounts. But they raise the number of elephants to 4,000 and 6,000 respectively. The name of one of the generals, Bhaddasāla is preserved by Buddhist tradition.¹

The immense riches of the Nandas have already been referred to. The family may also be credited with irrigation projects in Kalinga and the invention of a particular kind of measure (*Nandopakramāṇi mānāni*).² The existence of a body of capable ministers is vouched for both by Brāhmaṇical and Jaina tradition. But in the end they proved no match for another traditional figure whose name is indissolubly linked up with the fall of the Nandas and the rise of a more illustrious race of rulers.

No detailed account of this great dynastic revolution has survived. The accumulation of an enormous amount of wealth by the Nanda kings probably implies a good deal of financial extortion. Moreover, we are told by the classical writers that Agrammes (the Nanda contemporary of Alexander) "was detested and held cheap by his subjects as he rather took after his father than conducted himself as the occupant of a throne."³

The Purāṇic passage about the revolution⁴ stands as follows :

*Uddharishyati tām sarvām
Kauṭilyo vai dvījarshabhāḥ*

¹ *Milinda-Paṇḥo*, SBE, xxxvi, pp. 147-8.

² S. C. Vasu's trans. of the *Aṣṭādhyāyī* of Pāṇini, rule illustrating *sūtra* II. 4. 21.

³ McCrindle, *The Invasion of India by Alexander*, p. 223. Cf. Ref. to Nanda's avarice DKA 125, Jaina *Parīkṣitā parvan*, vi. 244.—

tataścha kechit sāmāntā madenāndhaṁ bhaviṣṇavaḥ

Nandasya na natiṁ chakrurasau nāpitasūriti.

⁴ The dynastic change is also referred to by the *Kauṭilya Arthaśāstra*, the *Kāmandakiya Nīṭisāra*, the *Mudrārākṣasa*, the *Chandā Kauśika*, the *Ceylonese Chronicles*, etc.

*Kauṭilyaś-Chandraguptam tu
tato rājye bhishekshyati.*¹

The *Milinda-Paṇho*² refers to an episode of the great struggle between the Nandas and the Mauryas: "There was Bhaddasāla, the soldier in the service of the royal family of Nanda, and he waged war against king Chandagutta. Now in that war, Nāgasena, there were eighty Corpse dances. For they say that when one great Head Holocaust has taken place (by which is meant the slaughter of ten thousand elephants, and a lac of horses and five thousand charioteers, and a hundred *koṭis* of soldiers on foot), then the headless corpses arise and dance in frenzy over the battle-field." The passage contains a good deal of mythical embellishment. But we have here a reminiscence of the bloody encounter between the contending forces of the Nandas and the Mauryas.³

¹ Some Mss. read *dvirashṭabhiḥ* in place of *dvijarashabhaḥ*. Dr. Jayaswal (*Ind. Ant.*, 1914, 121) proposed to emend it to *Virashṭrābhiḥ*. *Virashṭrās* he took to mean the *Āraṭṭas* and added that Kauṭilya was helped by the *Āraṭṭas* "the band of robbers" of Justin. Cf. Cunningham, *Bhilsa Topes*, pp. 88, 89. Pargiter, however, suggests, (*Dynasties of the Kali Age*, pp. 26, 35) that *dvijarashabhaḥ* (the best among the twice-born, i.e., Brāhmaṇas) may be the correct reading instead of "*dvirashṭabhiḥ*."

² IV. 8. 26. Cf. SBE, xxxvi, pp. 147-48.

³ Cf. *Ind. Ant.*, 1914, p. 124n.

CHAPTER III. THE PERSIAN AND MACEDONIAN INVASIONS.

SECTION I. THE ADVANCE OF PERSIA TO THE INDUS.

While the kingdoms and republics of the Indian interior were gradually being merged in the Magadhan Empire, those of North-West India (including modern Western Pākistān) were passing through vicissitudes of a different kind. In the first half of the sixth century B.C., the *Uttarāpatha* (northern region) beyond the *Madhyadeśa* (Mid-India, roughly the Ganges-Jumna Doāb, Oudh and some adjoining tracts), like the rest of India, was parcelled out into a number of small states the most important of which were Kamboja, Gandhāra and Madra. No sovereign arose in this part of India capable of welding together the warring communities, as Ugrasena-Mahāpadma had done in the East. The whole region was at once wealthy and disunited, and formed the natural prey of the strong Achaemenian monarchy which grew up in Persia (Irān).

Kurush or **Cyrus** (558-530 B.C.¹) the founder of the Persian Empire, is said to have led an expedition against India through Gedrosia, but had to abandon the enterprise, escaping with seven men only.² But he was more successful in the Kābul valley. We learn from Pliny that he destroyed the famous city of Kāpiśī, at or near the confluence of the Ghorband and the Panjshir. Arrian informs us³ that "the district west of the river Indus as far as the river Cophen (Kābul) is inhabited by the Astaceni-

¹ 550-529 B. C. according to *A Survey of Persian Art*, p. 64.

² H. and F., *Strabo*, III, p. 74.

³ Chinnock, *Arrian's Anabasis*, p. 399.

(Āshṭakas)¹ and the Assacenian (Aśvakas), *Indian* tribes. These were in ancient times subject to the Assyrians, afterwards to the Medes, and finally they submitted to the Persians, and paid tribute to Cyrus, the son of Cambyses, as ruler of their land." Strabo tells us that on one occasion the Persians summoned the Hydraces (the Kshudrakas) from India (*i.e.*, the Pañjāb) to attend them as mercenaries.

In the Behistun or Bahistān inscription of Dārayavaush or **Darius I** (c. 522-486 B.C.) the third sovereign of the Achaemenian dynasty, the people of Gandbāra (Gadāra) appear among the subject peoples of the Persian Empire. But no mention is there made of the Hidus (Hindus, people of Sindhu or the Indus Valley) who are explicitly referred to in the Hamadan Inscription, and are included with the Gandhārians in the lists of subject peoples given by the inscriptions on the terrace at Persepolis, and around the tomb of Darius at Naqsh-i-Rustum.² From this it has been inferred that the "Indians" (Hidus) were conquered at some date between 519 B.C. (the probable date of the Behistun or Bahistān inscription),³ and 513 B.C.⁴ The preliminaries to this conquest are described by Herodotus:⁵ "He (Darius, being desirous to know in what part the Indus,

¹ Patañjali (IV. 2. 2) refers to "Āshṭakam nāma dhanva;" (*cf.* *Hasht-nagar*, and *Aṭhakanagara*, Lüders, 390).

² *Ancient Persian Lexicon and the Texts of the Achaemenian Inscriptions* by H. C. Tolman; Rapson, *Ancient India*; Herzfeld, *MASI*, 34, pp. 1 ff.

³ In the opinion of Jackson (*Camb. Hist. India*, I, 334) the Bahistān Rock Inscription is presumably to be assigned to a period between 520 and 518 B.C. with the exception of the fifth column, which was added later. Rapson regarded 516 B.C. as the probable date of the famous epigraph¹ while Herzfeld prefers the date 519 B.C. (*MASI*, No. 34, p. 2).

⁴ Olmstead, *History of the Persian Empire*, 145. Herzfeld is, however, of the opinion that reference to the 'Thatagush' in early Persian epigraphs shows that (part of) the Pañjāb, like Gandhāra, was Persian from the days of Cyrus the Great.

⁵ McCrindle, *Ancient India as described in Classical Literature*, pp. 4-5.

which is the second river that produces crocodiles, discharges itself into the sea, sent in ships both others on whom he could rely to make a true report and also Scylax of Caryanda. They accordingly setting out from the city of Caspatyrus¹ and the country of Paktyike (Pakthas ?)² sailed down the river towards the east and sunrise to the sea; then sailing on the sea westwards, they arrived in the thirtieth month at that place where the king of Egypt despatched the Phoenicians, to sail round Libya. After these persons had sailed round, Darius subdued the Indians and frequented the Sea."

Herodotus tells us that "India" constituted the twentieth and the most populous satrapy of the Persian Empire, and that it paid a tribute proportionately larger than all the rest,—360 talents of gold dust, equivalent to £1,290,000 of the pre-war period. There is no reason to believe that all this gold came from Bactria or Siberia. Gold deposits are not unknown in several tracts of the North-West Frontier, and quantities of gold are recovered from the alluvium of rivers. A small quantity of the precious metal used to be imported by Bhotiya traders from the Tibetan Hills.³ Gandhāra was included in the seventh satrapy. The details regarding "India" left by Herodotus leave no room for doubt that it embraced the Indus Valley and was bounded on the east by the desert of Rājaputāna. "That part of India towards the rising sun is all sand; for of the people with whom we are acquainted, the Indians live the furthest towards the east and the sunrise, of all the inhabitants of Asia, for the Indians'

¹ *Camb. Hist. Ind.*, I. 336. The city was probably situated in ancient Gandhāra; Herod. IV. 44.

² *Camb. Ibid.*, 52. 389. Paktyike is apparently the ancient name of the modern Pathan country on the north-west borderland of the sub-continent of India.

³ Crooke, *The North-Western Provinces of India*, 1897, p. 10; *Amrita Bazar Patrika*, 19-7-39, p. 6; cf. Watters, *Yuan Chwang*, I. 225, 239.

country towards the east is a desert by reason of the sands." Curtius refers to extensive deserts beyond the Beas.

The organisation of the empire into *Satrapies* served as a model to several succeeding dynasties, and was given a wider extension in India by the Śakas and the Kushāns in the centuries immediately preceding and succeeding the Christian era. The *Deśa-goptrī* of the Gupta Age was the lineal successor of the Satrap (*Kshatra-pāvan*) of earlier epochs.

The Persian conquerors did much to promote geographical exploration and commercial activity. At the same time they took from the country not only an enormous amount of gold and other commodities such as ivory and wood, but denuded it of a great portion of its man-power. Military service was exacted from several tribes. Contact between the East and the West became more intimate with important results in the domain of culture. If the Achaemenians brought the Indian bowmen and lancers to Hellenic soil, they also showed the way of conquest and cultural penetration to the peoples of Greece and Macedon.

Khshayārshā or **Xerxes** (486-465 B.C.), the son and successor of Darius I, maintained his hold on the Indian provinces. In the great army which he led against Hellas both Gandhāra and "India" were represented. The Gandhārians are described by Herodotus as bearing bows of reed and short spears, and the "Indians" as being clad in cotton garments and bearing cane bows with arrows tipped with iron. One of the newly discovered stone-tablets at Persepolis¹ records that Xerxes "by Ahuramazda's will" sapped the foundations of certain temples of the *Daivas* and ordained that "the *Daivas* shall not be worshipped".

¹ The Illustrated London News, Feb. 22, 1936, p. 328. See, Old Persian Inscriptions, 152.

Where the *Daivas* had been worshipped, the king worshipped Ahuramazda together with *Bltam* (divine world order). 'India' may have been among the lands which witnessed the outcome of the religious zeal of the Persian king.

The Persian Empire rapidly declined after the death of Xerxes. But if Ktesias who resided at the Court of Artaxerxes II, Mnemon 405-358 B. C., is to be believed, the Great King used to receive costly presents from India even in the fourth century B. C.¹ The South Tomb Inscription at Persepolis,² usually assigned to Artaxerxes II, continues to mention the Sattagydiāns, the Gandharians and the Hi(n)dus side by side with the Persians, the Medians, the Susians and others apparently as subjects of the Achaemenian King.

Among interesting relics of Persian dominion in India mention is sometimes made of a Taxila inscription in Aramaic characters of the fourth or fifth century B.C.³ But Herzfeld points out⁴ that the form *Priyadarśana* occurs in the record which should be referred to the reign of Aśoka, and not to the period of Persian rule. To the Persians is also attributed the introduction of the *Kharoshthī* alphabet, the "Persepolitan capital" and words like "*dipi*" (rescript) and "*nipishṭa*" ("written") occurring in the inscriptions of Aśoka. Persian influence has also been traced in the preamble of the Aśokan edicts.

¹ *Ind. Ant.*, Vol. X (1881), pp. 304-310.

² S. Sen, *Old Persian Inscriptions*, 172f.

³ *JRAS.*, 1915, I, pp. 340-347.

⁴ *Ep. Ind.*, XIX. 253.

SECTION II. THE LAST OF THE ACHÆMENIDS AND ALEXANDER.

Artaxerxes II died in or about 358 B.C. After a period of weak rule and confusion, the crown went to Darius III Codomannus (335-330 B.C.). This was the king against whom Alexander, the great king of Macedon, led forth his famous phalanx. After several engagements in which the Persian forces suffered repeated defeats, the Macedonian conqueror rode on the tracks of his vanquished enemy and reached the plain watered by the river Bumodus.

Three distinct groups of Indians figured in the army which mustered under the banner of the Persian monarch in that region. "The *Indians who were conterminous with the Bactrians* as also the Bactrians themselves and the Sogdianians had come to the aid of Darius, all being under the command of Bessus, the Viceroy of the land of Bactria. They were followed by the Sacians, a Scythian tribe belonging to the Scythians who dwell in Asia. These were not subject to Bessus but were in alliance with Darius. . . Barsaentes, the Viceroy of Arachotia, led the Arachotians and the men who were called *Mountaineer Indians*. There were a few elephants, about fifteen in number, belonging to the *Indians who live this side of the Indus*. With these forces Darius had encamped at Gaugamela, near the river Bumodus, about 600 stades distant from the city of Arbela."¹ The hold of the Achaemenians on the Indians in the various provinces on the frontier had, however, grown very feeble about this time, and the whole of north-western India was parcelled out into innumerable kingdoms, hyparchies and

¹ Chinnock, *Arrian's Anabasis*, pp. 142-143.

republics. A list of the more important among these is given below :—

1. The **Aspasian** territory (Alishang-Kūnar-Bajaur valley) :

It lay in the difficult hill country north of the Kābul river watered by the Khoes, possibly the modern Alishang, and the Euaspla, apparently the Kūnar. The name of the people is derived from the Irānian "*Aspa*," i.e., the Sanskrit "*Aśva*" (horse) or *Aśvaka*. The Aspasiens were thus the western branch of the *Aśvakas* (Assakenians).¹ The chieftain, *hyparch*, of the tribe dwelt in a city on or near the river Euaspla, supposed to be identical with the Kūnar, a tributary of the Kābul. Other Aspasian cities were Andaka and Arigaeum.²

2. The country of the **Guraeans** :

It was watered by the river Guraeus, **Gauri**, or Pañj-kora, and lay between the land of the Aspasiens and the country of the Assakenians.

3. The Kingdom of **Assakenos** (part of Swat and Buner) :

It stretched eastwards as far as the Indus and had its capital at *Massaga*, a "formidable fortress probably situated not very far to the north of the Malakand Pass but not yet precisely identified." The name of the Assakenians probably represents the Sanskrit **Aśvaka** 'land of horses,' not **Aśmaka**, 'land of stone.' The territory occupied by the tribe was also known in different ages as *Suvāstu*, *Udyāna* and, according to some, *Oddiyāna*. The *Aśvakas* do not appear to be mentioned by Pāṇini unless we regard them as belonging to the same stock as the *Aśmakas*³ of the south

¹ *Camb. Hist. Ind.*, 352. n. 3, Cf. *assānam āyatanam*, 1491 ante.

² *Chinnock's Arrian*, pp. 330-331.

³ IV. I. 173.

for which there is no real ground. They are placed in the north-west by the authors of the *Mārkaṇḍeya Purāṇa* and the *Bṛihat Saṃhitā*. The Assakenian king had a powerful army of 20,000 cavalry, more than 30,000 infantry and 30 elephants. The reigning king at the time of Alexander's invasion is called by the Greeks Assakenos. His mother was Kleophis. Assakenos had a brother¹ who is called Eryx by Curtius and Aphrikes by Diodoros.² There is no reason to believe that these personages had any relationship with king Śarabba, whose tragic fate is described by Bāṇa and who belonged apparently to the southern realm of the Āśmakas in the valley of the Godāvārī.

4. Nysa :

This was a small hill-state which lay at the foot of Mt. Meros between the Kophen or Kābul river and the Indus.³ It had a republican constitution. The city was alleged to have been founded by Greek colonists long before the invasion of Alexander.⁴ Arrian says,⁵ "The Nysaeans are not an Indian race, but descended from the men who came to India with Dionysus." Curiously enough, a Yona or Greek state is mentioned along with Kamboja in the *Majjhima Nikāya*⁶ as flourishing in the time of Gautama Buddha and Assalāyana : "Yona Kambojesu dveva vaṇṇā Ayyo c'eva Dāsoca (there are only

¹ *Invasion of Alexander*, p. 378.

² He led the flying defenders of the famous fortress of Aornos against the Greeks (*Camb. Hist. Ind.*, I. 356. Aornos is identified by Sir Aurel Stein with the height of Una between the Swat and the Indus (*Alexander's Campaign on the Frontier*, *Benares Hindu University Magazine*, Jan., 1927). The southern side of the stronghold was washed by the Indus (*Inv. Alex.*, 271).

³ *Inv. Alex.*, 79, 193.

⁴ McCrindle, *Invasion of Alexander*, p. 79; Hamilton and Falconer, *Strabo*, Vol. III, p. 76. Dr. K. P. Jayaswal informed me that he referred to the Nysaeon Indo-Greeks in a lecture delivered as early as 1919.

⁵ Chinnock's *Arrian*, p. 399.

⁶ II. 149.

two social grades among the Yonas and the Kambojas, viz., Aryan and Dāsa).''

According to Holdich the lower spurs and valleys of Kohi-Mor in the **Swat** country are where the ancient city of Nysa once stood.¹ At the time of Alexander's invasion the Nysaeans had Akouphis for their President. They had a Governing Body of 300 members.²

5. **Peukelaotis** (in the Peshāwar District):

It lay on the road from Kābul to the Indus. Arrian tells us³ that the Kābul falls into the Indus in the land called Peukelaotis, taking with itself the Malantus, Soastus and Guræus. Peukelaotis represents the Sanskrit **Pushkarāvati**. It formed the western part of the old kingdom of Gandhāra. The people of the surrounding region are sometimes referred to as the "Astakenoi" by historians. The capital is represented by the modern Mīr Ziyārat and Chārsadda, about 17 miles N. E. of Peshāwar, on the Swat river, the Soastus of Arrian, and the Suvāstu of the Vedic texts.

The reigning *hyparch* at the time of Alexander's invasion was Astes⁴ identified with Hasti or Ashtaka. He was defeated and killed by Hephaestion, a general of the Macedonian king.

6. **Taxila** or Takshaśilā (in the Rāwalpindi District):

Strabo says⁵ "between the Indus and the Hydaspes (Jhelum) was Taxila, a large city, and governed by good laws. The neighbouring country is crowded with inhabitants and very fertile." The kingdom of Taxila formed the eastern part of the old kingdom of Gandhāra.

¹ Smith, EHI., 4th ed., p. 57. *Camb. Hist.*, I, p. 353.

² *Invasion of Alexander*, p. 81.

³ Chinnock's *Arrian's Anabasis of Alexander and Indica*, p. 403.

⁴ Chinnock, *Arrian*, p. 228.

⁵ H. and F's. tr., III, p. 90.

In B. C. 327 the Taxilian throne was occupied by a *hyparch*, or *basileus*, whom the Greeks called Taxiles. When Alexander of Macedon arrived in the Kābul valley he sent a herald to the king of Taxila to bid him come and meet him. Taxiles accordingly did come to meet the conqueror, bringing valuable gifts. When he died his son Mophis or Omphis (Sanskrit Āmbhi) succeeded to the government. Curiously enough, the reputed author of the *Kautilya Arthasāstra*, himself a native of Taxila according to the *Mahāvamsa Tīkā*, refers to a school of political philosophers called Āmbhīyas, and Dr. F. W. Thomas connects them with Taxilā.¹

7. The kingdom of **Arsakes** :

The name of the principality represents the Sanskrit **Uraśā** which formed part of the modern **Hazāra** District. It adjoined the realm of Abisares, and was probably, like the latter, an offshoot of the old kingdom of Kamboja. Uraśā is mentioned in several *Kharoshthī* inscriptions, and, in the time of the geographer Ptolemy, absorbed the neighbouring realm of Taxilā.

8. **Abhisāra** :

Strabo observes² that the kingdom was situated among the mountains *above* the Taxilā country. The position of this state was correctly defined by Stein who pointed out that *Dārvābhisāra*³ included the whole tract of the lower and middle hills lying between the Jhelum and the Chenāb. Roughly speaking, it corresponded to the Punch and some adjoining districts in Kāśmīra with a part at least of the Hazāra District of the North-West Frontier Province. It was probably an offshoot of the old kingdom of Kamboja. Abisares, the contemporary of Alexander,

¹ *Bārhaspatya Arthasāstra*, Introduction, p. 16.

H. & F's tr., III, p. 20.

Cf. *Mbh.* VII. 21, 43.

was a shrewd politician of the type of Charles Emanuel III of Sardinia. When the Macedonian invader arrived in Taxila he informed him that he was ready to surrender himself and the land which he ruled. And yet before the battle which was fought between Alexander and the famous Poros, Abisares intended to join his forces with those of the latter.¹

9. The kingdom of the Elder Poros :

This territory lay between the Jhelum and the Chenāb and roughly corresponded to parts of the modern districts of **Guzrāt and Shāhpur**.² Strabo tells us³ that it was an extensive and fertile district containing nearly 300 cities. Diodoros informs us⁴ that Poros had an army of more than 50,000 foot, about 3,000 horse, above 1,000 chariots, and 130 elephants. He was in alliance with Embisaros, *i.e.*, the king of Abhisāra.

Poros probably represents the Sanskrit Pūru or **Paurava**. In the *Ṛig-Veda* the Pūrus are expressly mentioned as on the Sarasvatī. In the time of Alexander, however, we find them on the Hydaspes (Jhelum). The *Bṛihat Samhitā*,⁵ too, associates the 'Pauravas' with 'Madraka' and 'Mālava.' The *Mahābhārata*,⁶ also, refers to a "*Puram Paurava-rakshitam*", city protected by the Pauravas, which lay not far from Kāsmīra. It is suggested in the *Vedic Index*⁷ that either the Hydaspes was the earlier home of the Pūrus, where some remained after the others had wandered east, or the later Pūrus represent a successful onslaught upon the west from the east.

¹ Chinnock, *Arrian*, p. 276. *Inv. Alex.*, 112.

² It apparently included the old territory of Kekaya.

³ H. & F.'s tr., III, p. 91.

⁴ *Invasion of Alexander*, p. 274.

⁵ XIV, 27.

⁶ II, 27, 15-17.

⁷ Vol. II, pp. 12-13.

10. The country of the people called **Glauganikai**¹ (Glauganicians) by Aristobulus, and Glausians by Ptolemy :

This tract lay to the west of the Chenāb and was conterminous with the dominion of Poros.² It included no less than seven and thirty cities, the smallest of which had not fewer than 5,000 inhabitants, while many contained upwards of 10,000.

11. **Gandarīs** (in the Rechna Doāb) :

This little kingdom lay between the Chenāb and the Rāvi and (if Strabo has given the correct name of the territory) probably represented the easternmost part of the old *Mahājanapada* of Gandbāra.³ It was ruled by the Younger Poros, nephew of the monarch who ruled the country between the Jhelum and the Chenāb.

12. The **Adraistai** (in the Bari Doāb) :⁴

They dwelt on the eastern side of the Hydraotes or the Rāvi, and their main stronghold was Pimprama.

13. **Kathaiōi** or Cathaeans (probably also in the Bari Doāb) :

Strabo points out⁵ that "some writers place Cathaia and the country of Sopeithes, one of the *nomarchs*, in the tract between the rivers (Hydaspes and Acesines, *i.e.*, the Jhelum and the Chenāb); some on the other side of the Acesines and of the Hydarotis, *i.e.*, of the Chenāb and the Rāvi, on the confines of the territory of the other Poros, the nephew of Poros who was taken prisoner

¹ With the second part of the name *anika*, troop or army, may be compared that of the *Sauvānikas* of the Gupta period. Dr. Jaysawal, who, doubtless following Weber in *IA*, II (1879), p. 147, prefers the restoration of the name as *Glauchukāyannaka*, does not apparently take note of this fact.

² Chinnock, *Arrian*, p. 276. *Ind. Alex.* 112. The country was subsequently given to the elder Poros to rule.

³ But see *Camb. Hist. Ind.*, I, 370, n. 4; the actual name of the territory in olden times was, however, *Madra*.

⁴ *Adrijas?* *Mbh.*, VII, 159.5.

Yaudheyā Adrijān rājan Madrakān Mālavān api.

⁵ H. & P.'s tr., III, p. 92.

by Alexander.¹ The Kathaioi probably represent the Sanskrit Kaṭha, Kāṭhaka,² Kantha³ or Krātha.⁴ They were the most eminent among the independent tribes dwelling in the area of which the principal centre was Sangala (Sāṅkala). This town was probably situated in the **Gurudāspur** district, not far from Fathgarh.⁴ Anspach locates it at Jandiāla to the east of **Amritsar**.⁵

The Kathaians enjoyed the highest reputation for courage and skill in the art of war. Onesikritos tells us that in Kathaia the handsomest man was chosen as king.⁶

14. The **kingdom of Sophytes** (Saubhūti), probably along the banks of the Jhelum :

In the opinion of Smith, the position of this kingdom is fixed by the remark of Strabo⁷ that it included a mountain composed of fossil salt sufficient for the whole of India; Sophytes was, therefore, according to him, the "lord of the fastness of the Salt Range stretching from the Jhelum to the Indus." But we have already seen that the classical writers agree in placing Sophytes' territory *east of the Jhelum*. Curtius tells us⁸ that the nation ruled by Sopeithes (Sophytes), in the opinion of the "barbarians," excelled in wisdom, and lived under good laws and customs. They did not acknowledge and rear children according to the will of the parents, but as the officers entrusted with the medical inspection of infants might direct, for if they

¹ Jolly, SBE., VII. 16; *Ep. Ind.*, III. 8.

² *Cf.*, Pāṇini, II. 4. 20.

³ Mbh., VIII. 85. 16.

⁴ JRAS., 1903, p. 687.

⁵ *Camb. Hist. Ind.*, I. 371.

⁶ McCrindle, *Ancient India as described in Classical Literature*, p. 38.

⁷ H. & P. 's tr., III, p. 93.

⁸ *Invasion of India by Alexander*, p. 219.

remarked anything deformed or defective in the limbs of a child they ordered it to be killed. In contracting marriages they did not seek an alliance with high birth but made their choice by the looks, for beauty in the children was highly appreciated. Strabo informs us¹ that the dogs in the territory of Sopeithes (Sophytes) were said to possess remarkable courage. We have some coins of Sophytes bearing on the obverse the head of the king, and on the reverse the figure of a cock.² According to Smith the style is suggested probably by the "owls" of Athens. Strabo calls Sophytes a *nomarch* which probably indicates that he was not an independent sovereign, but only a viceroy of some other king.³

15. The kingdom of **Phegelas** or Phegeus (in the Bari Doāb) :

It lay between the Hydraotes (Rāvi) and the Hyphasis (Bias).⁴ The name of the king, Phegelas, probably represents the Sanskrit *Bhagala*—the designation of a royal race of Kshatriyas mentioned in the *Gaṇapāṭha*.⁵

16 The **Siboi** (in the lower part of the Rechna Doāb) :

They were the inhabitants of the Shorkot region in Jhang district below the junction of the Jhelum

¹ H. & F., III, p. 93.

² Whitehead (*Num. Chron.*, 1943, pp. 60-72) rejects the identification of Sophytes with Saubhūti. He thinks that "Saubhūti is a philologist's creation. There is no historical evidence that Saubhūti existed" (p. 63). Subhūti (from which Saubhūti is apparently derived) is a fairly common name in Indian literature. (*The Questions of King Milinda*, Part II, SBE. XXXVI, pp. 315, 323; Geiger, the *Mahāvamsa*, tr., 151n, 275). It is by no means improbable that a Hindu Rajah should strike a piece bearing a Hellenized form of his name, as the Hinduised Scythian rulers did in later ages.

³ Was it the Great King of W. Asia or some Indian potentate? Among other *nomarchs* mention may be made of Spitaces, a nephew and apparently a vassal of the elder Poros (*Camb. Hist. Ind.*, 36, 365, 367).

⁴ *Inv. Alex.*, p. 281, 401.

⁵ *Invasion of Alexander*, p. 401. Cf. *Kramadīśvara*, 769.

and the Chenāb.¹ They were probably identical with the Śiva people mentioned in a passage of the *Rig-Veda*² where they share with the Alinas, Pakthas, Bhalānases, and Viśāṇins the honour of being defeated by Sudās.³ The *Jātakas* mention a Sivi country and its cities Aritṭhapura⁴ and Jetuttara.⁵ It is probable that Śiva, Śivi, Śibi, and Siboi were one and the same people. A place called Śiva-pura is mentioned by the scholiast on Pāṇini as situated in the northern country.⁶ It is, doubtless, identical with Śibipura mentioned in a Shorkot inscription edited by Vogel. In the opinion of that scholar the mound of Shorkot marks the site of this city of the Śibis.⁷

The Siboi dressed themselves with the skins of wild beasts, and had clubs for their weapons.

The *Mahābhārata*⁸ refers to a *rāshṭra* or realm of the Śivis ruled by king Uśīnara, which lay not far from the Yamunā.⁹ It is not altogether improbable that the Uśīnara country¹⁰ was at one time the home of the Śivis. We find them also in Sind, in Madyamikā (Tambavatī nagarī ?) near Chitor in Rājputāna,¹¹ and in the *Daśa-kumāra-charita*, on the banks of the Kāverī.¹²

¹ *Inv. Alex.*, p. 232.

² VII. 18. 7.

³ *Vedic Index*, Vol. II, pp. 381-382. A 'Śaibya' is mentioned in the *Āitareya Brāhmaṇa* (VIII. 23; *Vedic Index*, I. 31).

⁴ *Ummadanti Jātaka*, No. 527; cf. Pāṇini, VI. 2. 100.

⁵ *Vessantara Jātaka*, No. 547. See also *ante*, p. 198, n 6.

⁶ Patañjali, IV, 2. 2; *Ved. Ind.*, II, p. 382. IHQ, 1926, 758.

⁷ *Ep. Ind.*, 1921, p. 16.

⁸ III. 130-131.

⁹ Cf. Siba (Cunn. AGI., revised ed., pp. 160-161).

¹⁰ *Vide* pp. 65, 66 *ante*.

¹¹ Vaidya, *Med. Hind. Ind.*, I, p. 162; *Carm. Lec.*, 1918, p. 173. Allan *Coins of Anc. Ind.* cxxiii.

¹² The southern Śivis are probably to be identified with the Choia ruling family (Kielhorn, *List of Southern Inscriptions*, No. 685).

17. The **Agalassoï** :

This people lived near the Siboi, and could muster an army of 40,000 foot and 3,000 horse.

18. The Sudracæ or **Oxydrakai** :

The accounts of Curtius and Diodoros¹ leave the impression that they lived not far from the Siboi and the Agalassoï, and occupied part of the territory below the confluence of the Jhelum and the Chenāb. At the confluence Alexander garrisoned a citadel and *thence* came into the dominions of the Sudracæ and the Malli (Mālava). The former may have occupied parts of the Jhang and Lyallpur districts. The name of the Sudracæ or the Oxydrakai represents the Sanskrit **Kshudraka**.² They were one of the most numerous and warlike of all the Indian tribes in the Pañjāb. Arrian in one passage refers to the "leading men of their cities and their provincial governors" besides other eminent men. These words afford us a glimpse into the internal condition of this and similar tribes.

19. The **Malloi** :

They seem to have occupied the right bank of the lower Hydraotes (Rāvi) and are mentioned as escaping across that river to a city of the Brāhmaṇas. The Akesines (Chenāb) is said to have joined the Indus in their territory.³ Their name represents the Sanskrit **Mālava**. According to Weber, Āpiśali (according to Jayaswal, Kātyāyana), speaks of the formation of the compound "*Kshaudraka-Mālacāḥ*." Smith points out that the *Mahābhārata* couples the tribes in question as forming

¹ *Ind. Alex.* 233-4. 286-7.

² *Mbh.*, II. 52. 15; VII. 68.9.

³ *Megasthenes and Arrian* (2nd ed.), p. 196. The accuracy of this statement may be doubted. The Malloi territory seems to have included part of the Jhang district, besides a portion of South Lyallpur, West Montgomery, and perhaps North Multan.

part of the Kaurava host in the Kurukshetra war.¹ Curtius tells us² that the Sudrae and the Malli had an army consisting of 90,000 foot soldiers, 10,000 cavalry and 900 war chariots.

Sir R. G. Bhandarkar informs us that Pāṇini refers to the Mālavas as living by the profession of arms.³ In later times they are found in Rājputāna, Avanti and the Mahī valley.

20. The **Abastanoi** :

Diodoros calls them the Sambastai,⁴ Arrian Abastanoi, Curtius Sabarcae, and Orosius Sabagrae. They were settled on the lower Akesines (Chenāb) apparently below the Mālava country, but above the confluence of the Chenāb and the Indus. Their name represents the Sanskrit *Āmbashṭha* or *Ambashṭha*.⁵ The Ambashṭhas are mentioned in several Sanskrit and Pāli works. An Āmbashṭha king is mentioned in the *Aitareya Brāhmaṇa*⁶ whose priest was Nārada. The *Mahābhārata*⁷ mentions the Ambashṭhas along with the Śivis, Kshudrakas, Mālavas and other north-western tribes. The Purāṇas represent them as Ānava Kshatriyas and kinsmen of the Śivis.⁸ In the *Bārhaspatya Arthaśāstra*,⁹ the Āmbashṭha country is mentioned in conjunction with Sind :

Kāśmīra-Hūn-Āmbashṭha-Sindhavaḥ.

¹ *EHI.*, 1914. p. 94n.; *Mbh.*, VI. 59. 135.

² *Invasion of Alexander*, 234.

³ *Ind. Ant.*, 1913, p. 200.

⁴ *Invasion of Alexander*, p. 292.

⁵ Dr. Surya Kānta draws a distinction between *Ambashṭha* and *Ambashṭha*, regarding the former as a place-name, and the latter as the name of a particular class of people, 'an elephant-driver, a Kshatriya, a mixed caste'. (*B. C. Law* Vol. II, pp. 127ff). To us the distinction seems to be based upon philological conjectures.

⁶ VIII. 21.

⁷ II. 52. 14-15.

⁸ Pargiter, *AIHT.*, pp. 108-109.

⁹ Ed. F. W. Thomas, p. 21.

In the *Ambaṭṭha Sutta*,¹ an Ambaṭṭha is called a Brāhmaṇa. In the *Smṛti* literature, on the other hand, Ambashṭha denotes a man of mixed Brāhmaṇa and Vaiśya parentage. According to *Jātaka* IV. 363, the Ambaṭṭhas were farmers. It seems that the Ambashṭhas were a tribe or clan who were at first mainly a fighting race, but some of whom took to other occupations, viz., those of priests, farmers and, according to *Smṛti* writers, physicians (*Ambashṭhānām chikitsitam*).²

In the time of Alexander, the Ambashṭhas were a powerful tribe having a democratic government. Their army consisted of 60,000 foot, 6,000 cavalry and 500 chariots.³

In later times the Ambashṭhas are found in South-Eastern India near the Mekala range, and also in Bihār and possibly in Bengal.⁴

¹ *Dialogues of the Buddha*, Part I, p. 139.

² *Manu*. X. 47. Dr. Surya Kānta suggests the reading (*Low Volume*, II, 134) *cha kṣētinam*. In his dissertation he speaks of the possibility of Ambashṭha being a Sanskritized form of a Celtic word meaning 'husbandman, tiller of the ground'. It is also pointed out that the word may be an exact parallel to 'mahāmātra' inasmuch as 'ambhaṣ' means 'of large measure', 'an elephant', so that Ambashṭha would mean 'one sitting on the elephant', i.e., a driver, a keeper, a sāmānta, or a Kshatriya. They lived on warfare, presumably as *guḍārohas*, and banner-bearers.

A distinction is drawn between Ambashṭha and Ambashṭha. The last-mentioned expression is considered to be a place-name, based on the plant name Amba. For other notes on the subject see Prabāsi, 1951 B. S. I, 206; *JUPHS*, July-Dec., 1945, pp. 148 ff; *History of Bengal* (D. U.), pp. 568 ff.

³ *Invasion of Alexander*, p. 262.

⁴ Cf. Ptolemy, *Ind. Ant.*, XIII, 361; *Bṛhat Saṁhitā*; XIV. 7; *Mekhalā-mushṭha* of *Mārkaṇḍeya P.*, LVIII. 14, is a corruption of *Mekalā-Ambashṭha*. Cf. also the Ambashṭha Kāyasthas of Bihār, the Gauḍa Ambashṭha of the *Surjan-Charita* (*DHNI*, II. 1061 n^o) of the time of Akbar, and the Vaidyas of Bengal whom Bharata Mallika classes as Ambashṭha. This is not the place to discuss the authenticity or otherwise of the tradition recorded by Bharata and some of the Purāṇas. The origin of the Vaidyas, or of any other caste in Bengal, is a thorny problem which requires separate treatment. What the author aims at in these pages is to put some available evidence, early or late, about the Abastacoi. That some Ambashṭhas, and Brāhmaṇas too, took to the medical profession is clear from the evidence of *Manu* and

21-22. The **Xathroi** and the **Ossadioi**

The Xathroi are according to McCrindle¹ the **Kshatri** of Sanskrit literature mentioned in the Laws of Manu as an impure tribe, being of mixed origin. V. de Saint-Martin suggests that in the Ossadioi we have the **Vasāti** of the *Mahābhārata*,² a tribe associated with the Śibis and Sindhu-Sauvīras of the Lower Indus Valley.³ Like the Abastanoi, the Xathroi and the Ossadioi seem to have occupied parts of the territory drained by the lower Akesines (Chenāb) and situated between the confluence of that river with the Rāvi and the Indus respectively.

23-24. The **Sodrai** (sogdoi) and the **Massanoi**:

They occupied Northern Sind with contiguous portions of the Pañjāb (Mithan-koṭ area) and the Babawalpur state, below the confluence of the Pañjāb rivers. The territories of these two tribes lay on opposite banks of the Indus. The Sodrai are the **Sūdra** tribe of Sanskrit literature, a people constantly associated with the Ābhiras who were settled near the Sarasvatī.⁴ Their royal seat (*basileion*) stood on the Indus. Here another Alexandria was founded by the Macedonian conqueror:

Atri (*Samhitā*, 378) and Bopadev. It is equally clear that the Vaidya problem cannot be solved in the way it has been sought to be done in some recent publications. Due attention should be given to historical evidence bearing on the point like that of Megasthenes and of certain early Chalukya, Pāṇḍya, and other epigraphs, e.g. the Talamañchi plates, *Ep. Ind.* IX 101; Bhandarker's List 1371, 2061, etc.

¹ *Invasion of Alexander*, p. 156 n.

² VII. 19. 11; S9. 37; VIII. 44 99.

³ "Abhishāhaḥ Sūrasenāḥ Sivayo'tha Vaśātayaḥ" (*Mbh.*, VI. 106. 8).

"Vaśāti Sindhu-Sauvīrā itiprāyo' tikutsitāḥ."

"Gāndhārāḥ Sindhu-Sauvīrāḥ Sivayo'tha Vaśātayaḥ" (*Mbh.*, VI. 51 14)

⁴ *Paṭaṅjali*, 1.2.3; *Mbh.*, VII. 19.6; IX. 37. 1.

25. The kingdom of **Mousikanos**.¹

This famous state included a large part of modern Sind. Its capital has been identified with Alor in the **Sukkur** district. The characteristics of the inhabitants of the realm of Mousikanos as noticed by Strabo are given below:²

"The following are their peculiarities; to have a kind of Lacedæmonian common meal, where they eat in public. Their food consists of what is taken in the chase. They make no use of gold nor silver, although they have **mines of these metals**. Instead of slaves, they employed youths in the flower of their age, as the Cretans employ the Aphamiotæ, and the Lacedæmonians the Helots. They study no science with attention but that of *medicine*;³ for they consider the excessive pursuit of some arts, as that of war, and the like to be committing evil. There is no process at law but against murder and outrage, for it is not in a person's own power to escape either one or the other; but as contracts are in the power of each individual, he must endure the wrong, if good faith is violated by another; for a man should be cautious whom he trusts, and not disturb the city with constant disputes in courts of justice."

From the account left by Arrian it appears that the "Brachmans," i.e., the Brāhmanas exercised considerable influence in the country. They were the instigators of a revolt against the Macedonian invader.⁴

¹ Bevan in *Comb. Hist. Ind.* p. 377, following Lassen (*Ins. Alex.* 157 n) restores the name as Mūshika. Dr. Jayaswal in his *Hindu Polity* suggests Muchukarṇa. Cf. *Manahikāra* (*Patanjali*, IV. 1. 4).

² H. & P. III. p. 96.

³ This trait they shared with the Ambashthas (*of. Manu*, X. 47).

⁴ Chinnock, *Arrian*, p. 310. Cf. Strabo, xv. i. 66,—"Nearchos says that the Brachmans engage in the affairs of the state and attend the king as councillors,"

26. The principality of **Oxykanos** :

Curtius calls the subjects of Oxykanos the Praesti (**Proshthas** ?).¹ Oxykanos himself is styled both by Strabo and Diodoros Portikanos. Cunningham places his territory to the west of the Indus in the level country around **Larkhāna**.²

27. The principality of **Sambos** :³

Sambos was the ruler of a *mountainous country* adjoining the kingdom of Mousikanos, with whom he was at feud. His capital, called Sindimāna, has been identified, with little plausibility, with Sehwan, a city on the Indus.⁴ According to Diodoros 'a city of the Brāhmaṇas' (Brāhmaṇavāṭa ?) had to be stormed whilst the operations against Sambos were going on.⁵

28. **Patalene** :

It was the Indus delta, and took its name from the capital city, Patala probably near the site of Bahmaṇābād.

Diodoros tells us⁶ that Tauala (Patala) had a political constitution drawn on the same lines as the Spartan; for in this community the command in war was vested in two hereditary kings of different houses, while a Council of Elders ruled the whole state with paramount authority. One of the kings in the time of Alexander was called **Moeres**.⁷

The states described above had little tendency to unity or combination. Curtius tells us⁸ that Āmbhi, ruler of

¹ *Mbh.*, VI. 9. 61.

² *Invasion of Alexander*, p. 153; *AGI*, Revised ed. 300.

³ Sambhu, according to Beron (*Camb. Hist. Ind.*, 377). Sām̐ba is a possible alternative.

⁴ McCrindle, *Invasion of Alexander*, p. 404; *AGI*, Revised ed., 302 f.

⁵ *Diod.* XVII. 163, 1; cf. *Alberuni* (I. 316; II. 262).

⁶ *Inv. Alex.*, p. 296.

⁷ *Inv. Alex.*, p. 256, cf. **Maurya**.

⁸ *Inv. Alex.*, p. 202.

Taxila, was at war with Abisares and Poros. Arrian informs us that Poros and Abisares were not only enemies of Taxila but also of the neighbouring autonomous tribes. On one occasion the two kings marched against the Kshudrakas and the Mālavas.¹ Arrian further tells us that the relations between Poros and his nephew were far from friendly. Sambos and Mousikanos were also on hostile terms. Owing to these feuds and strifes amongst the petty states, a foreign invader had no united resistance to fear; and he could be assured that many among the local chieftains would receive him with open arms out of hatred for their neighbours.

The Nandas of Magadha do not appear to have made any attempt to subjugate these states of the *Uttarāpatha* (North-West India). The task of reducing them was reserved for a foreign conqueror, *viz.*, Alexander of Macedon. The tale of **Alexander's conquest** has been told by many historians including Arrian, Q. Curtius Rufus, Diodoros Siculus, Plutarch and Justin. We learn from Curtius that Scythians and Dahae served in the Macedonian army.² The expedition led by Alexander was thus a combined Saka-Yavana enterprise. The invader met with no such general confederacy of the native powers like the one formed by the East Indian states against Kūpika-Ajātaśatru. On the contrary he obtained assistance from many important chiefs like Āmbhi of Taxila, Sangæus (Sañjaya ?) of Pushkarāvati, Kopbaïos or Cophæus (of the Kābul region ?), Assagetes (Aśvajit ?), and Sisikottos (Śaśīgupta) who got as his reward the satrapy of the Assakenians.³ The only princes or peoples who thought of combining against the invader were Poros and Abisares, and the Mālavas (Malloi), Kshudrakas

¹ Chinnock, *Arrian*, p. 279.

² *Inv. Alex.*, p. 208.

³ *Inv. Alex.*, p. 112.

(Oxydrakai), and the neighbouring autonomous tribes. Even in the latter case personal jealousies prevented any effective results. Alexander met with stubborn resistance from individual chiefs and clans, notably from Astes (Hastī or Ashtaka ?), the Aspasians, the Assakenians, the elder Poros, the Kathaians, the Malloi, the Oxydrakai, and the Brāhmanas of the kingdom of Mousikanos. Massaga, the stronghold of the Assakenians, was stormed with great difficulty, Poros was defeated on the banks of the Hydaspes (B.C. 326), the Malloi and the Oxydrakai were also no doubt crushed. But Alexander found that his Indian antagonists were different from the effete troops of Persia. Diodoros informs us that at Massaga, where Alexander treacherously massacred the mercenaries, "the women, taking the arms of the fallen, fought side by side with the men."¹ Poros, when he saw most of his forces scattered, his elephants lying dead or straying riderless, did not flee—as Darius Codomannus had twice fled—but remained fighting, seated on an elephant of commanding height, and received nine wounds before he was taken prisoner.² The Malloi almost succeeded in killing the Macedonian king. But all this was of no avail. A disunited people could not long resist the united forces of the Hellenic world led by the greatest captain of ancient Europe. Alexander succeeded in conquering the old Persian Provinces of Gandhāra and "India," but was unable to try conclusions with Agrammes king of the Gangaridæ and the Prasii, i.e., the last Nanda king of Magadha and the other Gangetic provinces in Eastern India. Plutarch informs us that the battle with Poros depressed the spirits of the Macedonians and made them very unwilling to advance further into India. Moreover, they were afraid of the "Gandaritai and the Praisinai" who

¹ *Ine. Alex.*, p. 270

² *Cf. Bury, History of Greece for Beginners*, pp. 428-29.

were reported to be waiting for Alexander with an army of 80,000 horse, 200,000 foot, 8,000 war-chariots and 6,000 fighting elephants. As a matter of fact when Alexander was retreating through Karmania he received a report that his satrap Philippos, governor of the Upper Indus Province, had been murdered (324 B.C.). Shortly afterwards the Macedonian garrison was overpowered. The Macedonian governor of the Lower Indus satrapy had to be transferred to the north-west borderland beyond the Indus and no new satrap was appointed in his place. The successors of Alexander at the time of the Triparadeisos agreement in 321 B.C., confessed their inability to remove the Indian Rājās of the Pañjāb without royal troops under the command of some distinguished general. One of the Rājās, possibly Poros, was treacherously slain by Endemos, an officer stationed in the Upper Indus satrapy. The withdrawal of the latter (cir. 317 B.C.) marks the ultimate collapse of the first serious attempt of the *Yavanas* to establish an empire in India.

The only permanent **effect of Alexander's raid** seems to have been the establishment of a number of *Yavana* settlements in the *Uttarāpatha*. The most important of these settlements were :

1. The city of Alexandria (modern Charikar or Opian ?)¹ in the land of the Paropanisadae, i.e., the Kābul region.
2. Boukephala, possibly on the east side of the Hydaspes (Jhelum).
3. Nikaia, where the battle with Poros took place,
4. Alexandria at or near the confluence of the Chenāb and the Indus, to the north-east of the countries of the Sodrai, or Sogdoi, and Massanoi, and

¹ According to Tarn (*The Greeks in Bactria and India*, 1st. ed., 492) Alexandria stood on the west bank of the united Panjabir-Ghorband rivers near the confluence facing Kapisa on the east bank. It is represented by the modern Begram.

5. Sogdian Alexandria,¹ below the confluence of the Pañjāb rivers.

Aśoka recognised the existence of Youa (Yavana) settlers on the north-western fringe of his empire, and appointed some of them, (*e.g.*, the Yavana-rāja Tushāspha)² to high offices of state. Boukephala Alexandria flourished as late as the time of the *Periplus of the Erythraean Sea*.³ One of the Alexandrias (Alasanda) is mentioned in the *Mahāvamśa*.⁴

Alexander's invasion produced one indirect result. It helped the cause of Indian unity by destroying the power of the petty states of north-west India, just as the Danish invasion contributed to the union of England under Wessex by destroying the independence of Northumbria and Mercia. If Ugrasena-Mahāpadma was the precursor of Chandragupta Maurya in the east, Alexander was the forerunner of that emperor in the north-west.

¹ *Inv. Alex.*, pp. 298, 351; Bury, *History of Greece for Beginners*, p. 433; *Camb. Hist. Ind.*, I. 376f.

² For the nationality of Tushāspha and significance of the term "Yavana," see Raychaudhuri, *Early History of the Vaishnava Sect*, 2nd Ed., pp. 28f, 314 *post*.

³ Schoff's tr., p. 41.

Giger's tr., p. 194.

CHAPTER IV. THE MAURYA EMPIRE : THE ERA OF DIGVIJAYA

SECTION I. THE REIGN OF CHANDRAGUPTA MAURYA.

*Mlechchhairudvejyamānā bhujayugamadhunā
saṁśritā rājamūrtteḥ
Sa śrīmadbandhubhṛtyaśchiramavatu mahīm
pārthicaś-Chandraguptaḥ.
—Mudrārākṣasa.*

In B.C. 326 the flood of Macedonian invasion had overwhelmed the Indian states of the Pañjāb, and was threatening to burst upon the *Madhyadeśa*. Agrammes was confronted with a crisis not unlike that which Arminius had to face when Varus carried the Roman Eagle to the Teutoburg Forest, or which Charles Martel had to face when the Saracens carried the Crescent towards the field of Tours. The question whether India was, or was not, to be Hellenized awaited decision.

Agrammes was fortunate enough to escape the onslaught of Alexander. But it is doubtful whether he had the ability or perhaps the inclination to play the part of an Arminius or a Charles Martel, had the occasion arisen. But there was at this time another Indian who was made of different stuff. This was Chandragupta, the Sandrokoptos (Sandrokottos, etc.) of the classical writers. The **rise of Chandragupta** is thus described by Justin :¹

“India after the death of Alexander had shaken, as it were, the yoke of servitude from its neck and put his governors to death. The author of this liberation was

Sandrocottus. This man was of humble origin, but was stimulated to aspire to regal power by supernatural encouragement; for, having offended Alexander¹ by his boldness of speech and orders being given to kill him, he saved himself by swiftness of foot; and while he was lying asleep, after his fatigue, a lion of great size having come up to him, licked off with his tongue the sweat that was running from him and after gently waking him, left him. Being first prompted by this prodigy to conceive hopes of royal dignity he drew together a band of robbers,² and solicited the Indians to support his new sovereignty.³ Sometime after, as he was going to war with the generals of Alexander, a wild elephant of great bulk presented itself before him of its own accord and, as if tamed down to gentleness, took him on its back and became his guide in the war and conspicuous in fields of battle. Sandrocottus thus acquired a throne when Seleucus was laying the foundations of his future greatness.”

The above account, shorn of its marvellous element, amounts to this, that Chandragupta, a man of non-monarchical rank, placed himself at the head of the

¹ Some modern scholars propose to read 'Nandrum' (Nanda) in place of 'Alexandrum.' Such conjectural emendations by modern editors often mislead students who have no access to original sources and make the confusion regarding the early career of Chandragupta worse confounded (*cf.* *Indian Culture*, Vol. II. No. 3, p. 538; for 'boldness of speech', *cf.* Grote XII. 141, case of Kleitus, and pp. 147 ff., case of Kallisthenes)

² The original expression used by Justin has the sense of 'mercenary soldier' as well as that of 'robber'. And the former sense is in consonance with Indian tradition recorded by Hemachandra in the *Parīśiṣṭaparacan* (VIII, 233-54):

*Dhāturādopārjitena diantipēno Chaqiprasūh
chakrepattiyādi sāmāgrīn Nandamuchchhettumadyatah.*

i.e., Chāpakya gathered for Chandragupta an army with wealth found underground, (lit. 'with the aid of mineralogy') for the purpose of uprooting Nanda.

³ According to the interpretation accepted by Hultzsch—'instigated the Indians to overthrow the existing government.'

Indians who chafed under the Macedonian yoke, and after Alexander's departure defeated his generals and "shook the yoke of servitude from the neck" of India. The verdict of the Hydaspes was thus reversed.¹

The ancestry of Chandragupta is not known for certain. Hindu literary tradition connects him with the Nanda dynasty of Magadha.² Tradition recorded in Mediaeval inscriptions, however, represents the Maurya family (from which he sprang) as belonging to the solar race.³ From Māndhātṛi, a prince of that race, sprang the Maurya line." In the *Rājputāna Gazetteer*,⁴ the Moris (Mauryas) are described as a Rājput clan. Jaina tradition recorded in the *Paṇḍitaśāstra*⁵ represents Chandragupta as the son of a daughter of the chief of a village of peacock-tamers (*Mayūra-*

¹ The anti-Macedonian movement led by Chandragupta, and those who co-operated with him, probably began in Sind. The Macedonian Satrap of that province withdrew before 321 B.C. Ambhi and the Paurava remained in possession of portions of the Western and Central Panjāb and some adjoining regions till sometime after the Triparadeisos agreement of 321 B.C.

² The *Mudrārākṣasa* calls him not only *Mauryaputra* (Act II, verse 6) but also *Nandānaya* (Act IV). Kāśhemendra and Somadeva refer to him as *Pāṇananda-sūta*, son of the genuine Nanda, as opposed to Yoga-Nanda. The commentator on the *Viṣṇu Purāṇa* (IV, 24—Wilson IX, 187) says that Chandragupta was the son of Nanda by a wife named Murā, whence he and his descendants were called Mauryas. Dhuggirāja, the commentator on the *Mudrārākṣasa*, informs us on the other hand that Chandragupta was the eldest son of Maurya who was the son of the Nanda king Sarrvārthasiddhi by Murā, daughter of a *Vṛishala* (Sūdra?).

³ *Ep. Ind.*, II, 222. The *Mahāvamsa* also connects the Mauryas with the Sākya who, as is well-known, claimed to belong to the race of Aditya (the Sun). Cf. also *Avadānakalpalatā*, No. 59.

⁴ II A, the *Mewar Residency*, compiled by Major K. D. Erskine (p. 14).

⁵ Page 56; VIII, 229f.

poshaka).¹ The *Mahāvamsa*² calls him a scion of the *Khattiya* clan styled *Moriya* (Maurya). In the *Divyāvadāna*³ Bindusāra, the son of Chandragupta, claims to be an anointed Kshatriya, *Kshatriya Mūrdhābhishikta*. In the same work⁴ Aśoka, the son of Bindusāra, calls himself a Kshatriya. In the *Mahāparinibbāna Sutta*⁵ the *Moriyas* are represented as the ruling clan of Pipphalivana, and as belonging to the Kshatriya caste. As the *Mahāparinibbāna Sutta* is the most ancient of the works referred to above, and forms part of the early Buddhist canon, its evidence should be preferred to that of later compositions. It is, therefore, practically certain that Chandragupta belonged to a Kshatriya community, viz., the *Moriya* (Maurya) clan.

In the sixth century B. C. the *Moriyas* were the ruling clan of the little republic of Pipphalivana which probably lay between Rummindei in the Nepalese Tarai and Kasia in the Gorakhpur district. They must have been absorbed into the Magadhan empire along with the other states of Eastern India. Tradition avers that they were reduced to great straits in the fourth century B. C., and young Chandragupta grew up among peacock-tamers, herdsmen and hunters in the Vindhyan forest. The classical notices of his encounter with a lion and an

¹ Buddhist tradition also testifies to the supposed connection between the expressions *Moriya* (Maurya) and *Mora* or *Mayūra* (peacock)—see Turnour, *Mahāvamsa* (Mahāwansa), xxxix f. Achen informs us that tame peacocks were kept in the parks of the Maurya Palace at Pataliputra. Sir John Marshall points out that figures of peacocks were employed to decorate some of the projecting ends of the architraves of the east gateway at Sāñchi (*A Guide to Sāñchi*, pp. 44, 62). Foucher (*Monuments of Sanchi*, 231) does not regard these birds as a sort of hereditary badge for the dynasty of the Mauryas. He apparently prefers to imagine in them a possible allusion to the *Mora Jataka*.

² Geiger's Translation, p. 27. *Moriyānaṃ Khattiyaṇaṃ vaṃsa jāta*.

³ Cowell and Neil's Ed., p. 370.

⁴ Page 409.

⁵ *SBE*. XI, pp. 134-135.

elephant accord well with his residence amidst the wild denizens of that sequestered region. During the inglorious reign of Agrammes, when there was general disaffection amongst his subjects, the Moriyas evidently came into prominence, probably under the **leadership of Chandragupta**. These clansmen were no longer rulers and were merely Magadhan subjects. It is, therefore, not at all surprising that Justin calls Chandragupta a man of humble origin. Plutarch, as well as Justin, informs us that Chandragupta paid a visit to Alexander. Plutarch says¹ "Androkottus himself, who was then a lad, saw Alexander himself and afterwards used to declare that Alexander might easily have conquered the whole country, as the then king was hated by his subjects on account of his mean and wicked disposition." From this passage it is not unreasonable to infer that Chandragupta visited Alexander with the intention of inducing the conqueror to put an end to the rule of the tyrant of Magadha. His conduct may be compared to that of Rānā Saṁgrāma Siṁha who invited Bābur to put an end to the *regime* of Ibrāhim Lūdi.² Apparently Chandragupta found Alexander as stern a ruler as Agrammes, for we learn from Justin that the Macedonian king did not scruple to give orders to kill the intrepid Indian lad for his boldness of speech.³ The young Maurya apparently thought of ridding his country of both the oppressors, Macedonian as well as Indian. With the help of Kauṭilya, also called Chāṇakya or Viṣṇugupta, son of a Brāhmaṇa of Taxila, he is said to have over-

¹ *Life of Alexander* lxii.

² Regarding the conduct of Saṁgrāma Siṁha, see Tod's *Rājasthān*, Vol. I, p. 240, n (2). Anne Susannah Beveridge, the *Bābur-nāma in English*, Vol. II, p. 529.

³ As already stated the substitution of 'Nanda' for Alexander cannot be justified.

thrown the infamous Nanda. Traditional accounts of the conflict between Chandragupta and the last Nanda are preserved in the *Milindapañho*, the *Purāṇas*, the *Mudrārākshasa*, the *Mahāvamśa Tīkā* and the *Jaina Pariśiṣṭaparvan*. The *Miliadapañho*¹ tells us that the Nanda army was commanded by Bhaddasāla. The Nanda troops were evidently defeated with great slaughter, an exaggerated account of which is preserved in the *Milindapañho*.

"Sometime after" his acquisition of sovereignty, Chandragupta went to war with the prefects or generals of Alexander² and crushed their power.

The overthrow of the Nandas, and the liberation of the *Pañjāb* were not the only achievements of the great Maurya. Plutarch tells us³ that he overran and subdued the whole of India with an army of 600,000 men. Justin also informs us that he was "in possession of India." In his *Beginnings of South Indian History*,⁴ Dr. S. Krishnaswami Aiyangar says that Māmulanār, an ancient Tamil author, makes frequent allusions to the Mauryas in the past having penetrated with a great army as far as the Podiyil Hill in the Tinnevely district. The statements of this author are said to be supported by Parapar or Param Korranār and Kallil Āttiraiyanār. The advanced party of the invasion was composed of a warlike people called Kośar. The invaders advanced from the Koṅkan, passing the hills Elilmalai, about sixteen miles north of Cannanore, and entered the Kongu (Coimbatore) district, ultimately going as far as the Podiyil Hill (Malaya?).

¹ SBE., Vol. XXXVI, p. 147.

² Cf. Smith, *Aśoka*, third edition, p. 14n. For the relative date of the assumption of sovereignty and the war with the prefects see *Indian Culture*, II. No 3, pp. 559ff, *Age of the Nandas and Mauryas*, p. 137.

³ Alex. LXII.

⁴ Chap. II, cf. *JRAS*, 1924, 666.

⁵ For the Kośar see *Indian Culture*, I, pp. 97 ff. Cf. Kośakāra, ANM. 251 ff.

Unfortunately the name of the Maurya leader is not given. But the expression *Vamba Moriyar*, or Maurya upstarts,¹ would seem to suggest that the first Maurya, i.e., Chandragupta, and his adherents were meant.²

Certain Mysore inscriptions refer to Chandragupta's rule in North Mysore. Thus one epigraph says that Nāgarkhaṇḍa in the Shikārpur Tāluq was protected by the wise Chandragupta, "an abode of the usages of eminent Kshatriyas."³ This is of the fourteenth century and little reliance can be placed upon it. But when the statements of Plutarch, Justin, Māmulanār, and the Mysore inscriptions referred to by Rice, are read together, they seem to suggest that the first Maurya did conquer a considerable portion of trans-Vindhyan India.

Whatever we may think of Chandragupta's connection with Southern India, there can be no doubt that he pushed his conquests as far as Surāshtra in Western India. The Junāgaḍh Rock inscription of the *Mahākshatrapa* Rudradāman refers to his *Rāshṭriya* or High

¹ *Beginnings of South Indian History*, p. 99. Cf. *Maurye nava rājani* (*Mudrārākhasa*, Act IV).

² Barnett suggests (*Camb. Hist. Ind.*, I, 596) that the 'Vamba Moriyar' or 'Bastard Mauryas' were possibly a branch of the Kōṅkanī Mauryas. But there is hardly any genuine historical record of the penetration of the Mauryas of the Kōṅkan deep into the southern part of the Tamil country. For other suggestions, see *JRAS.*, 1929, pp. 93-96. Some Tamil scholars hold that "the Moriyar were not allowed to enter Tamilakam, and the last point they reached was the Venkaṭa hill" (*IHQ.*, 1928, p. 146). They also reject Dr. Aiyangar's statement about the Kōṣar. But the view that the arms of Chandragupta possibly reached the Pāṇḍya country in the Far South of India which abounded in pearls and gems receives some confirmation from the *Mudrārākhasa*, Act, III, verse 19, which suggests that the supremacy of the first Maurya eventually extended "from the lord of mountains (the Himalayas), cooled by showers of the spray of the divine stream (Ganges) playing about among its rocks, to the shores of the southern ocean (Dakṣiṇārpaṇa) marked by the brilliance of gems flashing with various colours". The description, however, may be purely conventional. Prof. N. Sastri is critical of the account in the Tamil texts (*ANM*, p. 263f).

³ Rice, *Mysore and Coorg from the Inscriptions*, p. 19. Fleet, however, is sceptical about the Jain tradition (*Ind. Ant.* 1892, 166 ff.). Cf. also *JRAS.* 1911, 814-17.

Commissioner, Pushyagupta, the Vaiśya, who constructed the famous Sudarśana Lake.¹

Reference has already been made to an Aramaic Inscription from Taxila which mentions the form *Priyadarśana*, a well-known epithet of Aśoka Maurya. But it is well to remember that in the *Mudrārākshasa* *Piadamśana* is used as a designation of Chandasiri or Chandragupta himself.² Further, in Rock Edict VIII of Aśoka, his ancestors, equally with himself, are styled *Devānampiya*. It is, therefore, not unreasonable to conclude that, like his famous grandson, Chandragupta, too, was known as 'Devānampiya Piyadasi' (or 'Priyadarśana'), and it is not always safe to ascribe all epigraphs that make mention of Priyadarśana, irrespective of their contents, to Aśoka the Great.

The Seleukidan War.

We learn from Justin³ that when Chandragupta acquired his throne in India Seleukos (Seleucus), a general of Alexander, was laying the foundations of his future greatness. Seleukos was the son of Antiochos, a distinguished general of Philip of Macedon, and his wife Laodike. After the division of the Macedonian Empire among the followers of Alexander he carried on several wars in the east. He first took Babylon,⁴ and then his

¹ The subjugation of the whole of Northern India (*Udichi*) from the Himālayas to the sea is probably suggested by the following passage of the *Kauṭīliya Arthaśāstra* (IX, 1: traditionally ascribed to a minister of Chandragupta: "*Deśaḥ Pṛithivī; tasyāṁ Himavat Samudrāntaram Udichinam yojanasa-hasra parimānam atiriyak Chakravartī-Kshetram.*" Cf. *Mudrārākshasa*, Act III, Verse 19.

² Act VI.

³ Watson's tr., p. 141.

⁴ Seleukos obtained the satrapy of Babylon first after the agreement of Triparadeisos (321 B.C.) and afterwards in 312 B.C. from which year his era is dated. In 306 B.C. he assumed the title of king (*Camb. Anc. His.*, VII, 161; *Camb. Hist. Ind.*, I, 433).

strength being increased by this success, subdued the Bactrians. He next made an expedition into India. Appianus says¹ that he crossed the Indus and waged war on Chandragupta, king of the Indians, who dwelt about it, until he made friends and entered into relations of marriage² with him. Justin also observes that after making a league with Chandragupta, and settling his affairs in the east, Seleukos proceeded to join in the war against Antigonos (301 B. C.). Plutarch supplies us with the information that Chandragupta presented 500 elephants to Seleukos. More important details are given by Strabo who says :³

"The Indians occupy (in part) some of the countries situated *along the Indus*, which formerly belonged to the Persians: Alexander deprived the Ariani of them, and established there settlements (or provinces) of his own. But Seleucus Nicator gave them to Sandrocottus in consequence of a marriage contract, and received in turn 500 elephants." "The Indians occupied *a larger portion of Ariana*, which they had received from the Macedonians."⁴

It will be seen that the classical writers do not give us any detailed record of the actual conflict between Seleukos and Chandragupta. They merely speak of the results. There can be no doubt that the invader could not make much headway, and concluded an alliance which was cemented by a marriage contract. In his *Asoka*⁵ Dr. Smith observes that the current notion that the Syrian

¹ *Syr. 55; Ind. Ant.*, Vol. VI, p. 114, Hultsch, xxxiv.

² Appianus uses the clear term *kedos* (connection by marriage), and Strabo (XV) only an *epigamia*. The cession of territory in consequence of the marriage contract clearly suggests that the wedding did take place.

³ *H & F.*, III, p. 125.

⁴ *Ibid.*, p. 78. Tarn, *Greeks in Bactria and India*, 100.

⁵ *Third Ed.*, p. 15.

king 'gave his daughter in marriage' to Chandragupta is not warranted by the evidence, which testifies merely to a 'matrimonial alliance.' But the cession of territory "in consequence of the *epigamia*" may rightly be regarded as a dowry given to a bridegroom. The Indian Emperor obtained some of the provinces situated along the Indus which formerly belonged to the Persians. The ceded country comprised a *large portion of Ariana* itself, a fact ignored by Tarn. In exchange the Maurya monarch gave the "comparatively small recompense of 500 elephants". It is believed that the territory ceded by the Syrian king included the four satrapies: Aria, Arachosia, Gedrosia and the Paropanisadaï, *i.e.*, Herat, Kandahâr, Makrân and Kābul. Doubts have been entertained about this by several scholars including Tarn. The inclusion of the Kābul valley within the Maurya Empire is, however, proved by the inscriptions of Aśoka, the grandson of Chandragupta, which speak of the Yonas and Gandhāras as vassals of the Empire. And the evidence of Strabo probably points to the cession by Seleukos of a large part of the Iranian Tableland besides the riparian provinces on the Indus.

Megasthenes

We learn from the classical writers that after the war the Syrian and Indian Emperors lived on friendly terms. Athenaios tells us that Chandragupta sent presents including certain powerful aphrodisiacs to the Syrian monarch.¹ Seleukos sent an envoy to the Maurya court, whose name was Megasthenes. Arrian tells

¹ *Inv. Alcx.*, p. 405. Cf. Smith, *EHI*, 4th ed., p. 153. The treaty between Chandragupta and Selenkos ushered in a policy of philhellenism which bore fruit in the succeeding reigns. In the days of Bindusāra and Aśoka there was not only an exchange of embassies with the Hellenistic powers of the West, but the services of Greek philosophers and administrators were eagerly sought by the imperial government.

us¹ that Megasthenes originally lived with Sibyrtios, the satrap of Arachosia. He was sent from thence to Pāṭaliputra where he often visited the Maurya Emperor, and wrote a history on Indian affairs. The work of Megasthenes has been lost. The fragments that survive in quotations by later authors like Strabo, Arrian, Diodoros and others, have been collected by Schwanbeck, and translated into English by McCrindle. //As Professor Rhys Davids observes, Megasthenes possessed very little critical judgment, and was, therefore, often misled by wrong information received from others. But he is a truthful witness concerning matters which came under his personal observation. ✓The most important piece of information supplied by him is, as Rhys Davids pointed out, the **description of Pāṭaliputra** which Arrian quotes in Chapter X of his *Indica* :

“The largest city in India, named Palimbothra, is in the land of the Prasians, where is the confluence of the river Erannobaos² and the Ganges, which is the greatest of rivers. The Erannobaos would be third of the Indian rivers Megasthenes says that on the side where it is longest this city extends 80 *stades* ($9\frac{1}{2}$ miles) in length, and that its breadth is fifteen ($1\frac{3}{4}$ miles); that the city has been surrounded with a ditch in breadth 6 *plethra* (606 feet), and in depth 30 cubits; and that its wall has 570 towers and 64 gates.”³

There were many other cities in the empire besides Pāṭaliputra. Arrian says, “It would not be possible to record with accuracy the number of the cities on account of their multiplicity. Those which are situated

¹ Chincock's tr., p. 254.

² Erannobaos = Hiraṇyavāha, i.e., the Soṇa (*Harshacharita*, Pārab's ed., 1918, p. 19). Cf. “*Anuśaṅgam Pāṭaliputram*” (Patañjali, II, 1.12). For references to “Pāṭaliputra in a Tamil classic” see Aiyangar Com. Vol. 355 ff.

³ Cf. Patañjali, IV. 3.2: “Pāṭaliputrakāḥ prāsādāḥ Pāṭaliputrakāḥ prākāśā itī.”

near the rivers or the sea are built of wood : for if they were built of brick they could not long endure on account of the rain and because the rivers overflowing their banks fill the plains with water. But those which have been founded in commanding places, lofty and raised above the adjacent country, are built of brick and mortar." The most important cities of Chandragupta's empire besides the metropolis, were Taxila, Ujjain, Kauśāmbī and possibly Puṇḍranagara.¹

Ælian gives the following account of the **palace of Chandragupta**. "In the Indian royal palace² where the greatest of all the kings of the country resides, besides much else which is calculated to excite admiration, and with which neither Susa, nor Ekbatana can vie (for, methinks, only the well-known vanity of the Persians could prompt such a comparison³), there are other wonders besides. In the parks tame peacocks are kept, and pheasants which have been domesticated; there are shady groves and pasture ground planted with trees, and branches of trees which the art of the woodsman has deftly interwoven; while some trees are native to the soil, others are brought from other parts, and with their beauty enhance the charms of the landscape. Parrots

¹ Puṇḍranagara has been identified with Mahāsthānagarh in the Bogra District of Bengal. The identification seems to be confirmed by an inscription, written in early Mauryan Brāhmī character, which has been discovered at Mahāsthāna. The record makes mention of *Puṇḍanagara* and its storehouse filled with coins styled *Gaṇḍakas*, *Kākanikas*, etc. and refers to a people called *Saṭvargikas*. (Barua, *IHQ*, 1934, March, 57 ff; D. R. Bhandarkar, *Ep. Ind.*, April, 1931, 83 ff; P. C. Sen, *IHQ*, 1933, 722 ff.) Dr. Bhandarkar reads *Sa(m)va(m)giya* in the place of *Saṭvargika* which is more plausibly suggested by Dr. Barua. If the record really belongs to the early Maurya period the reference to coins is interesting. Dr. K. P. Jayaswal thinks that coins of the Maurya age bear certain symbols that can be recognized (cf. *JRAS*, 1936, 437 ff.).

² The "*Sugāṅga*" palace was the favourite resort of Chandragupta (*JRAS*, 1923, 587.)

³ The statement should be remembered by those modern writers who find traces of Persian influence in Maurya architecture.

are natives of the country, and keep hovering about the king and wheeling round him, and vast though their numbers be, no Indian ever eats a parrot. The Brachmans honour them highly above all other birds—because the parrot alone can imitate human speech. Within the palace grounds are artificial ponds in which they keep fish of enormous size but quite tame. No one has permission to fish for these except the king's sons while yet in their boyhood. These youngsters amuse themselves while fishing in the unruffled sheet of water and learning how to sail their boats."¹

The imperial palace probably stood close to the modern village of Kumrahār.² The unearthing of the ruins of the Maurya pillar-hall and palace near Kumrahār, said to have been built on the model of the throne-room and palace of Darius at Persepolis, led Dr. Spooner to propound the theory that the Mauryas were Zoroastrians.³ Dr. Smith observed that the resemblance of the Maurya buildings with the Persian palace at Persepolis was not definitely established. Besides, as Professor Chanda observes, "Ethnologists do not recognize high class architecture as test of race, and in the opinion of experts the buildings of Darius and Xerxes at Persepolis are not Persian in style, but are mainly dependent on Babylonian models and bear traces of the influence of Greece, Egypt and Asia Minor."

We learn from Strabo⁴ that the king usually remained within the palace under the protection of **female guards**⁵

¹ McCrindle, *Ancient India as described in Classical Literature*, pp. 141-42.

² Smith, *The Oxford History of India*, p. 77. Macphail, *Aśoka*, pp. 23-25.

³ *J. R. A. S.*, 1915, pp. 63 ff, 405 ff.

⁴ H. & F.'s Tr., Vol. III, p. 106; cf. Smith, *EHI.*, 3rd ed., p. 123.

⁵ The same writer tells us that these women were *bought* from their parents. In view of this statement it is rather surprising that Megasthenes is quoted as saying that none of the Indians employed slaves. Note also the story narrated by

(cf. *stri gaṇair dhanvidhiḥ* of the *Arthaśāstra*) and appeared in public only on four occasions, viz., in time of war; to sit in his court as a judge; to offer sacrifice and to go on hunting expeditions.

Chandragupta's Government

Chandragupta was not only a great soldier and conqueror, he was a great administrator. Megasthenes, the Greek ambassador at his court, has left detailed accounts of his system of government. The edict of his grandson Aśoka, and the *Arthaśāstra* attributed to his minister, **Kauṭilya**, confirm in many respects the particulars of the organisation of the empire given by the distinguished envoy. The *Arthaśāstra* certainly existed before Bāṇa (seventh century A.D.) and the *Nandisūtra* of the Jainas (not later than the fifth century A.D.). But it is doubtful if, in its present shape, it is as old as the time of the first Maurya. Reference to *Chinapaṭṭa*, China silk, which, be it remembered, occurs frequently in classical Sanskrit literature, points to a later date, as China was clearly outside the horizon of the early Mauryas, and is unknown to Indian epigraphy before the Nāgārjunikoṇḍa inscriptions. Equally noteworthy is the use of Sanskrit as the official language, a feature not characteristic of the Maurya epoch. A date as late as the Gupta period is, however, precluded by the absence of any reference to the Denarius in the sections dealing with weights and coins. Quite in keeping with this view is the reference to the *Arthaśāstra* contained in Jaina canonical works that were reduced to writing in the Gupta age. We have already adduced grounds for believing that *Arthaśāstra* probably existed before the second century A.D.¹ *Though*

Athenians that Amitrochates (i.e., Bindusāstra) begged Antiochos Soter to buy and send him a professor (Moonahan, *The Early History of Bengal*, pp. 164, 176, 179).

¹ P. 91, ante.

a comparatively late work, it may be used, like the *Junāgaḍh Inscription of Rudradāman*, to confirm and supplement the information gleaned from earlier sources.

The **Supreme Government** consisted of two main parts :

1. The *Rājā* and
2. The “**Councillors**” and “**Assessors**” (*Mahāmātras*, and *Amātyas* or *Sachivas*).

The *Rājā* or sovereign was the head of the state. He was considered to be a mere mortal, though a favoured mortal, the beloved of the deities.¹ The possession of the material resources of a great empire and control over a vast standing army gave him real power. But there was a body of **ancient rules**, *Porāṇā pakitī*, which even the most masterful despot viewed with respect. The people were an important element of the state. They were looked upon as children for whose welfare the head of the state was responsible, and to whom he owed a debt which could only be discharged by good government. There was a certain amount of decentralisation, notably in the sphere of **local government**, and there was usually at the imperial headquarters, and also at the chief centres of provincial government, a body of ministers who had a right to be consulted specially in times of emergency. Nevertheless the powers of the king were extensive. He had military, judicial, legislative, as well as executive functions. We have already seen that one of the occasions when he left his palace was **war**.² He considered plans of military operations with his *Senāpati*³ or Commander-in-Chief.

¹ Cf. ante 198n 10.

² Cf. Strabo, XV, i; and Kauṭilya Bk. X.

³ Kauṭ., p. 38. In the last days of the Maurya empire we find the *Senāpati* overshadowing the king and transferring to himself the allegiance of the troops.

He also sat in his **court to administer justice**. "He remains there all day thus occupied, not suffering himself to be interrupted even though the time arrives for attending to his person. This attention to his person consists of friction with pieces of wood, and he continues to listen to the cause, while the friction is performed by four attendants who surround him."¹ The *Kauṭīliya Arthaśāstra* says,² "when in the court, he (the king) shall never cause his petitioners to wait at the door, for when a king makes himself inaccessible to his people and entrusts his work to his immediate officers, he may be sure to engender confusion in business, and to cause thereby public disaffection, and himself a prey to his enemies. He shall, therefore, personally attend to the business of gods, of heretics, of Brāhmaṇas learned in the Vedas, of cattle, of sacred places, of minors, the aged, the afflicted, the helpless and of women;—all this in order (of enumeration) or according to the urgency or pressure of those works. All urgent calls he shall hear at once."

As to the king's legislative function we should note that the *Kauṭīliya Arthaśāstra*³ calls him "*dharmo-pravartaka*," and includes **Rājaśāsana** among the sources of law. As instances of royal "*Sāsanas*" or rescripts may be mentioned the Edicts of Aśoka, the famous grandson of Chandragupta.

Among **executive functions** of the king, our authorities mentions the posting of watchmen, attending to the accounts of receipts and expenditure, appointment of ministers, priests and superintendents, correspondence with the *Mantriparishad* or Council of Ministers, collection

¹ H. & F., Strabo III, pp. 106-107.

² Shamasastri's translation, p. 43.

³ Bk. III, Chap. I.

of the secret information gathered by spies, reception of envoys, etc.¹

It was the king who laid down the broad lines of policy and issued rescripts for the guidance of his officers and the people. Control was maintained over the most distant officials by an army of secret reporters and overseers and, in the days of Chandragupta's grandson, by itinerant judges. Communication with them was kept up by a network of roads, and garrisons were posted at strategic points.

Kauṭilya holds that *Rājatva* (sovereignty) is possible only with assistance.² A single wheel can never move. Hence the king shall employ *Sachivas* and hear their opinion. The **Sachivas** or **Amātyas** of Kauṭilya correspond to the "seventh caste" of Megasthenes which assisted the king in deliberating on public affairs. This class was small in numbers, but in wisdom and justice excelled all the others.³

The most important amongst the *Sachivas* or *Amātyas* were undoubtedly the **Mantrins** or High Ministers, probably corresponding to the **Mahāmātras** of Aśoka's Rock Edict VI and the "advisers of the king" referred to by Diodoros.⁴ They were selected from those *Amātyas* whose character had been tested under all kinds of allurements.⁵ They were given the highest salary, viz., 48,000 *paṇas* per annum.⁶ They assisted the king in examining

¹ Kauṭilya, Bk. I, Ch. xvi ; xvii ; Bk. VIII, Ch. i. Cf. Aśoka's Rock Edicts III (regulation about *alpa vyayata* and *alpa bhāṇḍatā*), V (appointment of high officials), VI (relations with the *Parishad*, and collection of information from the *Paṭivedakā*), and XIII (diplomatic relations with foreign powers).

² Cf. Manu, VII. 55.

³ Chinnoek, *Arrian*, p. 413.

⁴ II. 41.

⁵ *Sarvopadhā śuddhā Mantrināḥ kuryāt.*—*Arthasāstra*, 1919, p. 17. For *upadhā* see also the Junāgaḍh Rock Inscription of Skanda Gupta.

⁶ Kauṭilya, p. 247. According to Smith (EHI, 4th ed., p. 119) the value of a silver *paṇa* may be taken as not far from a shilling.

the character of the *Amātyas* who were employed in ordinary departments.¹ All kinds of administrative measures were preceded by consultation with three or four of them.² In works of emergency (*ātyayike kārye*) they were summoned along with the *Mantriparishad*.³ They exercised a certain amount of control over the Imperial Princes.⁴ They accompanied the king to the battle-field, and gave encouragement to the troops.⁵ Kauṭilya was evidently one of those *Mantrins*. Another minister (or *Pradeshṭri*?) was apparently Maniyatappo, a Jāṭīlian, who helped the king to "confer the blessings of peace on the country by extirpating marauders who were like unto thorns."⁶ That there were at times more than one *Mantrin* is proved by the use of the plural *Mantrinah*.

In addition to the *Mantrins* there was the *Mantriparishad*, i.e., Assembly of Counsellors or Council of Ministers. The existence of the *Parishad* as an important element of the Maurya constitution is proved by the third and sixth Rock Edicts of Aśoka.⁷ The members of the *Mantriparishad* were not identical with the *Mantrins*. In several passages of Kauṭilya's *Arthaśāstra* the *Mantrins* are sharply distinguished from the *Mantriparishad*.⁸ The latter evidently occupied an inferior position. Their salary was only 12,000 *panas*, whereas the salary of a *Mantrin* was 48,000. They do not appear to have been consulted on ordinary occasions, but were summoned

¹ *Ibid.*, p. 16.

² *Ibid.*, pp. 26, 28.

³ *Ibid.*, p. 29 Cf. Aśoka's Rock Edict VI.

⁴ *Ibid.*, p. 333.

⁵ *Ibid.*, p. 368 Cf. the Udayagiri Inscription of Śāla.

⁶ Turnour's *Mahāvamśa*, p. xlii. The evidence is late.

⁷ Note also Pliny's reference to noble and rich Indians who sit in council with the king (Monshao, *The Early History of Bengal*, 149) ; cf. *Mbh.* iii, 127.

8. *Amātyaparishad* ; xii, 320, 139 *Amātya Samiti*.

⁹ Cf. pp. 26, 29, 247.

along with the *Mantrins* when *Ātyayika kārya*,¹ i.e., works of emergency had to be transacted. The king was to be guided by the decision of the majority (*Bhūyishthāh*). They also attended the king at the time of the reception of envoys.² From the passage "*Mantripari-shadam dvādaśāmātyān kurvāta*"—"the Council of Ministers should consist of twelve *Amātyas*," it appears that the *Parishad* used to be recruited from all kinds of *Amātyas* (not necessarily from *Mantrins* alone). From Kauṭilya's denunciation of a king with a "*Kshudraparishad*,"³ a small council, his rejection of the views of the *Mānavas*, *Bārhaspatyas* and the *Auśanasas*, his preference for an "*Akshudra-parishad*," a council that is not small, and his reference to Indra's *Parishad* of a thousand *Rishis*, it may be presumed that he wanted to provide for the needs of a **growing empire**. Such an empire was undoubtedly that of Chandragupta who may have been prevailed upon by his advisers to constitute a fairly big assembly.⁴

Besides the *Mantrins* and the *Mantriparishad*, there was another class of *Amātyas* who filled the **great administrative and judicial appointments**.⁵ The *Kauṭīliya Arthasāstra* says⁶ that the "*dharmopadhāśuddha*"² *Amātyas*, officers purified by religious test, should be employed in

¹ *Arthasāstra*, 29. Cf. *Mbh.*, iv. 30. 8. Aśoka's R. E. VI.

² *Arthasāstra*, p. 45.

³ P. 259.

⁴ The *Diṅyāvadāna* (p. 372) refers to the five hundred councillors (*Pañcāmātyasatāni*) of Bindusāra, son and successor of Chandragupta Maurya. Patañjali refers to Chandragupta *Sabhā*. But we have no indication as to its constitution.

⁵ Cf. the *Karma-Sachivas* of the Junāgaḍh Rock Inscription of Rudradāman I.

⁶ P. 17. Cf. McCrindle, *Megasthenes and Arrian*, 1926, 41, 42.

civil¹ and criminal² courts; the “*arthopadhāsuddha*” *Amātyas*, officers purified by money-test, should be employed as *Samāhartṛi* (“Chancellor of the Exchequer and Minister of the Interior”) and *Sannidhātṛi* (High Treasurer and Keeper of Stores;³ the “*kāmopadhāsuddha*” *Amātyas*, officials purified by love-test, should be appointed to superintend the pleasure grounds, the “*bhayopadhāsuddha*” *Amātyas*, officers purified by fear-test, should be appointed to do work requiring immediate attention (*āsanna kārya*), while those who are proved to be impure should be employed in mines, timber and elephant forests,⁴ and manufactories. Untried *Amātyas* were to be employed in ordinary or insignificant departments (*sāmānya adhikaraṇa*). Persons endowed with the qualifications required in an *Amātya* (*Amātyasampadopeta*) were appointed *Nisṛisṭārthāḥ* or Ministers Plenipotentiary, *Lekhakas* or Ministers of Correspondence, and *Adhyakshas* or Superintendents.

The statements of the *Kauṭīliya Arthaśāstra* regarding the employment of *Amātyas* as the chief executive and judicial officers of the realm, are confirmed by the classical writers. Strabo, for example, observes,⁵ “the seventh caste consists of counsellors and assessors (*Symbouloi* and *Synedroi*) of the king. To these persons belong the offices of state, tribunals of justice, and the whole

¹ Civil (*Dharmasthīya*) Courts were established “in the cities of *Saṅgrahana* (in the midst of a collection of ten villages), *Dronamukha* (in the centre of four hundred villages), *Sthāniya* (in the centre of eight hundred villages), and at places where districts met (*Janapada-sandhi*;? union of districts),” and consisted of three *Dharmasthas* (judges versed in the sacred law) and three *Amātyas*.

² A Criminal (*Kaṇṭakaśodhana*) Court consisted of 3 *Amātyas*, or 3 *Pradeshṭṛis*. The functions of the latter will be described later on.

³ For the duties of these officers see *Kauṭīliya's Arthaśāstra*, Bk. II, 5-6, 35; Bk. IV, 4; Bk. V, 2. For the revenue system under the Mauryas, see Ghoshal, *Hindu Revenue System*, pp. 165 ff.

⁴ Cf. *Nāgavana* of Pillar Edict V.

⁵ H. & F., Vol. III, p. 103. Cf. *Diodoros*, II. 41.

administration of affairs." Arrian also says, "from them are chosen their rulers, governors of provinces, deputies, treasurers, generals, admirals, controllers of expenditure, and superintendents of agriculture."

The **adhyakshas** who formed the pivot of the Kauṭīliyan administration, are evidently referred to by Strabo's translators as "Magistrates" in the following passage:¹

"Of the **Magistrates**, some have the charges of the market,² others of the city, others of the soldiery.³ Some⁴ have the care of the rivers, measure the land, as in Egypt, and inspect the closed **reservoirs from which water is distributed by canals**, so that all may have an equal use of it. These persons have charge also of the hunters, and have the power of rewarding or punishing those who merit either. They collect the taxes, and superintend the occupations connected with land, as wood-cutters, carpenters, workers in brass, and miners. They superintend the public roads, and place a **pillar at every ten stadia** to indicate the byways and distances. Those who have **charge of the city (astynomoi)** are divided into six bodies of five each.⁵ Next to the Magistrates of the city is a third body of **governors, who have the care of military affairs**. This class also consists of six divisions each composed of five persons.⁶

¹ One class of *Adhyakshas*, those in charge of women, are referred to in the Aśoka inscriptions as *Mahāmātras*.

² "District" according to the *Cambridge History of India*, I. 417.

³ Cf. the *Durga-rākṣāra-danḍa-mukhyas* of Kauṭilya, Bk. XIII, Chs. III and V.

⁴ i.e., the district officials (*Agronomoi*).

⁵ Each body was responsible for one of the following departments, viz., (1) the mechanical arts, (2) foreign residents, (3) registration of births and deaths, (4) trade, commerce, weights and measures, (5) supervision and sale of manufactured articles and (6) collection of tithes on sales. In their collective capacity they looked after public buildings, markets, harbours and temples. Prices were regulated by them.

⁶ Each division or Board was responsible for one of the following departments, viz., the navy, transport and commissariat (cf. *Viśhī karmāyī* of

The Magistrates in charge of the city and those in charge of military affairs are evidently the same as the **Nagarādhyaśhas** and **Balādhyaśhas** of the *Arthaśāstra*.¹ Dr. Smith remarks,² "the Boards described by Megasthenes as in charge of the business of the capital and the army are unknown to the author (Kautilya), who contemplated each such charge as the duty of a single officer. The creation of the Boards may have been an innovation effected by Chandragupta personally."³ But the historian overlooks the fact that Kautilya distinctly says: "*Bahumukhyam anityam chādhyakṣaṇam sthāpayet*," "each department shall be officered by several temporary heads;"⁴ "*Adhyakṣaḥ Saṅkhyāyaka-Lekhaka-Rūpadarśaka-Nivāgrāhaka-Ottarādhyaśha-sakhāḥ karmāṇi kuryuḥ*," "the Superintendents shall carry on their duties with the assistance of accountants, scribes, coin-examiners, stock-takers and additional secret overseers." Evidently Dr. Smith notices only the *Adhyakṣas* but ignores the existence of the *Uttarādhyaśhas* and others. As in regard to the *Arthaśāstra* Smith notices only the *Adhyakṣas*, so in regard to the classical accounts he takes note only of the

Kautilya, Bk. X, Ch. iv), the infantry, the cavalry, the chariots and the elephants. In the *Santiparva* of the *Mahābhārata* the divisions are stated to be six (CIII. 38) or eight (LIX. 41-43):

*Rathā Nāga Hayāśchaiva Pādātāśchaiva Pāṇḍava
Viśhīr Nāgaś Charātāśchaiva Dehikā iti chāṣṭamam
Aṅganyetāni Kaurava prakāśāni balasya tu*

"Chariots, elephants, horses, infantry burden-carriers, ships, spies with local guides as the eighth—these are the open "limbs" of a fighting force, O descendant of Kuru."

The *Raghuvamśa* IV, 26) refers to *Shakṛdham balam*. Cf. Mbh. V. 96. 16.

¹ Mysore Ed., 1919, p. 55. *Nagara-Dhānya-Vyācakārika-Kārmāntika-Balādhyaśhaḥ*, Cf. *Balapradhāna* and *Nigamapradhānaḥ* of Mbh., V. 2. 6.

² EHI, 1914, p. 141. Cf. Monahan, *Early History of Bengal*, pp. 167-61, Stein, *Megasthenes and Kautilya*, pp. 283 ff.

³ *Arthaśāstra*, 1919, p. 60. On page 57 we have the following passage—*Hasty-aiva-ratha-padātām-aneka-mukhyam-avasthāpayet*, i.e., elephants, cavalry, chariots, and infantry shall each be placed under many chiefs.

Boards, but ignores the **chiefs** who are expressly mentioned in two passages,¹ viz.—

“One division is associated with the *Chief Naval Superintendent*,” “another (division) is associated with the *person who has the charge of the bullock-teams*.”² The Chief Naval Superintendent and the Person in Charge of the Bullock-teams, doubtless, correspond to the *Nāvadhyaksha* and the *Go’dhyaksha* of the *Arthashastra*. It is a mistake to think that the *Nāvadhyaksha* of the early Hindu period was a purely civil official, for he was responsible for the destruction of *Himsrikās* (pirate ships?) and the *Mahābhārata*³ clearly refers to the navy as one of the *angas* or limbs of the Royal Forces. The civil duties of the *Nāvadhyaksha* have their counterpart in those of Megasthenes’ Admiral relating to the “letting out of ships on hire for the transport both of passengers and merchandize.”⁴

Central popular assemblies like those that existed among the *Licchhavis*, *Mallas*, *Śākya*s and other *Saṅghas* had no place in the Maurya constitution. The custom of summoning a great assembly of *Grāmikas* or Village Headmen seems also to have fallen into disuse. The royal council gradually became an aristocratic body attended only by nobles and rich men.⁴

Administration of Justice

At the head of the judiciary stood the king himself. Besides the royal court there were special tribunals of justice both in cities (*nagara*) and country parts (*janapada*) presided over by *Vyāvahārika Mahāmātras* and *Rājukas* respectively. Greek writers refer to judges who listened

¹ H. & F., Strabo, III, p. 101.

² XII. lix, 41-42.

³ Strabo, XV, I, 46.

⁴ Pliny quoted in Monahan's *Early History of Bengal*, 148.

to cases of foreigners. Petty cases in villages were doubtless decided by the headmen and the village elders. All our authorities testify to the severity of the penal code.] But the rigours of judicial administration were sought to be mitigated by Aśoka, grandson of Chandragupta, who meted out equal justice to all and instituted the system of itinerant *Mahāmātras* to check maladministration in the outlying provinces. Considerable discretion was, however, allowed to the *Rājūkas*. We are informed by Greek writers that "theft was a thing of very rare occurrence" among Indians. They express their surprise at this for they go on to observe that the people "have no written laws but are ignorant of writing, and conduct all matters by memory." The assertion about the Indians' ignorance of writing is hardly correct. Nearchus and Curtius record that Indians use pieces of closely woven linen and the tender bark of trees for writing on. Strabo tells us that a philosopher who has any useful suggestion to offer, commits it to writing. Attention may also be invited to the marks on Mauryan pillars intended to show the by-roads and distances.¹

Provincial Government

The Empire was divided into a number of provinces which were subdivided into *āhāras* or *vishayas* (districts), because "No single administration could support the Atlantean load." The exact number of provinces in Chandragupta's time is unknown. In the time of his grandson, Aśoka, there were at least five, viz. :

1. Uttarāpatha ²	...	capital, Taxila
2. Avantirāṭṭha ³	...	„ Ujjyini

¹ Monahan, *Early History of Bengal*, pp. 143, 157, 167 f.

² *Diryāvadāna*, p. 407.

³ *The Questions of King Milinda*, pt. II, p. 250n. *Mahārahas* Ch. XIII; *Mahābodhivamsa*, p. 98.

- | | | |
|--|-----|--------------------------|
| 3. Dakṣiṇāpatha | ... | capital, Suvarṇagiri (?) |
| 4. Kalinga | ... | „ Tosali |
| 5. Prāchya, Prāchina (Prasii) ¹ | ... | „ Pāṭalīputra. |

Of these only the first two and the last one can be said, with any amount of certainty, to have formed parts of Chandragupta's Empire. But it is not altogether improbable that Dakṣiṇāpatha, too, was one of Chandragupta's provinces. The outlying provinces were ruled by princes of the blood royal who were usually styled *Kumāras*. We learn from the *Kauṭīliya Arthaśāstra*² that the salary of a *Kumāra* was 12,000 paṇas per annum.

The Home Provinces, i.e., Prāchya and the Madhyadeśa (Eastern India and Mid-India), were directly ruled by the Emperor himself with the assistance of *Mahāmātras* or High Officers stationed in important cities like Pāṭalīputra, Kauśāmbī, etc.

Besides the Imperial Provinces, Maurya India included a number of territories which enjoyed a certain amount of autonomy. Arrian refers to **peoples who were autonomous and cities which enjoyed a democratic Government.**³ The *Kauṭīliya Arthaśāstra*⁴ refers to a number of **Saṅghas** i.e., economic, military or political corporations or confederations evidently enjoying autonomy in certain matters, e.g., Kamboja, Surāshṭra, etc. The Kambojas find prominent mention as a unit in the Thirteenth Rock Edict of Aśoka. R. E. V. alludes to various *nations or peoples on the western border (Aparātā)* in addition to those named specifically.⁵ It is not improbable that Surāshṭra was included among these nations which, judged by the title of its local rulers, enjoyed a

¹ Cf. the *Questions of Milinda*, II, 250a.

² P. 247.

³ Moonshian, *The Early History of Bengal*, 160; Chinnoek, *Arrian*, 413.

⁴ P. 378.

⁵ I. H. Q. 1931, 631.

considerable amount of autonomy. The commentary on the *Petavatthu* refers to one of the local *Rājas* named Piṅgala,¹ the contemporary of Aśoka. Another contemporary,² the *Yavana-rāja* Tushāspā finds mention in Rudradāman's inscription at Junāgaḍh. The *Yavana-rāja* was probably a Greek chief of the North-West who was appointed to look after the affairs of Surāshṭra by Aśoka, just as Rājā Mān Singh of Amber was appointed *Subadār* of Bengal by Akbar. His relations with Aśoka may also be compared to that subsisting between the *Rājā* of the Śākya state and Pasenadi. In the time of the first Maurya Surāshṭra had an officer named Pushyagupta, the *Vaiśya* who is described as a *Rāshṭriya* of Chandragupta. In the *Bombay Gazetteer*,³ the word *Rāshṭriya* was taken to mean a brother-in-law. Kielhorn, however, in the *Epigraphia Indica*,⁴ took the term to mean a provincial Governor. This rendering does not seem to be quite adequate because we have already seen that Surāshṭra had possibly its group of *Rājās* in the Maurya Age and could not be regarded as an Imperial Province under a bureaucratic governor of the ordinary type. The *Rāshṭriya* of the inscription seems to have been a sort of Imperial High Commissioner,⁵ and the position of Pushyagupta in Surāshṭra was probably like that of Lord

¹ Law, *Buddhist Conception of Spirits*, 47 ff.

² Attempts in recent times to assign Tushāspā to the post-Aśokan period lack plausibility. In the Junāgaḍh epigraph the name of the suzerain invariably accompanies that of the local ruler or officer. There is no reason to think that the relationship between Aśoka and Tushāspā was different from that between Chandragupta and Pushyagupta or between Rudradāman and Suviśākha.

³ Vol. I, Part I, p. 13.

⁴ Vol. VIII, p. 46.

⁵ Cf. the type met with in the Near East after the First World War. The High Commissioner acted for the *de facto* paramount power. His office does not preclude the possibility of the existence of a local potentate or potentates. Note also Wendel Wilkie's observation (*One World*, p. 13) on the British "ambassador" to Egypt who is "for all practical purposes its actual ruler."

Cromer in Egypt. Neither the *Arthaśāstra* nor the edicts of Aśoka mention clearly any class of officials called *Rāshṭriya*.¹ It is, however, probable, that the *Rāshṭriya* was identical with the *Rāshṭrapāla* whose salary was equal to that of a *Kumāra* or Prince.²

A hereditary bureaucracy does not seem to have come to existence in the early Maurya period at least in the territory of Surāshṭra. The assumption of the title of *Rājā* by local rulers and the grant of autonomy to the *Rājukas* in the days of Aśoka ultimately let loose centrifugal forces which must have helped in the dismemberment of the empire.

Overseers and Spies

The classical writers refer to a class of men called Overseers (*Episkopoi*) who "overlook what is done throughout the country and in the cities, and make report to the king where the Indians are ruled by a king, or the magistrates where the people have a democratic Govern-

¹ The Aśokan inscriptions, however, mention the *Rathikas* and the *Pāli English Dictionary*, edited by Rhys Davids and Stede compares *Ratthika* with *Rāshṭriya*.

² *Arthaśāstra*, p. 247. For *Rāshṭriya* see also *Mbh.*, XII. 85, 12; 87. 2. According to Amara (V. 14) a *Rāshṭriya* is a *rājasyāla* (brother-in law of the king). But Kahiravāmin says in his commentary that except in a play a *Rāshṭriya* is a *Rāshṭrādhipāta*, i.e., an officer appointed to look after or supervise the affairs of a *rāshṭra*, state or province. Cf., the Macedonian *episkopos*. Note the position of Eudamos in relation to the Indian *Rājās* of the Pañjāb, and that of Pratibāra *Tantrapālas* of the tenth century A.D. Dr. Barua draws attention (in *IO*, X, 1944, pp. 88 ff.) to several texts including Buddhaghoṣa's statement that during a royal state-drive the place assigned to the *Rāshṭriyas* was just between the *Mahāmātras* and Brahmins shouting the joy of victory. They themselves were gorgeously dressed holding swords and the like in their hands. This may well be true. But the texts cited by him are not adequate enough to prove that in the days of Chandragupta Maurya the *Rāshṭrika* or *Rāshṭriya* was nothing more than the foremost among the bankers, business magnates, etc., who functioned as Mayors, Sheriffs and Justices of the Peace. The analogy of Tushāpāra and Suvishākhā mentioned in the same epigraph suggests that the *Rāshṭriya* here was a more exalted functionary, and that the evidence of Kahiravāmin cannot be lightly brushed aside.

ment."¹ Strabo calls this class of men the *Ephori* or Inspectors. "They are," says he, "intrusted with the superintendence of all that is going on, and it is their duty to report privately to the king...The best and the most faithful persons are appointed to the office of Inspectors."² The Overseer of Arrian and the Inspector of Strabo may correspond to the *Rāshṭriya* of the Junāgaḍh Inscription or to the *Pradeshṭri* or the *Gūḍha-Purushas* (secret emissaries) of the *Arthaśāstra*. *Pradeshṭri* may be derived from *Pradiś* which means 'to point,' 'to communicate.'³

Strabo speaks of different classes of Inspectors. He tells us that the City Inspectors employed as their co-adjutors the city courtesans; and the Inspectors of the Camp, the women who followed it. The employment of women of easy virtue as spies is also alluded to by the *Kauṭillya Arthaśāstra*. According to that work there were two groups of spies, *viz.* :

1. *Samsthāh*, or stationary spies, consisting of secret agents styled *Kāpaṭika*, *Udāsthita*, *Gṛihapatika*, *Vaidehaka* and *Tāpasa*, *i.e.*, fraudulent disciples, recluses, householders, merchants and ascetics.

2. *Saṅcharāh* or wandering spies,⁴ including emissaries termed *Satri*, *Tikshṇa* and *Rashada*, *i.e.*, class-mates, firebrands and poisoners and certain women described as *Bhikshukīs* (mendicants), *Parivrājikās* (wandering nuns), *Muṇḍas* (shavelings) and *Vṛishalīs*. It is to the last class, *viz.*, the *Vṛishalīs* that Strabo evidently refers.⁵ We

¹ Chinnock, *Arrian*, p. 413.

² H. and F., *Strabo*, III, p. 103.

³ *Cf.*, Thomas, *JRAS.*, 1915, p. 97.

⁴ *Cf.*, Lüders, *Ins.* No. 1200.

A *Vṛishalī* is taken to mean a *gaṇikā* or courtesan by the author of the *Dhagavadajjukiyam* (p. 94).

have also explicit references to courtesan (*pūnśchalī*, *veśyā*, *rūpājīvā*) spies in the *Arthaśāstra*.¹

Care of Foreigners

It is clear from the accounts of Diodoros² and Strabo³ that the Maurya government took special care of foreigners. "Among the Indians officers are appointed even for foreigners, whose duty is to see that no foreigner is wronged. Should any one of them lose his health, they send physicians to attend him, and take care of him otherwise, and if he dies they bury him, and deliver over such property as he leaves to his relatives. The judges also decide cases in which foreigners are concerned with the greatest care and come down sharply on those who take unfair advantage of them."⁴

Village Administration

The administrative and judicial business of villages was, in Ancient India, carried on by the *Grāmikas*,⁵ *Grāmabhojakas* or *Āyuktas* who were, no doubt, assisted by the village elders.⁶ The omission of the *Grāmika* from the list of salaried officials given in the *Arthaśāstra*⁷ is significant. It probably indicates that in the days of the author of the treatise the *Grāmika* was not a salaried

¹ Pp. 224, 316 of the *Arthaśāstra* (1919).

² II. 42.

³ XV. I. 50.

⁴ McCrindle, *Megasthenes and Arrian*, 1926, p. 42.

⁵ Fick, *Social Organisation*, 162; *Arthaśāstra*, pp. 157. 172. Cf. Lüders, *Ins.* Nos. 48, 69a. The Kalinga Edicts refer to *Āyuktas* who helped the princely viceroys and *Mahāmātras* in carrying out Imperial Policy. In the early Post-Mauryan and Scythian Age they are distinctly referred to as village officials (Lüders' List, No. 1347). In the Gupta Age the designation is applied to various functionaries including district officers.

⁶ *Grāma-vṛiddhas*, *Artha*, pp. 48, 161, 169, 178. Cf. Lüders, *Ins.*, No. 1327. Rock Edicts, V and VIII refer to *Mahātakas* and *Vṛiddhas*.

⁷ Bk. V, Ch. III.

servant of the crown, but possibly an elected ¹ official of the villagers. The king's servant in the village was the *Grāma-bhṛitaka*² or *Grāma-bhojaka*.³ Above the *Grāmika* the *Arthaśāstra* places the *Gopa*,⁴ who looked after 5 or 10 villages, and the *Sthānika* who controlled one quarter of a *janapada* or district. The work of these officers was supervised, according to that treatise by the *Samāharṭṛi* with the help of the *Pradeshtṛis*.⁵ Rural administration must have been highly efficient. We are told by Greek observers that the tillers of the soil received adequate protection from all injury and would devote the whole of their time to cultivation.

Revenue and Expenditure

The cost of civil and military administration even at the centre must have been enormous. The chief sources of revenue from villages were the *Bhāga* and the *Bali*. The *Bhāga* was the king's share of the produce of the soil which was normally fixed at one-sixth, though in special cases it was raised to one-fourth or reduced to one-eighth. *Bali* seems to have been an extra impost from the payment of which certain tracts were exempted. According to Greek writers husbandmen paid, in addition to a fourth part of the produce of the soil, a land tribute because, according to their

¹ There is, however, evidence to show that in early times *adhikṛitas* were appointed for villages by the paramount ruler (*Praśna Upanishad*, III. 4).

² *Artha*, pp. 175, 248.

³ The *Grāma-bhojaka* of the *Jātakas* was an *amātya* of the king (Fick, *Social Organization in N.-E. Ind.* p. 160).

⁴ The *Gopas* proper do not find mention in early epigraphs but Lüders, *Ins.* No. 1266, mentions "*Senā-gopas*."

⁵ *Artha*, pp. 142, 217. We do not know how far the system described in the treatise on polity applies to the early Maurya period. In the days of Aśoka the work of supervision was done largely by special classes of *Mahāmātras* (cf. R.E.V. and the *Kaliṅga Edicts*), *Pulisā* (agents) and *Rājukas* (Pillar Edict. IV).

belief, "all India is the property of the crown and no private person is permitted to own land." Taxes on land were collected by the *Agronomoi* who measured the land and superintended the irrigation works. Other state dues included tribute and prescribed services from those who worked at trades, and cattle from herdsmen. In urban areas the main sources of revenue included birth and death taxes, fines and tithes on sales. The *Mahābhāshya* of Patañjali has an interesting reference to the Mauryas' love of gold which led them to deal in images of deities. The distinction between taxes levied in rural and in fortified areas respectively is known to the *Arthaśāstra* which refers to certain high revenue functionaries styled the *Samāhartri* and the *Sannidhātri*. No such officials are, however, mentioned in Maurya inscriptions. Greek writers, on the other hand, refer to 'treasurers of the state' or 'superintendents of the treasury'.

A considerable part of the revenue was spent on the army. The artisans, too, received maintenance from the Imperial exchequer. Herdsmen and hunters received an allowance of grain in return for clearing the land of wild beasts and fowls. Another class which benefited from royal bounty were the philosophers among whom were included Brāhmanas as well as *Śramanas* or ascetics. Vast sums were also spent for irrigation, construction of roads, erection of buildings and fortifications, and establishment of hospitals in the days of Chandragupta's grandson.

The Last Days of Chandragupta

Jaina tradition recorded in the *Rājavalikathe*¹ avers that Chandragupta was a Jaina and that, when a great famine occurred, he abdicated in favour of his son

¹ *Ind. Ant.*, 1892, 157.

Simhasena and repaired to Mysore where he died. Two inscriptions on the north bank of the Kāverī near Seringapatam of about 900 A.D., describe the summit of the Kalbappu Hill, i.e., Chandragiri, as marked by the footprints of Bhadrabāhu and Chandragupta *Munipati*.¹ Dr. Smith observes:² "The Jain tradition holds the field, and no alternative account exists." Chandragupta died about 300 B.C., after a reign of 24 years.³

If the *Parīśiṣṭaparvan*⁴ of Hemachandra is to be believed Chandragupta had a queen named Durdharā who became the mother of Bindusāra, the son who succeeded him on the throne. In the absence of corroborative evidence, however, the name of the queen cannot be accepted as genuine.

¹ Rice, *Mysore and Coorg from the Inscriptions*, pp. 8-4.

² The *Oxford History of India*, p. 75. As already stated, Fleet is sceptical about the Jain tradition (*Ind. Ant.*, 1892, 155 f.). According to Greek evidence Chandragupta was a follower of the sacrificial religion (see p. 277 *ante*). The epithet *Vṛishala* applied to him in the *Mudrārākhya* suggests that in regard to certain matters he did deviate from strict orthodoxy (*Indian Culture*, II, No. 3, pp. 558 ff. See also O. J. Shah, *Jainism in Northern India*, 135n, 138).

³ For the date of Chandragupta Maurya see *Indian Culture*, Vol II, No. 3, pp. 560 ff. Buddhist tradition of Ceylon puts the date 162 years after the *parinirvāṇa* of the Buddha, i.e., in 332 B.C., if we take 514 B.C., to be the year of the Great Decease; and 324 B.C., if we prefer the Cantonese date 486 B.C., for the death of the Buddha. The earlier date is opposed to Greek evidence. The date 324 B.C. accords with the testimony of Greek writers. The *Jaina* date 313 B.C., for Chandragupta's accession if it is based on a correct tradition, may refer to his acquisition of Avanti in Malwa, as the chronological datum is found in a verse where the Maurya king finds mention in a list of successors of Pālaka, king of Avanti. Cf. I.H.Q., 1929, p. 403. Filliozat (*Manuel des études indiennes*, I, 212-219) and others who prefer the late Jaina evidence, ignore the much earlier Ceylonese testimony, see Raychaudhuri, *HCIP*, AIU, Vol II, 92 ff.; ANM 156 ff.; the date 313 B.C. moreover does not accord well with what is known about the synchronism of Aśoka with some of the Hellenistic kings mentioned in Edict XIII, notably Magas of Cyrene whom a contemporary poet, Callimachus seems to place long before the Syrian War of Ptolemy III (c. 247-6 B.C.). Tarn in Cary, *Greek World*, 393 f.

⁴ VIII. 439-443, For another tradition see Bigandet, II. 128

SECTION II. THE REIGN OF BINDUSĀRA.

Chandragupta Maurya was succeeded in or about the year 300 B.C. by his son Bindusāra Amitraghāta. The name or title *Amitraghāta* (slayer of foes) is a restoration in Sanskrit¹ of the *Amitrachates* of Athenaios, and *Allitrochades* of Strabo, who is stated to have been the son of Sandrocottus. Fleet prefers the rendering *Amitrakhāda* or devourer of enemies, which is said to occur as an epithet of Indra.² In the *Rājavalikathe* the name of Chandragupta's son and successor is given as Simhasena. From Aśoka's Rock Edict VIII (e. g. the Kālsī Text) it appears probable that Bindusāra, as well as other predecessors of Aśoka, used the style *Devānampiya*.

If the author of the *Ārya-Manjūsri Mūla Kalpa*, Hemachandra and Tāranātha are to be believed, Kauṭilya or Chāṇakya continued to serve as minister for some time after the accession of Bindusāra.³ "Chāṇakya says Tāranātha, "one of his (Bindusāra's) great lords, procured the destruction of the nobles and kings of sixteen

¹ Cf., Weber, *IA*, ii (1873), p. 148, Lassen, and Cunningham (*Bhilsa Topes*, p. 92). The term *Amitraghāta* occurs in Patañjali's *Mahābhāṣya* III. 2. 2. Cf., also *Mbh.* 30. 19; 62. 8; VII. 22. 16, where *Amitraghātin* occurs as an epithet of princes and warriors. Dr. Jarl Charpentier observes (in *Le Monde Oriental*, quoted in *Calcutta Review*, May-June, 1926, p. 399), "that the Greek word *Amitrachates* as a synonym of Bindusāra, should be rendered *Amitraghāta* seems clear not only from the *Mahābhāṣya* but also from the royal title *amitrāṇāṁ hantā* in *Ait. Br.*, VIII. 17." In *JRAS.*, 1928, January, however, he prefers to restore *Amitrachates* as *Amitrakhāda* (p. 135). Cf. *Rig-veda*, X. 152. 1.

² *JRAS.*, 1909, p. 24.

³ Jacobi, *Parīśiṣṭaparvan*, p. 62; VIII. 416 ff; *Ind. Ant.*, 1875, etc. For the alleged connection of Bindusāra and Chāṇakya with another minister named Subaudhu, the author of the *Vāsavadattā Nāṭyadhārā*, see *Proceedings of the Second Oriental Conference*, pp. 208-11 and *Parīśiṣṭa*, VIII. 417. The *Divyāvadāna* (p. 372) mentions Khallātaka as Bindusāra's *agrāmātya* or chief minister.

towns,¹ and made the king master of all the territory between the eastern and western seas." The conquest of the territory between the eastern and western seas has been taken by some scholars to refer to the annexation of the Deccan.² But we should not forget that already in the time of Chandragupta the Maurya Empire extended from Surāshṭra to Bengal (Gangaridae), *i.e.*, from the western to the eastern sea. Tāranātha's statement need mean nothing more than the suppression of a general revolt. No early tradition expressly connects the name of Bindusāra with the conquest of the Deccan.³ The story of the subjugation of sixteen towns may or may not be true, but we are told in the *Divyāvadāna*⁴ that at least one town of note, *viz.*, Taxila, revolted during the reign of Bindusāra. The king is said to have despatched Aśoka there. While the prince was nearing Taxila with his troops, the people came out to meet him, and said, "We are not opposed to the prince nor even to king Bindusāra, but the wicked ministers (*Duṣṭāmātyāḥ*) insult us". The high-handedness of the Maurya officials in the outlying provinces is alluded to by Aśoka himself in his Kalinga Edict.⁵ Addressing his *Mahāmātras* the Emperor says :

"All men are my children : and, just as I desire for my children that they may enjoy every kind of prosperity and happiness both in this world and in the next, so also I desire the same for all men. You, however, do

¹ Were these the capitals of the sixteen *mahājanapadas*?

² Cf. Smith, *EHJ.*, 3rd ed., p. 149, *JRAS.*, 1919, 598; Jayaswami, *The Empire of Bindusāra*, *JBORS.*, ii. 79ff.

³ See, however, Subramaniam, *JRAS.*, 1923, p. 96, "My Guru's Guru had written in his commentary on a *Saṅgam* work that the Tulu-nāda was established by the son of Chandragupta," perhaps Tuliya (Tuli=Bindu).

⁴ Cowell and Neil's Ed., p. 371.

⁵ Smith, *Aśoka*, third edition, pp. 194-95.

*not grasp this truth to its full extent.*¹ Some individual, perchance, pays heed, but to a part only, not the whole. See then to this, for the principle of government is well established. Again, *it happens that some individual incurs imprisonment or torture*, and when the result is his imprisonment without due cause, *many other people are deeply grieved*. In such a case you must desire to do justice² ...and for this purpose, in accordance with the Law of Piety, I shall send forth in rotation every five years such persons (*Mahāmātras*) as are of mild and temperate disposition, and regardful of the sanctity of life, who knowing this my purpose will comply with my instructions.³ From Ujjain, however, the Prince for this purpose will send out a similar body of officials and will not over-pass three years. *In the same way from Taxila.*"

Taxila made its submission to Aśoka. The Maurya prince is further represented as entering the "Svaśa rājya" (**Khaśa** according to Burnouf).⁴

Foreign Relations

In his relations with the Hellenistic powers Bindusāra pursued a pacific policy. We learn from the classical

¹ "You do not learn how far this (my) object reaches." (Hultzsch, *Inscriptions of Aśoka*, p. 95).

² "It happens in the administration (of justice) that a single person suffers either imprisonment or harsh treatment. In this case (an order) cancelling the imprisonment is (obtained) by him accidentally, while (many) other people continue to suffer. In this case you must strive to deal (with all of them) impartially." (Hultzsch, p. 96).

³ "I shall send out every five years (a *Mahāmātra*) who will be neither harsh nor fierce, (but) of gentle actions (*viz.*, in order to ascertain) whether (the judicial officers) paying attention to this object...are acting thus, as my instruction (implies)." (Hultzsch p. 97).

⁴ *Divyāvadāna*, p. 372. The emendation **Khaśa** is supported by the testimony of Tāranātha (IHQ. 1930, 334). For the **Khaśas** see *JASB*, (Extra No. 2. 1899).

writers¹ that the king of Syria despatched to his court an ambassador named Deīmachos. Pliny² tells us that (Ptolemy II) Philadelphos King of Egypt (B. C. 285-247), sent an envoy named Dionysios. Dr. Smith points out that it is uncertain whether Dionysios presented his credentials to Bindusāra or to his son and successor, Aśoka. It is, however, significant that while Greek and Latin writers refer to Chandragupta and Amitraghāta they do not mention Aśoka. This is rather inexplicable if an envoy whose writings were utilized by later authors, really visited the third of the great Mauryas. Patrokles,³ an officer who served under both Seleukos and his son, sailed in the Indian seas and collected much geographical information which Strabo and Pliny were glad to utilize. Athenaios tells an anecdote of private friendly correspondence between Antiochos (I, Soter), king of Syria, and Bindusāra which indicates that the Indian monarch communicated with his Hellenistic contemporaries on terms of equality and friendliness. We are told on the authority of Hegesander that Amitrochātes (Bindusāra), the king of the Indians, wrote to Antiochos asking that king to buy and send him sweet wine, dried figs, and a sophist, and Antiochos replied: We shall send you the figs and the wine, but in Greece the laws forbid a sophist to be sold.⁴ In connection with the demand for a Greek sophist it is interesting to recall the statement of Diodoros that one Iamboulos was carried to the king of Palibothra (Pāṭaliputra) who had a great love for the Graecians. Dion Chrysostom asserts that the poetry of Homer is sung by the Indians

¹ e. g., Strabo.

² McCrindle, *Ancient India as described in Classical Literature*, p. 108.

³ Smith, *Aśoka*, third edition, p. 19.

⁴ McCrindle, *Inv. Alex.*, p. 409. Hultsch, *Aśoka*, p. xxxv. Bindusāra's interest in philosophy is also proved by his association with Ajīva-parivrajakas, (*Dīvyāvadāna*, 370 ff), Cf., also the first lines of Pillar Edict VII.

who had translated it into their own language and modes of expression.¹ Garga and Varāhamihira in a later age testify to the honour that was paid to Greeks for their knowledge of astronomy.²

Bindusāra's Family

Bindusāra had many children besides Aśoka, the son who succeeded him on the throne. We learn from a passage of the Fifth Rock Edict in which the duties of the *Dharma-mahāmātras*³ are described, that Aśoka had many brothers and sisters. The *Divyāvadāna* mentions two of these brothers, namely, Susīma and Vigataśoka.⁴ The Ceylonese Chronicles seem also to refer to these two princes though under different names, calling the former Sumana and the latter Tishya. Susīma-Sumana is said to have been the eldest son of Bindusāra and a step-brother of Aśoka, while Vigataśoka-Tishya is reputed to have been the youngest son of Bindusāra and a co-uterine brother of Aśoka, born of a Brāhmaṇa girl from Champā.⁵ Hiuen Tsang mentions a brother of Aśoka named Mahendra. Ceylonese tradition, however, represents the latter as a son of Aśoka. It is possible that the Chinese pilgrim has confounded the story of Vigataśoka with that of Mahendra.⁶

¹ McCrindle, *Ancient India*, p. 177. Cf. Grote, XII. p. 169, possible representation of a Greek drama on the Hydaspes.

² *Bṛhat Samhitā*, II, 14. Aristoxenus and Eusebius refer to the presence in Athens, as early as the fourth century B. C., of Indians who discussed philosophy with Socrates. (A note by Rawlinson quoted in the *Amrita Bazar Patrika*, 22-11-36, p. 17).

³ "High Officers for the Establishment and Propagation of the Law of Duty." Pp. 369-73; Smith, *Aśoka* 3rd ed., pp. 247 ff.

⁴ According to R. L. Mitra (*Sanskrit Buddhist Literature of Nepal*, 8) and Smith the name of Aśoka's mother was Subhadraśrī. Bigandet II* 128 mentions Dhammā as the mother of Aśoka and Tissā.

⁵ Cf. Smith, *Aśoka*, 3rd ed., p. 267.

Bindusāra died after a reign of 25 years according to the *Purāṇas*, and 27 or 28 years according to Buddhist tradition.¹ According to the chronology adopted in these pages his reign terminated about 273 B.C.²

¹ Hultzsch points out (p. xxxii) that Burmese tradition assigns 27 years to Bindusāra, while Buddhaghoṣa's *Samanta-pāsādikā* agrees with the *Mahāraṃsa* in allotting 28 years to that king.

² Cf. Smith, *Asoka*, p. 73.

SECTION III. THE EARLY YEARS OF AŚOKA

Both the *Divyāvadāna* and the Ceylonese Chronicles agree that there was a **fratricidal struggle** after the death of Bindusāra. Aśoka is said to have overthrown his eldest step-brother with the help of Rādhagupta whom he made his *Agrāmātya* (Chief Minister). Dr. Smith observes,¹ "the fact that his formal consecration or coronation (*abhisheka*) was delayed for some four years² until 269 B.C., confirms the tradition that his succession was contested, and it may be true that his rival was an elder brother named Susima." In his *Aśoka*³ published a few months later, he says, "it is possible that the long delay may have been due to a disputed succession involving much bloodshed, but there is no independent evidence of such a struggle." Dr. Jayaswal⁴ gave the following explanation for the delay in Aśoka's coronation: "it seems that in those days for obtaining royal *abhisheka*⁵ the age of 25 was a condition precedent. This seems to explain why Aśoka was not crowned for three or four years after accession."⁶ The contention can hardly be accepted. The *Mahābhārata*, for instance, informs us that the *abhisheka* of king Vichitravīrya took place when he was a mere child who had not yet reached the period of youth:

*Vichitravīryaṅcha tadā
bālam aprāptayauvanam*

¹ *The Oxford History of India*, p. 93.

² *Mahāvamsa*, Geiger's translation, p. 25.

³ Third edition.

⁴ JBORS., 1917, p. 438.

⁵ There were other kinds of *abhisheka* also, e.g., those of *Tururāja*, *Kumāra*, and *Senāpati*, as we learn from the epics and the Kaṭṭilya (trans., 377, 391).

*Kururājye mahābahur
abhyashīñchadanantaram.*¹

Dr. Smith characterises² the Ceylonese tales which relate that Aśoka slew many of his brothers as silly because Aśoka certainly had brothers and sisters alive in the seventeenth and eighteenth years of his reign whose households were objects of his anxious care. But we should remember that the Fifth Rock Edict refers only to the family establishments of his brothers (*olodhanesu bhātinam*) as existing. This does not necessarily imply that the brothers themselves were alive. We should however, admit that there is nothing to show, on the contrary, that the brothers were dead. The Fifth Rock Edict, in our opinion, proves nothing regarding the authenticity or untrustworthiness of the Ceylonese tradition. In the Forth Rock Edict Aśoka himself testifies to the growth of unseemly behaviour to kinsfolk and slaughter of living creatures.

The first four years of Aśoka's reign is, to quote the words which Dr. Smith uses in another connection, "one of the dark spaces in the spectrum of Indian history; vague speculation, unchecked by the salutary limitations of verified fact, is at the best, unprofitable."³

Like his predecessors⁴ Aśoka assumed the title of *Devānampiya*. He generally described himself as *Devānampiya Piyaḍasi*.⁵ The name Aśoka is found only in literature, and in two ancient inscriptions, viz., the Māski Edict of Aśoka himself, and the Junāgaḍh inscription

¹ Mbh., I. 101. 12. As the *Ādiparva* refers to Dattāmītra and Yastana rule in the lower Indus valley its date cannot be far removed from that of Aśoka and Khāravēla. Cf. also the cases of Samprati *Parīśiṣṭa parvan*, IX. 53, who was anointed king though a baby in arms, and of Amma II, Eastern Chalukya.

² E.H.I., 3rd ed., p. 155.

³ Cf. Rock Edict VIII, Kālat, Shābbāzgarhi and Mānsahra Texts.

⁴ We have already seen that the epithet "*Piadaṁsana*" is sometimes applied to Chandragupta also (Bhandarkar, *Aśoka*, p. 5; Hultzsch, CII, Vol. I, p. xxx).

of the *Mahākshatrapa* Rudradāman I. The name Dharmāsoka is found in one Mediaeval epigraph, viz., the Sārnāth inscription of Kumāradevī.¹

During the first thirteen years of his reign Aśoka seems to have carried on the traditional Maurya policy of expansion within India, and of friendly co-operation with the foreign powers, which was in vogue after the Seleukidan war. Like Chandragupta and Bindusāra he was aggressive at home but pacific abroad. The friendly attitude towards non-Indian powers is proved by the exchange of embassies and the employment of *Yavana* officials like Tushāspha.² In India, however, he played the part of a conqueror. The *Divyāvadāna* credits him, while yet a prince with the suppression of a revolt in Taxila and the conquest of the Svaśa (Khaśa?) country. In the thirteenth year of his reign (eight years after consecration), he effected the **conquest of Kalinga**. We do not know the exact limits of this kingdom in the days of Aśoka. But if the Sanskrit epics and *Purāṇas* are to be believed, it extended to the river Vaitaraṇī in the north,³ the Amarakaṇṭaka Hills in the west⁴ and Mahendragiri in the south.⁵

An account of the Kalinga war and its effects is given in Rock Edict XIII. We have already seen that certain places in Kalinga formed parts of the Magadhan dominions in the time of the Nandas. Why was it necessary for Aśoka to reconquer the country? The question admits of only one answer, viz., that it

¹ Dharmāsoka-narādhipasya samaye Śri Dharmachakro Jino yādrik tannaya rakshitāḥ punarayañchakre tatopyadbhutam.

² Note also the part played by the Yona named Dhammarakkhita (*Mahāvamsa*, trans., p. 82).

³ Mbh., III. 114. 4.

⁴ *Kūrma Purāṇa*, II. 39, 9, *Vāyu*, 77, 4-13.

⁵ *Raghuvamśa* IV, 38-43; VI. 53-54.

severed its connection with Magadha after the fall of the Nandas. If the story of a general revolt in the time of Bindusāra be correct then it is not unlikely that Kalinga, like Taxila, threw off the allegiance of Magadha during the reign of that monarch. It appears, however, from Pliny, who probably based his account on the *Indika* of Megasthenes, that Kalinga was already an independent kingdom in the time of Chandragupta. In that case there can be no question of a revolt in the time of Bindusāra. Pliny says,¹ "the tribes called Calingae are nearest the sea...the royal city of the Calingae is called Parthalis. Over their king 60,000 foot soldiers, 1,000 horsemen, 700 elephants keep watch and ward in 'procinct of war'. "²

The Kalinga kings probably increased their army considerably during the period which elapsed from the time of Megasthenes to that of Aśoka, because during the war with Aśoka the casualties exceeded 2,50,000. It is, however, possible that the huge total included not only combatants but also non-combatants. The existence of a powerful kingdom so near their borders, with a big army 'in procinct of war,' could not be a matter of indifference to the kings of Magadha. Magadha learnt to

¹ Ind. Ant., 1877, p. 338.

² If, as is probable, Kalinga included at this time the neighbouring country of Aśmaka, then Parthalis may be the same as "Potali". For an interesting account of Kalinga and its early capitals Dantakūra and Tosali, see Sylvain Lévi, "*Pré-Aryen et Pré-Dravidien dans l'Inde*," J. A., Juillet-Septembre, 1923; and *Indian Antiquary*, 1926 (May), pp. 94, 95. "The appellation of Kalinga, applied to Indians throughout the Malay world, attests the brilliant rôle of the men of Kalinga in the diffusion of Hindu civilisation." Not far from the earliest capital (Paloura-Dantapura-Dantakūra) lay the *aphetorion*, "where vessels bound for the Golden Peninsula ceased to hug the shore and sailed for the open sea." Note, in this connection, the name Ho-ling (Po-ling, Kalinga) applied by the Chinese to Java (Tahakuso, I-tsing, p. xlvii) an island which was known by its Sanskrit name to Ptolemy (150 A. D.) and even to the *Bhāmāyaga* (*Kishk.* 40. 30). For the connection of early Kalinga with Ceylon, see *IA*, VIII. 2, 225.

her cost what a powerful Kalinga meant, in the time of Khāravēla.

We learn from the Thirteenth Rock Edict that Aśoka made war on the Kalinga country and annexed it to his empire. "One hundred and fifty thousand persons were carried away captive, one hundred thousand were slain, and many times that number died." Violence, slaughter, and separation from their beloved ones befell not only to combatants, but also to the *Brāhmaṇas*, ascetics, and householders.

The conquered territory was constituted a viceroyalty under a prince of the royal family stationed at Tosālī,¹ apparently situated in the Purī district. The Emperor issued two special edicts prescribing the principles on which both the settled inhabitants and the border tribes should be treated. These two edicts are preserved at two sites, now called *Dhauḷī*² and *Jaugaḍa*.³ They are addressed to the *Mahāmātras* or High Officers at Tosālī and Samāpā.⁴ In these documents the Emperor makes the famous declaration "all men are my children," and charges his officers to see that justice is done to the people.

The conquest of Kalinga was a great landmark in the history of Magadha, and of India. It marks the close of that career of conquest and aggrandisement which was ushered in by Bimbisāra's annexation of Aṅga. It

¹ Tosālī (variant Tosala) was the name of a country as well as a city. Lévi points out that the *Gaṇḍarīyūha* refers to the country (*Janapada*) of *Amita-Tosala* in the *Dakṣiṇāpūṭha*, "where stands a city named Tosala." In Brāhmanical literature Tosala is constantly associated with (South) Kosala and is sometimes distinguished from Kalinga. The form Tosalei occurs in the Geography of Ptolemy. Some mediaeval inscriptions (*Ep. Ind.*, IX. 286; XV 3) refer to *Dakṣiṇa* (South) Tosala and *Uttara* (North) Tosala.

² In Purī.

³ In Gaṇjam.

⁴ For the identification of Samāpā, see *Ind. Ant.*, 1923, pp. 66 ff.

opens a new era—an era of peace, of social progress, of religious propaganda and at the same time of political stagnation and, perhaps, of military inefficiency during which the martial spirit of imperial Magadha was dying out for want of exercise. The era of military conquest or *Digvijaya*¹ was over, the era of spiritual conquest or *Dhamma-vijaya* was about to begin.

We should pause here to give an account of the **extent of Aśoka's dominions** and the manner in which they were administered before the Emperor embarked on a new policy.

Aśoka mentions Magadha, Pāṭaliputra, Khalatikapavata (Barābar Hills), Kosambī, Lumbini-gāma, Kalinga (including Tosālī, Samāpā and Khepimṅgalapavata or the Jaugaḍa Rock), Aṭavī (the forest tract of Mid-India perhaps identical with Ālavī of the Buddhist texts), Suvarṇagiri, Isila, Ujjayinī and Takshaśilā expressly as being among those places which were under his rule.

Beyond Takshaśilā the empire stretched as far as the confines of the realm of "*Amṭiyako Yonarāja*," usually identified with Antiochos II Theos of Syria (261-246 B. C.), and included the wide territory round Shāh-bāzgarhi² and Mānsahra³ inhabited by the Yonas, Kambojas and the Gandhāras. The exact situation of this **Yona** territory has not yet been determined. The *Mahāvamsa* evidently refers to it and its chief city Alasanda which Cunningham and Geiger identify with the town of Alexandria (Begram, west of Kāpiśa)

¹ Cf. *sara-sake vijaya* (Bühler, cited in Hultzsch's *Inscriptions of Aśoka*, p. 26).

² In the Peshawār District.

³ In the Hazāra District.

founded by the Macedonian conqueror near Kābul.¹ **Kamboja**, as we have already seen, corresponds to Rājapura or Rajaur near Punch in Kaśmīra and some neighbouring tracts including Kāfiristān. The tribal territory of the **Gandhāras** at this time probably lay to the west of the Indus, and did not apparently include Takshaśilā which was ruled by a princely Viceroy, and was the capital of the province of Uttarāpatha.² The capital of Trans-Indian Gandhāra was Pushkarāvātī, identified by Coomaraswamy with the site known as Mīr Ziyārat or Balā Hisār at the junction of the Swāt and Kābul rivers.³

The inclusion of **Kaśmīra** within Aśoka's empire is proved by the testimony of Hiuen Tsang's *Records*⁴ and Kalhaṇa's *Rājatarāṅgiṇī*⁵. Kalhaṇa says: "The faithful Aśoka reigned over the earth. This king who had freed himself from sins and had embraced the doctrine of the *Jina* covered Śushkalettra and Vitastātra with numerous *Stūpas*. At the town of Vitastātra there stood within the precincts of the *Dharmārāṇya Vihāra* a *Chaitya* built by him, the height of which could not be reached by the eye. That illustrious king built the town of Śrīnagarī. This sinless prince after removing the old stuccoed enclosure of the shrine of *Vijayeśvara* built in its stead a new one of stone. He...erected within the enclosure of *Vijayeśa*, and near it, two temples which were called *Aśokeśvara*." The description of Aśoka as a follower of the *Jina*, i.e., *Buddha*, and the builder of numerous *stūpas* leaves no room for doubt that the

¹ Conn. AGI, 18. Geiger, *Mahācāṃsa*, 194. The Yona territory probably corresponds to the whole or a part of the Province of the *Paropamisadae*.

² Cf. Kaliṅga Edict; *Divyāvadāna*, p. 407, *Rājño'sokasy-uttarāpathe Takshaśilā nagaram*, etc.

³ Cf. *Carm. Lec.*, 1918, p. 51. *Indian and Indonesian Art*, 55

⁴ Watters, Vol. I, pp. 267-71.

⁵ I. 102-06.

great Maurya monarch is meant. We are told by Kalhaṇa himself that he is indebted for much of the above account to an earlier chronicler named Chhavillākara.

The inscriptions near Kālsī and those on the Rummindei and the Nigāli Sāgar pillars prove the inclusion of the Dehra-Dūn District and the Tarāi within the limits of Aśoka's Empire, while the monuments at Lalitapātan and Rāmpurwā attest his possession of the valley of Nepāl and the district of Champāran. Further evidence of the inclusion of the **Himālayan region** within Aśoka's empire is possibly furnished by Rock Edict XIII which refers to the Nābhapaṁtis of Nābhaka, probably identical with Na-pei-kea of Fa Hien,¹ the birthplace of Krakuchchhanda Buddha, about 10 miles south or south-west of Kapilavastu.²

According to Bühler, Rock Edict XIII also mentions two vassal tribes Viśa (Besatae of the *Periplus*?) and Vajri (Vrijikas?). More recent writers do not accept Bühler's reading and substitute (*Rāja*) *Visayamhi*, 'in the (king's) territory,' in its place. There is, thus no indubitable reference either to the Vrijikas or the 'Besatae' in the inscriptions of Aśoka.

We learn from the classical writers that the country of the **Gangaridae**, i.e., Bengal,³ formed a part of

¹ Legge, 64.

² "The *Brahma (vaiva-ta?) Purāṇa* assigns Nābhikapura to the territory of the Uttara-Kurus" (Hultzsch, CII, Vol. I, p. xxxixn). Mr. M. Govinda Pai (*Aiyangar Com. Vol. 36*), however, invites attention to the Nābhakānanas, apparently a southern people, mentioned in the Mbh. vi. 9. 59. In connection with the northern limits of the Maurya empire attention may also be invited to the statement in the *Divyāvadāna* (p. 372) about Aśoka's subjugation of the Svaśa (Khaśa?) country. According to a legend narrated by the Chinese pilgrims (Watters, *Yuan Chwang*, II, p. 295) exiles from Takshaśilā settled in the land to the east of Khoten in the days of Aśoka.

³ For early references to Vaṅga, see Lévi "Pré-Aryen et Pré-Dravidien dans l'Inde." For its denotation, see *Mānasi-o-Marmavāṇi*, Srāvāṇa, 1336

the dominions of the king of the Prasii, *i.e.*, Magadha, as early as the time of Agrammes, *i.e.*, the last Nanda king.¹ A passage of Pliny clearly suggests that the "Palibothri," *i.e.*, the rulers of Pāṭaliputra, dominated the whole tract along the Ganges.² That the Magadhan kings retained their hold on Bengal as late as the time of Aśoka is suggested by the testimony of the *Divyāvadāna*³ and of Hiuen Tsang who saw *Stūpa* of that monarch near Tāmralipti and Karṇasuvarṇa (in West Bengal), in Samatāṭa (East Bengal) as well as in Puṇḍravardhana (North Bengal). Kāmarūpa (Assam) seems to have lain outside the empire. The Chinese pilgrim saw no monument of Aśoka in that country.

We have seen that in the south the Maurya power at one time, had probably penetrated as far as the Podiyil Hill in the Tinnevely district.⁴ In the time of Aśoka the Maurya frontier had receded probably to the Pennār river near Nellore as the Tamil Kingdoms are referred to as "*Prachamta*" or border states and are clearly distinguished from the imperial dominions (*Vijita* or *Rājavishaya*), which stretched only as far south as the Chitaldrug District of Mysore. The major part of the

Several scholars find it mentioned in the *Āitareya Āraṇyaka*. But this is doubtful. Bodhāyana brands it as an impure country and even Patañjali excludes it from *Aryāvarta*. The country was, however, Aryanised before the *Manusmṛiti* which extends the eastern boundary of *Aryāvarta* to the sea, and the Jain *Prajñāpanā* which ranks Aṅga and Vāṅga in the first group of Aryan peoples. The earliest epigraphic reference to Vāṅga is probably that contained in the Nāgar-junikonda Inscriptions.

¹ McCrindle, *Inv. Alex.*, pp. 221, 281.

² *Ind. Ant.*, 1877, 339. *Megasthenes and Arrian* (1926), p. 141-2.

³ P. 427. Cf. Smith's *Aśoka*, 3rd ed, p. 255. The Mahāsthāna Inscription which is usually attributed to the Maurya period, contains no reference to Aśoka.

⁴ Mr. S. S. Desikar thinks that the last point reached by the Mauryas was the Veṅkaṭa hill (IHQ., 1928, p. 145). Prof. N. Sastri lays stress (ANM, pp. 253ff) on the legendary features of the account in Tamil texts.

Deccan was ruled by the viceregal princes of **Suvarṇagiri**¹ and **Tosali**, the *Mahāmātras* of Isila and Samāpā and the officers in charge of the **Aṭavi** or Forest Country.² But in the belt of land on either side of the Nerbudda, the Godāvarī and the upper Mahānadi there were, in all probability, certain areas that were technically outside the limits of the empire proper. Aśoka evidently draws a distinction between the forests and the inhabiting tribes which are in the dominions (*vijita*) and peoples on the border (*antā avijitā*) for whose benefit some of the *special* edicts were issued. Certain vassal tribes are specifically mentioned, *e.g.*, the Andhras, Palidas (Pāladas, Pārimidas), Bhojas and Raṭhikas (Riṣṭikas, Rāshṭrikas?). They enjoyed a status midway between the Provincials proper and the unsubdued borderers. The word *Petenika* or *Pitinika* mentioned in Rock Edicts V and XIII should not, according to Dr. D. R. Bhandarkar and some other writers, be read as a separate name but as an adjective qualifying *Riṣṭika* (Edict V) and *Bhoja* (Edict XIII). They draw our attention to certain passages in the *Āṅuttara Nikāya*³ where the term *Pettanika* occurs in the sense of one who enjoys property given by his father.⁴ The view that *Pitinika* is merely

¹ A clue to the location of this city is probably given by the inscriptions of the later Mauryas of the Koṅkaṇ and Khāndesh, apparently the descendants of the Southern Viceroy (*Ep. Ind.*, III. 136). As these later Maurya inscriptions have been found at Vāda in the north of the Thāpa district (*Bomb. Gaz.*, Vol. I, Part II, p. 14) and at Wāghli in Khāndesh (*ibid.*, 284), it is not unlikely that Suvarṇagiri was situated in that neighbourhood. Curiously enough, there is actually in Khāndesh a place called Songir. According to Hultzsch, (*CII.* p. xxxviii) Suvarṇagiri is perhaps identical with Kanakagiri in the Hyderabad State, south of Maski, and north of the ruins of Vijayanagara. Isila may have been the ancient name of Siddāpura.

² Edict XIII.

³ III. 76, 78 and 300 (P.T.S.).

⁴ *Ind. Ant.*, 1919, p. 80. *Cf.* Hultzsch, *Aśoka*, 10; *IHQ*, 1925, 387. Other scholars, however, identify the *Pitinikas* with the *Paṭhānakas* or natives of

an adjective of Rathika (Ristika) or Bhoja is not, however, accepted by Dr. Barua who remarks that "it is clear from the Pali passage, as well as from Buddhaghosha's explanations, that *Ratthika* and *Pettonika* were two different designations."

The **Andhras** are, as we have already seen, mentioned in a passage of the *Aitareya Brāhmaṇa*. The **Bhojas** are also mentioned in that work as rulers of the south.¹ Pliny, quoting probably from Megasthenes says that the Andaræ (Andhras) possessed numerous villages, thirty towns defended by walls and towers, and supplied their king with an army of 100,000 infantry, 2,000 cavalry and 1,000 elephants.² The earliest Andhra capital (Andhapura) was situated on the Telavāha river which, according to Dr. D. R. Bhandarkar, is either the modern Tel or Telingiri, both flowing near the confines of the Madras Presidency and the Central Provinces. But the identification is by no means certain.³ The Palidas were identified by Bühler with the

Palibhāṇ, and some go so far as to suggest that they are the ancestors of the Sātavāhana rulers of Palibhāṇ. See Woolner, *Aśoka Text and Glossary*, II, 113; also JRS., 1923, 92. Cf. Barua, *Old Brāhmī Ins.*, §. 211.

¹ For other meanings of Bhoja, see Mbh., Ādi., 84, 22; IA, V, 177; VI, 25-28; VII, 36, 254.

² Ind. Ant., 1877, p. 339.

³ P. 93 ante. In historical times the Andhras are found in possession of the Rṣiabhā and Guṇṭūr districts as we learn from the Mayidavolu plates and other records. The earliest capital of the Andhra country or "Andhrāpatha" known from the inscriptions is apparently Dharmśakaḍa at or near Amarāvati (or Revāḍa). Kubiraka of the Bhāṭṭiprola inscription (c. 200 B. C) is the earliest known ruler. One recension, in the Brāhmī script, of the Rock Edicts of Aśoka, has recently been discovered in the Kurnool District (IHQ, 1928, 791; 1931, 817 ff; 1933, 113 ff.; IA, Feb., 1933, p. 39) which falls within the "Andhra" area of the Madras Presidency. Recent discoveries of the Aśokan epigraphs include, besides the Yerragudi inscriptions (Kurnool District) two new Rock Edicts at Kophal in the South-West corner of the Hyderabad State. The Kophal inscriptions are found on the Gavimāṭh and the Palkigunḍu Hills. They belong to the class of Minor Rock Edicts.

Pulindas¹ who are invariably associated with the Nerbudda (Revā) and the Vindhyan region :—

Pulinda-rāja sundarī nābhimaṇḍala nipīta salilā
(Revā).²

*Pulindā Vindhya Pushikā(?) Vaidarbhā Daṇḍakaiḥ saha*³
*Pulindā Vindhya Mūlikā Vaidarbhā Daṇḍakaiḥ saha*⁴

Their capital Pulinda-nagara lay not far from Bhilsā and may have been identical with Rūpnāth, the find-spot of one recension of Minor Rock Edict I.⁵

Hultzsch, however, doubts the identification of the "Palidas" of Shahbazgarhi with the Pulindas, for the Kālsī and Gīrnār texts have the variants Pālada and Pārimda—names that remind us of the **Pāradas** of the *Vāyu Purāṇa*.⁶ the *Harivaṃśa*⁷ and the *Bṛihat Samhita*.⁸ In those texts the people in question are mentioned in a list of barbarous tribes along with the Śakas, Yavanas, Kambojas, Pahlavas, Khasas, Māhishikas, Cholas, Keralas, etc. They are described as *muktakeśā* ("having dishevelled hair"). Some of the tribes mentioned in the list belong to the north, others to the south. The association with the Andhras in Aśokan inscriptions suggests that in the Maurya period they may have been in the Deccan. But the matter must be regarded as not definitely settled. It is interesting to note in this connection that a river Pārādā (identified

¹ Hultzsch, *Asoka*, 48 (n. 14).

² Subhanda's *Vāsavadattā*.

³ *Mastya P.* 114, 48.

⁴ *Vāyu*, 56, 126.

⁵ The Navagrāma grant of the Mehārāja Hastin of the year 196 (A. D. 517) refers to a Pulinda-rāja-rāshya which lay in the territory of the Parivrajaka kings, i.e., in the Dabhāla region in the northern part of the present Madhya Pradesh (*Ep. Ind.*, xvi, 126).

⁶ Ch. 88, 128. Cf. Farabee in Gedroie (MacCrindle, Ptolemy, 1927), 320.

⁷ I, 14.

XIII, 9.

with the Paradi or Par river in the Surat District) is mentioned in a Nāsik inscription.¹

The **Bhojas** and the **Raṭhikas** (Riṣṭikas) were evidently the ancestors of the Mahābhojas and the Mahārāṭhis of the Sātavāhana period.² The Bhojas apparently dwelt in Berar,³ and the Raṭhikas or Riṣṭikas possibly in Mahārāshṭra or certain adjoining tracts.⁴ The former were, in later ages, connected by matrimonial alliances with chieftains of the Kanarese country.

In the west Aśoka's Empire extended to the Arabian Sea and embraced all the **Aparāntas**⁵ including no doubt the vassal state (or confederation of states) of Surāshṭra the affairs of which were looked after by the *Yavana-rāja* Tushāspha with Giri-nagara (Girnar) as his capital. Dr. Smith says that the form of the name shows that the *Yavana-rāja* must have been a Persian. But according to this interpretation the *Yavana* Dhammadeva, the *Śaka* Ushavadāta (Risahabha-datta), the *Parthian* Suviśākha and the *Kushān* Vāsudeva must have been all native Hindus of India. If Greeks and other foreigners adopted Hindu names there is no wonder that some of them assumed Irāṇic appellations. There is, then, no good ground for assuming that Tushāspfa was not a Greek, but a Persian.⁶

¹ Rapson, *Andhra Coins*, lvi. Pargiter places the Pāradus in the north-west, *AIHT*, p. 268. Cf. Paraḍens, Gedrosia (Ptolemy, ed. 1927), 320 and *Paraitakni*, *Ind. Alex.*, 41.

² Smith, *Aśoka*, third ed., pp. 169-70.

³ Cf. Bhoja-kata, Bhat kuli in Amraoti.

⁴ The *Rāmāyaṇa*, IV. 41. 10, places the Riṣṭikva between the Vidarbhas of (Berar) and the Māhishakas of the Nerbudda valley or of Mysore. *Raṭhika* is also used as an official designation and it is in that sense that the expression seems to be used in the Yerragudi inscription (*Ind. Culture*, I, 310; *Aiyangar Com.* Vol. 36; *IHQ*, 1933, 117).

⁵ Śūrpāraka, Nāsik, etc., according to the *Mārkandeya* P. 57, 49 52.

⁶ Cf. IA, 1919, 145; *EHVS*, 2nd, ed., pp. 26-29.

Rapson¹ seems to think that the Gandhāras, Kambojas, Yavanas, Rishṭikas, Bhojas, Petenikas, Pāladas and Andhras lay beyond Aśoka's dominions, and were not his subjects, though regarded as coming within his sphere of influence. But this surmise can hardly be accepted in view of the fact that Aśoka's *Dharma-mahāmātrās* were employed amongst them "on the revision of (sentences of) imprisonment or execution, in the reduction of penalties, or (the grant of) release" (Rock Edict V).² In the Rock Edict XIII, they seem to be included within the *Rāja-Vishaya* or the King's territory, and are distinguished from the real border peoples (*Amla, Prachamta*), viz., the Greeks of the realm of Antiochos and the Tamil peoples of the south (*Nīcha*). But while we are unable to accept the views of Rapson, we find it equally difficult to agree with Dr. D. R. Bhandarkar³ who denies the existence of Yonas and others as feudatory chieftains in Aśoka's dominions. The case of the *Yavana-rāja* Tushāspa clearly establishes the existence of such vassal chiefs whose peoples undoubtedly enjoyed partial autonomy though subject to the jurisdiction of special Imperial officers like the *Dharma-mahāmātrās*.

Having described the extent of Aśoka's empire we now proceed to give a brief account of its **administration**. Aśoka continued the Council government of his predecessors. There are references to the Emperor's dealings with the *Parishā* or *Parisha* in Rock Edicts III and VI. Senart took *Parishad* to mean *Sangha* and Bühler understood by it the Committee of caste or sect.

¹ CHI., pp. 514, 516.

² "They are occupied in supporting prisoners (with money), in causing (their) fetters to be taken off, and in setting (them) free" (Holtzsch, *Aśoka*, p. 8).

Aśoka, 28.

But Dr. K. P. Jayaswal pointed out that the *Parishā* of the Edicts is *Mantriparishad* of the *Arthaśāstra*.¹ The inscriptions prove that Aśoka retained also the system of Provincial Government existing under his forefathers. Tosali, Suvarṇagiri, Ujjayinī and Takshaśilā were each under a prince of the blood (*Kumāla* or *Ayaputa*).²

The Empire and the Princes were helped by bodies (*Nikāyā*) of officials who fell under the following classes :—

1. The *Māhāmātras*³ and other *Mukhyas*.
- 2-3. The *Rājūkas* and the *Raṭhikas*.
4. The *Pradeśikas* or *Prādeśikas*.
5. The *Yutas*.⁴
6. *Pulisā*.
7. *Paṭivedakā*.
8. *Vachabhūmikā*.
9. The *Lipikaras*.
10. The *Dūtas*.
- 11-12. The *Āyuktas* and *Kāranakas*.

¹ Compare the references to the "*Sarājikā Parishā*" in the *Mahāvastu*, Senart, Vol. III, pp. 362, 392. For different kinds of *Parishā*, see *Aṅguttara* I. 70.

² That *Ayaputa* or *Āryaputra* meant a member of a ruling house or clan appears probable from the evidence of the *Bālucharita*, attributed to Bhāsa, in which Vasudeva is addressed by a *Bhāṭa* as *Āryaputra*. Pandit T. Ganapati Śāstri further points out that in the *Scapnanātaka* the term *Āryaputra* is employed as a word of respect by the chamberlain of Vāsavadattā's father in addressing King Udayana (*Introduction to the Pratimā-nātaka*, p. 32). An interesting feature of Aśoka's administration was the employment of a Yavana governor or *episkopos* in one territory to which reference has already been made.

³ Cf. also *Arthaśāstra*, pp. 16, 20, 58, 64, 215, 237-39; Rājasekhara, *KM*, XLV. 53.

⁴ The *Yuktas* of the *Arthaśāstra*, pp. 59, 65, 199. *Rāmāyaṇa*, VI, 217, 34; *Mahābhārata*, II, 56, 18; *Manu*, VIII. 34; cf. the *Rāja-yuktas* of the *Sāntiparva*, 82. 9-15.

There was a body of *Mahāmātras* in each great city and district of the empire.¹ The inscriptions mention the *Mahāmātras* of Pāṭaliputra, Kauśāmbī, Tosālī, Samāpā, Suvarṇāgiri and Isila.² In the Kalinga Edicts we have certain *Mahāmātras* distinguished by the terms *Nagalaka* and *Nagala-Viyohālaka*. The *Nagalaka* and *Nagala-Viyohālaka* of the Edicts correspond to the *Nāgaraka* and *Paura-vyāvahārika* of the *Arthaśāstra*³ and no doubt administered justice in cities.⁴ In Pillar Edict I mention is made of the *Amṭa Mahāmātras* or the Wardens of the Marches, who correspond to the *Antapālas* of the *Arthaśāstra*⁵ and the *Goptris* of the age of Śkanda Gupta. The *Kauṭīliya* tells us that the salary of an *Antapāla* was equal to that of a *Kumāra*, a *Paura-vyāvahārika*, a member of the *Mantriparishad* or a *Rāshṭrapāla*.⁶ In Edict XII mention is made of the *Ithūjhaka Mahāmātras* who, doubtless, correspond to the *Stry-adhyakshas* (the Guards of the Ladies) of the epics.⁷

¹ The empire, as already stated, was divided into a number of provinces (*diśā, deśa* etc). Each province seems to have been further subdivided into *ānālas* or districts under regular civil administration, and *koṭṭa-vishayas* or territories surrounding forts (Hultzsch. p. xl). Each civil administrative division had a *pura* or *nagara* (city) and a rural part called *janapada* which consisted of *grāmas* or villages. An important official in each *janapada* was the *Rājūka*. The designations *Prādeśika* and *Raṭhika* possibly suggest the existence of territorial units styled *pradeśa* and *raṭṭha* or *rāshṭra*.

² *Mahāmātras* of Śrāvastī are according to certain scholars, mentioned in the Sobgaura copperplate inscription found in a village on the Rāptī, not far from Gorakhpur. But the exact date of the record is not known (Hoernle, JASB, 1894, 84; Fleet, JRAS, 1907, 523 ff.; Barua, *Ann. Bhand. Or. Res. Inst.*, xi, i (1930), 32ff.; IHQ, 1934, 54ff.; Jayaswal, *Ep. Ind.*, xxii, 2).

³ P. 20, 143 f. Cf. the royal *epistates* or city governor in the Antigonid realm (Tarn, GBL, 24).

⁴ Cf. also *Nagara-dhanya Vyāvahārika*, p. 55. The *Nagalaka* may have had executive functions as well, as is suggested by the evidence of the *Arthaśāstra* (II. Ch. 36).

⁵ Pp. 20, 247.

⁶ P. 247.

⁷ Rām. II. 16. 3 *Vṛiddhān cetrāpānin...stryadhyakshān*; Mbh. IX, 20, 68, 90; XV. 22, 20; 23, 12. Cf. the *Antarvamsika* of the *Arthaśāstra*.

As to the *Rājūkas*, Dr. Smith takes the word to mean a governor next below a *Kumāra*.¹ Bühler identifies the *Rājuka* of the Aśokan inscriptions with the *Rajjūka* or the *Rajjugāhaka Amachcha* (Rope-holder, Field-measurer or Surveyor) of the *Jātakas*.² Pillar Edict IV refers to the *Rājūkas* as officers "set over many hundred thousands of people," and charged with the duty of promoting the welfare of the *Jānapadas* to whom Aśoka granted independence in the award of honours and penalties. The reference to the award of penalties (*Daṇḍa*) probably indicates that the *Rājūkas* had judicial duties. In the Rock Edict III as well as in Pillar Edict IV they are associated with the *Yutas*, and in the Yerraguḍi inscriptions with the *Rathikas*.³ Strabo⁴ refers to a class of Magistrates (*Agronomoi*) who "have the care of the rivers, measure the land, as in Egypt, have charge also of hunters and have the power of rewarding or punishing those who merit either." The measuring of the land connects those Magistrates with the *Rajjugāhaka Amachcha* of the *Jātakas*,⁵ while the power of rewarding and punishing people connects them with the *Rājūkas* of Aśoka. It is probable, therefore, that the *Agronomoi* referred to by Strabo were identical with the *Rājūkas* and the *Rajjugāhaka Amachchas*. The *Arthaśāstra*⁶ refers to a class of officials called "*Chora Rajjukas*," but there

¹ *Aśoka*, 3rd ed., p. 94.

² *The Social Organisation in North-East India* by Fick, translated by S. Maitra, pp. 148-51.

³ I.H.Q. 1933, 117; Barua takes the expressions *Jānapada* and *Rathika* of the Yerraguḍi copy of the Minor Rock Edict to mean 'people of the district' and 'citizens of the hereditary tribal states' respectively. But *Rathika* of the record probably corresponds to *Rāshṭriya* of the Junāgaḍh inscription of Rudradāman so that the expressions *Jānapadas* and *Rathikas* mean 'people of the country parts,' and 'officials of the district.' Cf. *Rathika Mahāmātra* of *Bṛīhat Saṁ.*, XV. 11.

⁴ H. & F., Vol. III, p. 103.

Cf. Maitra, Fick, pp. 148-49.

P. 234.

is no reference to the *Rajjukas* proper although on p. 60 "*Rajju*" is mentioned in conjunction with "*Chora Rajju*."

As regards the *Pradeśikas* or *Prādeśikas*, Senart, Kern and Bühler understood the term to denote local governors or local chiefs. Smith took it to mean District Officers. Hultzsch compares it with *Prādeśikeśvara* of Kalhaṇa's *Rājataranginī*.¹ The word occurs only in the Third Rock Edict where the functionaries in question are included with the *Rājūkas* and the *Yutas* in the ordinance of the *Anusamyāna* or circuit. Thomas derives the word from *pradeśa* which means report² and identifies the *Prādeśikas* or *Pradeśikas* of the Edict with the *Pradeshtṛis* of the *Arthasāstra*.³ The most important functions of the *Pradeshtṛis* were *Bali-pragraha* (collection of taxes or suppression of recalcitrant chiefs), *Kaṇṭakaśodhana* (administration of criminal justice), *Choramārgaṇa*, (tracking of thieves) and *Adhyakshāṇām adhyaksha purushāṇām cha niyamanam* (checking superintendents and their men). They acted as intermediaries between the *Samāhartrī* on the one hand and the *Gopas*, *Sthānikas* and *Adhyakshas* on the other.⁴ It is, however, doubtful if the *Prādeśikas* can really be equated with Reporters. The more probable view is that they correspond to the subordinate governors, the *nomarchs*, *hyparchs* and *meridarchs* of the Hellenistic kingdoms.

As to the *Yutas* or *Yuktas*, they are described by Manu⁵ as the custodians of *Pranashṭādhigata dravya*

¹ IV. 126.

² JRAS, 1915, p. 97, *Arthasāstra*, p. 111. In the Vishṇu Purāṇa, V, 26
³ *Pradeśa* has apparently the sense of counsel, instruction. S. Mitra suggests, (*Indian Culture*, I, p. 310) that the *Prādeśikas* were *Mahāmātras* of the Provincial governments, while the *Rājūkas* were *Mahāmātras* of the central government.

⁴ Cf. The Irda grant where *Pradeshtṛis* find mention along with *Sanghamukhyas* and others.

⁵ Cf. *Arthasāstra*, pp. 142, 200, 217, 222. as stated above *Pradeshtṛis* also occur in the Irda grant, *Ep. Ind.*, XXII, 150 ff.

⁶ VIII. 31.

(lost property which was recovered). In the *Arthasāstra* too, they are mentioned in connection with *Samudaya* or state funds¹ which they are represented as misappropriating. Hultzsch suggests that they were 'secretaries' employed for codifying royal orders in the office of the *Mahāmātras*. The *Pulisā* or Agents are apparently identical with the *Purushas* or *Rāja Purushas* of the *Arthasāstra*.² Hultzsch prefers to equate them with the *Gūḍha-purushas* and points out that they were graded into high ones, low ones, and those of middle rank.³ They were placed in charge of many people⁴ and controlled the *Rājūkas*. The *Paṭivedakā* or Reporters are doubtless the *Chāras* mentioned in Chapter 16 of the *Arthasāstra*,⁵ while the *Vachabhūmikas* or "Inspectors of cowpens" were evidently charged with the superintendence of "*Vraja*" referred to in Chapter 24.⁶ The *Lipikaras* are the royal scribes one of whom, *Chapaḍa*, is mentioned by name in Minor Rock Edict II. *Dūtas* or envoys are referred to in Rock Edict XIII. If the *Kauṭīliya* is to be believed, they were divided into three classes, viz., *Nisprishṭārthāḥ* or Plenipotentiaries, *Parimitarthāḥ* or Charges d'Affaires and *Sāsanaharas* or conveyers of royal writ.⁷ The *Āyuktas* possibly find mention in the Kalinga Edicts. In the early Post-Mauryan and Scythian Age *Āyuttas* appear as village officials.⁸ In the Gupta Age they figure as officers in charge of

¹ Cf. also *Mbh.*, ii. 5. 72. *Kachchichāya vyāye yuktah sarve ganaka lekhaḥkḥ.*

² Pp. 69, 76.

³ The three classes of *Purushas* are also known to the Great epic (*Mbh.*, ii. 5. 74).

⁴ Pillar Edict VII.

⁵ P. 35.

⁶ Pp. 59-60.

⁷ With the *Sāsanaharas* may be compared the *Lekha-harakas* of the *Harshacharita*, *Uchchhāsa* II, p. 52.

⁸ Lüders' List, No. 1347.

Vishayas or districts,¹ and also as functionaries employed in restoring the wealth of conquered kings. The full designation of the officers in question was *Āyukta-Purusha*.² They may have been included under the generic name of *Pulisā* referred to above. The *Kāranakas* who appear to be mentioned in the Yerraguḍi copy of Aśoka's Minor Rock Edict, probably refer to judicial officers, teachers, or scribes.³

¹ *Ep. Ind.*, XV, No 7, 138

² *Fleet*, CII, pp. 8, 14.

³ Cf. *Kāranika*, Officer-in-Charge of Documents or Accounts (IHQ, 1935, 586). In inscriptions of the seventh century A.D. the word *karāṇa* stood for *Adhikarāṇa* (Departmental or District Secretariat). *Prabāsi*, 1350 B.S. *Srāvāṇa*, 294. In *Mbh.* ii. 5, 34, *Kāranika* has, according to the commentary, the sense of a teacher. In the text itself the officers in question instruct the *Kumāras* and have to be *dharme sarvaśāstreshu kovidāḥ*, implying that their duties included among other things, those relating to *Dharma* (law, justice?).

✓ CHAPTER V. THE MAURYA EMPIRE :

THE ERA OF DHAMMAVIJAYA AND DECLINE.

SECTION 1. AŚOKA AFTER THE KALINGA WAR.

*Chakkavatti ahum rājā Jambusaṇḍassa issaro
muddhābhisitto khattiyo manussādhipatī ahum
adaṇḍena asatthena vijeyya paṭhavim imam
asāhasena dhammena samena maṇusāsīyā
dhammena rajjam kāretvā asmim paṭhavimaṇḍale*
—*Aṅguttara Nikāya.*

We have already seen that the Kalinga war opened a new epoch in the history of Magadha and of India. During the first thirteen years of his reign Aśoka was a typical Magadhan sovereign—the inheritor of the policy of Bimbisāra, of Mahāpadma and of Chandragupta—conquering peoples, suppressing revolt, annexing territory. After the Kalinga war all this is changed. The older political philosophy which tradition associates with the names of Vassakāra and Kauṭilya gave way to a new statecraft inspired by the teaching of the sage of the Sākyas. Before proceeding to give an account of the remarkable change we should say a few words about the religious denominations of India and the condition of society during the reign of the great innovator.

In the days of Aśoka the people of India were divided into many sects of which the following were the most important:—

1. The orthodox *Deva*-worshippers.¹
2. The *Ājīvikas* or the followers of Gosāla Maṅkhaliputta.²

¹ Among the *Devās* worshipped in the Maurya period, Patañjali makes special mention of Śiva, Skanda and Viśākha.

² This teacher was born in Saravap, probably near Sāvasthī or Śrāvastī. Jaina writers represent him as a person of low parentage and of contemptible

3. The *Nirgranthas* or *Jainas*, i.e., the followers of Niganṭha Nātaputta who is commonly called Mahāvīra or Vardhamāna.

4. The followers of Gautama Buddha Śākyamuni.

5. Other sects alluded to in Pillar Edict VII.

In Edict IV we have the following account of the prevailing state of society: "for a long period past, even for many hundred years, have increased the sacrificial slaughter of living creatures, the killing of animate beings, unseemly behaviour to relatives, unseemly behaviour to *Brāhmaṇas* and ascetics (*Śramaṇas*)."¹ Kings used to go out on so-called *Vihāra yātrās*² in which hunting and other similar amusements used to be practised.³ The people performed various ceremonies (*maṅgala*)⁴ on occasions of sickness, weddings of sons,⁵ the weddings of daughters, the birth of children, and

character. The attitude of Buddhist authors is also not friendly. In reality he was one of the leading sophists of the sixth century B. C., and, for a time, was a close associate of Mahāvīra. According to the *Ajivika* belief as expounded in the *Sāmañña-phala Sutta* "the attainment of any given condition, of any character, does not depend on human effort (*purisa-kāre*). There is no such thing as power or energy, or human strength or human vigour (*purisaparakkamo*). All beings...are bent this way and that by their fate (*niyati*)."⁶ (*Dialogues*, Pt. I, p. 71; Barua, *The Ajivikas*, 1920, p. 9). An *Ajivaparivrajaka* appears as a court astrologer of Bindusāra in the *Divyāvadāna* (pp. 370 ff.). A tax on "Ajivakas" is referred to in an inscription of the twelfth century A.D. (Hultzsch, *SIL*, I, 88) showing that the sect flourished in S. India even in that late age. See also A. L. Basham, *The Ajivikas*.

¹ Cf. Ajātasatru's treatment of Bimbisāra, Viṇḍubha's massacre of the Śākyas, Udayana's cruelty towards Pipphala, and Nanda's haughty demeanour towards Chānakya.

² Tours of pleasure, cf. Kauṭilya, p. 332. *Mahābhārata*, XV, 1, 18:

*Vihārayātrāsu punaḥ Kurarōjo Yudhiṣṭhiraḥ
sarvān kāmān mahātējāḥ pradādāv-Ambikāro.*

³ R. Edict VIII.

⁴ For "Maṅgala" see also *Jātakas* No. 87, and No. 163 (*Hotthi-maṅgala*), and *Hansa-charita*, II (p. 27 of Parab's edition, 1918).

⁵ For *Avāha* and *Vivāha* see also *Mbh.*, V, 141, 14; Kauṭilya, VII, 15.

departure on journeys. The womankind performed many, manifold, trivial and worthless ceremonies.¹

From the references in the Edicts to Brāhmaṇas, Kaivartas (of Kevata *bhoga*) and Śramaṇas, *Bhikshu* and *Bhikṣuṇī-Saṃghas* it may be concluded that *Varna* (social gradation) and *Āśrama* (stages of socio-religious discipline) were established institutions. The position of the slaves and labouring poor in general (*dāsa*, *bhataka*) was, in some cases at any rate, not enviable. Women had to tolerate the *purdah* as well as polygamy. Ladies of the harem were under special guards (*stry-adhyaksha*). As will be seen in the following pages, the policy of Aśoka in regard to social matters was, in the main, one of mitigation and not, except in respect of certain kinds of *Samāja* and sundry obnoxious practices, of radical reform.

The Change of Aśoka's Religion

Aśoka had doubtless inherited the traditional devotion of Hindu kings to the gods (*devas*) and the Brāhmaṇas and, if the Kāśmīra chronicle of Kalhaṇa is to be believed, his favourite deity was *Śiva*. He had no scruples about the slaughter of men and animals: "formerly, in the kitchen of His Sacred and Gracious Majesty the King each day many hundred thousands of living creatures were slaughtered to make curries." The hecatombs of thousands of men and women sent to their doom during the Kalinga war have already been mentioned. The sight of the misery and bloodshed in that sanguinary campaign made a deep impression on him and awakened in his breast feelings of *anusochana*, "remorse, profound sorrow, and regret". About this time he came under the influence of Buddhist teaching. We read in Rock Edict XIII "after that, now that the Kalingas had been annexed, began His Sacred Majesty's zealous practice of the Law

¹ R. Edict IX.

of Piety (*dhramaśilana*), his love of that Law (*dhramakamata*), and his inculcation of that Law (*dhramanuśasti*)."¹

Although Aśoka became a Buddhist² he was not an enemy either of the *Devas* or of the *Brāhmaṇas*. Up to

¹ The view held by some wellknown writers that the conversion of Aśoka took place *before* the Kalinga war rests on the evidence of the *Mahāvamsa* (Ch. V) and on certain assumptions, viz., that Aśoka's *dhramakamata* became *tīra* (intense) immediately after the Kalinga war (there being no interval) and that Aśoka was indifferent during the period of *Upāsakatva* (when he was only a lay disciple) which, therefore, must have preceded the Kalinga war, immediately after which his devotion became *tīra*. But the so-called indifference or want of activity is only relative. On the other hand, the supporters of the new theory have to explain why a recent convert to Buddhism should engage in a sanguinary conflict involving the death of countless *Sramaṇas*. Why again do the Minor Rock Edicts refer to contact with the *Samgha*, and not the Kalinga war, as the prelude and cause of more intense activity? It is to be noted that activity in the period of *Upāsakatva* is also described as *porākrama*, though it was surpassed by the greater energy of the period after contact with the Holy Order. Note also the explicit reference to *dhramakamata* as the result of the annexation of Kalinga *sometime after* (*tato pachhā adhunā*) the war. The use of the expressions *tato pachhā* and *adhunā* suggests that an interval supervened between the war and the intensity of Aśoka's *dhramaśilana* and *dhramakamata*. Moreover, we learn from the Minor Edicts and Pillar Edict VI that pious proclamations began to be issued a little more than 2½ years after Aśoka became an *Upāsaka* and 12 years after his coronation. This would place his conversion a little less than 9½ years after his *Abhisheka*, i.e., a little less than 1½ years after the Kalinga war.

² *Sākya* (Rūpnāth), *Buddha Sākya* (Maski), *Upāsaka* (Sahasrām); see Hultzsch, CII, p. xlv. Cf. also Kalhana, *Rājatarangīni*, 1. 102ff. That Aśoka did become a Buddhist admits of no doubt. In the Bhābrū Edict he makes an open confession of his faith in the Buddha, the *Dharma* (Doctrine) and the *Samgha* (Order of Monks). He called the Buddha *Bhagavat*. He went on pilgrimage to the places of the Blessed One's nativity and enlightenment and worshipped at the former place. He declared that whatsoever had been spoken by the Buddha, all that was quite well spoken. He also believed in the cult of the "former" Buddhas. He took much interest in the exposition of the Buddhist Doctrine so that it might endure long. As to the *Samgha* he kept in close touch with it since his memorable visit to the Fraternity a year or so after his conversion. He impressed on the clergy the need of a correct exposition of the true doctrine and appointed special officers to busy themselves with the affairs of the Brotherhood. He also laid emphasis on *Vinaya-samutkarsha* and took steps to maintain the integrity of the Church and prevent schism within its fold.

the last he took pride in calling himself *Devānampiya*, beloved of the gods.¹ He found fault with unseemly behaviour towards Brāhmaṇas² and inculcated liberality to the same class. He was perfectly tolerant. "The king does reverence to men of all sects."³ He reprobated *ātmapāsamḍa-pūjā*, honour to one's own sect, when coupled with *para-pāsamḍa-garahā*, disparagement of other sects. That he was sincere in his professions is proved by the Barābar Cave Dedications to the *Ājīvika* monks. His hostility was chiefly directed not towards the *Devas* and the Brāhmaṇas, not even towards *Varṇāśrama*, but the killing of men in war and *Samājas* (festive gatherings), ill-treatment of friends and acquaintances, comrades and relatives, slaves and servants, the slaughter of animals in sacrifice, and the performance of vulgar, useless and offensive ceremonies.

The Change of Foreign Policy

The effect of the change of religion was at once felt in foreign policy. The Emperor declared that "of all the people who were slain, done to death, or carried away captive in Kalinga, if the hundredth part or the thousandth part were now to suffer the same fate, it would be a matter of regret to His Sacred Majesty. Moreover, should any one do him wrong, that too must be borne with by His Sacred Majesty, so far as it can possibly be borne with." In *Kalinga Edict I*, the Emperor expressed his desire that the unsubdued peoples in the frontiers of the imperial dominions (*Amtā avijitā*) "should not be afraid of him, that they should trust him, and should receive from him happiness not sorrow." The chiefest

¹ The title is reminiscent of the age of Hammurabi (Camb. Anc. Hist. I, p. 511).

² Edict IV.

³ Edict XII.

conquest in the Emperor's opinion was the conquest by righteousness (*Dhamma-vijaya*). In Edict IV he exultingly says, "the reverberation of the kettle-drums (*Bherighoso*) has become the reverberation of the Law of Piety (*Dhammaghoso*)."¹ Not content with what he himself did he called upon his sons and even his great grandsons to eschew new conquests—*putra papotra me asu navam vijayam ma vijetaviyam*. Here we have a complete renunciation of the old policy of military conquest or *Digvijaya* and the enunciation of a new policy, viz., that of *Dhammavijaya*.¹ The full political effects of this change of policy became manifest only after the death of Aśoka, perhaps even after the 27th year of his consecration. From the time of Bimbisāra to the Kalinga war the history of India was the story of the expansion of Magadha from a tiny state in South Bihār to a gigantic Empire extending from the foot of the Hindukush to the borders of the Tamil country. After the Kalinga war ensued a period of stagnation at the end of which the process is reversed. The empire gradually dwindled down in extent till it sank to the position from which Bimbisāra and his successors had raised it.

¹ The Aśokan conception of *Dhammavijaya* was similar to that described in the *Chakkaratti Sihanāda Sutta*, "conquest not by the scourge, not by the sword, but by righteousness" (*Dialogues of the Buddha*, Part III, p. 59). It was different from the Hindu conception explained and illustrated by the *Mahābhārata* (XII. 59, 38-39), the *Harivamśa* (I. 14.21), the *Kautilya* (p. 382), and the *Raghuvamśa* (IV. 43). Attention may be invited in this connection to a Statement of Arrian that "a sense of justice prevented any Indian king from attempting conquest beyond the limits of India" (*Camb. Hist. Ind.* I. 321); M'crindle, *Ancient India as described by Megasthenes and Arrian*, 209. Incidentally it may be pointed out that the discourse entitled the *Chakkaratti Sihanāda* (*Lion Roar of the Chakravarti* or emperor who 'conquers by righteousness') possibly affords a clue to a proper appreciation of the famous Sarnath Capital with its *Chakra* and crowning lions. Cf. also *Rāmāyaṇa* II. 10.33: *Yāvadāvartate chakram tāvati me vasundharā*, IC, XV, 1-4, p. 179f.

True to his principle Aśoka made no attempt to annex the frontier (*Prachamta, amta, sāmanta, sāmīpa*), kingdoms, viz., Chola, Pāṇḍya, Satiyaputra, Keralaputra Tainbaparāṇi (Ceylon) and the realm of *Aṁtiyako Yonarāja*, who is usually identified with Antiochos II Theos, King of Syria and Western Asia. On the contrary, he maintained friendly relations with them.

The **Chola** country was drained by the river Kāverī and comprised the districts of Trichinopoly and Tanjore. We learn from a South Indian inscription¹ that Hara, i.e., the god Śiva, asked Gunabhara (Mahendravarman I, Pallava), "How could I, standing in a temple on earth, view the great power of the Cholas or the river Kāverī?"² When Pulakeśin II Chalukya strove to conquer the Cholas "the Kāverī had her current obstructed by the causeway formed by his elephants."³ The Chola capital was Uraiyūr (*Sanskrit* Uragapura) or Old Trichinopoly.³ The principal port was at Kāviriṭṭinam or Pugār on the northern bank of the Kāverī.³

The **Pāṇḍya** country corresponded to the Madurā, and Tinnevely districts with perhaps the southern portions of Rāmnad and the Travancore Cochin state. It had its capitals at Kolkai and Madurā (*Dakṣhiṇa* Mathurā). The rivers Tāmraparṇī and Kṛitamālā or Vaigai flowed through it. Kātyāyana derives Pāṇḍya from Pāṇḍu. The Pāṇḍus are

¹ Hultzsch, *SII*, Vol. I, p. 34.

² Aelian, however, has the following reference to the realm of Soras (Chola?) and its chief city: "There is a city which a man of royal extraction called Soras governed at the time when Eukratides governed the Bactrians, and the name of that city is Perimunda (city of Perumal?). It is inhabited by a race of fish-eaters who go off with nets and catch oysters." For Urugapura in Cholika Visbhaya, see *Ep. Ind.*, X, 103.

³ For the early history of the Chola Kingdom and other Tamil states see CHI, Vol. I, Ch. 34; Smith, *EHI*, Ch. XVI; Kanakasabhai Pillay, *Tamil Eighteen Hundred Years Ago*; Krishnaswami Aiyangar, *Beginnings of South Indian History and Ancient India*; K. A. Nilakanta Sastri, *The Pāṇḍyan Kingdom, The Colas, etc.*

mentioned as the ruling race of Indraprastha in the *Mahābhārata* as well as in several *Jātakas*,¹ Ptolemy (cir. 150 A. D.) speaks of the country of the Pandouoi in the Pañjāb. There can be no doubt that Pāṇḍu was the name of a real tribe or clan in northern India. Kātyāyana's statement regarding the connection of the Pāṇḍyas with the Pāṇḍus receives some support from the fact that the name of the Pāṇḍya capital (Madurā) was identical with the famous city of Mathurā in the Sūrasena country which, according to Epic tradition, was the seat of a family intimately associated by ties of friendship and marriage with the Pāṇḍus of Indraprastha. The connection between the Pāṇḍus, the Sūrasenas and the Pāṇḍyas seems to be alluded to in the confused stories narrated by Megasthenes regarding Herakles and Pandaia.²

Satiyaputra is identified by Mr. Venkatesvaraiyar³ with *Satya-vrata-kshetra* or Kāñchīpura. But Dr. Aiyangar points out that the term *Satya-vrata-kshetra* is applied to the town of Kāñchī or a part of it, not to the country dependent upon it. There is besides the point whether *vrata* could become *puta*. Dr. Aiyangar supports Bhandarkar's identification with Satpute. He takes Satiyaputra to be a collective name of the various matriarchal communities like the Tulus and the Nāyars of Malabar.⁴ According to Dr. Smith⁵ Satiyaputra is represented by the Satyamaṅgalam Tāluk of Coimbatore. Mr. T. N. Subramaniam⁶ prefers Koṅgunāḍu ruled by the

¹ I find it difficult to agree with Dr. Barua, *Inscriptions of Aśoka*, Part II (1943), p. 232, that the "line of Yudhisṭhira" "that ruled at Indraprastha in the Kuru country" "has nothing to do with Pāṇḍu's eldest son."

² *Ind. Ant.*, 1877, p. 249.

³ *JRAS*, 1918, pp. 541-42.

⁴ *JRAS*, 1919, pp. 581-84.

⁵ *Aśoka*, Third Ed., p. 161.

⁶ *JRAS*, 1922, 86.

Koṣar people famous for their truthfulness. Mr. K. G. Sesha Aiyar¹ takes Satiyaputra to be the equivalent of Atiyamān, chief of Kutiraimalai with his headquarters at Takaḍūr, now in Mysore. Mr. P. J. Thoma, however, gives reasons for identifying it with "Satyabhūmi" of the *Keralolpatti*, a territory which corresponds roughly to "North Malabar including a portion of Kasergode Tāluk, South Canara."²

Keralaputra (Ketalaputo or Chera) is "the country south of Kūpaka (or Satya), extending down to Kanneti in Central Travancore (Karunagapalli Tāluk). South of it lay the political division of Mūshika."³ It was watered by the river Periyar, perhaps identical with the Churṇī of the *Arthaśāstra*⁴ on the banks of which stood its capital Vañji (near Cochin) and at its mouth the seaport of Muziris (Kranganur).

Ceylon was known in ancient times as Pārasamudra⁵ as well as Tāmraparṇī (Greek Taprobane).⁶ Tāmraparṇī,

¹ *Cera kings of the Sangam period*, 17-18, cf. now N. Sastri, ANM, 26.

² JRAS, 1923, p. 412. B. A. Saletore is, however, inclined to disparage the authority of the *Keralolpatti* (*Indian Culture*, I 668). But Kirtel points out (*Die Cosmographie Der Inder*, 1920, p. 78) that Satiya (variants Sattiratha, Sanipa) finds mention in the list of southern Janapadas, along with the Mūshikas, in the *Jambukhaṇḍa* section of the *Mahābhārata* (Bk. VI.). For other views see *Ind. Cult.*, Vol. II, 549 ff.; *Aiyangar. Com. Vol.*, 45-47. Mr. M. G. Pai suggests that 'Satiya' corresponds to *Sāntika* of the *Mārkaṇḍeya Purāṇa*, 58.37, and the *Byḥat Saṁhitā*, xiv, 27, and included South Kanara. Cf. *Setae* of pliny, (Bomb. Gaz. Gujrat, 533).

³ JRAS, 1923, p. 413.

⁴ P. 75. Cf. *Śuka saṁdēsa* (Aiyar, *Cera kings*, 94).

⁵ Greek Pārasimundu, see Ray Chaudhuri, *Ind. Ant.*, 1919, pp. 195-96, commentary on the *Kautilya*, Ch. XI; *Rāmāyaṇa*, VI, 3, 21 (Laṅkā described as *sthita "pāre samudrasya"*).

On reading Law's *Ancient Hindu Polity* (p. 87 n.) I find that the identification was also suggested by Mr. N. L. Dey. The equation Pārasamudra = Pārasimundu is not less plausible than the equations Sātavāhana = Śālivāhana; Kātāba = Kaḍāram = Kiḍāram = Kantoli (pace Dr Majumdar, *Suvaryadriya*, 56, 79. 168).

⁶ For other names of Ceylon see "*Megasthenes and Arrian*" published by Chuckerverti and Chatterjee, 1926, p. 60 n. For a short history of the island

i.e., Tāmraparṇī is mentioned in Rock Edicts II and XIII of Aśoka. Dr. Smith lately¹ took the word to mean not Ceylon but the river Tāmraparṇī in Tinnevely. He referred to the Girnar text “*ā Tambapamni*” which according to him indicated that the river was meant, not the island. Now, in Edict II the phrase “*ā Tambapamni*” comes after Ketalaputo and not after Pādā. The expression “Ketalaputo as far as the (river) Tāmraparṇī” is hardly appropriate because the Tāmraparṇī is a Pāṇḍyan river.² We, therefore, prefer to take Tāmraparṇī to mean Ceylon. Aśoka's Ceylonese contemporary was Devānampiya Tissa whose accession may be dated about 250 or 247 B.C.

Aśoka maintained friendly relations not only with the Tamil powers of the south, but also with his **Hellenistic frontager**, Antiochos II Theos, king of Syria and Western Asia (B.C. 261-246); and even with the kings the neighbours of Antiochos, namely, Ptolemy II, Philadelphos, king of Egypt (B.C. 285-247); Magas, king of Cyrene in North Africa (who probably died not later than B.C. 258)³; Antigonos Gonatas, king of Macedonia (B.C. 277 or 276-239); and Alexander who ruled over Epirus (B.C. 272-c.255) according to Norris, Westergaard, Lassen, Senart, Smith and Marshall.⁴ Beloch and Hultsch, however,

see *Camb. Hist. Ind.*, Chap. XXV, and *IHQ*, II. 1. p. 1 ff. According to tradition recorded in the *Dipavamsa* and the *Mahāvamsa* the first Aryan immigrants were led by Prince Vijaya of Lāla, whom the chronicles represent as a grandson of a Princess of Vaṅga. The identification of Lāla is, however, open to controversy, some placing it in Gujarāt, others identifying it with Rāḍha or Western Bengal. Barnett may be right in his assumption that the tradition of two different streams of immigration was knit together in the story of Vijaya. See also *IHQ*, 1923, 742 ff.

¹ *Aśoka*, 3rd Ed., p. 162.

² Even those who prefer to see in the passage a reference to a kingdom in the Valley of the Tāmraparṇī river, have to prove that such a kingdom did exist in the Maurya age apart from “Pādā” and Taprobane, and to explain the particular way in which it is mentioned in Edict II.

³ Tarn, *Antigonos Gonatas*, p. 449 f.

⁴ *Monuments of Sānci*, I, 23 n.

suggest¹ that Alikasudara of Edict XIII is the comparatively insignificant ruler, Alexander of Corinth, the son of Craterus (B.C. 252—*cir.* 244) and not Alexander of Epirus (272—*cir.* 255), the son of Pyrrhus.

Though Aśoka did not covet the territories of his neighbours, there is evidence that he gave them advice on occasions, and established philanthropic institutions in their dominions. In other words, he regarded them as objects of spiritual conquest (*Dhamma-vijaya*).

"My neighbours, too, should learn this lesson."²

"Among his frontagers the Cholas, the Pāṇḍyas, the Satyaputra, the Ketalaputra as far as Tāmraparṇī, Antiochos, the Greek king, and even the kings the neighbours of that Antiochos, everywhere have been made healing arrangements of His Sacred and Gracious Majesty the King."

In Edict XIII Aśoka declares that the "conquest of the Law of Piety,.....has been won by His Sacred Majesty.....among all his neighbours as far as six hundred leagues, where the king of the Greeks named Antiochos dwells, and beyond (the realm) of that Antiochos (where dwell) the four kings (*rājāno*) severally Ptolemy (Turamāyo), Antigonos (Amtekina), Magas (Maga or Maka), and Alexander (Alikasudaro)—(likewise) in the south (*micha*), the Cholas and the Pāṇḍyas as far as Tāmraparṇī.....Even where the envoys (*dūtā*) of His Sacred Majesty do not penetrate,³ those people, too, hearing His Sacred Majesty's ordinance based upon the Law of Piety and his instruction in the Law, practise

¹ JRAS, 1914, pp. 243 ff. *Ins. of Aśoka*, xxxi.

² M. R. Edict I.

³ Have we here a reference to countries like Saravabhumī named in the list of territories to which missionaries were sent according to the *Mahāvastu*?

and will practise the Law."¹ Buddhism doubtless made some progress in Western Asia and influenced later sects like the Manichaeans. But Greeks apparently were not much impressed by lessons on non-violence. When the strong arm of Aśoka, "who possessed the power to punish in spite of his repentance," was withdrawn, the Yavanas poured once more into the Kabul valley, the Pañjab and the *Madhya-deśa* and threw all the province into confusion. The southern missions were more successful. Curiously enough, the Ceylonese chronicles do not seem to refer to the envoys sent to the *independent* Tamil and Hellenistic kingdoms² but name the missionaries sent to Ceylon and **Suvannabhūmi** (Lower Burma and Sumatra). The Ceylonese mission was headed by prince Mahendra who secured the conversion of Devānampiya Tissa and many of his people. No direct reference to Suvannabhūmi occurs in the Edicts hitherto discovered.

The Change in Internal Policy

The effects of Aśoka's change of religion after Kalinga war were felt not only in foreign policy but also in internal affairs. The principal objects of his complaint according to Rock Edict IV and the Kalinga Edicts were :

¹ From Buddhism in Western Asia, see Beal, *Si-yu-ki*, II. 378; and Alberuni, p. 21; JHAS, 1913, 76; McCrindle, *Ancient India as Described in Classical Literature*, p. 193; Eliot, *Hinduism and Buddhism*, Vol. III, pp. 3, 450 f; cf. Smith, EHI, 4th ed., 197; Barlingame, trans, *Dhammapadam Commentary*, Introduction.

² Mention is however made of the Yona country along with Kamboja, Gandhāra and Himālaya (Geiger, 82). This Yona territory is perhaps to be identified with the homonymous land in the Kabul valley associated with Kamboja and Gandhāra in the Aśokan Inscriptions. But reference in a vague way to the Levantine world is not completely ruled out. The Deccan lands mentioned in connection with the traditional missionary activity of the Aśokan age include Mahishamagadha, Vanavāsa (in the Kanarese area), Aparāntaka (on the west coast), and Mahārāṣṭra (Mahārāṣṭra) in the upper valley of the Godavari.

1. The sacrificial slaughter (*ārambho*) of living creatures.
2. Violence (*vihiṃsā*) to animate beings.
3. Unseemly behaviour to (*asaṃpratipati*) to kinsmen (*jñātī*)
4. Unseemly behaviour to *Brāhmaṇas* and *Sramaṇas*.
5. Maladministration in the Provinces.

According to Rock Edict I, Aśoka saw much offence not only in the sacrificial slaughter of animals, but also in certain *Samājas* or festive gatherings which, as we learn from the *Kauṭīliya*,¹ were often witnessed by kings and emperors.² The *Samāja*, says Smith, was of two kinds. The popular festival kind accompanied by animal fights, heavy drinking and feasting, including much consumption of meat, was necessarily condemned by Aśoka, as being inconsistent with his principles. The other kind, the semi-religious theatrical performance, sometimes given in the temples of Sarasvatī, the goddess of learning, was apparently not included among offensive *Samājas*. Dr. Thomas³ describes the disapproved *Samāja* as "a celebration of games or contests taking place in an arena or amphitheatre surrounded by platforms (*mañcha*) for spectators (*prekshā*)."⁴ This kind of (*Samāja*) is apparently referred to in the following lines of the *Virāṭa parva* of the *Mahābhārata* :—

*Ye cha kechinniyotsyanti Samājeshu niyodhakāḥ.*¹

"Those combatants who will take part in wrestling in the *Samājas*."

¹ p. 48.

² For the holding of *Samājas* in Magadha and in neighbouring countries see *Vinaya*, IV. 267; *Mahāvastu*, III. 57 and 368.

³ *JRAS.*, 1914, pp. 392 ff

⁴ *Virāṭa*, 2, 7.

*Tatra Mallāḥ samāpetur digbhyo rājan sahasrasaḥ
Samāje Brahmaṇo rājan tathā Paśupati api
Mahākāyāḥ Mahāvīryāḥ Kālakanja ivāsuraḥ.*¹

"O king, there arrived, by thousands, boxers from all quarters, in that festive gathering in honour of Brahman as well as Paśupati (Śiva). They possessed gigantic bodies and immense strength like the Titans styled Kālakanja."

The harmless *Samāja* is well illustrated by the gathering in the temple of the goddess of learning referred to in Vātsyāyana's *Kāmasūtra* (*Pakshasya māsasya vā prajñāte' hani Sarasvatyā bhavane niyuktānām nityam Samājah*). According to Hultsch the harmless *Samāja* refers to edifying shows.²

Aśoka determined to put a stop to the practices, referred to above, which he did not approve. At the same time he sought to improve the moral and material condition of the people to such an extent as to effect the "association of gods with men".³ He did all this "in order that he might discharge the debt (which he owed) to living beings (that) he might make them happy in this (world) and (that) they might attain heaven in the other (world)." The means employed to achieve this object may be classed under four heads :

1. Administrative reforms.
2. Dissemination of instructions in the *Dhamma* (Law of Piety or Duty).
3. Benevolent activity; promotion of the welfare of man and beast.

¹ *Virāṭa*, 13, 15-16.

² See also IHQ, 1928, March 112 ff.

³ Cf. Minor Rock Edict I. Cf. The description in the *Harivaṃśa* of a prosperous realm where (*rājye mahodaye*) gods and men dwelt together (*Bhaviṣyaparva*, Ch. 32.1) "*Devatānām manushyānām sahaśāso' bhacattadā*." Hultsch, however, compares (xiv) *Deva* with *Divyāni rūpāni* of Rock Edict IV.

4. Religious toleration and prevention of schism in the Buddhist church.

Administrative Reforms

In the first place, Aśoka instituted the Quinquennial and Triennial *Anusamyāna* or Circuit of the *Yutas*, *Rājūkas* *Prādeśikas*, and *Mahāmātras*. Jayaswal and Smith¹ were of opinion that the whole administrative staff from the *Rājūkas* and the *Prādeśikas* down to the *Yutas* could not possibly have gone on circuit at once every five years. They interpreted the term as signifying a regular system of transfers from one station to another. But there is nothing in the text to show that *all* the officers were required to go on circuit *at once*. The *anusamyāna* of the *Yutas*, *Rājūkas* and *Prādeśikas* was quinquennial and was mainly intended for propaganda work. The *anusamyāna* of the *Mahāmātras* was specially instituted for the purpose of checking miscarriage of justice, arbitrary imprisonment and torture in the outlying provinces (Kaliṅga, and the Ujjayinī and Takshaśilā regions).

Secondly, Aśoka created a number of new posts, *e.g.*, *Dharma-mahāmātras* and possibly *Dharma-Yutas*.² The *Dharma-mahāmātras* were given a protective mission among people of all sects including the Brāhmanas and the *Nirgranthas* or Jainas, and among the Yavanas, Kambojas, Gandhāras, Rishikas and all the Aparāntas. "Among

¹ *Aśoka*, 3rd edition, p. 164; Mr. A. K. Bose (IHQ, 1933, 811) takes *anusamyāna* in the sense of 'a court-house or a citadel.' But the epic reference to *punyaśrthānusamyānam* (Mbh. i. 2, 123). 'going forth to holy places of pilgrimage,' suggests that the interpretation proposed by Kern and Bühler is the one least open to objection. See also Barua, *Aśoka Edicts in New Light*, 83 ff.

² *Dhammayuta* may not be an official designation. It may mean simply 'one devoted to Dhamma' (morality, righteousness). Cf. Bhandarkar, *Asoka*, 2nd ed., pp. 311, 343.

servants and masters, Brāhmaṇas and the wealthy (*Ibhya*s),¹ among the helpless and the aged, they are employed in freeing from worldly cares their subordinates (in the department) of the Law of Piety. They are also employed on the revision (of sentences of) imprisonment or execution, in the reduction of penalties, or (the grant of) release, on the grounds of motive, having children, instigation, or advanced years...At Pāṭaliputra and in all provincial (*bāhira*) towns, in the family establishments of the king's brothers and sisters, as well as of other relatives, they are everywhere employed." The *Dharma-mahāmātras* were further engaged everywhere in the imperial dominions (*viṣṭa*) or indeed in the whole world (*Prithivī*) as known to the Mauryas, among the *Dharma-yutas* with regard to "the concerns of the Law, the establishment of the Law, and the business of almsgiving." The border countries (*deśa*) were placed under the special care of the *Āvutikas*.²

The emperor was naturally anxious to keep himself fully informed without delay about all public affairs, specially about the doings of the *Mahāmātras* on whom the success of his mission mainly depended. He, therefore, gave *special directions to the Paṭivedakas* or Reporters that when a matter of urgency committed to the *Mahāmātras* and discussed in the *Parishad* or Council occasioned a division of opinion or *nijhatī* (adjournment?)³ he must be informed without delay.

¹ We have here a reference probably to the fourfold division of society into Brāhmaṇas, Kshatriyas or nobles (*Ibhya*s), Vaiśyas (*Āryas*), and Sūdras (*Bhāṭa*s).

² Cf. Hultzsch, *Aśoka*, 100 n 7.

³ For procedure in cases of disputations in an Assembly see also *Jaim. Up. Br.* III. 7.6. Can *Nijhatī* imply reference to the *Upadrashtṛis* hinted at in the 'rāhmaṇa' passage? The help of *Upadrashtṛis* was invoked by the Kuru-Pañchālas to arrive at a satisfactory agreement or understanding in case of dispute. (Cf. also Barua, *Aśoka Edicts in New Light* p. 78.)

It is apparent from the Kalinga Edicts and Rock Edict VI that Aśoka kept a watchful eye on the *Mahāmātras* especially on those who administered justice in cities. But he was more indulgent towards the *Rājukas* for whose intelligence he apparently entertained great respect. To the *Rājukas* "set over many hundred thousands of people" the emperor *granted independence* in the award of honours and penalties in order that those officials might perform their duties confidently and fearlessly. He wanted, however, to maintain some uniformity in penalties as well as in procedure. For this reason he issued the following rule :—

"To condemned men lying in prison under sentence of death a respite of three days is granted."

Lastly, Aśoka issued certain regulations restricting slaughter and mutilation of animals, and up to the twenty-seventh year of his coronation effected twenty-five jail deliveries. This suggests, as has been pointed out by Hultzsch, that the emperor used to proclaim an amnesty to criminals at almost every anniversary of his coronation.

Measures adopted to disseminate Instructions in the Law of Piety.

Though himself convinced of the truth of the Buddha's teaching, of the efficacy of worship at Buddhist holy places, of the necessity of making a confession of faith in the Buddhist Trinity, of keeping in close touch with the Buddhist Order of monks and maintaining its discipline and solidarity, Aśoka probably never sought to impose his purely sectarian belief on others. He attempted, however, to put an end to practices and institutions that he considered to be opposed to the fundamental principles of morality which, according to him, constituted the essence of all religions. The prospect that he held

before the people at large is not that of *sambodhi* (or of *nirvāṇa*) but of *svarga* (heaven) and of mingling with the *devas*. *SVARGA* could be attained and the gods could be approached by all people, high or low, if only they showed *parākrama*, zeal, not in adherence to a sectarian dogma or the performance of barren ritual (*maṅgala*) but in following the ancient rule (*porāṇa pakṛtī*), the common heritage of Indians of all denominations, viz., "obedience must be rendered to parents and elders; firmness (of compassion) must be shown towards living creatures; truth must be spoken; these same moral virtues must be practised. In the same way the teacher must be revered by the pupil, and fitting courtesy should be shown to the relatives." In Edict XIII we have the following: "hearkening to superiors, hearkening to father and mother, hearkening to teachers (or elders), and proper treatment of friends, acquaintances, comrades, relatives, slaves¹ and servants, with steadfastness of devotion." Edict VII lays stress on "mastery over the senses, purity of mind, gratitude, and steady devotion". In the Second Pillar Edict it is declared that the Law of Piety consisted in *Apāsinaṇe*, *bahukayāṇe*, *dayā*, *dāṇe*, *sache sochaye*, "little impiety, many good deeds, compassion, liberality, truthfulness, purity".

In the Pillar Edicts again prominence is given to self-examination and spiritual insight. Towards the end of his career Aśoka seems to have been convinced that reflection and meditation were of greater efficacy than moral regulations. But the need for such

¹ For the question of slavery in Maurya India, see Monahan, *Early History of Bengal*, pp. 164-65. It is to be noted that Aśoka did not abolish slavery, just as he did not do away with caste or *pardah*. He simply wanted to mitigate the rigours of the existing social polity.

regulations was keenly felt by him in the early years of his reign.

We learn from Minor Rock Edict I that for more than two-and-a-half years Aśoka was a lay disciple (*Upāsaka*). During the first year he did not exert himself strenuously. Later on he seems to have entered¹ the *Saṅgha* and begun to exert himself strenuously.² He issued the famous proclamation, "Let small and great exert themselves," and caused to be engraved the imperishable record of his purpose on the rocks and upon stone pillars wherever there were stone pillars in his dominions.

¹ "Approached," according to Hultzsch, in whose opinion the two-and-a-half years of *Upāsaka* include the period which followed his "Visit" (not "entry") to the *Saṅgha*. The view that Aśoka actually joined the Holy Order is, however, supported by I-tsing who mentions an image of Aśoka dressed in the garb of a Buddhist monk (Takakura, *I-tsing*, 73). That rulers and statesmen could be monks as well, even in early times, appears probable from Lüders Ins. No. 1144 which refers to a *Sramana mahāmātra* of Nāik in the days of the early Śātavāhana king Kṛishṇa, Cf. Milinda, IV.6. 49 (ref. to a Sramana King); Gelger, trans., *Mahāvastu*, 240 (Kujakappa Tissa).

² Rock Edict IV has been interpreted by scholars to mean that Aśoka sought to promote the observance of the Buddhist doctrine by exhibiting spectacles of aerial chariots (*Vimānadasanā*), of elephants (*Hastidasanā*), masses of fire (*Agikhaṇḍhāni*) and other representations of a *dīrgha*, i.e., divine (not terrestrial) nature. Dr. Bhandarkar (*Ind. Ant.*, 1912, p. 26), refers to the Pāli *Vimānavatthu* which describes the splendour of the various celestial abodes (*Vimānas*) in order to induce listeners and spectators to live good and unblemished lives, and thereby attain to these. Aśoka is said to have made representations of these *Vimānas* and paraded them in various places. *Hasti*, according to Dr. Bhandarkar, is *Seeto hasti*, i.e., Bodhiha himself who is also described as "*Gajātama*," i.e., *Gajottama*, the most excellent elephant. As regards *Agikhaṇḍha* (*Agniskandha*) Dr. Bhandarkar draws our attention to *Jātaka* No. 40 which refers to a blazing fire-pit created by Māra on the surface of which the Bodhisattva strode and gave a bowl to a hungry *Pecheheka Buddha* and extolled alms-giving. Hultzsch suggests that *Hasti* may refer to the vehicles of the four "*Mahārājas*" (*lokapālas* or guardians of quarters). He takes *Agikhaṇḍha* to refer to 'radiant beings of another world' while Jari Charpentier (*JHQ*, 1933, 87) understands it to mean piles of (hell-) fire. The interpretation of Hultzsch accords better with the testimony of the commentary on the *Rāmāyaṇa* (II, 88, 16) which explains *dīrgha* as *vīśiṣṭa devatādhiṣṭhitam*. The celestial elephant figures prominently in the Tāravaloka story of the *Kathā-sarīt-sāgara* (Pensez, VIII, 131), and

Aśoka at first utilised the existing administrative machinery for religious propaganda.¹ He commanded his Council (*Parishad*) to inculcate the *Dharma* on the subordinate officials styled *Yutas* and ordered the latter as well as the higher officials styled *Rājūkas*, and *Prādeśikas* to inculcate the same while they set out for tour (*anusamyāna*). The *Dharma* which they were to preach was explained thus: "An excellent thing is the hearkening to father and mother²; an excellent thing is liberality to friends, acquaintances, relatives, Brāhmaṇas and ascetics; excellent is abstention from the slaughter of living creatures; excellent is small expense with small accumulation."

Mountain of fire, *ibid* 50, 51: III. 6, 17; Cf. also *aggi-khando* in *Jataka*, VI 330, Coomaraswamy in B. C. Law. vol. I. 469; Note the *Sutta* referred to in Geiger, *Mahāvamsa*, trans. pp. 85, 110.

The passage containing the words *Vimānadasanā*, *Hastidasanā*, etc.' has been explained differently in *A Volume of Indian Studies presented to Professor E. J. Rapson*, p. 546 f. According to the interpretation that finds favour with some writers, the spectacles in question were exhibited not by Aśoka but by previous rulers to the accompaniment of the sound of drums. But thanks to Aśoka "the sound of the *bheri* had become the sound of *dharma*," that is to say instruction in *dharma* took the place of martial music that used to be heard on the occasion of pompous shows of edifying subjects in bygone times. What former kings could not accomplish by gaudy spectacles, was achieved by Aśoka by the simple unostentatious teaching of the true Doctrine. The *bheri* was now used to announce the king's rescripts on morality, cf. the Yerragudi copy of the Minor Rock Edict—*Rājake ānapitaviye bherinā jānapadaṃ ānāpayisati rāthikānaṃ cha* (*Ind. Culture*, I, p. 310; *IHQ*, 1933, 117).

¹ According to one view Aśoka sent special missionaries styled *Vyuṭha* to expound his teaching. The interpretation of *Vyuṭha* as missionary was suggested by Senart and accepted by Smith (*Aśoka*, Third Ed., p. 153 Dr. Bhandarkar takes *Vyuṭha* or *Vivutha* to mean "officials on tour." Hultzsch thinks that *Vyuṭha* refers to Aśoka himself while he was on tour (p. 169, note 8). The word has also the sense of dawn, day-break, day, in other words, it has a chronological significance. Other interpretations are also suggested by scholars. The least plausible is the one offered by Dr. Barua (*D. R. Bhandarkar* volume, 369.) who finds in the expression reference to the copies of the particular proclamation sent forth from the capital.

² Cf. *Sigālovāda Suttanta* (*Dialogues of the Buddha*. III, 173 ff.).

When he had been consecrated thirteen years, Aśoka created the new officials called *Dharma-mahāmātras* who were specially entrusted with the work of "*dhammādhi-thāna*" and "*dhammavadhi*", i.e., the establishment and increase of Piety.

While his officers were busy preaching the new Gospel, the emperor himself did not remain idle. Already in his eleventh regnal year he had "started on the path" leading to *Sambodhi* (*ayāya Sambodhim*)¹ and commenced the tours of Piety (*Dhamma-yātā*) in the place of the old tours of pleasure (*Vihāra yātā*). In the tours of Piety this was the practice—visiting ascetics and Brāhmaṇas, with liberality to them; visiting elders, with largess of gold; visiting the people of the country or perhaps rural areas (*Janapada*) with instruction in the Law of Piety, and discussion of that law. The memory of a pious tour in Aśoka's twenty-first regnal year² (B. C. 249 according to Smith) is preserved by the Rummindei and Nigāli Sāgar epigraphs in the Nepalese Tarai. These records prove that Aśoka visited the birth-place of Gautama and paid reverence to the *stupa* of Konākamana, one of the former Buddhas.³

In 242 B.C., according to Dr. Smith, Aśoka issued the Seven Pillar Edicts which contain, among other things, a review of the measures taken during his reign for the "promotion of religion, the teaching of moral duty".

¹ Some scholars take *Sambodhi* to mean 'supreme knowledge'. But Dr. D. R. Bhandarkar contends that *Sambodhi* is equivalent to the Bodhi Tree or the Mahābodhi Temple at Bodhi Gayā. According to the *Dīpāvadāna* (p. 393) Aśoka visited Bodhi in the company of the *Sthavira* or Elder Upagupta (Hultzsch, CII, xliii).

² Were these tours decennial?

³ He had enlarged the *stupa* of Konākamana six years earlier, but the personal presence on that occasion is by no means clear.

Benevolent Activity, Promotion of the Welfare of Man and Beast

Aśoka abolished the sacrificial slaughter of animals, offensive *Samājas* and the massacre of living creatures to make curries in the imperial kitchen. Rock Edict VIII refers to the abolition of the *vihāra-yātrās* or tours of pleasure in which hunting and other similar amusements used to be practised. Pillar Edict V contains a code of regulations¹ restricting the slaughter and mutilation of animals. Dr. Smith points out that the prohibitions against animal slaughter in this edict coincide to a considerable extent with those recorded in the *Arthaśāstra*.

The emperor established healing arrangements in two kinds, namely, healing arrangements for men and healing arrangements for beasts. Medicinal herbs also both for men and for beasts, wheresoever lacking, were imported and planted. Roots also and fruits,² wheresoever lacking, were imported and planted. On the roads wells were dug probably at intervals of 8 *kos*, flights of steps built for descending into the water, and banyan trees and mango groves planted for the enjoyment of man and beast.

Pillar Edict VII refers to the employment of superior officers (*Mukhyas*) in the distribution of alms, both the emperor's own and those of the queens and princes. One of the Minor Pillar Edicts refers to the donations of the second Queen Kāruvākī,³ mother of Tivara: "whatever gift has been given here by the second Queen—be it a mango-garden, or pleasure-grove (*ārāma*) or alms-house

¹ *Dhamma-nigama*, cf. Patañjali I, I, I.

² Cf. reference to figs in Bindusāra's correspondence with Antiochos.

³ Dr. Barna suggests the identification of this lady with Asandhimittā of the *Mahāvamsa* and the *Sumahgatalāsinī* (*Indian Culture*, I, 123). The suggestion, though ingenious, is hardly convincing.

(*dānagriha*) or aught else—is reckoned as proceeding from that queen.²²

Mention may also be made of remission of taxes by the emperor himself, *e.g.*, in *Lumminigāma*, and money-grants (*hirannapatividhāna*) to old men. The people of *janapadas* (districts), doubtless including the *grāmas*¹ (villages), were also sought to be benefited by the grant of autonomy and the establishment of uniformity of punishment and procedure (*daṇḍasamatā* and *vyāvahārasamatā*) as well as diffusion of moral instruction (*dhramanusastī*).

Religious Toleration and the Prevention of Schism in the Buddhist Church.

In Rock Edict XII the emperor declares that he “does reverence (*Pūjā*) to men of all sects (*Pāsamdāni*) whether ascetics (*Pavajitāni*) or householders (*Gharastāni*) by gifts and various forms of reverence”. That he was sincere in his professions is proved by the Barābar cave dedications in favour of the Ājīvika ascetics, who were more closely connected with the Jainas than with the Buddhists.

The emperor only cared for the “growth of the essence (*Sāra-Vaḍhi*) of the matter in sects”. He says that “he who does reverence to his own sect while disparaging the sects of others wholly from attachment to his own, with intent to enhance the splendour of his own sect, in reality by such conduct inflicts the severest injury on his own sect.” Concord (or concourse, *Samavāyo*) is praised by him as meritorious (*Samavāyo eva sādhu*).

Just as Aśoka tried to secure concord among the various sects, so he wanted to prevent schism within the

¹ References to *grāmas* are found in the compounds *Lummini-gāma* and *āma-kapota* (Pillar Edict V).

Buddhist church. Tradition affirms that a Buddhist Council was convened at Pāṭaliputra in the seventeenth year of his reign for the purpose of suppressing heresy and making a compilation of the true Buddhist doctrine (*Saddhammasaṅgaha*). The Sārnāth Edict and its variants may perhaps be regarded as embodying the resolution of this Council.¹

Aśoka as a Builder

The gift of cave dwellings to the Ājivika monks affords us a glimpse into another side of Aśoka's activity. As late as the fifth century A.D., sojourners in Pāṭaliputra were struck with wonder at the magnificence of the emperor's architectural achievements. Tradition credits him with the construction of a splendid palace besides numerous relic mounds, monasteries and temples. He is actually known to have enlarged the *stūpa* of Konākamāna, a 'former Buddha' and a predecessor of Śākyamuni. He also set up 'pillars of morality' *Dharma-stambhas*. Modern critics are eloquent in their praise of the polished surface of his columns and the fine workmanship of their crowning sculptures.²

Character of Aśoka. His Success and Failure

Aśoka is one of the most interesting personalities in the history of India. He had the energy of a Chandragupta, the versatility of a Samudragupta and the catholicity of an Akbar. He was tireless in his exertion and unflagging in his zeal—all directed to the promotion of the spiritual and material welfare of his people whom he looked upon as his children. His illustrious grandfather

¹ Smith, *Aśoka*, third, ed., p. 55.

² For Aśoka's achievements in the domain of art, see Smith, *HPAIC*, 13, 57 ff.; *Aśoka*, pp. 107 ff.; *CHI*, 618 ff.; Havell, *ARI*, 104 ff., etc.

was accustomed to dispose of cases even when indulging in the luxury of a massage of the limbs. Similarly, Aśoka used to listen to reports about the affairs of his people even while 'he was eating, in the harem, in the inner apartment, at the cowpen, in the palanquin and in the parks'. The great soldier who had brought under subjection a huge territory unconquered even by his ever victorious grandfather, could, at the same time, argue points of doctrine and discipline with a fraternity of erudite monks. The statesman who could pilot an empire through the storm and stress of a war that involved the death and deportation of hundreds of thousands of men was, at the same time, capable of organizing religious missions the sphere of whose activities embraced three continents, and transforming a local sect in the Ganges Valley into one of the great religions of the world. The man who penetrated into the jungles of the Nepalese Tarai to pay homage to the birth-place of the Buddhas, bore no ill-will towards the descendants of their Brāhmaṇa and Jaina opponents, and granted cave-dwellings to the adherents of a rival sect. The king who undertook tours with the object of granting largesses of gold to Brāhmaṇas and *Sramaṇas*, admitted to office *Yavanas* in whose country there were neither Brāhmaṇas nor *Sramaṇas*. He preached the virtues of concord and toleration in an age when religious feeling ran high and disruptive influences were at work within the fold of the Jaina and Buddhist churches. He preached non-violence when violence in war, religious ritual, royal pastime and festive gatherings was the order of the day. He eschewed military conquest not after defeat but after victory and pursued a policy of patience and gentleness while still possessed of the resources of a mighty empire. The forbearance of this strong man was only matched by his truthfulness, and he describes in burning words

which no Kalinga patriot could have improved upon, the terrible misery that he had inflicted on a hapless province. The example of Dharmāśoka, the pious king, exercised an ennobling influence on posterity. In the second century A.D. Queen Gautamī Balaśrī takes pride in the fact that her son was "alien to hurting life even towards an offending enemy" (*Kitāpārādhe pi satujane apānahisāruchi*). Even in the fifth century A.D., the rest-houses and free hospitals of Magadha excited the wonder and admiration of foreigners. The benefactions of Dharmāśoka were a source of inspiration to royal personages as late as the time of Govindachandra of the Gāhaḍavāla dynasty.

We have already seen that the political record of the great Maurya's early years was brilliant. His reign saw the final triumph of those centripetal forces that had been at work since the days of Bimbisāra. The conquest of Kalinga completed the unification of non-Tamil India under the hegemony of Magadha. The dream of a United Jambudvīpa was nearly realised.

But the policy of *Dhamma-vijaya* which he formulated after the Kalinga War was not likely to promote the cause for which a long line of able sovereigns from Bimbisāra to Bindusāra had lived and struggled. The statesman who turned civil administrators into religious propagandists, abolished hunting and jousts of arms, entrusted the fierce tribesmen on the North-West Frontier and in the wilds of the Deccan to the tender care of "superintendents of piety" and did not rest till the sound of the kettle-drum was completely hushed and the only sound that was heard was that of moral teaching, certainly pursued a policy at which Chandragupta Maurya would have looked askance. Dark clouds were looming in the north-western horizon. India needed men of the calibre of Puru and Chandragupta to ensure her protection

against the Yavana menace. She got a dreamer. Magadha after the Kalinga War frittered away her conquering energy in attempting a religious revolution, as Egypt did under the guidance of Ikhnaton. The result was politically disastrous as will be shown in the next section. Aśoka's attempt to end war met with the same fate as the similar endeavour of President Wilson.

According to Dr. Smith's chronology Aśoka died in 232 B.C., after a reign of about 40 years. A Tibetan tradition is said to affirm that the great Emperor breathed his last at Taxila.¹

¹ *The Oxford History of India*, p. 116. I cannot vouch for the authenticity of this tradition.

SECTION II. THE LATER MAURYAS AND THE DECLINE OF THEIR POWER.

The Magadha Empire under Aśoka extended from the foot of the Hindukush to the borders of the Tamil country. But the withdrawal of the strong arm of Piyadasi was perhaps the signal for the disintegration of this mighty monarchy. "His sceptre was the bow of Ulysses which could not be drawn by any weaker hand." The provinces fell off one by one. Foreign barbarians began to pour across the north-western gates of the empire, and a time came when the proud monarchs of Pāṭaliputra and Rājagṛiha (and Malwa) had to bend their knees before the despised provincials of 'Andhra' and Kalinga.

Unfortunately, no Megasthenes or Kauṭilya has left any account of the later Mauryas. It is impossible to reconstruct a detailed history of Aśoka's successors from the scanty data furnished by one or two inscriptions and a few Brāhmaṇical, Jaina and Buddhist works.

Aśoka had many children. In Pillar Edict VII, he pays attention to the distribution of alms made by all his children, and in particular to those made by the "Princes, sons of the Queens". It is to this last category that belonged some of the *Kumāras* who represented the Imperial authority at Takshaśilā, Ujjayinī and Tosālī. **Tivara**¹ the son of queen Kāruvāki, the only prince actually named in the inscriptions, does not appear to have mounted the imperial throne. Three other sons, namely, Mahendra, Kunāla (Dharma-vivardhana, Suyāśas?), and Jalauka are mentioned in literature. It is, however, uncertain whether Mahendra was a son of Aśoka or his brother.

¹ For Tivara as a Magadhan name see the *Book of Kindred Sayings*, II, pp. 128-30.

The *Vāyu Purāṇa* says that after Aśoka's death his son **Kunāla** reigned for eight years. Kunāla's son and successor was Bandhupālita, and Bandhupālita's *dāyāda* or heir was Indrapālita. After Indrapālita came Devavarman, Satadhanus and Bṛihadhratha.

The *Matsya Purāṇa* gives the following list of Aśoka's successor:—Daśaratha, Samprati, Śatadhanvan and Bṛihadhratha.

The *Vishṇu Purāṇa* furnishes the following names:—Suyaśas, Daśaratha, Saṅgata, Śālīsūka, Somaśarman Śatadhanvan and Bṛihadhratha.

The *Divyāvadāna*¹ has the following list:—Saṃpadī, Vṛihaspati, Vṛishasena, Pushyadharman and Pushyamitra.

Jaina writers refer to a Maurya king of Rājagriha, named Balabhadra.²

The *Rājatarāṅginī* mentions **Jalauka** as the successor of Aśoka in Kāśmīra, while Tārapātha mentions another successor Vīrasena who ruled in Gandhāra and was, as Dr. Thomas suggests, probably the predecessor of **Subhāgasena** of Polybius.³

It is not an easy task to reconcile the divergent versions of the different authorities. The reality of the existence of Kunāla is established by the combined testimony of the Purāṇic and Buddhist works (which represent him as the father of Saṃpadī) as well as the evidence of Hemchandra and Jinaprabhasuri, the well-known Jaina writers. The names Dharma-vivardhana occurring in the *Divyāvadāna* and the Records of Fa Hien and Suyāśas found in the *Vishṇu* and the *Bhāgavata Purāṇas* were probably *birudas* or epithets of this prince. Tradition is not unanimous regarding the accession of Kunāla to the imperial

¹ P. 433

² Jacobi, *Introduction to the Kaipāsūtra of Bhadrabāhu*, 1879. p. 9.

³ *Ind. Ant.*, 1875, p. 362; *Camb. Hist. Ind.*, I, p. 512.

throne. He is reputed to have been blind. His position was, therefore, probably like that of Dhṛitarāshṭra of the Great Epic and, though nominally regarded as the sovereign, he was physically unfit to carry on the work of government which was presumably entrusted to his favourite son Samprati, who is described by Jaina and Buddhist writers as the immediate successor of Aśoka.

Kunāla's son was Bandhupālita according to the *Vāyū Purāṇa*, Sampadī (Samprati) according to the *Divyāvadāna* and the *Pāṭaliputrakalpa* of Jinaprabhasuri,¹ and Vigataśoka according to Tāranātha.² Either these princes were identical or they were brothers. If the latter view be correct then Bandhupālita may have been identical with **Daśaratha** whose reality is established by the brief dedicatory inscriptions on the walls of cave-dwellings at the Nāgārjuni Hills which he bestowed upon the *Ājīvikas*. Daśaratha, who receives the epithet "*devānāmpīya*" in the inscriptions, was a grandson of Aśoka according to the *Matsya* and *Vishṇu Purāṇas*, and the predecessor of Samprati (variant Saṅgata) according to the same authorities.

Indrapālita must be identified with **Samprati** or Śālīsūka according as we identify Bandhupālita with Daśaratha or Samprati. "In the matter of the propagation of the Jaina faith, Jaina records speak as highly of Samprati as Buddhist records do of Aśoka."³ The *Pāṭaliputrakalpa* of Jinaprabhasuri⁴ says, "in Pāṭaliputra flourished the great king Samprati; son of Kunāla, lord of Bhārata with its three continents (*trikhaṇḍam Bharata-kshetram Jināyatanamaṇḍitam*), the great Arhanta who established *Vihāras* for *Śramaṇas* even in non-Aryan countries."

¹ See also *Parīśiṣṭaparvan*, IX, 51-53.

² *Ind. Ant.*, 1857, 362.

³ *Bomb., Gaz.*, I. i, 6-15. *Parīśiṣṭa*, XI. 65.

Dr. Smith shows good grounds for believing that the dominions of Samprati included Avanti and Western India.¹ In his *Aśoka*² he admits that the hypothesis that Aśoka left two grandsons, of whom one (Daśaratha) succeeded him in his eastern and the other (Samprati) in his western dominions, is little more than a guess.³ The Jaina writers represent Samprati as ruling over Pāṭaliputra as well as Ujjayinī. His name is mentioned in the Purāṇic list of Aśoka's *Magadhan* successors.

The existence of *Sālīśūka* is proved not only by the testimony of the *Vishṇu Purāṇa* but also by that of the *Gārgī Samhitā*⁴ and the *e Vāyu* manuscript referred to by Pargiter. He may have been identical with Vṛihaspati, son of Samprati, according to the *Divyāvadāna*, unless Vṛihaspati represented a different branch of the imperial family.

Devavarman and Somaśarman are variant readings of the same name. The same is the case with Śatadhanus⁵ and Śatadhanvan. It is not easy to identify Vṛishasena and Pushyadharman; they may be merely *birudas* or secondary names of Devavarman and Śatadhanvan. But the possibility that they represent a distinct branch of the Maurya line is not entirely excluded.

¹ *Parishistapāraṇa*, xi. 23. *śatācha Samprati nripo yagāḥ Ujjayinīḥ purim.*

² Third ed., p. 70.

³ Curiously enough, Prof. Dhruva maintains in spite of this and the clear evidence of Jaina literature that "historians say that on the death of Kunāla there was a partition of the Maurya Empire between his two sons Daśaratha and Samprati (JBOBS, 1930, 30)." Prof. Dhruva's emendations of the text of the *Yugapurāṇa* are largely conjectural and of little probative value.

⁴ Kern's *Bṛihatasaṃhitā*, p. 37. The *Gārgī Samhitā* says, "There will be *Sālīśūka*, a wicked quarrelsome king. Unrighteous, although theorising on righteousness, *dharmavādi adhārmikah* (sic) he cruelly oppresses his country."

⁵ For an interesting account of a King named Śatadhanu see *Vishṇu Purāṇa* III. 18. 81: *Bhāg.*, II. 8. 44. His identity is, however, uncertain.

The last of the Imperial Mauryas of Magadha, **Brihadratha**, is mentioned not only in the *Purāṇas* but also in Bāṇa's *Harsha-charita*. He was crushed by his general Pushyamitra who is perhaps wrongly described by the *Divyāvadāna* as of Maurya descent. A Maurya minister is said to have been imprisoned by the rigicide family.

Petty Maurya kings continued to rule in Western India as well as Magadha long after the extinction of the Imperial line. King Dhavala of the Maurya dynasty is referred to in the Kaṇaswa inscription of A. D. 738.¹ Dr. D. R. Bhandarkar identifies him with Dhavalappadeva, the overlord of Dhanika, mentioned in the Dabok (Mewar) inscription of *cir.* A. D. 725.² Maurya chiefs of the Koṅkaṇ and Khāndesh are referred to in Early Chalukya and Yādava epigraphs.³ A Maurya ruler of Magadha named Pūrṇavarman is mentioned by Hiuen Tsang.

There can be no doubt that during the sovereignty of the later Mauryas the Magadha Empire experienced a gradual decay. Aśoka died in or about the year 232 B. C. Within a quarter of a century after his death a Greek army crossed the Hindukush which was the Maurya frontier in the days of Chandragupta and his grandson. The *Yuga Purāṇa* section of the *Gārgī Samhitā* bears testimony to the decline of the Maurya power in the *Madhyadeśa* after the reign of Śāliśūka :

¹ *Ind. Ant.*, XIII, 163; *Bomb. Gaz.*, I. Part 2, p. 284. Kaṇaswa is in the Kotah State, Rājputāna. It is not unlikely that Dhavala was a descendant of some princely Viceroy of Ujjain. See also reference to the Mauryas in the Navasārikā grant Fleet, *DKD*, 375.

² *Ep. Ind.*, XII, p. 11. But see *Ep.* XX, 122. The date A. D. 725 is not accepted by other scholars who prefer A. D. 813.

³ *Bomb. Gaz.*, I. Part 2, pp. 283, 284. Bühler suggests (*Ep. Ind.*, III, p. 136) that these Maurya chieftains of the Koṅkaṇ were probably descendants of the princely Viceroy of the Deccan. He also draws our attention to the family name 'More' which is met with in the Mahratta country, and is apparently a corruption of 'Maurya.'

*Tataḥ Sāketam ākramya
 Pañchālān Mathurāṁstathā
 Yavanā dushṭavikrāntāḥ
 prāpsyanti Kusumadhvajam
 tataḥ Pushpapure prāpte
 kardame prathite hite
 ākulā vishayāḥ sarve
 bhaviṣhyanti na saṁśayaḥ.¹*

“Then the viciously valiant Greeks, after reducing Sāketa (in Oudh), the Pañchāla country and Mathurā, will reach (or take) Kusumadhvaja. Pushpapura (Pāṭaliputra) being reached....all provinces will undoubtedly be in disorder.”

Where was now the power that had expelled the prefects of Alexander and hurled back the battalions of Seleukos?

According to Mahāmahopādhyāya Haraprasād Śāstri² a reaction promoted by the Brāhmaṇas had sapped the foundations of the Maurya authority and dismembered the empire.

Among the causes of the alienation of the Brāhmaṇas the foremost place is given to Aśoka's Edict against animal sacrifices. The Edict, in Paṇḍit Śāstri's opinion, was certainly directed against the Brāhmaṇas as a class and was specially offensive because it was promulgated by a Śudra ruler. As to the first point we should remember that prohibition of animal sacrifices did not necessarily imply hostility towards Brāhmaṇas. Long before Aśoka Brāhmaṇa sages whose teachings have found a place in the Holy *Śruti*, the most sacred literature of the Brāhmaṇas, declared themselves in no uncertain terms against sacrifices, and in favour of *Ahiṁsā* (non-violence).

¹ Kern. *Epikat Samhitā*, p. 37.

² JASB, 1910, pp. 259 ff.

In the *Muṇḍaka Upaniṣad*¹ we have the following *Sloka* :—

*Plavā hyete adṛiḍhā yajñarūpā
asṭādaśoktam avaram yeshu karma
etachchhreyo ye'bhinandanti mūḍhā
jarāmṛityum tē punarevāpi yanti.*

“ Frail, in truth are those boats, the sacrifices, the eighteen in which this lower ceremonial has been told. Fools, who praise this as the highest good, are subject again and again to old age and death.” In the *Chhāndogya Upaniṣad*² Ghora Āṅgīrasa lays great stress on *Ahimsā*.

As to the second statement we should remember that tradition is not unanimous in representing the Mauryas as of *Sūdra* extraction. Certain *Purāṇic* texts assert no doubt, that after Mahāpadma there will be kings of *Sūdra* origin.³ But this statement cannot be taken to mean that all the post-Mahāpadman kings were *Sūdras*, as in that case the Śuṅgas and the Kāṇvas also will have to be classed as *Sūdras*.⁴ The *Mudrārākṣha*, the evidence of which is cited to prove that Chandragupta was a *Sūdra*,⁵ is a late work, and its evidence is contradicted by

¹ 1. 9, 7; S. B. E. *The Upaniṣads*, pt. II, p. 31.

² III. 17. 4.

³ *Tatoḥ prabhṛtirājāno bhaviṣyāḥ Sūdrayonayāḥ*. The reading in other texts is, however, *Tato nripā bhaviṣyanti Sūdrapṛāyāstendharmikāḥ* (DKA, 25).

⁴ Among real *Sūdra* (or partially *Sūdra*) kings may be included the Nandas, a few rulers mentioned in the *Garuḍa Purāṇa* (Ch. 145. 4) and the *Si-yü-ki* of Hiuen Tsang (Watters, I. 322; II. 252), and certain princes of Western India and the Indus Valley mentioned on pp. 54-55 of Patgiter's *Dynasties of the Kali age*.

⁵ In the play Chandragupta is styled '*Nandānaya*' and *Vṛishala*. As to the former appellation we should note that the play describes Nanda as *abhiṣāṇa*. Further it calls Chandragupta *Mauryaputra*, and though commentators try to reconcile the epithets *Nandānaya* and *Mauryaputra*, we learn from early Buddhist writers that Maurya is not a metonymic of Chandragupta or of his father, but the designation of an old clan. The Greeks, too, refer to a tribe called *Morieia* (Weber IA. ii. (1873) p. 148; Max Müller, *Sans. Lit.*, 280; Cunningham, *JASB*, XXIII, 680). As to the epithet *Vṛishala* it should be remembered

earlier authorities. As already pointed out above¹ the *Mahāparinibbāna sutta* represents the Moriyas (Mauryas) as belonging to the *Kshatriya* caste. The *Mahāvamsa*² refers to the Moriyas as a noble (*kshatriya*) clan and represents Chandragupta as a scion of this clan. In the *Divyāvadāna*³ Bindusāra, son of Chandragupta, said to a girl, “*Tvaṃ Nāpinī ahaṃ Rāja Kshatriyo Mūrdhābhishikṭaḥ katham mayā sārdaṃ samāgamo bhaviṣhyati?*” Thou art a barber girl, I am a consecrated *kshatriya* (king). How can I unite myself with thee?” In the same work⁴ Aśoka says to one of his queens (Tishyarakṣitā), “*Devi ahaṃ Kshatriyaḥ katham palāṇḍuṃ paribhakṣayāmi?*” ‘Queen, I am a *kshatriya*, how can I take onion?’ In a Mysore inscription Chandragupta is described as “an abode of the usages of eminent *kshatriyas*.”⁵ The *Kauṭīliya*’s preference of an “*abhiyāta*” king seems also to suggest that the sovereign of the reputed author was born of a noble family.⁶

Having referred to the prohibition of animal sacrifices Paṇḍit Śāstrī goes on to say: “this was followed by

that a Purāṇic text applies it even to the founder of the so-called Andhra dynasty (Pargiter, DKA, 28). But we learn from contemporary epigraphs that the dynasty regarded itself as ‘*Bamhaṇa*.’ According to Manu (X. 43) the epithet *Vṛishala* could be applied to degraded *Kshatriyas* (cf. IHQ, 1930, 271 ff. Cf. also Mbh. XII. 90, 15 ff., “The Blessed *Dharma* is *Vṛisha*. He who deals with it in such a way that it ceases to be of any use, i.e., transgresses it, is called a *Vṛishala*, *Vṛishohi Bhagavān Dharmo yastasya kurute hyalam*). The Mauryas by their Greek connection and Jaina and Buddhist leanings certainly deviated from the *Dharma* as understood by the great Brāhmaṇa law-givers. Attention may be invited in this connection to the epithet *Vasalaka* (*Vṛishala*) applied by Brāhmaṇas to the Buddha himself (Mookerji, *Hindu Civilization*, 264).

¹ P. 267 *supra*.

² Geiger’s Translation, p. 27.

³ P. 370.

⁴ P. 409.

⁵ Rice, *Mysore and Coorg from the Inscriptions*, p. 10.

⁶ Cf. *Aṛiṣaṣṭra*, p. 326. See also *supra*, 266 f. (the reign of Chandragupta).

another edict in which Aśoka boasted that those who were regarded as gods on earth have been reduced by him into false gods. If it means anything it means that the Brāhmanas who were regarded as *Bhūdevas* or gods on earth had been shown up by him."

The original passage referred to above runs thus:—

Y (i)-imāya kālāya Jambudīpasi amisā devā husu te dāni m (i) s-kaṭā.

Paṇḍit Śāstrī followed the interpretation of Senart. But Sylvain Lévi¹ has shown that the word *amisā* cannot stand for Sanskrit *amṛishā*, for in the Bhābrū edict we find *Musā* and not *Misā* for Sanskrit *mṛishā* (falsely or false). The recently discovered Māski version reads *misibhūtā* for *misamkaṭā*, showing that the original form was *miśribhūtā*. It will be grammatically incorrect to form *misibhūtā* from Sanskrit *mṛishā*. The word *miśra* means mixed. And *miśribhūtā* means "made to mix" or made to associate. The meaning of the entire passage is "during that time the men in India who had been unassociated with the gods became associated with them."² There is thus no question of "showing up" anybody.³

Paṇḍit Śāstrī adds that the appointment by Aśoka of *Dharma-mahāmātras*, i.e., of superintendents of morals,

¹ Hultsch, *Aśoka*, 168.

² Cf. *Āpastamba Dharmasūtra*, II. 7. 16, 1: "Formerly men and gods lived together in this world. Then the gods in reward of their sacrifices went to heaven, but men were left behind. Those men who perform sacrifices in the same manner as the gods did, dwell with the gods and Brahma in heaven." My attention was first drawn to this passage by Dr. D. R. Bhandarkar. Cf. also *Harivaṃśa* (III. 32. 1): "*Devatānām manushyānām sahaśāśobhavattadā*;" and SBE, XXXIV, p. 222-3 (Śaṅkara's Com. on the *Vedāntasūtras*): "The men of ancient times, in consequence of their eminent religious merit, conversed with the gods face to face. *Smṛiti* also declares that 'from the reading of the *Veda* there results intercourse with the favourite divinity.'"

³ The true import of the passage was pointed out by Dr. Bhandarkar in the *Indian Antiquary*, 1912, p. 170.

was a direct invasion of the rights and privileges of the Brāhmanas. It is hardly correct to represent the *Dharma-mahāmātras* as mere superintendents of morals when their duties consisted in the establishment of the Law of Piety (which included liberality to Brāhmanas), the promotion of the welfare of the Yavanas, Kambojas, Gandhāras, Ristikas, Brāhmanas and others, revision of sentences of imprisonment or execution, the supervision of the family establishments of the Emperor's brothers and other relatives, and the administration of alms-giving.¹ These duties were not essentially those of a mere superintendent of morals, and were not a direct invasion of the rights and privileges of the Brāhmanas. Moreover, there is nothing to show that the *Dharma-mahāmātras* were wholly recruited from non-Brāhmanas.

Our attention is next drawn to the passage where Aśoka insists upon his officers strictly observing the principles of *Danḍa-samatā* and *Vyavahāra-samatā*. Paṇḍit Śāstrī takes the expressions to mean 'equality of punishment' and 'equality in lawsuits' irrespective of caste, colour and creed, and adds that this order was very offensive to the Brāhmanas who claimed many privileges including immunity from capital punishment.

The passage containing the expressions *Danḍa-samatā* and *Vyavahāra-samatā* should not be divorced from its context and interpreted as if it were an isolated *ukase*. We quote the passage with the context below :—

" To my *Rājūkas* set over many hundred thousands of people I have granted independence (or discretion) in the award of honours and penalties. But as it is desirable that there should be uniformity in judicial procedure

¹ Aśoka, third ed., pp. 168-69.

(*Vyavahāra-samatā*) and uniformity in penalties (*Danḍa-samatā*), from this time forward my rule is this—"To condemned men lying in prison under sentence of death a respite of three days is granted by me."

It is clear from the extract quoted above that the order regarding *Vyavahāra-samatā* and *Danḍa-samatā* is to be understood in connection with the general policy of decentralisation which the Emperor introduced. Aśoka allowed discretion to the *Rājūkas* in the award of penalties, but he did not like that the *Danḍa* and *Vyavahāra* prevalent within the jurisdiction of one *Rājūka* should be entirely different from those prevailing within the jurisdiction of others.¹ He wanted to maintain some uniformity (*samatā*) both in *Danḍa* (penalties) as well as in *Vyavahāra* (legal procedure). As an instance he refers to the rule about the granting of a respite of three days to condemned men. The *Samatā* which he enforced involved a curtailment of the autonomy of the *Rājūkas* and did not necessarily infringe on the alleged immunity of the Brāhmaṇas from capital punishment.

But were the Brāhmaṇas really immune under all circumstances from capital punishment in ancient India? We learn from the *Pañchaviṃśa Brāhmaṇa*² that a *Purohita* (priest) might be punished with death for treachery to his master. The *Kauṭīliya*,³ tells us that a Brāhmaṇa guilty of treason was to be drowned. Readers of the *Mahābhārata* are familiar with the stories of the punishments inflicted on Māṇḍavya and Likhita.⁴ The life of a Brāhmaṇa was not so sacrosanct in ancient as in mediaeval and modern India. We learn from the

¹ I am indebted for this suggestion to Mr. S. N. Majumdar.

² *Vedic Index*, II, p. 84. The story of Kutsa and his chaplain, Caland, *Pañch. Br.*, XIV. 6.8; cf. *Dṛiḥadāraṇyaka Up.*, III, 9. 26.

³ P. 229.

⁴ *Ādi*, 107 and *Sānti*, 23, 36.

Aitareya Brāhmaṇa that king Hariśchandra of the Ikshvāku family did not scruple to offer a Brāhmaṇa boy as a victim in a sacrifice.

Against the surmises regarding the anti-Brāhmaṇical policy of Aśoka we have the positive evidence of some of his inscriptions which proves the Emperor's solicitude for the well-being of the Brāhmaṇas. Thus in Rock Edict III he inculcates liberality to Brāhmaṇas. In Edict IV he speaks with disapproval of unseemly behaviour towards the same class. In Edict V he refers to the employment of *Dharma-mahāmātras* to promote the welfare and happiness of the Brāhmaṇas.

Paṇḍit Sāstrī says further that as soon as the strong hand of Aśoka was removed the Brāhmaṇas seemed to have stood against his successors. We have no evidence of any such conflict between the children of Aśoka and the Brāhmaṇas. On the other hand, if the Brāhmaṇa historian of Kaśmīra is to be believed, the relations between Jalauka, one of the sons and successors of Aśoka, and the Brāhmaṇical Hindus were entirely friendly.¹

In conclusion Paṇḍit Sāstrī refers to the assassination of the last Maurya Emperor of Magadha by Pushyamitra Śuṅga and says, "We clearly see the hands of the

¹ Note also the employment of Brāhmaṇa officers, e.g., Pushyamitra, by the later Mauryas. Kalhaṇa has nothing but praise for Aśoka. Another Brāhmaṇa writer, Bāṇa, applies the epithet *anārya* (ignoble) not to the Maurya kings, but to the Brāhmaṇa general who overthrew the last of them. Viśakhadatta compares Chandragupta with the Boar Incarnation of Viṣṇu. Certain epic and Purāṇic writers, it is true, refer to the Mauryas as *asuras*, and the *Gārgī-Saṁhitā* draws pointed attention to the oppressive rule of some of the later members of the family. But there is little to suggest that the Brāhmaṇas were special victims of Maurya tyranny. On the contrary, members of the class were freely admitted to high office as evidenced by the case of Pushyamitra. The epithet *asura* or *asura-deśik* was applied not only to the Mauryas but to all persons 'beguiled by the Buddha.' The testimony of the Purāṇas in this respect is contradicted by that of contemporary epigraphs which refer to Aśoka and the only one among his imperial descendants who has left any epigraphic record as *devānāmpīya*, that is, the beloved (and not the enemy) of the gods.

Brāhmaṇas in the great revolution." But the Buddhist remains at Bhārhut erected "during the sovereignty of the Śuṅgas" do not bear out the theory which represents them as the leaders of a militant Brāhmaṇism. Are inferences deduced from uncorroborated writings of late authors like the compiler of the *Divyāvadāna* and perhaps Tāranātha, to be preferred to the clear testimony of contemporary monuments? Even admitting that Pushyāmītra was a militant Brāhmaṇist we fail to see how the decay and dismemberment of the Maurya empire can be attributed primarily to him or to his Brāhmaṇist followers. The empire was a shrivelled and attenuated carcass long before Pushyāmītra's *coup d'état* of c. 187 B.C. We learn from the *Rājatarāṅgīnī* that immediately after the death of Aśoka one of his own sons, **Jalauka**, made himself independent in Kāśmīra and conquered the plains including Kanauj. If Tāranātha is to be believed another prince, Virasena, apparently wrested Gandhāra from the hands of the feeble successor of the great Maurya at Pāṭaliputra. The virtual secession of Vidarbha or Berar is vouched for by the *Mālavikāgnimitram* of Kālidāsa. The loss of the northern provinces is confirmed by Greek evidence. We learn from Polybius that about 206 B.C., there ruled over them a king named Sophagāsenus, **Subhāgasena**, probably a successor of Virasena). We quote the passage referring to the king below :—

"He (Antiochos the Great) crossed the Caucasus (Hindukush) and descended into India; renewed his friendship with Sophagāsenus, the king of the Indians; received more elephants, until he had 150 altogether, and having once more provisioned his troops, set out again personally with his army, leaving Androsthenes of Cyzicus, the duty of taking home the treasure which this king had agreed to hand over to him."

It will be seen that Subhāgasena was a king and not a petty chief of the Kabul valley as Dr. Smith would have us believe. He is called "king of the Indians," a title which was applied by the classical writers to great kings like Chandragupta and Demetrios. There is nothing in the account of Polybius to show that he was vanquished by the Syrian king in war or was regarded by the latter as a subordinate ruler. On the contrary, the statement that Antiochos "renewed his friendship (or alliance) with Sophagasen^{us}, king of the Indians" proves that the two monarchs met on equal terms and friendly relations were established between them. The renewal of friendship on the part of the Greek king, and the surrender of elephants on the part of his Indian brother, only remind us of the relations subsisting between Chandragupta and Seleukos. Further the expression "renewal of friendship" seems to suggest that Subhāgasena had had previous dealings with Antiochos. Consequently he must have come to the throne sometime before 206 B.C. The existence of an independent kingdom in the north-west before 206 B.C. shows that the Maurya Empire must have begun to break up nearly a quarter of a century before the usurpation of Pushyamitra.

We have seen that the theory which ascribes the decline and dismemberment of the Maurya Empire to a Brāhmaṇical revolution led by Pushyamitra does not bear scrutiny. Was the Maurya disruption due primarily to the Greek invasion? The earliest Greek invasion after Aśoka, that of Antiochos the Great, took place about 206 B.C., and we have seen that the combined testimony of Kalhaṇa and Polybius leaves no room for doubt that the dissolution of the empire began long before the raid of the Hellenistic monarch.

What then were the primary causes of the disintegration of the mighty empire? There are good grounds

for believing that the government of the outlying provinces by the imperial officials was oppressive. Already in the time of Bindusāra ministerial oppression had goaded the people of Taxila to open rebellion. The *Divyāvadāna* says¹

“ *Atha Rājño Vindusārasya Takshaṣilā nāma nagaram viruddham. Tatra Rājñā Vindusāren Āsoko visarjitah... yāvat Kumāraschaturaṅgena balakāyena Takshaṣilām gataḥ, śrutvā Takshaṣilā nivāsinaḥ paurāḥ . . . pratyudgamyā cha kathayanti 'na vayam Kumārasya viruddhāḥ nāpi Rājño Vindusārasya api tu duṣṭāmātyā asmākaṁ paribhavam kurvanti.' ”*

“ Now Taxila, a city of king Bindusāra's, revolted. The king Bindusāra despatched Āsoka there. . . while the prince was nearing Taxila with the fourfold army, the resident *Pauras* (citizens of Taxila), on hearing of it. . . came out to meet him and said:—‘ We are not opposed to the prince nor even to king Bindusāra. But these wicked ministers insult us.’ ”

Taxila again revolted during the reign of Āsoka and the cause was again the tyranny of the ministers. *Rājñ-ośokasy-ottarāpathe Takshaṣilā nagaram viruddham . . .*². Prince Kunāla was deputed to the government of the city. When the prince went there the people said “ *na vayam Kumārasya viruddhā na rājño'-śokasy-āpi tu duṣṭātmano' mātyā āgatyāsmākaṁ apamānaṁ kurvanti.* ”

The *Divyāvadāna* is no doubt a late work, but the reality of ministerial oppression to which it refers, is affirmed by Āsoka himself in the Kalinga Edicts. Addressing the High officers (*Mahāmātras*) in charge of Tosālī he says: “ All men are my children; and just as I desire for my children that they may enjoy every kind

¹ P. 371.

² *Divyāvadāna*, 407f.

of prosperity and happiness both in this world and in the next, so also I desire the same for all men. You, however, do not grasp this truth to its full extent. Some individual, perchance, pays heed, but to a part only, not the whole. See then to this, for the principle of government is well-established. Again, it happens that some individual incurs imprisonment or torture and when the result is his imprisonment without due cause, many other people are deeply grieved...Ill performance of duty can never gain my regard... The restraint or torture of the townsmen may not take place without due cause. And for this purpose, in accordance with the Law of Piety, I shall send forth in rotation every five years such persons as are of mild and temperate disposition, and regardful of the sanctity of life. . .From Ujjain, however, the Prince for this purpose will send out a similar body of officials, and will not over-pass three years. In the same way—from Taxila.'''

From the concluding words of the Edict it appears that official maladministration was not confined to the province of Kalinga. The state of affairs at Ujjain and Taxila was similar. It is thus clear that the loyalty of the provincials was being slowly undermined by ministerial oppression long before Pushyamitra's *coup d'état* of c. 187 B.C.² and the Greek invasion of c. 206 B.C. Aśoka no doubt did his best to check the evil, but he was ill served by his officers. It is significant that the provincials of the north-west—the very people who complained of the oppression of the *dushtāmātyas* as early as the reign of Bindusāra, were among the first to break away from the Maurya empire.

¹ Smith, *Aśoka*, Third Ed., pp. 194-96.

² The Jaina date 313-108=205 B.C. for Pushyamitra's accession may refer to the assumption of power by Pushyamitra in Avanti, while the date c. 187 B.C. refers to the dynastic revolution in Magadha.

The Magadhan successors of Aśoka had neither the strength nor perhaps the will to arrest the process of disruption.¹ The martial ardour of imperial Magadha had vanished with the last cries of agony uttered in the battle-fields of Kalinga. Aśoka had given up the aggressive militarism of his forefathers and had evolved a policy of *Dhamma-vijaya* which must have seriously impaired the military efficiency of his empire.² He had called upon his sons and even great-grandsons to eschew new conquests, avoid the shedding of blood and take pleasure in patience and forbearance as far as possible. These latter had heard more of *Dhamma-ghosha* than of *Bheri-ghosha*. It is, therefore, not at all surprising that the *rois faineants* who succeeded to the imperial throne of Pāṭaliputra proved unequal to the task of maintaining the integrity of the mighty fabric reared by the genius of Chandragupta and his Chancellor.

On the contrary, if the *Gārgī Saṃhita* is to be believed, one of his successors, namely Śāliśūka, actually quickened the pace by his tyranny—*Sarāthīra mardate ghorāṇi dharmarāṭi adharmikāḥ* (sic). Some of Aśoka's descendants (e.g., Jalauka) set up independent sovereignties, and were thus directly responsible for the dismemberment of the empire.


¹ Cf. the events narrated on page 353 f. ante, and "Garga's" attack on the policy of so-called *Dharmavijaya*, "conquest conformable to Dharma" attributed to Śāliśūka, which, in the opinion of the present writer, is hard to dissociate from *Dhamma-Vijaya* as promulgated by Aśoka himself and recommended for adoption by his "sons and even great-grandsons." Attention to the passage in the *Gārgī Saṃhita* was also drawn by Jaysawal (JBORS. IV, 361)—*sthāpāyishyati mohātmā vijayaṁ nāma dharmikam*, "the fool will establish the so-called conquest of Dharma." The expression *mohātmā* reminds one of the later meaning of 'Deśanāshpiya' (fool, idiot like a brute, beast, Apte, *Sanskrit-English Dictionary*, 510). An eminent writer takes *Vijaya* to be a proper name, the appellation of the elder brother of Śāliśūka, whom the latter established on the throne. But it is not clear why the enthronement of a righteous (*dharmika*) man should earn for the person responsible for the action the opprobrious epithet *mohātmā*. Besides, *Vijaya* does not occur as a royal name in any of the lists of later Mauryas known to tradition. (For reference to divergent views see *Cal. Rev.*, Feb., 1943, p. 123 ff; Feb., 1946, p. 79 ff). As pointed out by Dr. Sircar, conjectural emendations of the text of the *Gārgī Saṃhita* in support of a particular theory do not carry conviction (*Cal. Rev.* 1943, April, 39ff).

(Contd. on the next page.)

The disintegration which set in before 206 B.C. was accelerated by the invasions led by the *Yavanas* referred to in the *Gārgī Samhitā* and the *Mahābhāshya* of Patañjali. The final *coup de grace* was given by Pushyamitra the Baimbika.

The royal hunt and jousts of arms in *Samājas* were abolished. The army seems to have been practically inactive during the last 29 years of Aśoka's reign as the emperor himself declares with a feeling of exultation that 'the sound of the *bheri* had become the sound of the True Law, *Dharma*.' The Chinese *Hou Hanshu* (quoted by S. Konow, CII, Vol. II, p. lxvii) testifies to the fact that people of India "practise the religion of the Buddha; it has become a habit with them not to kill and to fight." The ease with which general Pushyamitra overthrew his king, in the very sight of the army, shows that unlike the earlier kings of the dynasty who took the field in person, the last of the Mauryas lost touch with his fighting forces, and ceased to command their affection. The largesses of gold lavished on the religious must also have crippled the financial resources of the empire. The system of autonomous *Rājukas* instituted by Aśoka must have let loose centrifugal forces that his successors were unable to check.

GENEALOGY OF THE MAURYA DYNASTY



CHAPTER VI. THE BAIMBIKA-SUNGA EMPIRE AND THE BACTRIAN GREEKS.

SECTION I. THE REIGN OF PUSHYAMITRA.

*Satataṁ kampayāmāsa Yavanāneka eva yaḥ
balapaurushasampannān kṛitāstrānamitaujaśaḥ
yathāsurān Kālakeyān devo vajradharastathā.*

—*Mahābhārata*.¹

*Audbhijjo bhavitā kaśchit senānīḥ Kāśyapo dvijaḥ
aśvamedham Kaliyuge punaḥ pratyaharishyati.*

—*Harivaṁśa*.²

The Mauryas had done much for Indian unity by bringing the greater part of the country under "one umbrella," by defending it against the generals of Alexander and Seleukos, by establishing a uniform system of administration, by using *Prākṛit* for official purposes throughout the length and breadth of the empire and attempting to knit together the different sections of its composite population by the strong tie of a common *Dharma*. With the fall of the dynasty Indian history for the time being loses its unity. The command of one single political authority is no longer obeyed from the snowy heights of the Hindukush to the verdant plains of Bengal and the Upper Carnatic. Hordes of outlanders pour through the north-western gates of the country and establish aggressive monarchies in Gandhāra, Western Mālwa and neighbouring regions. The Pañjāb is seized by foreigners and the Deccan by local dynasts. The political connection of the *Madhyadeśa* with the valleys of the Indus and the Godāvarī is

¹ II. 4. 23.

² III. 2. 40.

temporarily snapped, and the splendour of the Magadhan metropolis is dimmed by the rising glory of Śākala, Vidiśā, Prathishthāna and other cities. Brāhmaṇism gains ground in the Ganges valley and the Deccan, while Jainism flourishes in Orissa. The sects of the *Māheśvaras* and the *Bhāgavatas* become powers to reckon with. The study of Sanskrit receives an impetus at the hands of the grammarians of the Madhyadeśa, while Prākṛit literature enjoys the patronage of the courts of Prathishthāna and Kuntala in Southern India.

Bṛihadratha, the last Maurya Emperor of Magadha, was, according to the *Purāṇas* and the *Harsha-charita*, assassinated by his general, Pushyamitra, who usurped the throne, and founded a new line of kings.

The origin of the usurping family is wrapped up in obscurity. According to the *Divyāvadāna* Pushyamitra was lineally descended from the Mauryas. The *Mālavikāgnimitram*, on the other hand, makes Agnimitra, son of Pushyamitra, a scion of the **Baimbika** family,¹ while the *Purāṇas*, and apparently the *Harsha-Charita*² represent

¹ In the *Mālavikāgnimitram* (Act IV. Verse 14; Tawney's translation, p. 69) Agnimitra claims to belong to the Baimbika-kula. A king named Bimbaki is mentioned in *The Ocean of Story*, Penzer I, 112, 119. Mr. H. A. Shah suggests (*Proceedings of the Third Oriental Conference*, Madras, p. 379) that the Baimbikas were connected with the family of Bimbisāra. It is more probable that the epithet 'Baimbika' (in the passage *ḍākshīṇyaṁ nāma bimbosthi Baimbikānāṁ kulacratam*) is connected with *bimbikā*, a kind of plant (*IC*, 1938, Jan. 865) and also perhaps with the river Bimbikā mentioned in the Bharhut Inscriptions (Barua and Sinha, p. 8). Cf. *Pādma*, *Bhūmikhaṇḍa* 90, 24; Baimbaki in *Paṭaṅjali*, IV, 1. 97. In the *Harivamśa* (*Bhaviṣya*, II. 40) the Brāhmaṇa *Senānī* who is to restore the *Aśvamedha* in the Kālī yuga is represented as an *Audbhijja*, 'Plant-born', and a *Kāśyapa*. Jaysawal identifies him with Pushyamitra. Curiously enough, the *Baudhāyana Śrauta Sūtra* (ed. Caland, Vol. III, p. 449) represents the *Baimbakayaj* as *Kāśyapas*.

² It is, however, to be noted that the *Harsha-charita* never applies the designation *Suṅga* to Pushyamitra himself, but only to one of the latest kings in the Purāṇic list. The *Purāṇas* may have combined the Baimbikas and *Suṅgas* under the common name of *Suṅga*.

these kings as **Śuṅgas**. One writer suggests that the Śuṅgas whose names ended in *Mitra* were Irāṇians, worshippers of Mithra (the Sun).¹ Others, regard them as Indian Brāhmaṇas. Curiously enough, Pāṇini² connects the Śuṅgas with the well-known Brāhmaṇa family of the Bhāradvājas. Sauṅgīputra, "son of a female descendant of Śuṅga," is the name of a teacher in the *Bṛihadāraṇyaka Upanishad*.³ Sauṅgāyani, "descendant of Śauṅga" is the name of a teacher in the *Vaṃśa Brāhmaṇa*. Macdonell and Keith point out that the Śuṅgas are known as teachers in the *Āśvalāyana Śrauta Sūtra*.⁴ In view of the conflicting statements in the *Mālavikāgnimitram*, the *Purāṇas*, etc., it is difficult to say whether Pushyamitra and his known descendants (down to Vasumitra) were Śuṅgas of the Bhāradvāja *Gotra* or Baimbikas of Kaśyapa lineage. The historic "Śuṅgas" of the time of Dhanabhūti are assigned by competent scholars to the period B.C. 100-75. This accords with the testimony of the *Harsha-charita* which, while denying this dynastic epithet to Pushyamitra, applies it to the latest kings of the Purāṇic list, the immediate predecessors of Vasudeva Kāṇva.

It is not known for certain when and why the family of Pushyamitra, like the Kadambas of a later date, exchanged the quill for the sword. There is no reason to think that Aśoka tyrannised over the Brāhmaṇas and that his oppression forced them to engage in non-priestly pursuits. Brāhmaṇa

¹ JASB, 1912, 287. Cf. 1910. 260.

² In *Sūtra* IV, 1, 117. Also *Kramadīśvara*, 763.

³ VI, 4. 31.

⁴ XII. 13. 5, etc. The *Vaṃśa Brāhmaṇa* seems to associate the Śuṅgas with the Madra country. *Ved. Index*, II, p. 123. For Tāranātha's reference to Pushyamitra, see JBORS, IV, pt. 3, 258. For Bhāradvājas as champions of autoeracy and of ministerial usurpation, see *Kauṭīliya*, 31, 316.

Senāpatis were by no means rare in ancient India.¹ The fact that officers of this class found employment under the Later Mauryas proves conclusively that the latter could not have pursued an anti-Brāhmaṇic policy.

The **Dominions of Pushyamitra** extended to the river Narmadā, and included the cities of Pāṭaliputra, Ayodhyā, Vidiśā, and, if the author of the *Divyāvadāna* and Tāranātha are to be believed, Jālandhara and Śākala.² It appears from the *Divyāvadāna*,³ that the Emperor himself continued to reside in Pāṭaliputra. The *Mālavikāgnimitram* tells us that Vidiśā (Besnagar in Eastern Mālwa) was governed by Prince Agnimitra, probably as his father's viceroy (*Goptṛi*).⁴ Another viceroy, also a relation of the emperor, may have governed Kosala.⁵ Agnimitra's queen had a brother of inferior caste, named Vīrasena. He was placed in command of a frontier fortress on the banks of the Narmadā (*Atthi devī vaṇṇāvaro*

¹ Cf. the cases of Droṇa, Kṛipa and Aśvatthāman in the *Mahābhārata* in ancient times, of Ravidēva in the *Indian Antiquary*, VIII. 20, of Kholeśvara, the commander of Yādava kings, and of Someśvara, the Brāhmaṇa general of the Pāla kings.

² Jaina writers, e.g., Merutuṅga, include Avanti within the dominions of Pushyamitra. This province was lost to the Śātavāhanas, and Śākala to the Greeks.

³ P. 434.

⁴ *Mālavikāgnimitram*, Act V, pp. 370, 391 of G. Vidyānidhi's ed. esp. verse 20. *Saṃpadyate na khalu Goptari nā Agnimitre*.

⁵ The possible existence of this vicereignty is disclosed by an inscription discovered at the door of a temple at Ayodhyā, which records the erection of a "ketana" (abode) by a Kosalādhipa who was the sixth (brother or descendant?) of *Senāpati* Pushyamitra, the performer of two horse-sacrifices (*Nāgarī Prachārīṇi Patrikā*, *Vaiśākha*, Sam. 1981; JBORS, X (1924) 203; XIII (1927) facing 247. *Mod. Review*, 1924; October, p. 431; *IHQ*, 1929, 602f.; Ep. Ind. XX. 54ff.). It is interesting to note that the title, '*Senāpati*' clung to the *deva* (king) Pushyamitra even after the performance of the *Aśvamedha*. Cf. the epithet *Vāhinīpati* applied to king Virāṭa in the *Mahābhārata* and the title *Yacuga* applied to Kushān emperors besides other epithets. Cf. also the style *Mahārāja Mahāsenāpati* in CII., Vol. 3, p. 252, and the title *Mahāmaṇḍaleśvara* applied to Bijjala and others even after the assumption of the full royal style (*Bomb. Gaz.*, II. ii. 474ff.).

bhādā Viraseṇo nāma, so bhaṭṭiṇā antav (p) āladugge Nammadātire¹ ṭhāvīdo).

Affairs in the Deccan

It appears from the *Mālavikāgnimitram* that the foundation of the dynasty of Pushyamitra almost synchronised with the establishment of a new kingdom in the Deccan, viz., **Vidarbha** or Berar. Agnimitra's *Amātya* (Minister) refers to the kingdom as "*achirādhishṭhita*" (established not long ago) and compares its king to a tree which is newly planted and, therefore, not firm (*navasamropana-sithila-staruḥ*). The king of Vidharbha is represented as a relation (sister's husband) of the Maurya minister (*Sachiva*) and a natural enemy (*Prakṛityamitra*) of the family of Pushyamitra. It appears that during the reign of Brihadratha Maurya there were two parties or factions in the Magadha Empire, one headed by the king's *Sachiva* or minister, the other headed by his *Senāpati* or general. The minister's partisan Yajñasena got the rulership of Vidarbha, while the general's son Agnimitra obtained the viceroyalty of Vidiśā. When the general organised his *coup d'état*, killed the king, and imprisoned the minister, Yajñasena apparently declared his independence and commenced hostilities against the usurping family. This is why he is called *achirādhishṭhita-rājya* and *prakṛity-amitra* by Agnimitra and his *Amātya*.

¹ Act I. Some manuscripts mention Mandākinī as the name of the river (cf. *IHQ.*, 1925, 214). A stream called Mandākinī lies 5 miles south of the Tāptī (*Ind. Ant.*, 1902, 254). Another Mandākinī flowed near Chitrakūṭa (*Rām.* 92, 10-11). Lüders' Inscriptions, Nos. 687-688, seem to suggest that Bharhut (in Baghelkhand) was governed by a Śuṅga feudatory. If Pushyamitra was a Śuṅga Baghelkhand must have formed part of the empire of his family. In the *Monuments of Sāncī*, I. iv. 271, the author does not agree with Bühler in assigning the ins. to the middle of the second century B.C. He prefers B.C. 100-75. Palaeographically the epigraphs are classed with the ins. of Indrāgnimitra, Brahmanitra and Vishnūmitra.

The *Mālavikāgnimitram* says that when Kumāra Mādhavasena, a cousin of Yajñasena and a partisan of Agnimitra, was secretly on his way to Vidiśā, he was captured by an *Antapāla* (Warden of the Marches) of Yajñasena and kept in custody. Agnimitra demanded his surrender. The Vidarbha king promised to give him up on condition that his brother-in-law, the Maurya minister, should be released. This enraged the ruler of Vidiśā who ordered Virasena to march against Vidarbha. Yajñasena was defeated. Mādhavasena was released and the kingdom of Vidarbha was divided between the two cousins, the river Varadā (Wardha) forming the boundary between the two states. Both the rulers seem to have accepted the suzerainty of the House of Pushyamitra.

In the opinion of several scholars an enemy more formidable than Yajñasena threatened Pushyamitra's dominions from Kalinga (Orissa). In his *Oxford History of India*¹ Dr. Smith accepts the view that **Khāravēla, king of Kālīṅga**, defeated Pushyamitra who is identified with Bahapatimita or Bahasatimita, a prince supposed to be mentioned in the *Hāthīgumphā* Inscription of the Kalinga monarch. Prof. Dubreuil also seems to endorse the view that Khāravēla was an antagonist of Pushyamitra, and that the *Hāthīgumphā* Inscription is dated the 165th year of *Rāja-Muriya-kāla* (era of king Maurya) which corresponds to the 13th year of the reign of Khāravēla.

Dr. R. C. Majumdar, however, points out² that of the six letters of the *Hāthīgumphā* Inscription which have been read as *Bahasati-mitam*, the second letter seems to have a clear *u* sign attached to it, and the third and fourth letters look like *pa* and *sa*. Even if the reading *Bahasati-mitam*,

¹ Additions and corrections, and p. 58n. Cf. also S. Konow in *Acta Orientalia*, I. 29. S. Konow accepts Jayaswal's identification, Bahasatimita = Pushyamitra.

² *Ind. Ant.*, 1919, p. 189. Cf. Allan *CICAI*, p. xcvi.

or *Bahapati-mitam*, be accepted as correct, the identification of Bahasati (Bṛihaspati-mitra) with Pushyamitra merely on the ground that Bṛihaspati (Jīva) is the regent, *nakshatrā-dhipa*, of the *nakshatra* or zodiacal asterism Pushya, also named Tishya, in the constellation Cancer or the Crab, cannot be regarded as final in the absence of more convincing evidence.¹ In this connection we should note that the *Divyāvadāna*² distinguishes between a king named "Vṛihaspati" and king Pushyamitra,³ and represents Pāṭaliputra as the residence of the latter whereas the Magadhan antagonist of Khāravela is possibly called "*Rājagahanapa*"⁴ and apparently resided in the city of Rājagṛiha.

✓ The date "165th year of the *Muriyakāla*" was deduced from a passage of the Hāthīgumphā Inscription which was read as follows :⁵—"Pānamtariya-saṭhi-vasa-sate Rāja-Muriya-kāle vochechhine...". There is another passage in the same inscription which runs thus :—*Paṁchame cha* (or *che*) *dānī vase Naṁda-rāja 'ti-vasa-sata* (m ?)—*oghāṭitam Tanasuliya-vāṭā-panāḍim nagaram pavesayati*.⁶ If *Pānamtariya-saṭhi-vasa-sate* be taken to mean "in the 165th year",

¹ Cf. Chanda in *IHQ*, 1929, p. 594ff.

² Pp. 433-34.

³ It is not suggested that Vṛihaspati of the *Divyāvadāna* is necessarily to be identified with any king named Bṛihaspatimitra mentioned in inscriptions, though the possibility is not entirely excluded. What we mean to point out is that the name "Bṛihaspati" is not to be equated with Pushyamitra, simply because Bṛihaspati is the "regent" of the asterism *Pushya*, because in literature 'Vṛihaspati', 'Pushyadharman' and 'Pushyamitra' occur as names of distinct individuals. Regarding the proposed identification of Pushyamitra with Bṛihaspatimitra, see also *IHQ*, 1930, p. 23.

⁴ Cf. Lüders' reading, *Ep. Ind.*, X, App. No. 1345. With Jayaswal, S. Konow (*Acta Orientalia*, I. 26) reads "*Rājagaham upapīḍāpayati*," though he admits that "*Rājagahanapa* (m) *pīḍāpayati*" is also possible.

⁵ Cf. Bhagwanlal Indraji, *Actes du sixième congrès international des Orientalistes*. Pt. III, Section 2, pp. 133 ff.; Jayaswal *JBORS*, 1917, p. 459.

⁶ *Ibid*, p. 455. For the interpretation of the passage, see p. 229 *supra*. S. Konow translates it differently :—"And now in the fifth year he has the

ti-vasa-sata should be taken to mean 103 years, and we shall have to conclude that Khāravēla flourished some 165 years after a Maurya king, and only 103 years after Nandarāja, which is impossible as the Nandas preceded the Mauryas. If, on the other hand, *ti-vasa-sata* be taken to mean 300 years, *pānamtariya-saṭhi-vasa-sata* should be taken to mean not 165 but 6,500 years. In other words Khāravēla will have to be placed 6,500 years after a Maurya which is also impossible. Jayaswal himself subsequently gave up the reading "...*Pānamtariya-saṭhi-vasa-sate Rāja-Muriya-kāle vochchhine cha chhe-yāṭhi Argasi ti kamtāriyam upādiyati*" in line 16, and proposed to read "*Paṭālīko chatare cha veduriyagabhe tham̐bhe paṭiṭhāpayati pānatariyā sata-sahasehi. Muriya kalam̐ vochhinam̐ cha choyāṭhi agasatikamtariyam upādāyati.*" He translated the passage thus:—"on the lower-roofed terrace (i.e., in the verandah) he establishes columns inlaid with beryl at the cost of 75,00,000 (*Paṇas*), he (the king) completes the Muriya time (era), counted and being of an interval of 64 with a century." With regard to this new reading and translation Mr. R. P. Chanda observed² "the rendering of *vochhine* as 'counted' is even more far-fetched than 'expired'. The particle *cha* after *vochhine* makes it difficult to read it as *vochhinam* qualifying the substantive *Muriyakālam*. Even if we overlook *vochhine*, the passage appears to be a very unusual way of stating a date. Still more unusual is the statement of a date as an

aqueduct which was shut (or opened) in the year 103 (during the reign of) the Nanda king, conducted into the town from Tanasuliya Vāṭa."

¹ JBORS, Vol. IV, Part iv, p. 394f. For Dr. Barua's suggestions see IHQ, 1938, 269.

² M. A. S. I., No. 1. p. 10. Cf. also S. Konow in *Acta Orientalia*, I. 14-21. Like Fleet S. Konow finds no date in the passage but regards the reading *Rāja Muriya kāla* as certain. According to him Khāravēla restored some texts missing in the time of the Maurya king Chandragupta. Dr. Barua does not regard the reading *Muriya* as certain.

independent achievement in a *praśasti*." According to Fleet the use of the term "*vochchhina*" which is applied to sacred texts which have been 'cut off,' 'interrupted'—quite prohibits the existence of a date. It may be added that there is no reliable evidence of the existence of a *Rāja-Muriya-kāla* in the sense of an era founded by the first Maurya. The use of regnal years by Aśoka points to the same conclusion.¹ Jayaswal himself admits in the *Epigraphia Indica*,² that "there is no date in a Maurya era in the 16th line," of the Hāthīgumphā inscription.³

Dr. Jayaswal at one time took *ti-vasa-sata* to mean 300 years and placed Khāravela and Pushyamitra three centuries after Nandarāja whom he identified with Nandavardhana.

¹ An era of Samprati, grandson of Aśoka, is however, mentioned in an ancient Jain MS. (EHI 4, p. 202a). If we refer the year 164 to this era, the date of Khāravela must be brought down to (cir 224-164=) 60 B.C. In "*A note on the Hāthīgumphā Inscription of Khāravela*" Barnett suggests the following rendering of the passage which is supposed to contain the words *Muriya-kāla*: "And when the Mauryan (?) time-reckoning which consisted of lustræ (*antara*) of five (years) each, had broken down, he found (a new time-reckoning) consisting of lustræ of 7 years each (*saptikāntariyam*) and mounting up to the 64th year (*chatuṣṣaṣṭiyagram*)."⁴ To reform the calendar Khāravela introduced a new cycle of 64 years consisting of 9 Yugas of 7 years each. According to Dr. F. W. Thomas (JRAS, 1922, 84) *antara*=*antargriha*=cell. The passage means that cells which had been left unfinished during the time of the Maurya kings were constructed by Khāravela.

² XX. 74.

³ His latest reading of the inscriptional passage is as follows:—

"*Paṭalaka chaṭturo cha veḍḍariya-gabhe thaṣṭhe paṭiṭhāpoyati, pānāteriya ratarahase(hi); Muriya-kāla-vochchināṣ cha choyath(i) Aṅga satika(m) tūriyam upādayati.*"

"*Paṭalaka(?) (he) sets up four columns inlaid with beryl at the cost of seventy-five hundred thousands; . . . (he) causes to be compiled expeditiously the (text) of the sevenfold Aṅgas of the sixty-four (letters).*" *Ep. Ind.*, XX, pp. 80, 89.

But we have already seen that Nandavardhana or Nandivardhana was a Śaiśunāga king and that the Śaiśunāgas do not appear to have had anything to do with Kalinga. "It is not Nandivardhana but Mahāpadma Nanda who is said to have brought 'all under his sole sway' and 'uprooted all Kshatriyas' or the old reigning families. So we should identify 'Nandārāja' of the Hāthīgumphā inscription, who held possession of Kalinga either with the all-conquering Mahāpadma Nanda or one of his sons."¹ Professor Barua objects to the identification of "Nandārāja," the conqueror of Kalinga, with a king of the pre-Aśokan Nanda line on the ground that in the Aśokan inscriptions it is claimed that Kalinga was *not* conquered (*avijita*) before Aśoka. But such claims are on a par with the Gupta boast that Samudra Gupta was *ajita-rājajetā*, conqueror of unconquered kings,² and that the *Aśvamedha* sacrifice had been revived, after a long period of abeyance, by him. We know that as a matter of fact the claims, if taken too literally, had very little substance in them. The suggestion in the *Cambridge History of Ancient India* that Nandarāja may have been a local ruler of Kalinga is negated by the internal evidence of the Hāthīgumphā Inscription.³ A post-Aśokan "neo-Nanda" line of **Magadha** is also unknown to sober history.⁴

¹ M. A. S. I., No. I, p. 12.

² Allan, *Gupta Coins*, p. ex. Cf. Jahāngir's boast that "not one of the mighty emperors has conquered" Kangra, (*ASI, AR*, 1905-6, p. 11). *Avijita* may simply refer to the fact that Kalinga was not included within the limits of Aśoka's *Vijita* (empire) or *Rāja-vishya* (Royal Dominions).

³ Cf. the passage—"Nandārāja nītan cha Kalinga Jinasaṁnivesam" which proves clearly that Nanda was an outsider.

⁴ A late Nanda or *Nandodbhava* line is known to epigraphy. But it ruled in Orissa. See R. D. Banerji. Orissa, I. 202; Kumar Bidyādhara Singh Deo, *Nandapur*, I. 46; Ep. Ind. xxi, App. Ins. No. 2043.

As Mahāpadma Nanda and his sons ruled in the fourth century B.C., Khāravela is to be assigned either to the third century B.C., (taking *ti-vasa-sata* to mean 103)¹ or to the first century B.C. (taking *ti-vasa-sata* to mean 300). In neither case could he be regarded as a contemporary of Pushyamitra who ruled from about 187 to 151 B.C.

The Yavana Invasion

The only undoubted historical events of Pushyamitra's time, besides the *coup d'etat* of c. 187 B.C., and the Vidarbha war, are the Greek invasion from the North-West referred to by Patañjali or a Predecessor and Kālidāsa, and the celebration of two horse-sacrifices.

Patañjali is usually regarded as a contemporary of Pushyamitra. Sir R. G. Bhandarkar draws our attention to the passage in the *Mahābhāshya*—*iha Pushyamitraṃ yājayāmaḥ* : "here we perform the sacrifices for Pushyamitra"—which is cited as an illustration of the *Vārttika* teaching the use of the present tense to denote an action which has been begun but not finished.² The instances given by Patañjali of the use of the imperfect to indicate an action well-known to people, but not witnessed by the speaker, and still possible to have been seen by him, are, "*arunad Yavanaḥ Sāketam : arunad Yavano Madhyamikām.*" This, says Sir R. G. Bhandarkar, shows that a certain Yavana or Greek chief had besieged Sāketa or Ayodhyā

¹ Konow (*Acta Orientalia*, Vol. I, pp. 22-26) accepts the date 103, but refers it (along with another date, 113, which he, with Fleet, finds in line 11) to a Jaina era. This era he is inclined to identify with that of Mahāvīra's *Nirvāṇa*. Apparently he is not aware of the existence of another Jaina reckoning, viz., the era of Samprati. Dr. K. P. Jayaswal (*Ep. Ind.*, XX. 75) now assigns the date 103 to a Nanda era and says that the date refers to the time when the Tanasuliya Canal, which Khāravela extended to the capital in the 5th year of his reign, was originally excavated.

² *Ind. Ant.*, 1872, p. 300.

and another place called *Madhyamikā*¹ when Patañjali wrote this. It is, however, possible that the instances cited by the great grammarian are stock illustrations (*mūrdhābhishikta udāharāṇa*) which are simply quoted by him from earlier authorities. But a war with Greeks in the days of Pushyamitra is vouched for by Kālidāsa. In his *Mālavikāgnimitram* the poet refers to a conflict between prince Vasumitra, grandson and general of Pushyamitra, and a Yavana on the southern (or right) bank of the Sindhu.² Unfortunately the name of the leader of the invaders is not given either in the *Mahābhāshya* or in the *Mālavikāgnimitram*. There is considerable divergence of opinion with regard to his identity. But all agree that he was a Bactrian Greek.

The **Bactrian Greeks** were originally subjects of the Seleukidan Empire of Syria (and Western Asia). We learn from Strabo, Trogus and Justin that "about the middle of the third century B.C. when the Seleukid rulers were pre-occupied in the west" Diodotos, "Governor of the thousand cities of Bactria" (Balkh region to the south of the Oxus), revolted and assumed the title of king. He was succeeded, according to Justin, by his son Diodotos II who entered into an alliance with Arsakes who about this time (c. 247 B.C.) tore Parthia in Northern Irān from the Seleukidan Empire.

The successor of Diodotos II was Euthydemos. We learn from Strabo³ that Euthydemos and his party occasioned the revolt of all the country near the province of Bactriana. We are told by Polybius that Antiochos III (223-187 B.C.) of Syria made an attempt to recover the lost provinces but afterwards made peace with Euthydemos.

¹ Nāgari near Chitor: cf. *Mbh.*, II. 32.8; *Ind. Ant.*, VII, 267.

² The Indus or possibly a stream of the same name in Central India (*cf.* *IEQ.* 1925, 215).

³ *H. & F.'s Tr.*, Vol. II, p. 251.

The historian says, "Antiochos the Great received the young prince (Demetrios, son of Euthydemos) and judging from his appearance, conversation and the dignity of his manners that he was worthy of royal honour he first promised to give him one of his daughters,' and secondly conceded the royal title to his father. And having on the other points caused a written treaty to be drawn up and the terms of the treaty to be confirmed on oath, he marched away, after liberally provisioning his troops, and accepting the elephants belonging to Euthydemos. He crossed Caucasus (Hindukush) and descended into India; renewed his friendship with Sophagasenos, the king of the Indians; received more elephants, until he had 150 altogether, having once more provisioned his troops set out again personally with his army, leaving Androsthenes of Cyzicus, the duty of taking home the treasure which this king had agreed to hand over to him."

Not long after the expedition of Antiochos the Great, the Bactrian Greeks themselves formed the design of extending their kingdom by the conquest of the territories lying to the south of the Hindukush. Strabo says, "the Greeks who occasioned its (Bactria's) revolt became so powerful that they became masters of Ariana and India, according to Apollodoros of Artemita.² Their chiefs, particularly Menander (if he really crossed the Hypanis³ to the east and reached the Isamus⁴) conquered more nations than Alexander. These conquests

¹ Tarn's scepticism (*Greeks in Bactria and India*, 82, 301) about the marriage is not warranted by cogent evidence. His arguments are in part of a negative character. He seems to prefer his own interpretation of certain coins of Agathokles to the clear testimony of Polybios.

² Artemita lay to the east of the Tigris. The books of Apollodoros are assigned to a date between c. 150 B.C. and 87 B.C. (Tarn, *Greeks*, 44ff.).

³ I.e., the Hyphasis or Vipāśā (the Beas).

⁴ The Trisāmā? In the *Bhāgavata Purāṇa* (V. 19, 17) a river of this name is mentioned in conjunction with the Kauśiki, Mandākinī, Yamunā, etc. Sircar prefers the Ikshumatī.

were achieved partly by Menander, partly by Demetrios, son of Euthydemos, king of the Bactrians. They got possession not only of Patalene (the Indus Delta), but of the kingdoms of Saraostos (Surāshtra or Kāthiāwār), and Sigerdis (probably Sāgaradvīpa)¹ which constitute the remainder of the coast. Apollodoros in short says that Bactriana is the ornament of all Ariana. They extended their empire even as far as the Seres and Phryni."²

Strabo gives the credit for spreading the Greek dominion furthest to the east into India partly to Menander and partly to Demetrios, son of Euthydemos and son-in-law of Antiochos the Great.

Menander has been identified with the king Milinda who is mentioned in the *Milinda-pañho* as a contemporary of the Buddhist *Thera* (Elder) Nāgasena, and also in the *Avadāna-kalpalatā* of Kshemendra.³ This monarch was born at Kalsigrāma⁴ in the "Island" of Alasanda or Alexandria⁵ and had his capital at Sāgala or Sākala, modern Siālkoṭ, in the Pañjāb,⁶ and not at Kābul as Dr. Smith seemed to think.⁷ The extent of his conquests is indicated by the great variety and wide diffusion of his coins which have been found over a very wide extent of country as far west as Begram near Kābul and as far east as Mathurā.⁸ The author of the *Periplus* states

¹ *Mbh.*, II. 31. 66, Cutch? *Bom. Gaz.*, I. i. 16f; cf. Tarn, *GBI*, 2nd ed. 527.

² *Strabo*, Hamilton and Falconer, Vol. II, pp. 252-53. The Chinese and peoples of the Tarim basin are apparently meant.

³ *Stūpa avadāna* (No. 57); Smith, *Catalogue of Coins, Indian Museum*, p. 3; *SBE.*, 36, xvii.

⁴ Treuckner, *Milindapañho*, p. 83.

⁵ *Ibid.*, p. 82 (*CHI*, 550). The identity of this "Alexandria" is uncertain. Tarn (p. 141) seems to prefer Alexandria in the Kābul Valley. The *Milinda*, VI. 21, seems to suggest location on the sea unless a different Alexandria is meant.

⁶ *Milinda*, pp. 3, 14.

⁷ *EHL.*, 1914, p. 225.

⁸ *SBE.*, Vol. XXXV, p. xx. Tarn, 228.

that small silver coins, inscribed with Greek characters and bearing the name of Menander were still current in his time (cir. 60-80 A.D.) at the port of Barygaza (Broach). Plutarch tells us that Menander was noted for justice, and enjoyed such popularity with his subjects that upon his death, which took place in camp, diverse cities contended for the possession of his ashes. The statement of Plutarch is important as showing that Menander's dominions included many cities. The recently discovered Bajaur Relic Casket Inscription confirms the numismatic evidence regarding the westward extension of his empire.¹

Demetrios has been identified by some with king Dattāmitra mentioned in the *Mahābhārata*,² the "great Emetreus, the king of Inde" of Chaucer's *Knights Tale* and Timitra of a Besnagar seal.³ The wide extent of his conquests is proved by the existence of several cities named after him or his father in Afghanistan as well as India. Thus in the work of Isidore of Charax⁴ we have a reference to a city named Demetriaspolis in Arachosia. The *Vyākaraṇa* (grammar) of Kramadīśvara mentions a city in Sauvīra called Dattāmitri.⁵ Ptolemy the Geographer

¹ Ep. Ind. XXIV, 7 ff, XXVI, 318f, XXVII, ii, 52f. The King's name is given as Mina-edra.

² I, 139, 23. Krimisa, the Yaksha (AIU, p. 107) with whom he is identified by Dr. Bagchi belongs to the domain of folklore.

³ EHI⁴, p. 255n.

⁴ JRAS, 1915, p. 830. *Parthian Stations*, 19.

⁵ Ind. Ant., 1911. *Foreign Elements in the Hindu Population*; Bomb. Gaz., I. ii, 11, 176, Kramadīśvara, p. 796. The reference is probably to a Demetrias in the lower Indus Valley. Johnston differs from the view (JRAS, April, 1939; IHQ, 1939). We should, however, not ignore the evidence of Mbh. I, 139, verses 21-23, which clearly refer to a Yavanādhipa and Dattāmitra in connection with Sauvīra. If Dattāmitra is not Demetrios and Dattāmitri not a city founded by him, it will be interesting to know with whom Dattāmitra and the Yavanādhipa of the epic are proposed to be identified. A Nasik (Deccan) Inscription (No. 1140 Lüders' List) makes mention of a Yopaka from the north (Otarāha), a native of Dattāmitri. Thus epic and epigraphic evidence together with that of Sanskrit grammarians clearly establishes the connection between the Yonas or Yavanas (Greeks), Dattāmitri and Sauvīra.

mentions the city of Euthymedia (? Euthydemia¹) which was identical with Śākala,² and was, according to the *Milinda-pañho*, the capital of an Indo-Greek kingdom in the time of Menander.

It is permissible to conjecture that one of the two conquering kings, viz., Menander and Demetrios, was identical with the Yavana leader who penetrated to Śāketa in Oudh, Madhyamikā near Chitor, and the river Sindhu possibly in Central India, in the time of Pushyamitra. Goldstücker, Smith and many other scholars identified the invader with Menander who crossed the Hypanis (Beas) and penetrated as far as the Isamus (Trisāmā³?). On the other hand, Dr. Bhandarkar suggested, in his *Foreign Elements in the Hindu Population*, the identification of the invader with Demetrios. We learn from Polybios that Demetrios was a young man at the time of Antiochos III's invasion (between 211 and 206 B.C.). Justin says that Demetrios was "king of the Indians" when Eukratides was king of the Bactrians and Mithradates was the king of the Parthians. "Almost at the same time that Mithradates ascended the throne among the Parthians, **Eukratides** began to reign among the Bactrians; both of them being great men...Eukratides carried on several wars with great spirit, and though much reduced by his losses in them, yet, when he was besieged by Demetrios, king of the Indians, with a garrison of only 300 soldiers, he repulsed, by continual sallies, a force of 60,000 enemies."

¹ We are hardly justified in rejecting the reading 'Euthyde' (Tarn, p. 486) simply on the grounds urged by Tarn (p. 247) which do not appear to be convincing, and accept a reading which is "meaningless and wrongly accented." See also Keith in *D. R. Bhandarkar Volume*, 221f.

² *Ind. Ant.*, 1894, pp. 349-50.

³ As already stated, Trisāmā is a river mentioned in the *Bhāgavata Purāṇa*. Note the absence of any reference to the Ganges in Strabo's account of Menander's conquests.

Dr. Smith assigns Mithradates to the period from 171 to 136 B.C. (to 138/37 B.C. according to Debevoise). Eukratides and Demetrios must also be assigned to that period, that is the middle of the second century B.C.¹

We have seen that Demetrios was a young man and a prince in or about 206 B.C. We now find that he ruled as king of the Indians about the middle of the second century B.C. He was, therefore, the Indo-Greek contemporary of Pushyamitra who ruled from c. 187 to 151 B.C. Menander, on the other hand, must have ruled over the Indo-Greek kingdom much later, as will be apparent from the facts noted below. Justin tells us that Demetrios was deprived of his Indian possessions by Eukratides.² Eukratides was killed by his son with whom he had shared his throne.³ The identity of the parricide is uncertain but no one says that he was Menander.⁴

Justin furnishes the important information that the prince who murdered Eukratides was a colleague of his father. We know that Greek rulers who reigned conjointly sometimes issued joint coins. Thus we have joint coins of Lysias and Antialkidas, Agathokleia and Strato, of Strato I and Strato II, and of Hermaios and Kalliope. The only Greeks whose names and portraits appear on a

¹ The activity of Mithradates I began after the death of Antiochus IV in 163 B.C. See Tarn, pp. 197 ff. According to Debevoise, *A Political History of Parthia*, p. 20 ff. Antiochus IV, Epiphanes, crossed the Euphrates in 165 B.C. Mithradates I died in 138/37 B.C., the first Parthian date fixed by numismatic and cuneiform evidence. Eukratides assumed the title "Great" before 162 B.C. (date of Timarchus) (*The Cambridge Shorter History of India*, p. 64). His coins are copied by Plato (165 B.C.) as well as Timarchus.

² Watson's tr., p. 277.

³ *Ibid.*, p. 277.

⁴ According to Cunningham and Smith the parricide was Apollodotos. But Rapson shows good reasons for believing that Apollodotos did not belong to the family of Eukratides, but was, on the other hand, a ruler of Kāpiśa who was ousted by Eukratides (JRAS, 1905, pp. 784-85). Rawlinson points out (*Intercourse between India and the Western World*, p. 73) that Apollodotos uses the epithet

coin or medallion together with those of Eukratides are **Heliokles** and his wife Laodike. Cunningham and Gardner suggested that Heliokles and Laodike were the father and mother of Eukratides. But Von Sallet¹ proposed an entirely different interpretation of the coins in question. He thought that they were issued by Eukratides, not in honour of his parents, but on the occasion of the marriage of his son Heliokles with a Laodike whom Von Sallet conjectured to have been daughter of Demetrios by the daughter of Antiochos III. If Von Sallet's conjecture be accepted then it is permissible to think that Heliokles was the colleague of Eukratides referred to by Justin, and the murderer of his father.

It is clear from what has been stated above that Demetrios was succeeded by Eukratides, who, in his turn, was probably followed by Heliokles. Menander could not in that case have reigned earlier than Heliokles. It may, however, be argued that after Demetrios the Indo-Greek kingdom split up into two parts: one part which included the Trans-Jhelum territories was ruled by Eukratides and his son, the other part which included "Euthymedia" (Euthydemia?) or Śākala was ruled by Menander who thus might have been a younger contemporary of Eukratides (cir. 171-165 B.C.) and consequently of Pushyamitra (cir. 187-151 B.C.).

Now, the disruption of the Indo-Greek kingdom after Demetrios may be accepted as an historical fact. The existence of two rival Greek kingdoms in India and their

Philopator, and the title would be somewhat incongruous if he were a parricide. It may be argued that the parricide was Apollodotos Soter and not Apollodotos Philopator, but we should remember that the titles Soter and Philopator sometimes occur on the same coin (Whitehead, *Catalogue of Coins*, p. 48) and therefore it is impossible to justify the separation of Apollodotos Soter and Apollodotos Philopator as two entities.

¹ *Ind. Ant.*, 1880, p. 256.

mutual dissensions are proved by literary and numismatic evidence. The *Purāṇas* say :

*Bhavishyantiha Yavanā dharmataḥ kāmato'rthataḥ
naiva Mūrdhābhishiktās te bhavishyanti narādīpāḥ
yuga-dosha-durāchārā bhavishyanti nṛpās tu te
strinām bāla-vadhenaiḥ hatoḥ chaiva parasparam.*

"There will be Yavanas here by reason of religious feeling or ambition or plunder; they will not be kings solemnly anointed but will follow evil customs by reason of the corruptions of the age. Massacring women and children' and killing one another, kings will enjoy the earth at the end of the *Kali* age."

The *Gārgī Saṃhitā* informs us :

*Madhyadeśe na sthāsyanti Yavanā yuddha durmadāḥ
teshām anyonya sambhāvā (?) bhavishyanti na saṃśayaḥ
ātma-chakrotthitaṃ ghoram yuddham parama-dāruṇam.*

"The fiercely fighting Greeks will not stay in the *Madhyadeśa* (Mid-India); there will be a cruel, dreadful war in their own kingdom, caused between themselves."

Coins bear testimony to struggles between kings of the house of **Eukratides** and rulers of the family of **Euthydemos**. But the evidence which we possess clearly indicates that the contemporaries and rivals of Eukratides and Heliokles were **Apollodotos**, **Agathokleia** and **Strato I**, and not Menander. A square copper¹ coin of Eukratides has on the obverse a bust of the king and the legend "*Basileus Megalou Eukratidon*." On the reverse there is the figure of Zeus and the legend "*Kavisiye nagara-*

¹ Cf. *Cunn. AGI*. Revised Ed. 274; *Camb. Hist. Ind.*, I. 370. "The Macedonians . . . gave away to a fury of blood-lust, sparing neither woman nor child."

² *Pargiter, Dynasties of the Kali Age*, pp. 56, 74.

³ Kern, *Bṛhat Saṃhitā*, p. 38.

⁴ *CHI*, 555, 690; Whitehead, *Indo-Greek Coins*, 26.

devatā." They are often coins (?) of Apollodotos restruck.¹ From this it is probable that Apollodotos was a rival of Eukratides, and was superseded in the rule of Kāpiśa, which lay in the district identified with Kāfiristān and the valleys of Ghorband and Panjshir, by the latter. Rapson further points out² that Heliokles restruck the coins of Agathokleia and Strato I ruling conjointly and also of Strato I reigning alone. Further, the restriking is always by Heliokles, never by Agathokleia and Strato I. From this it is clear that Agathokleia and Strato I ruled over an Indo-Greek principality either before, or in the time of Heliokles, but probably not after him.

We have seen that according to the evidence of Justin and the Kāpiśa coins Eukratides probably fought against two rivals, namely, Demetrios and Apollodotos; his son Heliokles also fought against two rivals, namely, Agathokleia and Strato I. As Demetrios and Apollodotos were both antagonists of Eukratides and used similar coin-types, the inevitable inference is that they were very near in time as well as in relationship to one another, in fact that one immediately followed the other. Now Demetrios was beyond doubt the son and successor of Euthydemus, consequently Apollodotos must have been his successor.

As Heliokles was in all probability a son of Eukratides, the rival of Apollodotos, he must have been a younger contemporary of Apollodotos. Consequently, Heliokles' antagonists, Agathokleia and Strato I, whose coins he restruck, were very near in time to Apollodotos. Strato I later on ruled conjointly with his grandson Strato II. There is no room for the long and prosperous reign of Menander in the period which elapsed from Demetrios to Strato II. According

¹ Rapson, *JRAS*, 1905, p. 785. According to some 'overstriking in itself is no evidence of conquest' but simply of commercial relationship (*JAOS*, 1950, p. 210).

² *JRAS*, 1905, pp. 166 ff. *CHI*, p. 553.

to the Buddhist tradition recorded in the *Milinda-pañho*, Milinda or Menander flourished "500 years," i.e., not earlier than the fifth century¹ after the *Parinirvāṇa*, *parinibbānato pañchavassa sate atikkante ete upajjissanti*.² This tradition points to a date not earlier than the period 144-44 B.C. according to Ceylonese reckoning, or 86 B.C.-14 A.D. according to Cantonese tradition, for Menander. Thus both according to numismatic evidence and literary tradition Menander could not have been the Indo-Greek contemporary of Pushyamitra.³ It is Demetrios who should, therefore, be identified with the Yavana invader referred to by Patañjali and Kālidāsa, one of whose armies was defeated by Prince Vasumitra.⁴

The Aśvamedha Sacrifices

After the victorious wars with Vidarbha (Berar) and the Yavanas Pushyamitra completed the performance of two horse-sacrifices. These sacrifices are regarded by some scholars as marking an early stage in the Brāhmaṇical reaction which was fully developed five centuries later in the time of Samudra Gupta and his successors. Buddhist writers are

¹ Cf. the interpretation of somewhat similar chronological data by Franke and Fleet (JRAS, 1914, pp. 400-1); and Smith EHI, 3rd Edition, p. 328.

² Treckner, the *Milinda-pañho*, p. 3. Tarn is not quite right in saying (134 n) that Apollodoros makes Menander contemporary with Demetrios, Trogu with Apollodotos, and some coin indications (CHI, p. 551) with Eukratides. Strabo following Apollodoros and possibly other authorities simply says that extensive Bactrian conquests in the Indian interior were achieved partly by Menander and partly by Demetrios. It is nowhere clearly stated that the two conquerors were contemporaries. The book of Trogu on which another conclusion is based, is lost. Coin indications are not clear enough. E.g., the imitation of certain coins of Demetrios by Maues does not prove chronological proximity.

³ Cf. 445n *infra*.

⁴ S. Konow (Acta Orientalia, I. 35) points out that there is no evidence that Menander transgressed the river Yamunā, and that Demetrios was the ruler who besieged Śāketa and Madhyamikā. In IHQ, 1929, p. 403, Mr. R. P. Chanda

alleged to represent Pushyamitra as a cruel persecutor of the religion of Śākyamuni. But the probative value of the *Dīpāvadāna*, on which some modern writers place their chief reliance in regard to the matter, is seriously impaired by the representation of the "persecuting" monarch as a Maurya, a descendant of Aśoka himself.¹ Moreover, the prime motive which is said to have inclined the king to a vicious policy is, according to this Buddhist work, *personal glory and not religious fanaticism*. Pushyamitra did not dispense with the services of pro-Buddhist ministers, and the court of his son was graced by Paṇḍita-Kauśikī.² The *Mahāvamsa*³ admits the presence, in Bihar, Oudh, Mālwa and adjacent provinces, of numerous monasteries with thousands of monks in the age of Duṭṭhagāmaṇi of Ceylon (C. 101-77 B.C.) which is partly synchronous with the Baimbika-Śuṅga period. The Buddhist monuments at Bhārhut erected "during the sovereignty of the Śuṅgas" do not also bear out the theory that the Śuṅgas, among whom Pushyamitra is included by the *Purāṇas*, were the leaders of a militant Brāhmanism. Though staunch adherents of orthodox Hinduism, kings of the line of Pushyamitra do not appear to have been as intolerant as some writers represent them to be.

The Mantri-parishad in the days of Pushyamitra.

Patañjali refers to the *Sabhā* of Pushyamitra. But it is uncertain as to whether the term refers to a Royal *Durbar*, a tribunal of justice, or a Council of Magnates. The existence of Councils or Assemblies of Ministers (*Mantri-Parishad*) is, however, vouched for by Kālidāsa. If the poet is to be believed the Council continued to be

regards Strabo's attribution of the Indian conquests to Demetrios as doubtful. But the cities in the Pañjāb and the Lower Indus Valley, named after Demetrios and possibly his father leave no room for doubt that Strabo is right.

¹ *IHQ*, Vol. V, p. 397; *Dīpāvadāna*, 433-34.

² *Mālavikāgnimitram*, Act I.

³ Geiger, trans., p. 193.

an important element of the governmental machinery. He gives us the valuable information that even viceregal princes were assisted by *Parishads*.¹ The *Mālarikāgnimitram* refers in clear terms to the dealings of Prince Agnimitra, the Viceroy of Vidiśā (in Eastern Mālwa), with his *Parishad*:

“*Deva evam Amātya-parishado vijñāpayāmi*”²

“*Mantri-prishado’ pyetad-eva darśanam
dvidhā vibhaktām śriyam-udrahantau
dhuram rathāśtāviva saṁgrahituh
tau sthāsyatas-te nripater nideśe
paraspar-āvagraha-nirvikārau*”³

*Rājā : tena hi Mantri-parishadīm brūhi senānye Vira-
senāya likhyatām evam kriyatām iti.*”⁴

It seems that the *Amātya-parishad* or *Mantri-parishad* was duly consulted whenever an important matter of foreign policy had to be decided upon.

¹ Bühler (*Ep. Ind.* III. 137) points out that Aśoka's *Kumāras* were also each assisted by a body of *Mahāmātras*. These may have corresponded to the *Kumārāmātyas* of the Gupta period.

² “King: I will announce this decision to the Council of Ministers.”

³ “This is also the view of the (Council of Ministers). Those two kings, upbearing the fortune of their superior lord divided between them, as the horses upbear the yoke of the charioteer, will remain firm in their allegiance to thee, not being distracted by mutual attacks.” Act V, verse 14.

⁴ “King: Tell the Council then to send to the General Virasena written instructions to this effect.” (Tawney, *Mālarikāgnimitra*, pp. 55-56.)

SECTION II. AGNIMITRA AND HIS SUCCESSORS.

Pushyamitra died in or about 151 B.C., probably after a reign of 36 years,¹ and was succeeded by his son **Agnimitra**.² The name of a prince named Agnimitra has been found on several copper coins discovered in Rohilkhand. Cunningham³ was of opinion that this prince was probably not to be identified with the son of Pushyamitra, but belonged to a local dynasty of North Pañchāla (Rohilkhand). He gave two reasons for this conclusion :

1. Agnimitra's is the only coin-name found in the Purāṇic lists. The names of the other "Mitra" kings occurring on coins of the so-called "Pañchāla series," do not agree with those found in the *Purāṇas*.

2. The coins are very rarely found beyond the limits of North Pañchāla.

As to the first point Rivett-Carnac⁴ and Jayaswal⁵ have shown that several coin-names besides that of Agnimitra can be identified with those found in the

¹ Only thirty years according to a Jaina tradition—" *ajjhasayam Muriyāyasm tisa cchēia Pusamittassa* " (IA. 1914. 118 f. Merutuṅga).

² The commentary on the *Amarakośa* seems to suggest that Agnimitra is the original of king Śūdraka of tradition (Oka, p. 122; *Ann. Ethnol. Or. Res. Inst.*, 1931, 369). On the other hand Keith refers to a tradition recorded in the *Vira charita* and by the younger Rājasekhara which represents Śūdraka as a minister of a Śātavāhana king. We are further told by another writer that Śūdraka defeated prince Svātī and ruled for a long time. A tale alluded to in the *Harsha-charita* represents him as an enemy of Chandraketu, lord of Chakora, apparently in South India (Keith, *The Sanskrit Drama*, p. 129; *Sanskrit Literature*, p. 292; Ghosh, *History of Central and Western India*, pp. 141 f.). The story of Śūdraka is essentially legendary and it is difficult to extract any historical truth out of it. The abeyance of Śātavāhana power in the Upper Deccan for a long period is a fact. But it is due to the irruption of foreign tribes from the north. Disloyal ministers may have helped to bring in the invader.

³ *Coins of Ancient India*, p. 79. Cf. Allan, *CICAI*, p. cxx.

⁴ *JASB*, 1880, 21 ff.; 87 ff.; *Ind. Ant.*, 1880, 311.

⁵ *JBORS*, 1917, p. 479. Cf. 1934, pp. 7 ff.

Purāṇic lists of Śuṅga and Kāṇva kings; for example, Bhadra-ghosha may be identified with Ghosha, the seventh king of the Purāṇic list of Śuṅga kings. Bhūmimitra may be identified with the Kāṇva king of that name. Jethamitra, who is identified with the successor of Agnimitra, viz., Vasu-Jyeshṭha or Su-Jyeshṭha, who is called simply **Jyeshṭha** in the *k Vishṇu* manuscript,¹ no doubt left coins that belong to a different series. But even he is closely connected with an Agnimitra. Several names indeed cannot be identified, but they may have been names of those Śuṅgas who survived the usurpation of Vasudeva Kāṇva and the remnant of whose power was destroyed by the so-called Andhras and Śiśunandī.²

As to the second point we should remember that "Mitra" coins, even those which undoubtedly belong to the so-called Pañchāla series, have been found in Oudh, the Basti district, and even Pāṭaliputra, as well as in Pañchāla. Names of two "Mitra" kings, Brahmamitra and Indramitra, of whom the latter undoubtedly belonged to the Pañchāla group, are found engraved on two rail pillars at Bodh Gayā as well as on coins discovered at Mathurā, Pañchāla and Kumrahar.³ In the face of these facts it is difficult to say that the "Mitras" in question were a local dynasty of North Pañchāla. The matter, however, must be regarded as *subjudice*.

¹ *Dynasties of the Kali Age*, p. 31, n. 12. Pace Allan, *CICAI.*, p. xcvi.

² *Dynasties of the Kali Age*, p. 49.

³ Cunningham, *Coins of Ancient India*, pp. 64, 68; Allan, *CICAI.*, pp. cxix, cxx; Marshall, *Archaeological Survey Report for 1907-8*, p. 40; Bloch *ASB*, 1908-9, p. 147; *IHQ*, 1960, pp. 1ff. The name *Im.....tra* occurs in a mutilated inscription on a rail pillar at Bodh Gayā with the title *Rāṇo* added before it. Marshall, Bloch and Rapson agree in identifying king *Im.....tra* with Indramitra of coins. Bloch further identifies him with Kauśikīputra Indrāgnimitra, husband of Āryā Kuraṅgi, whose name occurs on certain pieces of coping. The epithet Kauśikīputra reminds one of Paṇḍita-Kauśikī of the *Mālavikāgnimitram* (Act 1). The Kauśika family was apparently intimately associated with the rulers of the age. Kauśikī mentioned in the *Mālavikāgnimitram* was sister to the minister of a prince of Bezar. The sister of the prince herself was one of the queens of

Agnimitra's successor, as we have already seen, was Jyeshṭha (of the *k Vishṇu* manuscript), who is very probably identical with Jeṭhamitra of the coins.¹

The next king **Vasumitra** was a son of Agnimitra. During the life-time of his grandfather he had led the imperial army against the Yavanas and defeated them on the Sindhu (possibly in Central India) which probably formed the boundary between the empire of Pushyamitra and the Indo-Greek territories in Malwa.

Vasumitra's successor is called Bhadraka in the *Bhāgavata Purāṇa*, Ādraka and Odraka in the *Vishṇu*, Āndhraka in the *Vāyu*, and Antaka in the *Matsya Purāṇa*. Jayaswal identified him with Udāka, a name occurring in a Pabhosā inscription. The epigraph has been translated thus: "By Āsāḍhasena, the son of Gopālī Vaihidarī and maternal uncle of king Bahasatimitra, son of Gopālī, a cave was caused to be made in the tenth year of Udāka for the use of the Kassapiya Arhats." We learn from another Pabhosā inscription that Āsāḍhasena belonged to the royal family of Adhichhatrā (Abichhatrā), the capital of North Pañchāla. Jayaswal maintained that Odraka (identified with Udāka) was the paramount Śuṅga sovereign, while the family of Āsāḍhasena was either gubernatorial or feudatory to the Magadha throne. Marshall,² on the other hand, identified the fifth "Śuṅga" with king Kāśiputra.³ **Bhāgabhadra** mentioned in a Garuḍa Pillar Inscription found in the old city of Vidiśā, now Besnagar. Jayaswal identified Bhāgabhadra with Bhāga Śuṅga, i.e., Bhāgavata

Agnimitra. King Brahmanitra is the husband of Nāgadevī, another prominent donor mentioned in the epigraphs.

¹ *Coins of Ancient India*, p. 74. Allan. *CIOAI*, xvi. Note the connection of Jeṭhamitra with Agnimitra. The name of a Jyeshṭhamitra is said to occur also in a Brāhmi inscription on certain stone fragments recently discovered at Korum (*Amrita Bazar Patrika*, July 11, 1936, p. 5).

² *A Guide to Sāncī*, p. 11 n.

³ Sitcar suggests Kautalputra.

of the *Purāṇas*. This theory has to be given up in view of the discovery of another Besnagar Garuḍa Pillar Inscription (of the twelfth year after the installation of Mahārāja **Bhāgavata**) which proves that there was at Vidiśā a king named Bhāgavata apart from king Kāsīputra Bhāgabhadra. In the absence of clear evidence connecting "Udāka" with Vidiśā it cannot be confidently asserted that he belonged to the house of Agnimitra and Bhāgavata. The view of Marshall seems to be more probable.¹

It appears that the successors of Agnimitra at Vidiśā cultivated friendly relations with the Greek sovereigns of the Western Pañjāb. The policy of the Bactrian Greeks in this respect resembled that of their Seleukidan predecessors. Seleukos, we know, first tried to conquer the Magadha Empire, but, frustrated in his attempts, thought it prudent to make friends with the Mauryas. The Bactrians, too, after the reverses they sustained at the hands of Pushyamitra's general, and weakened moreover by internal dissensions, apparently gave up, for a time at least, their hostile attitude towards the imperial power in the Ganges valley. We learn from the Besnagar Inscription of the reign of Bhāgabhadra that Heliodora (Heliodoros), the son of Diya (Dion), a native of Taxila, came as an ambassador from Mahārāja Amtalikita (**Antialkidas**) to Rajan Kāsīputra Bhāgabhadra the Saviour (*Trātara*) who was prospering in the fourteenth year of his reign. The ambassador, though a Greek, professed the *Bhāgavata* religion and set up a *Garuḍadhva* in honour of Vāsudeva (Kṛishṇa), the god of gods.

¹ Dr. Barna points out (IHQ, 1930, 23) that "in the absence of the word *raja* preceding *Udākara*, it is difficult to say at once whether *Udāka* is the personal name of a king or the local name of the place where the cave was excavated."

He was apparently well-versed in the *Mahābhārata*¹ which he might have heard recited in his native city of Taxila.

Nothing in particular is known regarding the three immediate successors of Bhadraka. The ninth king Bhāgavata had a long reign which extended over 32 years. Dr. Bhandarkar identifies him with the *Mahārāja* Bhāgavata mentioned in one of the Besnagar Inscriptions referred to above. Bhāgavata's successor **Devabhūti** or Devabhūmi was a young and dissolute prince. The *Purāṇas* state that he was overthrown after a reign of 10 years by his *Amātya* or minister Vasudeva. Bāṇa in his *Harshacharita* says that the over-libidinous Śuṅga was bereft of his life by his *Amātya* Vasudeva with the help of a daughter of Devabhūti's slave woman (*Dāsi*), disguised as his queen. Bāṇa's statement does not necessarily imply that Devabhūti was identical with the murdered Śuṅga. His statement may be construed to mean that Vasudeva entered into a conspiracy with the emissaries of Devabhūti to bring about the downfall of the reigning Śuṅga. (Bhāgavata), and to raise Devabhūti to the throne. But in view of the unanimous testimony of the *Purāṇas* this interpretation of the statement of Bāṇa cannot be upheld.

The Śuṅga power was not altogether extinguished after the tragic end of Devabhūti. It probably survived in Central India² till the rise of the so-called Andhras, Andhrabhṛityas or Sātavāhanas who "swept away the remains of the Śuṅga power" and probably appointed

¹ The three immortal precepts, lit. steps to immortality, *dama*, *chāra* and *apramāda*, self-control, self-denial and watchfulness, mentioned in the second part of Heliodora's inscription, occur in the *Mahābhārata* (V, 43. 22; XI. 7. 23: *Damas-tyāgo' pramādaścha te trayo Brahmanō hayāḥ*. Cf. also *GHŚ*, XVI. 1.2). See *JASB*, 1922, No. 10, pp. 269-271; *ASi*, 1908-1909, p. 123; *JRAS*, 1909, 1935, 1937, 1938; 1910, 815; 1914, 1031f; *IHQ*, 1939, 610; *Annals of the Bhandarkar Institute*, 1918-19, p. 59.

² Cf. *Dynasties of the Kali Age*, p. 49.

Śiśunandi¹ to govern the Vidiśā region. Śiśunandi's younger brother had a grandson (*dauhitra*) named Śiśuka who became the ruler of Purikā.²

¹ *Ibid.*, 49.

² For the location of purikā see JRAS, 1910, 416; cf *Ep. Ind.*, xxvi, 151.

SECTION III. IMPORTANCE OF THE BAIMBIKA-SUṂGA PERIOD OF INDIAN HISTORY.

The rule of the emperors of the "house" of Pusbyamitra marks an important epoch in the history of India in general and of Central India in particular. The renewed incursions of the Yavanas, which once threatened to submerge the whole of the *Madhyadeśa*, received a check, and the Greek dynasts of the borderland reverted to the prudent policy of their Seleukidan precursors. There was an outburst of activity in the domains of religion, literature and art, comparable to that of the glorious epoch of the Guptas. In the history of these activities the names of three Central Indian localities stand pre-eminent: Vidiśā (Besnagar), Gonarda and Bhārbut. As Foucher points out "it was the ivory-workers of Vidiśā who carved, in the immediate vicinity of their town, one of the monumental gates of Sāñchī." Inscriptions at or near Vidiśā (and Ghosunḍī) testify to the growing importance and wide prevalence of the *Bhāgavata* religion. Though no Aśoka arose to champion this faith, the missionary propaganda of its votaries must have been effective even in the realms of Yavana princes, and a Yavana *dūta* or ambassador was one of its most notable converts. Gonarda¹ was the traditional birth-place of the celebrated Patañjali, the greatest literary genius of the period, Bhārbut saw the construction of the famous railing which has made the sovereignty of the Suṅgas (*Suganṁ raja*) immortal.

¹ See IHQ. 1926, 267. According to the *Sutta Nipāta* Gonarda stood midway between Ujjain and Besnagar (Vidiśā)—*Carm. Lea.* 1913, 4; *Journal of the Andhra Historical Research Society*, Jan., 1935, pp. 1 ff. (Sircar's trans. of S. Lévi's note on Gonarda).

CHAPTER VII. THE FALL OF THE MAGADHAN AND INDO-GREEK POWERS.

SECTION I. THE KĀṆVAS, THE LATER ŚUṆGAS AND THE LATER MITRAS.

Yasudeva at whose instance the "over-libidinous Śuṅga" was "reft of his life" founded about 75 B.C. a new line of kings known as the Kāṇva or Kāṇvāyana dynasty. The *Purāṇas* give the following account of this family. "He (Yasudeva), the Kāṇvāyana, will be king 9 years. His son Bhūmimitra will reign 14 years. His son Nārāyaṇa will reign 12 years. His son Suśarman will reign 10 years. These are remembered as the *Suṅga-bhṛitya* Kāṇvāyana kings. These four Kāṇva Brāhmaṇas will enjoy the earth.¹ They will be righteous. In succession to them the "earth" will pass to the Andhras." **Bhūmimitra** may have been identical with the king of that name known from coins.²

¹ Possibly only Eastern Mālwa where stood the later "Śuṅga" capital Vidiśā or Besnagar, and some adjoining tracts.

² Mr. J. C. Ghosh is inclined to include among the Kāṇva kings a ruler named Sarvatāta who is known (from the Ghosundi Inscription, *Ind. Ant.* 1932, Nov., 203 ff; *Ep. Ind.*, xxii, 198ff.) to have been a devotee of Saṃkarshaṇa and Vāsudeva and a performer of the horse-sacrifice. But the identification of the Gājāyana family, to which the king belonged, with the Gālāyanas or Gādāyanas (*cf.* IHQ. 1933, 797ff) does not seem to be plausible. There seems to be no more reason to identify the Gājāyanas with the Gādāyanas than with the Gāhāyanas or Gāṅgāyanas of the Śunaka or Kaśyapa group (Caland, *Baudh. Śrauta sūtra* III, 423-454). It is important to remember the fact that the *Harivaṃśa* refers to a *Kaśyapa devīja* as the reviver of the *Aśvamedha* in the Kali Age. The Gāṅgāyanas no doubt also recall the Gaṅgas of Mysore who claimed to belong to the Kāṇvāyana gotra (*A New History of the Indian People*, Vol. VI. p 218). But the equation Gājāyana = Gāṅgāyana is not proved.

The chronology of the Kāṇva dynasty is a matter of controversy. In his *Early History of the Deccan*, Sir R. G. Bhandarkar observes, "the founder of the Andhra-bhṛityas is said to have uprooted not only the Kāṇvas, but 'whatever was left of the power of the Śuṅgas.' And the Kāṇvas are pointedly spoken of as Śuṅga-bhṛityas or servants of the Śuṅgas. It, therefore, appears likely that when the princes of the Śuṅga family became weak, the Kāṇvas usurped the whole power and ruled like the Peshwas in modern times, not uprooting the dynasty of their masters but reducing them to the character of nominal sovereigns. Thus then these dynasties reigned contemporaneously, and hence the 112 years that tradition assigns to the Śuṅgas include the 45 assigned to the Kāṇvas.

Now, the Purāṇic evidence only proves that certain princes belonging to the Śuṅga stock continued to rule till the so-called "Andhra-bhṛitya" conquest and were the contemporaries of the Kāṇvas. But there is nothing to show that these *rois faineants* of the "Śuṅga" stock were identical with any of the ten "Śuṅga" kings mentioned by name in the Purāṇic lists, who reigned 112 years. On the contrary, the distinct testimony of the *Purāṇas* that Devabhūti, the tenth and last "Śuṅga" of the Purāṇic lists, was the person slain by Vasudeva, the first Kāṇva, probably shows that the *rois faineants*, who ruled contemporaneously with Vasudeva and his successors, were later than Devabhūti, and were not considered to be important enough to be mentioned by name. Consequently the 112 years that tradition assigns to the ten "Śuṅga" kings from Pushyamitra to Devabhūti do not include the 45 assigned to the Kāṇvas. It is, therefore, not unreasonable to accept with slight modifications the views of Dr. Smith regarding the date of the family. According to the system of chronology adopted

in these pages, the period of Kāṇva rule extended from *cir.* B.C. 75 to *cir.* B.C. 30.

Very little is known about the history of Magadha proper after the Kāṇvas. To reconstruct the history of the province from the fall of the Kāṇvas to the rise of the Gupta dynasty is a difficult task. The so-called Andhras or Śātavāhanas who are represented as destroying the Kāṇva sovereignty, apparently in Eastern Mālwa, do not appear to have ruled in Magadha proper.¹ The greatest among them are called 'Sovereigns of the Deccan' (*Dakṣiṇāpathapati*) and an accurate idea of the field of their political and military activities may be obtained from the epithets '*trisamuda-toyapīlavāhana*,' 'whose chargers had drunk the water of the *three* oceans,' and '*trisamudrādhipati*,' 'overlord of the *three* seas' occurring in epigraphic and literary records. The sway of rulers like the Guptas, on the other hand, is said to have extended as far as the *four* seas.

The discovery of a clay seal with the legend *Mokhalinam*² suggests that at one time the Gayā region was under the sway of Maukharī chiefs. But the precise date of the record is not known. Equally uncertain is the date of *Mahārāja* Trikamala who ruled in the same

¹ There is no valid reason for connecting the Nūrruvar Kannar (*Silappadikāram*, xxvi, Dikshitar's trans. 299 f.) either with the Śātakarṇis or with Magadha. The expression "Kannar" sometimes stands alone proving that Nūrruvar is only a qualifying adjective, not a part of the name. The Ganges, even if it be the Bhāgirathī, and not Gautamī Gaṅgā or the Godāvarī, with which the family is associated, flows through other territories besides Magadha, showing that there is no necessary connection between that province and the kings in question.

² Fleet, CII, 14. The legend is written in Mauryan Brāhmī. The Maukharis in question may have exercised sway over some little principality under the suzerainty of the Mauryas or the Śuṅgas. Three inscriptions have recently been discovered at Baḍvā in the Kotah State in Rājputāna recording the erection of sacrificial pillars by Maukharī *Mahāsenāpatīs* (generals or military governors) in the third century A. D. (*Ep. Ind.* XXIII, 52).

region in the year 64 of an unspecified era. Epigraphic evidence of a late date points to some connection between the Licchhavis and Pushpapura (Pāṭaliputra). But it is difficult to say how far the tradition is genuine. The only rulers of note in the centuries immediately preceding the Christian era, whom we know from epigraphic evidence to have ruled in Magadha and the neighbouring provinces, are the so-called 'Mitras'. The prevalence of 'Mitra' rule is also hinted at by references in Jaina literature to Balamitra and Bhānumitra among the successors of Pushyamitra. From a study of available epigraphs Dr. Barua has compiled a list of 'Mitra kings'. It includes the names of Brihat-svātimitra, Indrāgnimitra, Brahmamitra, Brihaspatimitra (Dhar)mamitra and Viṣṇumitra. To these should perhaps be added the names of Varunamitra and Gomitra.¹ Of these only Indrāgnimitra, Brahmamitra and possibly Brihaspatimitra are definitely associated with Magadha in addition to other territories. The rest are connected with Kauśāmbī and Mathurā.

It is not known in what relationship most of these "Mitra" kings stood to one another or to the celebrated families of the Śuṅgas and the Kāṇvas.

In Pāṭaliputra as well as in Mathurā the "Mitras" seem to have been replaced eventually by the Scythian 'Murundās' and Satraps who, in their turn, were supplanted by the Nāgas and the Guptas. Some scholars place

¹ Allan refers to kings Brahmamitra, Dridhamitra, Suryamitra and Viṣṇumitra who issued coins identical in type with those of Gomitra. They were followed by rulers whose names ended in -datta, -bhātī and -ghoṣha. O. P. 90-51.

immediately before the Guptas a family called Kota which may have ruled in Pāṭaliputra.¹

¹ For statements in this section see Ep. Ind. VIII, 60ff; *Harshacharita* VIII, (p. 251); Cunn., *Mahābodhi*; ASI., 1908-9, 141; IHQ 1926, 441; 1929, 398, 595f; 1930, 1ff. 1933, 419; Kielborn, N. I. Inscriptions, No. 541; *Indian Culture*, I, 695; EHI. 3rd ed. 227n; JRAS., 1912, 122; Smith *Catalogue of Coins in the Indian Museum*, 185, 190, 194; Allan, CICA. p p. xcvi-xcviii, cx, 150ff, 169ff, 173ff, 195ff, 202ff.

SECTION II. THE ŚĀTAVĀHANAS AND THE CHETAS.

While the Śuṅgas and Kāṇvas were engaged in their petty feuds, new powers were rising in trans-Vindhyan India. These were the Śātavāhana¹ (the so-called Andhra or Andhra-bhṛitya²) kingdom of Dakṣiṇāpatha and the Cheta or Cheti kingdom of Kalinga.

The founder of the Śātavāhana dynasty was **Simuka** whose name is misspelt as Śiśuka, Sindhuka and Śipraka in the *Purāṇas*. Those works state that the "Andhra" Simuka will assail the Kāṇvāyanas and Suśarman, and destroy the remains of the Śuṅgas' power and will obtain this "earth". If this statement be true then it cannot be denied that Simuka was for some years a contemporary of Suśarman (40-30 B.C.) and flourished in the first century B.C. Rapson, Smith and many other scholars, however, reject the *unanimous* testimony of the *Purāṇas*. They attach more importance to a statement about which there is not the same unanimity, that the "Andhras" ruled for four centuries and a half. Accordingly, they place Simuka towards the close of the third century B.C., and say that the dynasty came to an end in the third century A.D.

A discussion of Simuka's date involves the consideration of the following questions :—

¹ The form Śātavāhana is found in the Bhāgalpur Grant of Nārāyaṇapāla and the form Śālivāhana in literature. See also Sir R. G. Bhandarkar, *EHD*, Section VII.

² The designation 'Andhra-jātiya' or 'Andhra' is found in the *Purāṇas* which represent the founder as a *bhṛitya* or servant of the last Kāṇva king. Sir R. G. Bhandarkar, following apparently the *Vishṇu Purāṇa*, styles the dynasty founded by Simuka *Andhra-bhṛitya*, i.e., Andhras who were once

1. What is the age of the script of the Nānāghāt record of Nāyanikā, daughter-in-law of Simuka (or of his brother and successor, Kṛishṇa) ?

2. What is the actual date of Khāravela's Hāthīgumphā Inscription which refers to a Śātakarṇi, who was apparently a successor of Simuka ?

3. What is the exact number of the so-called Andhra kings and what is the duration of their rule ?

As to the first point we should note that according to Mr. R. P. Chanda the inscription of Nāyanikā is later than the Besnagar Inscription of Bhāgavata, possibly the penultimate king of the "line" of Pushyamitra mentioned in the *Purāṇas*.¹ Consequently Simuka

servants. But that designation should properly be applied to the seven Ābbiras who are mentioned as the successors of the line of Simuka on page 45 of Pargiter's *Dynasties of the Kāli Age* (cf. *Vishṇu*, P. IV, 21, 13).

¹ MASI., No. 1, pp. 14-15. In *IBQ*, 1929 (p. 601) Mr. Chanda points to the agreement of the Nānāghāt script with the Besnagar Inscription of the time of Antialkidas. But the exact date of Antialkidas is uncertain. He may have belonged to the latter half of the second century B. C. or the first half of the next century.

Mr. R. D. Banerji, while disagreeing with the views of Mr. Chanda in regard to certain points, admits, after a detailed examination of certain epigraphs, that "the Nānāghāt inscriptions show the use of a very large number of Ksatrapa or early Kuṣāṇa forms side by side with older ones" (*Mem. Asiat. Soc. Bengal*, Vol. XI, No. 3, p. 145). According to Rapson (*Andhra Coins*, lxxvii) the form of the *akshara-da* found in the Nānāghāt record resembles that of a coin-legend which is assignable to the first or second century B. C.

It is not suggested that either Banerji or Rapson placed the Nānāghāt record in the first century B. C. But some of the facts they have placed before us do not preclude the possibility of a date in the first century B. C. The theory that the record belongs to the second century B. C. rests in some measure on the assumption tacitly accepted by the older generation of scholars that Khāravela's thirteenth year corresponds to the year 165 of the time of the Maurya kings (Bühler, *Indian Palaeography*, 39; Rapson xvii).

may be placed in the Kāṇva period, *i.e.*, in the first century B.C.—a date which accords with Purāṇic evidence.¹

As to the second point Mr. R. D. Banerji gives good grounds for believing that the expression *Ti-vasa-sata* occurring in the passage "*Pañchame che dāni vase Namdarāja ti-vasa-sata.....*" of the Hāthīgumphā Inscription means not 103 but 300.² This was also the view of Mr. Chanda and, at one time, of Dr. Jayaswal.³

¹ Bühler also observes (ASW1., Vol. V, 65) that the characters of the Nānāghaṭ inscriptions belong to a period anterior by about 100 years to that of the edicts of Gautamiputra Śātakarṇi and his son Pulumāyi. Scholars who place the Nānāghaṭ record in the first half of the second century B.C., and the epigraphs of the time of Gautamiputra Śātakarṇi in the second century A.D., will have to account for the paucity of Śātavāhana records during a period of about three hundred years (if that be the actual length of the interval between the age of the husband of Nāganikā and the reign of the son of Balaśrī). Mr. N. G. Majumdar (*The Monuments of Sāncī* Vol. I, pt iv, p. 277) places the Nānāghaṭ record during the period 100-75 B.C.

² JBORS, 1917, 495-497.

³ JBORS, 1917, 432; *cf.* 1918, 377, 385. The older view was changed in 1927, 238, 244. According to the usually accepted interpretation of a passage in the Hāthīgumphā record Khāravela, in his fifth year, extended an aqueduct that had not been used for "*ti-vasa-sata*" since Nandarāja. If "*ti-vasa-sata*" is taken to mean 103 years, Khāravela's accession must be placed 103-5=98 years after Nandarāja. His elevation to the position of *Yuvarāja* took place 9 years before the date, *i.e.*, 98-9=89 years after Nandarāja (*i.e.*, not later than 324 B.C.-89=235 B.C.). Khāravela's father was apparently on the throne at that time, and he seems to have been preceded by his father. But we learn from Aśoka's inscriptions that Kāliṅga was actually governed at that time by a Maurya *Kumāra* under the suzerainty of Aśoka himself. Therefore "*ti-vasa-sata*" should be taken to mean 300, and not 103 years. The figure 'three hundred' (a round number) is in substantial agreement with the Purāṇic tradition about the interval between the Nandas and Śātakarṇi I, 137 (period of the Mauryas)+112 (of the Śuṅgas)+45 (of the Kāṇvas)+23 (of Simuka)+10 (of Kṛishṇa)=327.

If *Ti-vasa-sata* means 300, Khāravēla and his contemporary Śātakarṇi may have flourished 300 years after Nandarāja, i.e., in or about 24 B.C. This agrees with the Purāṇic evidence according to which Śātakarṇi's father (or uncle) Simuka assailed the last Kāṇva king Suśarman (c. 40-30 B.C.).¹

We now come to the third point, viz., the determination of the exact number of Śātavāhana kings, and the duration of their rule.

Regarding each of these matters we have got in the *Purāṇas* quite a number of different traditions. As to the first the *Matsya Purāṇa* says—

“*Ekona-vimśatir² hyete Andhrā bhokshyanti vai mahīm,*”
but it gives thirty names.³

The *Vāyu Purāṇa*, with the exception of the ‘M’ manuscript, says—

Ityete vai nṛipās trimśad Andhrā bhokshyanti ye mahīm” (these thirty Andhras will enjoy the earth); but most of the *Vāyu* manuscripts name only seventeen, eighteen, or nineteen kings.

As to the duration of the Andhra rule several *Matsya* manuscripts assign to them a period of 460 years.

“*Teshām varsha śatāni syuḥ chatvāri shastir eva-cha.*”

Another *Matsya* manuscript puts it slightly differently :—

“*Dvādaśādhikam eteshām rājyam śata-chatusṭayam*”
i.e., the period of their sovereignty is 412 years;

¹ Simuka may have ascended the throne (in the Deccan) several years before the date 40-30 B.C. when he assailed the Kāṇvāyanas possibly in Central India. The period of his rule after the defeat of the Kāṇvas may have been less than 23 years. Thus the actual interval between the Nandas and Śātakarṇi may well have been a little less than 327 years.

² Variant *ekona-navatim* (DKA, 43).

³ Pargiter points out (p. 36) that 3 *Matsya* Mss. name 30, and the others vary the number from 28 to 21.

while the reigns of kings mentioned in certain *Vāyu* Mss. amount, according to Sir R. G. Bhandarkar, to only 272 years and a half.

Obviously according to one tradition there were about seventeen, eighteen or nineteen kings, whose rule lasted some three centuries, while according to another tradition there were thirty kings, the length of whose reigns covered a period of more than 400 years. In the opinion of Sir R. G. Bhandarkar the longer list includes the names of princes belonging to all the branches of the so-called *Andhra-bhṛitya* dynasty, and that the longer period represents the total duration of all the princes belonging to the several branches. The period of about three centuries, and the seventeen, eighteen or nineteen names given in the *Vāyu Purāṇa*, and hinted at in the *Matsya*, refer to the main branch. That there were several families of Śātavāhanas or Śātakārṇis, distinct from the main line that had its *principal* seat in the upper Valley of the Godāvarī, cannot be denied. The *Kāvya Mīmāṃsā* of Rājaśekhara and several other works as well as epigraphs in the Kanarese country and elsewhere testify to the existence of Śātavāhanas and Śātakārṇis who ruled over Kuntala¹ (the Kanarese districts) before the Kadambas. The fullest *Matsya* list includes a group of kings (Nos. 10-14), including one named "Kuntala" Śātakārṇi, who are (generally speaking) passed over in silence by the *Vāyu*.² Skandāsvāti, No. 11 of the full list, reminds one of *Skandānāga-Śātaka*, a prince of a Kanarese line of Śātakārṇis

¹ A Śātavāhana of Kuntala is referred to by the *Kāvya-Mīmāṃsā* (1934, Ch. X, p. 50) as having ordered the exclusive use of *Prākṛit* in his harem. He may have been identical with the famous king Hāla (cf. *Kuntala-janavayaṇa Hālena*, *ibid*, Notes, p. 197.)

² Even Hāla (No. 17) is omitted in the *Vāyu* Ms. (*DKA*, p. 36) and the *Brahmaṇḍa P.* (Rapson, *Andhra Coins*, lxvii).

mentioned in a Kanheri inscription.¹ As to Kuntala Śātakarṇi (No. 13), the commentary on Vātsyāyana's *Kāmasūtra* takes the word "Kuntala" in the name Kuntala Śātakarṇi Śātavāhana to mean "*Kuntala-rishaye jātātāt tat-samākhyah.*"² It is, therefore, fair to conclude that the *Matsya* MSS. which mention 30 Śātavāhana kings include not only the main group of kings but also those who were closely associated with Kuntala.

On the other hand, the *Vāyu*, *Brahmāṇḍa* and certain *Matsya* MSS., generally speaking, show a tendency to omit the Śātavāhanas of Kuntala and the rulers of the period of Śaka revival under Rudra-dāman I, and mention only about 19 kings most of whom belonged to the main line whose rule may have lasted for about three centuries. If the main line of Śātavāhana kings consisted only of about nineteen princes, and if the duration of their rule be approximately three centuries, there is no difficulty in accepting the Purāṇic statement that Simuka flourished in the time of the later Kāṇvas, that is to say, in the first century B.C., and that his dynasty ceased to rule in the Northern Deccan in the third century A.D. The sovereignty of the Śātavāhanas and Śātakarṇis of Kuntala lasted longer and did not come to an end probably before the fourth century A.D., when it was ended by the Kadambas. Thus the total duration of the rule of all the lines of

¹ Rapson, *Andhra Coins*, liii. The fact that he was a prince at the time of the record need not prove that he never came to the throne. The *Purāṇic* lists themselves often include names of princes (e.g., Arjuna, Abhimanyu, Siddhārtha) who never ruled as kings. Certain *Matsya* Mss. insert the group to which Skandasyāti belongs after no. 29, i.e., Chapṛasri (*DKA*, p. 36).

² He was so named because he was born in the Kuntala country. Cf. names like Uruvela-Nadi- and Gayā Kassapa (*Dialogues of the Buddha*, I. 194).

Śātakarṇis is really more than 400 years.¹ The kings of the Kuntala group (Nos. 10-14 of the DKA list) are no doubt usually placed before the great Gautamīputra and his successors. But Pargiter points out that in certain *Matsya* MSS. Nos. 10-15 are placed after the penultimate king of the line (No. 29).² As to Hāla (No. 17) if he is really the author of the *Gāthāsaptāśatī*, he could hardly have flourished before the fourth century A.D. The references to *Vikramāditya-charita*, *Āṅāraka-vāra* and *Rādhikā* make it difficult to assign to him a date before the Great Gautamīputra. We have many other instances of the inversion of the order of kings in the *Purāṇas*.³ The fact that the extant Purāṇic texts do misplace kings appears abundantly clear from the important discovery of a coin of Śiva Śrī Āpilaka whom Mr. Dikshit connects with the *later* Śātavāhanas though the *Purāṇas* place him *early* in the list.⁴

Regarding the **original home** of the Śātavāhana family there is also a good deal of controversy. Some scholars

¹ The period '300 years' (*Vāyu P.*) may refer to the rule of the *Srīparvatiya* Andhras (DKA, 46). Even then it is important to remember that the cessation of "Andhra" rule in the upper Deccan in the third century A.D. is not incompatible with a date for the founder in the first century B.C. For the rule of the Śātakarṇis survived in Kuntala till the rise of the Kadambas. Thus the *Purāṇas* are right in assigning to the entire line of 30 kings a period of about four centuries and a half.

² DKA, p. 26. On pp. 20, 35, Pargiter gives other instances of 'misplacement' of kings by the Purāṇic MSS.

³ See pp. 104, 115f *ante*.

⁴ See *Advance*, March 10, 1935, p. 9. The coin belongs to the Mahākosala society of Raipur (C.P.). It bears the figure of an elephant with Brāhmī legend on the obverse. The reverse is blank. On numismatic grounds the place of this ruler is according to Mr. K. N. Dikshit, more with the later kings of the dynasty than with the earlier ones as indicated in the *Purāṇas*. For the late date of Hāla of the Kuntala country see *R.G. Bhand. Com. Vol.*, 189. Cf. Reference to Rādhā in the *Saptaśatakam* (*Ind. Ant.*, III 25n.).

Mr. K. P. Chattopādhyāya deduces from the discrepant lists of the *Matsya*, and *Vāyu Purāṇas* and from epigraphic and numismatic evidence, certain

think that the Śātavāhanas were not Andhras (Telugus)

theories about (1) the existence of two contemporary Śātavāhana kingdoms ruled by son and father respectively, (2) cross-cousin marriages and (3) matrilineal succession, which he discusses in JASB, 1927, 503ff and 1939, 317-339. In his opinion the discrepancies in the Purāṇic lists cannot be due to any oversight or slip on the part of the editors (1927, p. 504). They are to be explained by the theory of an original version (that contained in the *Matsya*) which gives the full list of Gautamīputras as well as Vāsishṭhīputras, and a "revised text" (contained in the *Vāyu* and *Brahmāṇḍa*) which retains the Gautamīputras but from which certain names were deliberately expunged as the rulers in question were not considered by the revising authorities to possess the privilege of having the names preserved in the *purāṇas* (*ibid* p. 505). Kings (e.g., Vāsishṭhīputra Pulumāvi), whose names are "expunged" from the "revised text" of the *Vāyu* and the *Brahmāṇḍa Purāṇas*, belong to a "set" which is genealogically connected with the other, viz., the Gautamīputra group, whose names are retained in the revised versions, but "the succession did not coincide with the mode of descent." For instance, Gautamīputra Śātakarṇi, according to the revised list, was succeeded not by his son Pulumāvi, but by another Gautamīputra, viz., Yajña Śrī (p. 509). It is further added that 'on the coins of the Śātavāhanas the royal prefix and the mother's clan-name are associated together and also disappear together except in the case of the third king of the line.' In the inscriptions also the association is invariable (excluding the doubtful case of Śivamakasada), except in the case of the third king, Śrī Śātakarṇi of the Nānāghāṭ Cave Inscriptions. It is, therefore, to be concluded that, except for the third king of the line, the royal title and relationship to the mother went together. In other words, the succession was matrilineal (p. 516): "The son succeeded to the conquered realm, and the sister's son to the inherited kingdom" (p. 527).

This footnote cannot afford space for an exhaustive review of the dissertation of Mr. Chaṭṭopādhyāya. Nor is it concerned with theories and speculations about social organisation based on 'mother right or father right', cross-cousin marriage in general, and royal successions, that are not germane to the discussion about the Śātavāhana dynasty. We shall try to confine ourselves to the points that are really relevant to an enquiry about that illustrious line itself. A study of the Purāṇic lists analysed by Pargiter (*Dynasties of the Kali Age*, pp. 35ff.) would show that the discrepancies in the Purāṇic lists are not capable of as simple a solution as that proposed by Mr. Chaṭṭopādhyāya. It cannot be said, for example, that Gautamīputra (No. 23) is mentioned in all *Matsya* texts and retained in all *Vāyu* MSS., and that his son Pulumāvi (No. 24) of the so-called "Vāsishṭhīputra group" is always mentioned in the *Matsya* and omitted only in "later revised versions" of the *Vāyu*, etc. Gautamīputra is omitted in *Matsya* MSS., styled e, k and l by Pargiter (p. 36), and also in the e *Vāyu* MSS., while his son Pulumāvi is omitted in *Matsya* e, f and l MSS. but mentioned in the *Vishṇu* and *Bhāgavata* lists, notwithstanding the activities of the so-called revisers. The theory of succession of sisters' sons in the so-called revised list of the *Vāyu*, *Brahmāṇḍa*, etc., is clearly negated by numerous passages where a

but merely Andhra-bhṛityas, servants of the Andhras,

successor is distinctly referred to even in these *Parāṅga*s as the son of a predecessor (cf. the cases not only of the first Śrī Śātakarṇi but also of Śātakarṇi II, Lambodara, and even Yaśña Śrī—(*DKA*, p. 39, fn. 40, 44; p. 42, fn. 12,). The use of the expression *tato* (*DKA*, 30) in the *Matya Parāṅga* to indicate the relationship between Śātakarṇi I and Pūrṇotsaṅga when taken along with the words *tasyāpi Pūrṇotsaṅgaḥ* (*Vishnu* IV. 24. 12) and *Paurnamāsatsu tat sūtaḥ* (*Bhāg.* XII. 1. 21) leaves no room for doubt that *Parāṅga* evidence represents Pūrṇotsaṅga—*Paurnamāsa*, as the son and immediate successor of Śātakarṇi I and not a 'distant' offspring or a remote offshoot of a 'cross-cousin marriage', who got the throne by the rule of matrilineal succession. There may be no valid reason as asserted by Mr. Chaitṭopādhyāya for identifying him with Veditrī of the Nānāghāt record. But the reading Veditrī as pointed out by K. Śāstri is wrong. The proper reading is Khandasiri—Skandasiri. This prince has been plausibly identified with Pūrṇotsaṅga's successor, the fifth king of the *Parāṅga* list. It is, therefore, difficult to agree with the view (*JASB*, 1939, 325) that the prince in question (the so-called Veditrī) 'never came to the throne'. Pūrṇotsaṅga may have been some other 'kumāra'. Cf., the nameless prince (*kumāra*) 'Sātavāhana' of the Nānāghāt record who is mentioned along with 'Hakusiri' (Śaktiśrī). It is also to be noted that even the so-called older version of the *Matya* speaks of only 19 kings in one passage.

The Gautamiputras and the Vāsishṭhiputras did not rule over distinct regions. Gautamiputra Śātakarṇi is represented as the *Rājā* of Mūlaka, i.e., the district round Paithan, along with other territories. Pulumāvi, too, ruled over Paithan as we learn from the Geography of Ptolemy. The epithets 'Vijhā..... Malaya Mahida.....parata pati' and "*visamudatoyopita-rāḥana*" applied to Gautamiputra suggest that he was as much entitled to the designation *Dakṣiṇāpathapati* as his son.

The statement that, except for the third king, the royal title and relationship to the mother went together, is not borne out by recorded facts. In the Myākadonī Inscription, for example (*Ep. Ind.* XIV, pp. 153 ff.) We have the passage—*Rāṇo Sātavahanaṇah* : (i) *ri-Pulumā* (ā) *riya* without any mention of the metronymic Cf. also the passage *Rāṇo ŚrīChāga-sūtisa* (*Rapeon, Andhra Coins*, p. 33). As to cross-cousin marriages, several recorded cases, e.g., those of the wives of Śrī Śātakarṇi I and Vāsishṭhiputra Śrī-Sātakarṇi of the Kanheri Inscription, do not support the theory propounded by Mr. Chaitṭopādhyāya. The kings in question may, doubtless, have been polygamous. But that the extra queens, if any, included cousins is only a guess. The marriages actually hinted at in the epigraphic records of the Sātavāhanas (unlike those of the Ikshvākus) are not of the 'cross-cousin' type. Indian history knows of cases where a queen or other royal personage takes as much pride in the mother's family as in that of the father (cf. *ubhaya-kulāśāśhābhāṭa* Prabhāvatī. *JASB*, 1924. 38). Does Nayanika lay any claim to a Sātavāhana origin? The table of cross-cousin marriage on p. 325 of *JASB*, 1939 would make Śātakarṇi (No. 5 of the list) a brother of

of Kanarese origin. Mr. O. C. Gangoly points out¹ that in some class of literature a distinction is suggested between the Āndhras and the Śātavāhanas. In the *Epigraphia Indica*,² Dr. Sukṭhankar edited an inscription of Siri-Palumāvi, "king of the Śātavāhanas," which refers to a place called Śātavāhanihāra.³ The place finds mention also in the Hirahadagalli copper-plate inscription of the Pallava king Siva-skandavarman in the slightly altered form of Śātāhani-raṭṭha. Dr. Sukṭhankar suggests that the territorial division Śātavāhani-Śātāhani must have comprised a good portion of the modern Bellary district of the Madras Presidency, and that it was the original home of the Śātavāhana family'. Other indications point to the territory immediately south of the *Madhya-deśa* as the original home of the Śātavāhana-Śātakarnis. The *Vinaya Texts*⁴ mention a town called "*Setakannika*" which lay on the southern frontier of the *Majjhima-deśa*. It is significant that the earliest records of the Śātakarnis are found in the Northern Deccan and Central India; and the Hāthīgumphā Inscription of Khāravela, king of Orissa, refers to the family as, 'protecting the *West*.' The name 'Andhra' probably came to be

Nāyanikā and a brother-in-law of Śātakarni (No. 3 of the list) and a son of Mahārāṣṭri Transakayiro. This is negatived by the Nānāghāt epigraph which refers to the Mahārāṣṭri as *Amgiya* (or *Amhiya*) *kularardhana*, whereas both the Śātakarnis belong to the family of Simuka Śātavāhana according to Purāṇic evidence. Gautamī-Ba'āri who is turned into a sister or clan-sister of Śivasvatī (JASB, 1927, 590) refers merely to her position as a *badhā*, *mātā*, and *pitāmāhi*, but never for once suggests that she herself sprang from the family the restoration of whose glory is referred to in exulting terms.

¹ *JAHRS*, XI, pp. 1 and 2, pp. 14-16. The Āndhras contributed one melody which is recognised in the musical literature of India as *Andhrī*, while the Śātavāhanas contributed another named after them as *Śātavāhani* according to the text of the *Bṛhat-Deśi*.

² Vol. XIV (1917).

³ See also *Annals of the Bhandarkar Institute*, 1918-19, p. 21, 'On the Home of the so-called Andhra Kings.'—V. S. Sukṭhankar: *Cj. JRAS.*, 1923, 89 f.

⁴ S. B. E., XVII, 38.

applied to the kings in later times when they lost their northern and western possessions and became a purely Andhra power, governing the territory at the mouth of the river Kṛṣṇā.¹ The Sātavāhanas themselves never claim an 'Andhra' ancestry.

There is reason to believe that the so-called "Andhra," "Andhra-bhṛitya" or Sātavāhana kings were Brāhmaṇas with a little admixture of Nāga blood. The *Dvātrīṃśat-puttalikā* represents Sālivāhana (*Prakṛit* form of Sātavāhana) as of mixed Brāhmaṇa and Nāga origin.² The Nāga connection is suggested by names like Nāga-nikā³ and Skanda-nāga-Sātaka, while the claim to the rank of Brāhmaṇa is actually put forward in an inscription. In the Nāsik *prasasti* of Gautamīputra Śātakarṇi the king is called "*Eka Bamhaṇa*," i.e., the unique Brāhmaṇa. Some scholars, however, are inclined to take *Bamhaṇa* to mean merely a Brāhmaṇical Hindu, but this interpretation cannot be accepted in view of the fact that Gautamīputra is also called "*Khatiya-dapa-māna-madana*," i.e., the destroyer of the pride and conceit of Kshatriyas. The expression "*Eka-bamhaṇa*" when read along with the passage "*Khatiya-dapa-māna-madana*" leaves no room for doubt that Gautamīputra of the Sātavāhana family not only claimed to be a Brāhmaṇa,⁴ but a Brāhmaṇa

¹ Cf. the transformation of the Eastern Chālukyas into Cholas from the time when Kulottuṅga I mounted the Chola throne. For the origin and meaning of the names Sātavāhana and Śātakarṇi see also *Camb. Hist. Ind.*, Vol. I. p. 599n; JBORS., 1917, December, p. 442n; IHQ, 1929, 388; 1933, 88, 256 and JBAS., 1929, April; also *Bulletin of the School of Oriental Studies*, London, 1938, IX. 2 327f. Both Barnett and Jayaswal connect them with the Sātiya-putas. Przyluski thinks that the names may have been Sanskritised from Austro-Asiatic terms signifying, "Son of horse." For other interpretations see Aravamathan, *the Kaveri, the Maikharis*, p. 51n. (*karṇi*=ship; *Vāhana*=Oar or Sail); Dikshit, *Indian Culture*, II, 549ff.

² Cf. E. H. D., Sec. VII.

³ Bühler, ASWI, vol. v, p. 64 n4.

⁴ In *Indian Culture*, I, pp. 513ff. and *Ep. Ind.*, XXII. 32ff. Miss Bhramar Ghosh and Dr. Bhendarkar seem to reject the interpretation of the expressions "*Eka Bamhaṇa*" and "*Khatiya-dapa-māna-madana*" proposed by

like Paraśurāma who humbled the pride of the Kshatriyas. As a matter of fact in the *prāśasti* the king is described as "the unique Brāhmaṇa in prowess equal to Rāma."¹

According to the *Purāṇas* Simuka (c. 60-37 B.C.) gave the final *coup de grace* to the Śuṅga-Kaṇva power. He was succeeded by his brother **Krishṇa** (c. 37-27 B.C.). This king has been identified with Kaṇva "Rājā of the Śātavāhana-kula" mentioned in a Nāsik inscription.

Senart and Bâbler. It is suggested that the word *bamhaṇa* may stand for *Brahmaṇa*, that *Khatiya* may refer to the Nathoi or Khatriol tribe mentioned by classical writers, and that the expression *Rājāriśi-radha* used in reference to Gaṇṭamī Balaśri is enough to show that the Śātavāhana rulers never claimed themselves to be *Brahmarshis* or *Brāhmaṇa* sages. It is nobody's case that the Śātavāhanas claimed to be mere "Brāhmaṇa sages." But is it not a bit too ingenious to imagine that the well-known terms *Brāhmaṇa* and *Kshatriya* are not to be taken in their ordinary sense, and that they really stand for non-*Brāhmaṇa* and non-*Kshatriyas*? As to the use of the expression *Rājāriśi-radha*, would not *Brahmarshi* be a singularly inappropriate description of a family of kings even though they were *Brāhmaṇas*? The term *Rājāriśi* is not used exclusively to denote non-*Brāhmaṇa* rulers. In the *Padma Purāṇa* (*Pātāla-khaṇḍam*, 51, 73), for instance, Dadhichi is styled a *Rājāriśi*. In the *Vāyu Purāṇa* (57, 121ff.) the epithets "*Rājāreḥaya mahāśhatteḍh*" are used in reference to *Brahma-Kshatramaya nripāḥ*, '*Brahma-kshatradāga nripāḥ*, according to the reading of the Matsya text, 143, 37: 10) In the *Matsya Purāṇa* (50, 5-7) the epithet *Rājāriśi* is applied to a king who sprang from the family of the Maṇḍalyas who are called *Kshatropetā deijātayaḥ* and one of whom is styled *Brahmarshiḥ*. The *Annadāmaṅgala* refers to Krishṇa Chandra as *Rāja-Rājachakravarṭi Rishi-Rishirāja*.

Attention may no doubt be invited to the *Purāṇic* statement that the founder of the "Andhra" dynasty was a '*ṛṣishala*' (DKA, 38). But the explanation will be found in the *Mahābhārata*. The great epic (XII, 63 1ff.) informs us that 'drawing the bowstring, destruction of enemies... are not proper (*akṛtrayam paramam*) for a *Brāhmaṇa*. A *Brāhmaṇa* should avoid royal service (*rāja-preṣhyā*). A *Brāhmaṇa* who marries a *Ṛṣishālā* and takes to royal service (*rāja-preṣhyā*) and other work not legitimate for him is *skarmā*, a *Brāhmaṇa* so-called (*Brahma-bandhu*). He becomes a *Sūdra*. The Śātavāhanas actually drew the bowstring and intermarried with Dravidians and Sakas as the Mauryas had intermarried with Yavanas.

¹ A pun is here intended as Rāma seems to refer to Bala Deva as well. The use of the name of Rāma instead of Bala (*cf.* Bala-Kaṇva in *Hariv.* *Vishṇuparva*, 52, 20) is significant. Taken in conjunction with *ekabamhaṇa* it undoubtedly implies comparison with Bhṛigu-Rāma or Paraśu-Rāma as well.

The record tells us that a certain cave was caused to be made by a high official (*Śramaṇa Mahāmātra*) of Nāsik in the time of King Kaṇha.

Kaṇha-Krishṇa was succeeded according to the *Purāṇas* by Śātakarṇi (c. 27-17 B.C.). This Śātakarṇi has been identified with—

(1) King Śātakarṇi *Dakshināpatha-pati* (lord of the Deccan), son (or nephew) of Simuka Śātavāhana, mentioned in the Nānāghaṭ Inscription of Nāyanikā¹;

(2) Śātakarṇi, lord of the west, who was defied (or rescued?) by Khāravela, king of Kalinga;

(3) *Rājan Śrī Śātakarṇi* of a Sāñchi Inscription;

(4) The elder Saraganus mentioned in the *Periplus*;

(5) Śātakarṇi, lord of Pratishṭhāna, father of Śaktikumāra, mentioned in Indian literature; and

(6) *Siri-Sāta* of coins.²

The first, fifth and sixth identifications are usually accepted by all scholars. The second identification is also probable because the *Purāṇas* place Śātakarṇi, the successor of Kṛishṇa, after the Kāṇvas, *i.e.*, in the first century B.C., while the Hāthigumphā Inscription seems to place Khāravela 300 years after Nanda-rāja, *i.e.*, possibly in the first century B.C.

Marshall objects to the third identification on the ground that Śrī Śātakarṇi who is mentioned in the

The comparison of a militant ruler claiming Brāhmaṇahood and fighting against Kshatriyas, with Paraśu-Rāma is a favourite theme of writers of *Prastāsis*—cf. *Bhṛigupatirita dṛiṣṭa kshatrasaṁhāra-kārin* which is applied to Ambāprasad in the Chitor-gaḍh ins. of 1274 A.D.

¹ The usual view among scholars is that Śātakarṇi I is a son of Simuka. If he is a nephew (son of Kṛishṇa, brother of Simuka) as the *Purāṇas* assert, it is difficult to explain why Kṛishṇa's name should be omitted from the family group, mentioned in the Nānāghaṭ records, while the name of Simuka as well as that of the father of Śātakarṇi's queen should find prominent mention. The final decision must await future discoveries.

² *Andhra Coins* (Rapson), p. xciii. *CHI*, 531.

Nānāghāṭ and Hāthīgumphā Inscriptions reigned in the middle of the second century B.C.; his dominions, therefore, could not, in his opinion, have included Eastern Mālwa (the Sāñchi region) which, in the second century B.C., was ruled by the Śuṅgas and not by the "Andhras".¹ But we have seen that the date of the Hāthīgumphā Inscription is possibly the first century B.C. (300 years after Nanda-rāja). The *Purāṇas*, too, as is well-known, place the kings mentioned in the Nānāghāṭ Inscription not earlier than the Kāṇvas, i.e., in the first century B.C. As Śuṅga rule had terminated about this time the identification of the successor of Kṛishṇa of the Śātavāhana family with Śātakarṇi of the Sāñchi Inscription, therefore, does not conflict with what is known of the history of Eastern Mālwa in the second century B.C. Lastly, it would be natural for the first Śātakarṇi to be styled simply Śātakarṇi or the elder Śātakarṇi (Sara-ganus, from a *Prākṛit* form like Sādaganna), while it would be equally natural for the later Śātakarṇis to be distinguished from him by the addition of a geographical designation like Kuntala, or a metronymic like Gautamīputra or Vāsishṭhīputra.

We learn from the Nānāghāṭ Inscriptions that Śātakarṇi, son(?) of Simuka, entered into a matrimonial alliance with the powerful Arṅgiya or Ambhiya² family, the scions of which were called Mahārāṭhi, and became sovereign of the whole of Dakṣiṇāpatha. He seems also to have controlled Eastern Mālwa and undoubtedly performed the *Aśvamedha* sacrifice. The conquest of Eastern Mālwa by his family is possibly implied by coins and the Sāñchi Inscription when read along with the *Purāṇic* statement that in succession to the *Śuṅgabhritya* Kāṇvāyana kings,

¹ *A Guide to Sāñchi*, p. 13.

² *ASI*, 1923-24, p. 88.

the 'earth' will pass to the 'Andhras'. The inscription records the gift of a certain Ānamda, the son of Vasīṭhī, the foreman of the artisans of *Rājan* Siri-Śātakarṇi.² Śātakarṇi seems to have been the first prince to raise the Śātavāhanas to the position of paramount sovereigns of Trans-Vindhyan India. Thus arose the first great empire in the Godāvarī valley which rivalled in extent and power the Śuṅga empire in the Ganges valley and the Greek empire in the Land of the Five Rivers. According to the evidence of Indian as well as classical writers,³ the principal capital of the Śātavāhana Empire was at Pratiśṭhāna, "the modern Paithan on the north bank of the Godāvarī in the Aurangabad District of Hyderabad."


After the death of Śātakarṇi his wife Nāyanikā or Nāganikā, daughter of the Mahārāṭhi Tranakayiro Kalalāya, the scion of the Aṅgiya (?) family, was proclaimed regent during the minority of the princes Vedaśrī (? Khandasiri or Skandaśrī) and Śakti-Śrī (Sati Sirimat) or Haku-Siri. The last-mentioned prince is probably identical with Śakti-kumāra, son of Śālivāhana, mentioned in Jaina literature.⁴

¹ I.e., the Vidiśā region, etc., in Eastern Mālwa. For the connection of the Śuṅgas with Vidiśā, see Pargiter, *DKA*, 49. The Kāpṛvāyanas had become King 'among the Sungas' (Śuṅgeshu, *DKA*, 34), apparently in the Vidiśā territory. Cf. also Tewar Coins, IHQ, XXVIII, 1952, 68f.

² The conquest of West Mālwa is probably suggested by round coins of Śrī Sāta (Rapson, *Andhra Coins*, xcii-xciii).

³ Cf. Jinaprabhasuri, *Tirthakalpa*, JBBRAS, X, 123; and Ptolemy *Geography*, vii. 1. 82. See also *Āvaśyaka Sūtra*, JBORS, 1930, 290; Sir R. G. Bhandarkar, *EHD*, Sec. VII.

⁴ *Viracharitra*, Ind. Ant., VIII, 201. *ASWI*, V, 62n.



The Śātavāhanas were not the only enemies of the decadent Magadha empire in the first century B.C. We learn from the Hāthīgumphā Inscription that when Satakarṇi was ruling in the west, **Khāravela of Kalinga** carried his arms to Northern India and humbled the king of Rājagriha.

✓ Khāravela belonged to the **Cheta** dynasty. Mr. R. P. Chanda points out that Cheta princes are mentioned in the *Vessantara Jātaka*.³ The *Milinda-pañho* contains a statement which seems to indicate that the Chetas were connected with the Chetis or Chedis. The particulars given in that work regarding the *Cheta* king Sura Parichara agree with what we know about the *Chedi* king Uparichara.⁴

Very little is known regarding the history of Kalinga from the death of Aśoka to the rise of the Cheta or Cheti dynasty probably in the first century B.C. (three

¹ On page 57 of Rapson's *Andhra Coins* Kalalāya Mahārathi bears the name "Sadakana" (= Satakarṇi). His other name or epithet "Tranakayiro" reminds us of "Tanaka" which occurs as a variant of the name of the 18th "Andhra" king of Pargiter's list (DKA, 36, 41).

² *ASI. AR.*, 1923-24, p. 68; A. Ghosh, *History of Central and Western India*, 140. Mr. Ghosh identifies him with the fifth king of the Parāṇi list.

³ No. 547.

⁴ Rhys Davids, *Milinda*, SBE, XXXV, p. 267; Mbb. I, 63, 14. According to Sten Konow (*Acta Orientalia*, Vol. 1, 1923, p. 38) *Ceti* (not *Ceta*) is the designation of the dynasty of Khāravela occurring in the Hāthīgumpha Inscription.

hundred years after the Nandas). The names of the first two ¹ kings of the Cheta line are not clearly indicated in the Hāthīgumphā inscription. Lüders Ins. No. 1347 mentions a king named Vakradeva (Vakadepasiri or Kūdepasiri?) But we do not know for certain whether he was a predecessor or successor of Khāravela.

During the rule of the second king, who must have reigned for at least 9 years (c. 37-28 B.C.), Khāravela occupied the position of Crown Prince (*Yuvarāja*). When he had completed his 24th year, he was anointed *Mahārāja* of Kalinga (c. 28 B.C.). His chief queen was the daughter of a prince named Lalāka, the great-grandson (according to some) of Hathisimha. In the first year of his reign he repaired the gates and ramparts of his capital, Kalinga-nagara. In the next year (c. 27 B.C.), without taking heed of Śātakarṇi, he sent a large army to the west and with its aid, having reached the Kṛishṇaveṇā, struck terror into the hearts of the people (or city) of Musika (Asika?)-nagara.² According to another interpretation, "he went to the rescue of Śātakarṇi and having returned with his purpose accomplished, he with his allies made gay the city." He followed up his success by further operations in the west and, in his fourth year, compelled the *Raṭhikas* and *Bhojakas* to do him homage. In the fifth year (c. 24 B.C.) he had an aqueduct, that had been opened out 300 years back by Nandarāja, conducted into his capital.

Emboldened by his successes in the Deccan the Kalinga king turned his attention to the North. In

¹ For *Puruṣa-Yuga* (generation) see Hemachandra, *Parīkṣita-parān*, VIII. 326 *pūmi puruṣa-yugāni nava gācattarānecayāḥ*.

² Cf. Ep. Ind. XX, 79, 87. Barua reads Aśvaka or Ṛṣika (*Old Brāhmī Ins.*, p. 176; Asika *IHQ*. 1938, 263). Dr. F. W. Thomas, too, finds in the passage no reference to a Musika capital (*JRAS.*, 1922, 83). The alternative interpretation in the next sentence is his. Cf. Bühler, *Indian Palaeography*, 39.

the eighth year he stormed Gorathagiri (Barābar Hills near Gayā) and harassed (the king of?) Rājagriha.¹ If Dr. Jayaswal is right in identifying this king with Brihaspatimitra, then king Brihaspati must have ruled over Magadha after the Kāṇva dynasty.

The attack on Northern India was repeated possibly in the tenth and certainly in the twelfth year. In the tenth year the Kālīṅga king, in the opinion of some scholars, overran countries in *Bhārat-varsha*, which are surmised to refer to those in Upper India. In the twelfth year he claims to have terrified or harassed the kings of *Uttarāpatha* and watered his elephants in the *Gaṅgā* (Ganges).² The north-western expeditions apparently led to no permanent result. But in north-eastern India the Kālīṅga king was more successful; the repeated blows certainly "struck terror into the Magadhas," and compelled the Magadha king (Brihaspatimitra?) to bow at his feet.

Having subjugated Magadha, and despoiled Aṅga, the invader once more turned his attention to Southern India. Already in his eleventh year "he had had Pithuḍa ploughed with a plough drawn by an ass."³ Levi⁴ identified this city with **Pihūḍa** of the *Uttarādhyayana* (21), and 'Pitundra metropolis' of Ptolemy in the interior

¹ Some scholars find in line 8 of the Hāthigumphā Ins. a reference to the Yavana-*raja* (Di) mā (ta), i.e., Demetrios who "went off to Mathurā in order to relieve his generals who were in trouble" (*Acta Orientalia*, I. 27; *Cal. Rep.*, July, 1926, 153). But the reading is doubtful (*cf.* Barua, *Old Brāhmī Inscriptions in the Udayagiri and Khandagiri Caves*, pp. 17-18; *IRQ.*, 1929, 594). Even if the reading *Dimata* be correct, the reference may be to Diyumeta or Diomedes (Whitehead, *Indo-Greek Coins*, p. 36) and not necessarily to Demetrios.

² Some scholars find here a reference to the *Sugamṅga* palace (*Ep. Ind.*, xx, 88).

³ Barua interprets the passage differently. But *cf.* Nilakanta Sastri, *The Pandyan Kingdom*, p. 26.

⁴ *Ind. Ant.*, 1926, 145. Sea-faring merchants are represented as going by boat from Champā to Pihūḍa in the days of Mahāvīra, the Jina. *Cf.* *Mbb.* I. 65, 67, 186, VII. 50.

of the country of Masulipatam (Maisoloi). The conqueror seems to have pushed further to the south and made his power felt even in the Tamil country by princes amongst whom the most eminent was the king of the Pāṇdyas. In the thirteenth year Khāravela erected pillars on the Kumārī Hill (Udayagiri in Orissa) in the vicinity of the dwelling of the Arhats (Khaṇḍagiri?).

SECTION III. THE END OF GREEK RULE IN NORTH-WEST INDIA.

While the remnant of the Magadhan monarchy was falling before the onslaughts of the Śātavāhanas and the Chetas, the Greek power in the North-West was also hastening towards dissolution. We have already referred to the feuds of Demetrios and Eukratides. The dissensions of these two princes led to a double succession, one derived from Demetrios holding for a time Kāpiśa and then Śākala (Siālkoṭ) with a considerable portion of the Indian interior, the other derived from Eukratides holding Nicaea,¹ Takshaśilā and Pushka-rāvati as well as Kāpiśa (which was conquered from Apollodotos) and Bactria. According to Gardner and Rapson, Apollodotos, Antimachos, Pantaleon, Agathokles, Agathokleia,² the Stratos, Menander, Dionysios, Zoilos,³ Hippostratos and Apollophanes⁴ probably belonged to the **house of Euthydemos** and Demetrios. Most of

¹ It lay on the Jhelum between that river and the Chenāb and was probably conquered by Heliokles in the reign of Strato I (*CHI*, 553, 699).

² According to some numismatics (*CHI*, 553) she was probably Menander's queen. But the theory has to explain why the 'evidence' regarding the supposed relationship is so vague (*contra* Heliokles and Laodike, Hermaios and Kaliope). Cf. Whitehead in *Numismatic Chronicle*, Vol. XX (1940), p. 97, 1950, 216.

³ "Apollodotos Philopator, Dionysios and Zoilos show a common and peculiar monogram struck probably by the same moneyer in one mint." Hoards of coins of these three princes have been found on the upper Sutlej. Coins of Zoilos have also been found at Pathankot and near Śākala (*JRAS*, 1913, 645n1; *JASB* 1897, 8; Tarn, *The Greeks in Bactria and India*, 316 n).

⁴ Apollophanes shares a monogram with Zoilos and Strato (Tarn, *Greeks*, 317). Polyxenos, too, belongs to this group (p. 318). Whitehead considers him a close relation of Strato I (*Indo-Greek Coins*, 54n). The later kings of this group are connected with the Eastern Panjāb (*EHI*, 4th ed., pp. 257-58). Tarn infers from a statement of Ptolemy that after the death of Menander the eastern capital was shifted from Śākala to Bukephala (on the east bank of the Jhelum, Tarn, *Alexander the Great*, Sources and Studies, 236).

these sovereigns used similar coin-types,¹ specially the figure of the goddess Athene hurling the thunderbolt, which is characteristic of the Euthydemian line. Pantaleon and Agathokles strike coins with almost identical types.² They both adopt the metal nickel for their coins, and they alone use in their legends the *Brāhmī* alphabet. They seem, therefore, to have been closely connected probably as brothers. It is not improbable that Agathokleia was their sister.³ Agathokles (and possibly Antimachos) issued a series of coins⁴ in commemoration of Alexander, Antiochos Nikator (Antiochos III Megas according to Malala), Diodotos Soter, Euthydemos and Demetrios Aniketos (the Invincible).

Apollodotos, the Stratos, Menander and some later kings used the Athene type of coins. Apollodotos and Menander are mentioned together in literature. The author of the *Periplus of the Erythraean Sea* says that "to the present day ancient *drachmae* are current in Barygaza (Broach) bearing inscriptions in Greek letters, and the devices of those who reigned after Alexander, Apollodotos and Menander." Again, in the title of the lost forty-first book of Justin's work, Menander and Apollodotos are mentioned as Indian kings.⁵ It appears from the *Milinda-pañho* that the capital of the dynasty to which Menander belonged was Śākala or Sāgala.⁶

¹ For an interesting account of Indo-Greek coin-types see H. K. Deb, *IHQ*, 1934, 509 ff.

² Dancing girl in oriental costume according to Whitehead; Māyā, mother of the Buddha, in the nativity scene according to Foucher (*JRAS*, 1919, p. 90).

³ Agathokleia is also closely connected with the Stratos, being probably mother or queen of Strato I, and great (?) grandmother of Strato II of the *JRNS*, 1950, 216.

⁴ According to Tarn (447 f) the fictitious Seleukid pedigree is the key to the (pedigree) coin series of Agathokles, the Just.

⁵ Rhys Davids, *Milinda*, SBE, 35, p. xix. Cf. *JASB*, Aug., 1833.

⁶ "Atthi Yonakānaṃ nānāpuṭabhedanaṃ Sāgalannāma nagaram," *Jambudīpe Sāgala nagare Milindo nāma Rājā ahoṣi.* "Atthi kho

We learn from Ptolemy, the Geographer that the city had another name Euthymedia or Euthydemia, a designation which was probably derived from the Euthydemian line. An inscription on a steatite casket which comes from Shinkot in Bajaur territory refers to the 5th regnal year of *Māhārāja* Minadra (Menander). The record proves that in the 5th year of his reign the dominions of Menander probably included a considerable portion of the Trans-Indus territory. The Kāpiśa and Niçaea coins indicate how some of the rulers of the Euthydemian group were gradually pushed to the Indian interior. They had to remove their capital to Śākala.

To the rival **family of Eukratides** belonged Heliokles and probably Antialkidas who ruled conjointly with Lysias. A common type of Antialkidas is the Pilei of the Dioscouri, which seems to connect him with Eukratides; his portrait according to Gardner resembles that of Heliokles. It is not improbable that he was an immediate successor of Heliokles.¹ A Besnagar Inscription makes him a contemporary of Kāśi (Kośi = Kautsī?) putra Bhāgabhadra of Viḍiśā who ruled some time after Agnimitra probably in or about the latter half of the second century B.C. The capital of Antialkidas was probably at Takshaśilā or Taxila, the place from which his ambassador Heliodoros went to the kingdom of Bhāgabhadra. But his dominions seem also to have included Kāpiśi or Kāpiśa.² After his death the western Greek kingdom probably split up into three parts, viz.,

Nāgasena Sāgalam nāma nagaram, tattha Mūlinda nāma Rājā rajjam kareti." The form **Yonaka** from which chronological conclusions have been drawn in recent times, is comparable to **Maṭṭraka**, **Vijjika** (Pāṇini, IV. 2. 131).

¹ Gardner, *Catalogue of Indian Coins in the British Museum*, p. xxxiv.

² *Cāmb. Hist.*, 558.

Takshaśilā (ruled by the line represented by Archebios¹), Pushkalāvati (governed by Diomedes, Epander,² Philoxenos, Artemidoros, and Peukolaos), and Kāpiśi with the Kābul region held successively by Amyntas and Hermaeus (Hermaios). With Hermaios was associated his queen, Kalliope. Kāpiśa was, according to Chinese evidence, probably occupied by the Sai-wang (Śāka lord) some time in the latter part of the second century B.C. But the barbarian chieftain, like the Kushān *Yavuga* of later times, may have acknowledged the nominal suzerainty of the Greek *Basileas*, as Teutonic chieftains in Europe were, during the fifth century A.D., sometimes content with the rank of 'patrician' and 'consul,' under the nominal authority of the titular Roman emperor.

The Greek power must have been greatly weakened by the feuds of the rival lines of Demetrios and Eukratides. The evils of internal dissension were aggravated by foreign inroads. We learn from Strabo³ that the **Parthians** deprived Eukratides (and the Scythians) by force of arms of a part of Bactriana, which embraced the satrapies of Aspionus and Turiva (possibly Aria and Arachosia according to Macdonald). There is reason to believe that the Parthian king Mithradates I penetrated even into India. Orosius, a Roman historian, who flourished about 400 A.D., makes a definite statement to the effect that Mithradates (c. B.C. 171-138)

¹ A copper piece of this king is restruck, probably on a coin of Heliokles (Whitehead, p. 39).

² The 'Pallas and thunderbolt' type of his silver coins, probably connects him with the Śākala group, *ibid.*, 64. Among the rulers of the Gandhāra region we should perhaps also include Telephos whose coinage resembles that of Maues, *ibid.*, 80. A prince named Nikias apparently ruled in the Jhelum District (EHI, 4th ed., 238), and perhaps other tracts (*Num. Chron.*, 1940, p. 109). But the story of his naval victory over Maues is based on inadequate evidence.

³ H. and F.'s Vol. II, pp. 251-253.

subdued the natives between the Hydaspes¹ and the Indus. His conquest thus appears to have driven a wedge between the kingdom of Eukratides and that of his rival of the house of Euthydemos.

The causes of the final downfall of the Bactrian Greeks are thus stated by Justin: "the Bactrians harassed by various wars lost not only their dominions but their liberty; for having suffered from contentions with the Sogdians, the Drangians and the Indians (?) they were at last overcome as if exhausted by the weaker Parthians."²

The **Sogdians** were the people of the region now known as Samarkand and Bukhārā. They were separated from Bactriana by the Oxus and from the Sakas by the Jaxartes or the Syr Daria.³ By the term Sogdian Justin probably refers not only to the Sogdiani proper but also to the well-known tribes which, according to Strabo,⁴ deprived the Greeks of Bactriana, viz., the Asii, Pasiani, Tochari, Sacarauli and the Sacae or Sakas. The story of the Saka occupation of the Indo-Greek possessions will be told in the next chapter. The Latin historian Pompeius Trogus describes how Diodotos had to fight Scythian tribes, the Sarancae (Saraucae) and Asiani, who finally conquered Sogdiana and Bactria. The occupation of Sogdiana probably entitled them to the designation Sogdian used by Justin. Sten Konow⁵

¹ In the *Cambridge History of India*, Vol. I, p. 568, however, this river has been identified with a Persian stream, the Medus Hydaspes of Virgil.

² Sten Konow translates the passage from Justin thus: The Bactrians lost both their empire and their freedom, being harassed by the Sogdians (beyond the Oxus), the Arachoti (of the Argandāb valley of S. Afghanistan), the Drangae (lake-dwellers, near the Hamun Lake) and the Arei (of Herat), and finally oppressed by the Parthians (*Corpus*, ii. 1, xxi-xxii).

³ Strabo, XI. 8. 8-9.

⁴ H. and F.'s Tr., Vol. II, pp. 245-46. Cf. *JRAS.*, 1906, 193 f.; Whitehead, *Indo-Greek Coins*, 171, Bachhofer, *JAOS*, 61 (1941), 245 (criticism of Tarn).

⁵ *Modern Review*, April, 1921, p. 464. *Corpus*, II. 1, xxii, lvii f.

suggests the identification of the Tochari of the Classical writers with the Ta-hia of the Chinese historians. He further identifies the Asii, Asioi or Asiani with the Yüe-chi. We are inclined to identify the Tochari with the Tukhāras who formed an important element of the Bactrian population in the time of Ptolemy and are described by that author as a great people.¹ They are apparently "the war-like nation of the Bactrians" of the time of the *Periplus*.

The **Drangians**, literally 'lake-dwellers',² referred to by Justin, inhabited the country about the Hamun lake (*Zareh*) between Areia (Herat), Gedrosia (Baluchistān) and Arachosia (Kandahār) and the desert of Eastern Persia, close to and perhaps including at times within its political boundaries the neighbouring province now called Sīstān or Seistan (Śakasthāna).³ Numismatic evidence indicates that a family whose territory lay mainly in southern Afganisthān, viz., the so-called **dynasty of Vonones**, supplanted Greek rule in a considerable part of the Helmund valley, Ghazni and Kandahār (**Arachosia**). Vonones is a Parthian (Imperial) name. Hence many scholars call his dynasty a Parthian family, and some go so far as to assert that this Vonones is the Arsakid king of that name who reigned from A.D. 8 to 14.⁴ But names are not sure proofs of nationality. Sir R. G. Bhandarkar calls the dynasty Śaka.⁵ The best name for the family would be Drangian, because the chief centre of their power probably

¹ *Ind. Ant.*, 1884, pp. 395-96.

² Schoff, *Parthian Stations*, 32.

³ *Corpus*, xl; Whitehead, *Indo-Greek Coins*, 92; MASI, 34. 7. Isidore, places Drangiana (Zarangiana) beyond Phra (Farah), and locates Śakasthāna beyond this territory, (Schoff, 9). But Herzfeld points out that Sīstān is the Achaemenian 'Zraug'.

⁴ *Camb. Short Hist.*, 69.

⁵ Isidore of Charax who mentions the revolt of Tiridates against Phraates (26 B.C.) and is quoted by Pliny (Schoff, *Parthian Stations*, pp. 5, 13 ff. 17;

lay in the Helmund valley, Arachosia being ruled by a viceroy.¹ On coins Vonones is associated with two princes, viz.,

- (i) Spalahora (Spalyris) who is called *Mahārāja-bhrātā* (the king's brother).
- (ii) Spalaga-dama, son of Spalahora.

There is one coin which Edward Thomas and Cunningham attributed to Vonones and Azes I. But the coin really belongs to Maues.² There is a silver coin of a prince named Spalirises which bears on the obverse the legend *Basileus Adelphoy Spaliriso*y, and on the reverse "*Mahārāja bhrātā dhramiasa Spaliriśasa*," i.e., of Spalirises the Just, brother of the king. This king has been identified by some with Vonones and by others with Maues.³ Vonones was succeeded as supreme ruler by Spalirises.⁴ The coins of Spalirises present two varieties, viz.,

1. Coins which bear his name alone in both the legends :

JRAS. 1904, 706; 1906, 180; 1912, 990, refers (Parthian Stations, 9, para 16. ZDMG., 1906, pp. 57-58; JRAS., 1915, p. 831; Tarn. *The Greeks in Bactria and India*, 53) to Sigal in Sacastene (near Kandahar?) as the royal residence of the Sakas (not Parthians) about the beginning of the Christian era. The names of the brother or brothers and nephew of Vonones, (or Maues) ruling in southern Afghanistan seem to be Sæthian (cf. Rapson quoted in *Corpus* II. 1, xlii). Thus the local rulers of southern Afghanistan about B.C. 26 or a little later were probably Sakas. It is, however, possible that they acknowledged the supremacy of the great king of Parthia.

¹ *Corpus*, xlii.

² Whitehead, *Catalogue of Coins in the Panjāb Museum (Indo-Greek Coins)*, p. 93. Num. Chron., JRNS (1950), p. 298n. Smith, *Catalogue*, 33. Bachhofer (JAOS, 61, 239) and Tarn possibly repeat the mistake (*Greeks*, 344n 2).

³ Herzfeld identifies the royal brother of Spalirises with Maues (*Camb. Short Hist.*, 60).

⁴ It should be noted that certain coin-types of Spalirises are found re struck on coins of Vonones (CHI, 574) and on a copper coin of Spalyris and Spalagadama (*Corpus*, II. 1. xli). This proves that Spalirises was later than Vonones, Spalyris and Spalagadama. The square Omicron on a coin of Spalyris probably points to a date not earlier than Oroses II (55 to 38/7 B.C.). Tarn. *Greeks*, 326.

2. Coins on which his name occurs on the obverse in the Greek legend, and those of Azes on the reverse in the *Kharoshthi* legend.

The second variety proves that Spalirises had a colleague named Azes who governed a territory where the prevailing script was *Kharoshthi*. This Azes has been identified with king Azes of the Pañjāb about whom we shall speak in the next chapter.

As regards the Indian enemies of the Bactrian Greeks we must refer in the first place to the prince of the house of Pushyamitra who is represented in Kālidāsa's *Mālavikāgnimitram* as defeating the Yavanas on the Sindhu. An Indian named Bhadrayaśas seems to have had some share in the destruction of the Greek kingdom of the Eastern Pañjāb. The Nāsik *praśasti* of Gautamī-putra Śātakarṇi represents that king as the destroyer of the Yavanas, apparently of Western India.

The final destruction of Greek rule was, as Justin says, the work of the Parthians. Marshall tells us¹ that the last surviving Greek principality,² that of Hermaios in the Kābul valley, was overthrown by the Parthian king Gondophernes.³ The Chinese historian Fan-ye also refers to the Parthian occupation of Kābul.⁴ "Whenever any of the three kingdoms of Tien-tchou (India Proper), Ki-pin (Kāpiśa) or Ngansi (Parthia),

¹ *A Guide to Taxila*, p. 14.

² Among the latest Greek rulers of the Kābul Valley we have to include Theodamas whose existence is disclosed by a Bajaur Seal Inscription (*Corpus*, II, i. xv, 6).

³ In ASI, AR, 1929-30, pp. 56 ff., however, Marshall modifies his earlier views in regard to the conquest of the Greek kingdom of Kābul by the Parthians. He suggests that the Kābul Valley became a bone of contention between Parthians and Kushāns and changed hands more than once before the final eclipse of the Parthian power.

⁴ JRAS., 1912, 676; *Journal of the Department of Letters*, Calcutta University, Vol. I, p. 81.

became powerful, it brought Kābul into subjection. When it grew weak it lost Kābul. . . . Later, Kābul fell under the rule of Parthia."¹ The real conquest of Kābul by the Parthians could hardly have taken place till after the time of Isidore (last quarter of the first century B.C.)² because the writings of that geographer do not include the Kābul valley in the list of the eastern provinces of the Parthian Empire. By A.D. 43-44, however, Parthian rule had extended to this region as we learn from Philostratos.

¹ Cf. Thomas JRAS., 1906, 194. For the results of India's contact with the Hellenic world in the domains of religion, administration, literature, science and art see Bhandarkar, "Foreign Elements in the Hindu Population" (Ind. Ant., 1911); Raychaudhuri, "Early History of the Vaishnava Sect, 1st ed.," p. 106; Foucher, "The Beginnings of Buddhist Art," pp. 9, 111 f.; Coomaraswami, "History of Indian and Indonesian Art," pp. 41 f.; Sten Konow, "Corpus Inscriptionum Indicarum," Vol. II, Pt. 1. xv; Hopkins, "Religion of India," pp. 544 f.; Keith, "The Sanskrit Drama," pp. 57 f.; Keith, "A History of Sanskrit Literature," pp. 352 f.; Max Müller, "India—What can it teach Us," pp. 321 f.; Smith, EHI*, pp. 251-56; "A History of Fine Art in India and Ceylon," Chap. XI; Imp. Gaz., The Indian Empire, Vol. II, pp. 105 f., 137 f., etc.

² Tarn, *The Greeks in Bactria and India*, 53; Schoff, *The Parthian Stations of Isidore of Charax*, 17.

CHAPTER VIII. SCYTHIAN RULE IN NORTHERN INDIA

SECTION I. THE ŚAKAS.

In the second and first centuries B.C., Greek rule in parts of Kāfiristān, Gandhāra and possibly the Hazāra country, was supplanted by that of the Śakas. In the days of Darius, the Achaemenid king of Persia (B.C. 522-486), the Śakas lived beyond Sogdiana (*para-Sugdān*) in "the vast plains of the Syr Darya, of which the modern capital is the town of Turkestan."¹ But already towards the end of the first century B.C. they were established at Sigal in modern Sistān.² The story of their migration from central Asia has been recorded by Chinese historians. The *History of the First Han Dynasty* (*Ts'ien Han-Shu*) states "formerly when the Hiung-nū conquered the Ta-Yüe-tchi the latter emigrated to the west," and subjugated the Tahia; whereupon the *Sai-wang* went to the south, and ruled over Kipin."³ Sten Konow points out that the *Sai-wang* refer to the same people which are known in Indian tradition under the designation *Saka-murunda*,⁴ *Murunda* being a later form of a Śaka word which has the same meaning as Chinese "*wang*," i.e., king, master, lord. In

¹ E. Herzfeld, *MASI*, 34, 8.

² Schoff, *Isidore, Stathmoi Parthikoi*, 17.

³ C. 174-160 B.C. according to some scholars.

⁴ *JRAS.*, 1909, p. 22; 1932, 258; *Modern Review*, April, 1921, p. 464. The Saka occupation of Ki-pin must be posterior to the reign of Eukratides and his immediate (Greek) successors.

⁵ Professor Hermann identifies the *Sai-wang* with the *Sakarauloi* or *Sakarauloi* of Strabo and other classical authors. *Corpus*, II, 1, xxf. For *Murunda*, see pp. xx,

Indian inscriptions and coins it has frequently been translated with the Indian word *Svāmin*.

The name of the Saka king who occupied Kipin is not known. The earliest ruler of that region mentioned in Chinese records is Wu-t'ou-lao whose son was ousted by Yin-mo-fu, the son of the prince of Yung-k'ü,¹ with Chinese help. Yin-mo-fu established himself as king of Kipin during the reign of the Emperor Hsüan-ti, which lasted from 73 to 48 B.C., and killed the attendants of an envoy sent in the reign of the Emperor Yüan-ti (B.C. 48-33). In the reign of Chéng-ti (32-7 B.C.) the support of China was sought without success by the king of Kipin, probably the successor of Yin-mo-fu, who was in danger from some powerful adversary, apparently a king of the Yue-chi, who had relations with China about this time as is proved by the communication of certain Buddhist books to a Chinese official in 2 B.C.²

S. Lévi at first identified Kipin with Kaśmīra. But his view has been ably controverted by Sten Konow³ who accepts the identification with Kāpiśa.⁴ Gandhāra was at one time the eastern part of the realm of Kipin. A passage of Hemachandra's *Abhidhāna-Chintāmaṇi*

¹ The identification of Yung-k'ü with Yonaka (Tarn, 297) and that of Yin-mo-fu with Hermaios (Tarn, 346) are purely conjectural. Mention may be made in this connection of Zonkah in Tibbat (JASB, 1895, 97). But the problem of identification must await future discoveries.

² *Cal. Rev.*, Feb., 1924, pp. 251, 252; Smith, EHI, 3rd ed., p. 258n.; JRAS., 1913, 647; Ind. Ant., 1905, *Kashgar and the Kharoshthi*.

³ Ep. Ind., XIV, p. 291.

⁴ The country drained by the northern tributaries of the river Kābul, *ibid.*, p. 290; cf. Watters, *Yuan Chucang*, Vol. I, pp. 259-60. The city of Kāpiśi probably stood at the junction of the Ghorband and the Panjshir (Foucher, *Indian Studies presented to Prof. Rapson*, 343). Kipin according to the *Tsien Han-shu* joins Wu-i-shan-li (Arachosia and Persia according to Schoff, *Parthian Stations*, 41) on the south-west. *Corpus*, II, 1, xxiv; JRAS., 1912, 634n. Cf. Dr. Hermann (JRAS, 1913, 1058n.) who holds that Ki-pin was Gandhāra. The reference to a gold as well as a silver currency in Ki-pin is worthy of note (*Corpus*, II, 1, xxiv). Cf. the gold coin of the city of Pushkalāvati (CHI, 587, and the coin of Athama (442 *infra*).

seems to suggest that the capital of the Sai-wang (*Saka-Muraṇḍa*) was Lampāka or Laghman (*Lampā-kāstu Muraṇḍāḥ syuh*).¹ Sten Konow says that according to the *Ts'ien Han-shu*, or *Annals of the First Han Dynasty*, the Sai, i.e., the Śakas, passed the *Hientu* (the hanging passage), i.e., the gorge west of Skardu on their way to Kipin.² Though the Śakas wrested parts of Kipin (*Kāpiśa-Gandhāra*) from the hands of Greek *meridarchs* (governors) they could not permanently subjugate Kābul,³ where the *Basileus* (king) maintained a precarious existence. They were more successful in India. Inscriptions at Mathurā and Nāsik prove that the Śakas extended their sway as far as the Jumna in the east and the Godāvari in the south, and destroyed the power of the 'Mitrās' of Mathurā and the Śātavāhanas of Paiṭhan.⁴

No connected or detailed account of the Śaka potentates of Kipin is possible. Śakas are mentioned along with the Yavanas in the *Rāmāyaṇa*,⁵ the *Mahābhārata*,⁶ the *Manusamhitā*⁷ and the *Mahābhāshya*.⁸ The *Harivaṃśa*⁹ informs us that they shaved one-half of their heads. The Jaina work *Kālakāchārya-kathānaka* states that their kings were called Śāhi.¹⁰ Some of these 'Śāhis' are said to have been induced by a Jaina teacher

¹ Lampāka (Laghman) is 100 miles to the east of Kapisene (AGI, 49).

² Ep. Ind., XIV, 291. *Corpus*, II. 1. xxiii. For possible alternative routes of conquest, see JRAS., 1913, 929, 959, 1006, 1023.

³ *Journal of the Department of Letters*, Vol. I, p. 61.

⁴ Some of the Śakas seem to have penetrated to the far south of India. A Nāgarjunikoṇḍa Inscription refers to a Śaka named Moda and his sister Budhi. Ep. Ind., xx. 37.

⁵ I, 54. 22; IV. 43, 12.

⁶ II, 32, 17.

⁷ X. 44.

⁸ Ind. Ant., 1875, 244.

⁹ Chap. 14, 16. JRAS., 1906, 204.

¹⁰ ZDMG, 34, pp. 247ff., 262; Ind. Ant., X. 222.

to proceed to Suratt̥ha (Surāshtra) *Vishaya* (country) and Ujjain in Hindukadeśa (India) where they overthrew some local chiefs and ruled for four years till they were themselves ousted by the founder of the era of 58 B.C.

The Śakas are also mentioned in the *Prasastis* of Gautamīputra Śātakarṇi and Samudra Gupta. Their kingdom or empire "*Śakasthāna*" is probably mentioned in the *Mahāmāyūri* (95), in the Mathurā Lion Capital Inscription and in the Chandravalli Stone Inscription of the Kadamba Mayūraśarman. The passage in the Mathurā inscription containing the word *Śakasthāna* runs thus :—

Sarvasa Sakastanasa puyae.

Cunningham and Bühler interpreted the passage as meaning "for the merit, or in honour, (of the people) of the whole of *Sakasthāna*." Dr. Fleet, however, maintained that "there are no real grounds for thinking that the Śakas ever figured as invaders of any part of northern India above Kāthiawād and the western and southern parts of the territory now known as Mālwa." He took *Sarva* to be a proper name and translated the inscriptional passage referred to above as "a gift of *Sarva* in honour of his home."¹

Fleet's objection is ineffective. Chinese evidence clearly establishes the presence of Śakas in Kipin, i.e., Kāpiśa-Gandhāra.² As regards the presence of the tribe at Mathurā, the site of the inscription, we should note that the *Mārkaṇḍeya Purāṇa*³ refers to a Śaka settlement in the *Madhyadeśa*. Dr. Thomas⁴ points out that the

¹ JRAS., 1904, 703f.; 1905, 155, 543f.; Mr. N. G. Majumdar (JASB., 1924, 17) takes *Sakastana*, to mean *Sakrasthāna*, i.e., 'the place of Indra.' Cf. Fleet in JRAS., 1904, 705.

² Note also the Kāpiśa types of the coins of Manes and Spalirises (CHI, 560n, 562, 591) and the foundation of a Kāpiśa satrapy *Corpus*, ii, 1. 150f.).

³ Chapter 58.

⁴ Ep. Ind., IX, pp. 138ff.; JRAS., 1905, 207f., 215f.

epigraphs on the Lion Capital exhibit a mixture of Śaka and Persian nomenclature. The name Mevaki for instance, which occurs in the inscription, is a variant of the Scythian name Mauakes.¹ The termination “-ās” in Komūsā and °Šamūšo seems to be Scythic. Dr. Thomas further points out that there is no difficulty in the expression of honour to the “whole realm of the Śakas” since we find in the Wardak, Sui Vihār and other inscriptions even more comprehensive expressions, e.g., *Sarva sattvanam*—‘of all living creatures.’ As regards Fleet’s renderings “*svaka*” and “*sakaṭṭhāna*,” one’s own place, Dr. Thomas says that it does not seem natural to inscribe on the stone, honour to somebody’s own home. A *pūjā* addressed to a country is unusual, but inscription G of the Lion Capital contains a similar *pūjā* addressed to the chief representatives of the Śāka dominions.

Sakasthāna, doubtless, included the district of Scythia mentioned in the *Periplus*, “from which flows down the river Sinthus (Indus) the greatest of all the rivers that flow into the Erythraean Sea (Indian Ocean).” The metropolis of “Scythia” in the time of the *Periplus* was Minnagara; and its market town was Barbaricum on the seashore.

Princes bearing Śaka names are mentioned in several inscriptions discovered in Taxila, Mathurā and Western India. According to Dr. Thomas “whatever Śaka dynasties may have existed in the Pañjāb or India, reached India neither through Āfghānistān nor through Kāśmīra but, as Cunningham contended, by way of Sindh and the valley of the Indus.”² This theory cannot be accepted

¹ Cf. Maues, Moga, and Mavaces, the commander of the Śakas who went to the aid of Darius Codomannus (Chltonock, Arrian, p. 142). Cf. also the coin-name Mevaku (S. Konow, *Corpus*, xxxiii n.). In the period 106 to 101 B.C. the king of Ferghana bore the Śaka name of Mu-ku’a (Tarn, *Greeks*, 308f.).

² JRAS., 1906, p. 216.

in its entirety in view of the inadequate representation of Sind by Śaka coins, the Chinese account of the Śaka occupation of Kipin and the epigraphic evidence regarding the existence of a Scythian Satrapy at Kāpiśi and a Śaka principality in the Hazāra country.¹ We cannot also overlook the fact that some of the Śaka names hitherto discovered are those of the Northern Śakas who lived near the Sogdianoī.² The names Maues, Moga³ and Mevaki,⁴ for instance, are variants of the Śaka name Mauakes. We learn from Arrian that a chief named Mauakes or Movaces led the "Sacians (Śakas), a Scythian tribe belonging to the Scythians who dwelt in Asia," who lived outside the jurisdiction of the Persian governor of the Bactrians and the Sogdianians, but were in alliance with the Persian king. Chhaharata, Khakharāta or Kshaharāta, the family designation of several satrapal houses of Taxila, Mathurā, Western India and the Deccan, is perhaps equivalent to **Karatai** the name of a Śaka tribe of the North.⁵

The Conquest of the Lower Indus Valley, Cutch and parts of Western India may, however, have been effected by the Śakas of Western Śakasthāna (Sīstān) who are mentioned by Isidore of Charax. The name of the capitals

¹ CHI, 569n, JASB., 1924, p. 14; S. Konow, *Corpus*, II. i. 13f. The Śaka conquest of Ki-pin did not mean the total extinction of the Greek principality in the Kābul region. *The History of the Later Han Dynasty* (A.D. 25-230) refers to the existence, side by side, of the kingdoms of Ki-pin and Kābul before the conquest of the latter state by the Parthians. Like the Śātavāhanas, the Greeks of the Kābul territory may have restored their fallen fortunes to a certain extent after the first rush of barbarian invasion had spent its force. It is also possible that Scythian chiefs for a time acknowledged the nominal suzerainty of the Greek *Basileus*.

² *Ind. Ant.*, 1884, pp. 399-400.

³ Taxila plate.

⁴ Mathurā Lion Capital.

⁵ *Ind. Ant.*, 1884, p. 400; cf. *Corpus*, II. I. xxxvi: "Kharaoستا and Maues would belong to the north-western Śakas of Ki-pin and not to the branch which came to India from Seistān." Cf. xxxiii (case of Liakā).

of "Scythia" (which embraced the Lower Indus Valley) and of the kingdom of Mambarus (Nambanus?) in the time of the *Periplus* was Minnagara, and this was evidently derived from the city of Min in Śakasthāna mentioned by Isidore.¹ Rapson points out that one of the most characteristic features in the names of the Western Kshatrapas of Chashṭana's line, viz., "Dāman" (-dama) is found also in the name of a prince of the Drangianian house of Vonones. Lastly, the *Kārdamaka* family from which, according to a Kanheri Inscription, the daughter of the *Mahākshatrapa* Rudra claimed descent, apparently derived its name from the Kārdama river in the realm of the Persians.²

The earliest Śaka kings mentioned in Indian inscriptions are, perhaps, Damijada³ and **Maues**. The latter is usually identified with Moga of the Taxila plate. He is possibly mentioned also in the Maira Inscription.⁴ Maues-Moga was a mighty sovereign (*Maharaya*). His dominions included Chuksha near Taxila which was ruled by a satrapal, i.e., a viceregal, family. Numismatic evidence points to his sway over Kāpiśi⁵ and Pushkarāvati as well as Taxila.⁶ His satrapas probably put an end to Greek and Indian rule in the country round Mathurā. In parts of the Eastern Pañjāb and certain adjacent

¹ JRAS, 1915, p. 830.

² Shāmasastry's trans. of the *Arthaśāstra*, p. 86, n. 6. cf. Artemis (Ptolemy, 324), Gordomaris, Loeb, Marcellinus (ii, 389). For another view see Ind. Ant., XII. 273 n. The word *Kārdamika* occurs in the *Mahābhāshya* (IV. 2. 1. Word Index, p. 275); Kramadīśvara, 747; and Kardamila in Mbh. III. 135. 1. The Kārdama river may be identified with the Zarafshan which flowed through the old Achæmenian Satrapy of Bactria or Balkh. The *Uttarakāṇḍa* of the *Rāmāyaṇa* (Chs. 100 and 102) connects a line of Kārdama kings with Bāhli or Bāhlika (IHQ., 1933, pp. 37 ff.).

³ Or Namijada, Shahdaur Ins., *Corpus*, II. i. 14, 16.

⁴ At Maira in the Salt Range, a *Kharoshthī* Inscription has been found in a well which seems to be dated in the year 58 and possibly contains the word *Moasa*, 'of Moa or Moga.'

⁵ *Camb. Hist.*, Ind. I. 590 f.

Ibid., 701.

tracts indigenous tribes like the Audumbaras, Trigartas, Kunindas, Yaudheyas, Ārjunāyanas had begun to assert their independence probably after the collapse of the Euthydemian monarchy. Maues struck coins with the types of Eukratides and Demetrios. But the absence of the *Athena Alkis* type leads Tarn to surmise that he did not annex Menander's home kingdom (i.e., the district round Śākala).¹

The dates assigned to Maues by various scholars range from B.C. 135 to A.D. 154. His coins are found ordinarily in the Pañjāb, and chiefly in the western portion of the province of which Taxila was the ancient capital. There can thus be no doubt that Maues was the king of Gandhāra. Now, it is impossible to find for Maues a place in the history of the Pañjāb before the Greek king Antialkidas who was reigning at Taxila when king Bhāgabhadra was on the throne of Vidiśā in Central India for fourteen years. The date of Bhāgabhadra is uncertain but he must be placed later than Agnimitra, son of Pushyamitra, who ruled from *cir.* B.C. 151 to 143. The fourteenth year of Bhāgabhadra, therefore, could not have fallen before *c.* 129 B.C. Consequently Antialkidas could not have been ruling earlier than the second half of the second century B.C.,² and his reign could not have ended before 129 B.C. The Śaka occupation of Gandhāra must, therefore, be later than 129 B.C. All scholars except Fleet identify Maues with *Maharaya Moga* of the so-called Sirsukh or Taxila plate, dated in the year 78 of an unspecified era. The generally accepted view is that the era is of Śaka institution. As

¹ Tarn, *The Greeks in Bactria and India*, 322-330. The conquest of this kingdom may have been effected by Azes I. Whitehead, *Indo-Greek Coins*, 112; Tarn, *GBI*, 349; or by Rājuvula, Allan, *CICAI*, 185.

² *Cf.*, now Marshall, *Monuments of Sāñchī*, I, 268n.

the era is used *only* in Northern India and the borderland, it is permissible to conjecture that it came into existence after the Śaka occupation of those regions. We have already seen that this occupation could not have taken place before 129 B.C. The era used in the Taxila plate could not, therefore, have originated before 129 B.C. The year 78 of the era could not have fallen before B.C. ($129 - 78 =$) 51. Consequently the rule of Maues-Moga cannot have ended before B.C. 51. He must be placed even later, because we learn from Chinese records that Yin-mo-fu was in possession of Kipin or Kāpiśa-Gandhāra about 48-33 B.C., and he was *preceded* by Wu-tou-lao and his son. As there is no real ground for identifying Maues-Moga with any of these rulers he will have to be placed after 33 B.C. He cannot perhaps be placed later than the middle of the first century A.D., because we learn from Philostratos and the author of the *Periplus* that about the time or a little later both Taxila and Minnagara, the metropolis of Scythia, *i.e.* the Śaka kingdom in the Indus valley, had passed into the hands of the Parthians. It seems, therefore, that Maues-Moga ruled after 33 B.C., but before the latter half of the first century A.D. According to Fleet, Moga flourished in the year 22 A.D.—the year 78 of the era commencing 58 B.C. which afterwards came to be known as the *Kṛita-Mālava-Vikrama* era. But the matter must be regarded as not definitely settled. The Khalatse Inscription of the year 187 (?) of Uvima (? Wema Kadphises) and the Taxila Silver Vase Inscription of the year 191 of Jihonika possibly suggest that the era to which the dates of these inscriptions, and presumably that of the so-called Sirsukh (Taxila) plate of Moga, are to be referred, began much earlier than B.C. 58.

Numismatists say that Maues was succeeded on the throne of Gandhāra by **Azes** who put an end to the remnant of Greek rule in the Eastern Pañjāb by annexing the kingdom of Hippostratos. In the opinion of Marshall he also conquered the Jumna valley where the Vikrama era was in use.¹ The coins of Azes are very closely related to the issues of the rulers of the Vonones group, and the assumption has always been made that Azes, the king of the Pañjāb, is identical with Azes, the colleague of Spalirises. Some scholars think that there were two kings of the name of Azes and that the first Azes was the immediate successor, not of Maues, but of Spalirises and that Maues came not only after Azes I, but also after Azes II. But the last part of the theory cannot be accepted in view of the synchronism of Gondophernes and Azes II proved by the fact that Aspavarman served as *Strategos*, i.e., general or governor, under both the monarchs.² As Gondophernes ruled in the year 103,³ while Maues-Moga ruled in the year 78,⁴ and as both these dates are usually referred by scholars to the same era, both Gondophernes and his contemporary Azes II must be later than Maues-Moga. There is no room for Maues-Moga between Azes I and Azes II, because we shall see presently that the succession from Azes I to Azes II is clearly established by numismatic evidence. Maues came either before Azes I or after Azes II; but we have already seen that he could not have reigned after Azes II. He must, therefore, be placed before Azes I. He may have been ruling in the Pañjāb when Vonones was ruling in Sīstān. When Vonones was succeeded by Spalirises, Maues was succeeded by Azes I. We have already seen that Spalirises and Azes I issued

¹ *JRAS*, 1947, 22.

² Whitehead, *Catalogue of Coins in the Pañjāb Museum*, p. 150.

³ Cf. the Takht-i-Bāhī Inscription.

⁴ Cf. the Taxila Plate of Patika.

joint coins.¹ The relationship between the two monarchs is not known. They may have been related by blood, or they may have been mere allies like Hermaios and Kujūla Kadphises.²

King Azes I struck some coins bearing his own name in Greek on the obverse, and that of **Azilises** in *Kharoshthi* on the reverse.³ Then again we have another type of coins on which the name in Greek is Azilises, and in *Kharoshthi* is *Aya* (Azes). Drs. Bhandarkar and Smith postulate that these two joint types, when considered together, prove that Azilises, before his accession to independent power, was the subordinate colleague of an Azes, and that an Azes similarly was subsequently the subordinate colleague of Azilises. The two princes named Azes cannot, therefore, be identical, and they must be

¹ Rapson on pp. 573-574 of *CHI*, identifies Azes, the colleague of Spalirises, with Azes II, and makes him the son of Spalirises. On page 572, however, the suggestion is found that Azes II was the son and successor of Azilises. It is difficult to see how the two views can be reconciled. For an inscription of Azes see *Corpus*, II. i. 17 (Shahdān Inscription of Sivarakshita). The name of Aja or Aya (Azes) has also been recognised by certain scholars in the Kalawān Inscription of the year 134 and in the Taxila silver scroll record of the year 136. The absence of any honorific title before the name makes it difficult to say whether it refers to a king, and, if it does refer to a king, whether the ruler in question was Azes I Or Azes II. Moreover, if Aja or Aya is a royal name, then it would seem, from the analogy of other *early* Indian epigraphs, that the years 134 and 136 actually belonged to his reign; not years of an era which he *founded* but of an era which he *used*. The absence of any honorific title has, however, led some writers to suggest that Aja-Aya was the *founder* of the reckoning mentioned in the epigraphs, and not the *reigning* sovereign in the years 134 and 136. The identity of the reckoning with the era of 58 B.C. cannot be regarded as certain, though the theory has many advocates. Another thorny problem is the relation between this reckoning and the reckoning or reckonings used by Moga and Gondophernes. For the Kalawān Inscription see *Ep. Ind.* XXI. 251 ff.; *IHQ*, 1932. 825; 1933. 141; *India in 1932-33*, p. 182.

² Cf. Whitehead, p. 178; Marshall, *Taxila*, p. 16.

³ Coins of Azilises are imitated by Mahādeva Dharaghoṣha Audumbara (*CHI*, 529). Along with certain caskets discovered in Taxila (*ASI. AR*, 1934-35, pp. 29, 30) was a silver coin of the *diokouri* type of Azilises and a Roman coin issued by Augustus. The deposit was probably made early in the first century A.D. We have here new data for settling the chronology of the

distinguished as Azes I and **Azes II**. Whitehead, however, observes that the silver coins of Azilises are better executed and earlier in style than those of Azes. The best *didrachms* of Azes compare unfavourably with the fine silver coins of Azilises with Zeus obverse and Dioskouroi reverse, and with other rare silver types of Azilises. If Azilises preceded Azes, then following Dr. Smith we must have Azilises I and Azilises II, instead of Azes I and Azes II. In conclusion Whitehead says that the differences in type and style between the abundant issues of Azes can be adequately explained by reasons of locality alone, operating through a long reign.¹ Marshall, however, points out that the stratification of coins at Taxila clearly proves the correctness of Smith's theory, according to which Azes I was succeeded by Azilises, and Azilises by Azes II.²

A notable discovery has unearthed the unique *gold* coin of a king named **Athama**. Whitehead has no hesitation in recognising him as a member of the dynasty of Azes and Azilises. His date is, however, uncertain.

Unlike most of the Indo-Greek princes,³ the Śaka kings style themselves on their coins *Basileus Basileon*,

Maues—Azes group of kings. It may be remembered that Kadphises I copied the bust of Augustus or one of his immediate successors on his coins. Azilises should not be far removed in date from the Julian Emperors or from the period of Kushan invasion.

¹ Inferior workmanship according to some, is a sign of remoteness (from Gandhāra?) rather than of late date (*cf.* CHI, 569f.). G. Hoffmann and Sten Konow not only reject the duplication of Azes, but suggest the identification of Azes with Azilises. According to Marshall Azilises ruled north-westwards as far as Kāpidi (JRAS, 1947, 25 ff.).

² The coins which Smith assigns to Azes II are found generally nearer the surface than those of Azes I (JRAS., 1914, 979). For Konow's view, see *Ep. Ind.*, 1926, 274 and *Corpus*, II. i. xxxix-xi. The name 'Azes' is found in association with several rulers of various dates, while that of Azilises is found only with one (*viz.*, Azes). This possibly points to the plurality of the kings named Azes.

³ With the exception perhaps of Eukratides one of whose coins bears

corresponding to the *Prākṛit* on the reverse *Mahārājasa* *lājarājasa*. They also appropriate the epithet *Mahatasa*, corresponding to the Greek *Megalos*, which we find on the coins of Greek kings. The title *Rājarāja*—king of kings—was not an empty boast. Moga had under him the viceroys (*satraps*) Liaka and Patika of Chuksha (Chach) in the Western Punjab. One of the kings named Azes had under him at least one subordinate ruler, e.g., the *Stratagos* Aspavarman. The title *Satrap* or *Kshatrapa* occurs in the Behistun Inscription of Persia in the form *Khshathrapāvan* which means 'protector of the kingdom.' "Strategos," a Greek word, means a general. It is obvious that the Scythians continued in North-Western India the Perso-Hellenic system of government by *Satraps* and military governors. Coins and Inscriptions prove the existence of several other Satrapal families besides those mentioned above.

The North Indian *Kshatrapas* or *Satraps* may be divided into three main groups, viz. :—

1. The *Satraps* of *Kāpiśi*, *Puspapura* and *Abhisāra-prastha*,
2. The *Satraps* of the Western *Pañjāb*, and
3. The *Satraps* of *Mathurā*.

A *Mañikiālā* inscription affords the bare mention of a *Satrap* of *Kāpiśi*, who was the son of the *Satrap* *Grauvahryaka*.² A *Kābul Museum Stone Inscription* of the year 83³ discloses the name of a *Satrap* of *Puspapura*

the legend *Maharajasa rajatirajasa Evukratidasa* (*Corpus*, II. i. xxix n.), and of a few other rulers including *Harmalos* (*Whitehead*, p. 85).

¹ Cf. *Ksha-pāvan* of the *Rig-veda* (*Vedic Index*, I. 208). *Rāshṭra-pāla* of the *Arthashastra* and *Goptri* or *Deda-goptri* of the *Mālavikāgnimitram* and the Gupta inscriptions.

² *Bapsco*, *Andhra Coins*, ci; *Ancient India*, 141; *JASB.*, 1924, 14, *Corpus*, II. i. 180-1.

³ *Acta Orientalia*, xvi, Pars iii, 1937, pp. 234 B.

named Tiravharṇa. 'Puspapura', the city of flowers, may have reference to Pushkarāvati (lotus-city). The name of Śivasena, 'the *Kshatrapa* in the town of Abhisāraprastha' occurs in the legend of a copper seal ring found in the Pañjāb.¹ The territory of the three Satraps may have corresponded to Yona, Gandhāra and Kamboja of Aśokan epigraphs.

The **Pañjāb Satraps** belonged to three families, viz.—

(a) The **Kusulua** or **Kusuluka Group**.—It consisted of Liaka and his son Patika, possibly of the Chhabarata or Kshabarāta family, who apparently governed the district of Chuksha.² According to Fleet there were two Patikas.³ But in the opinion of Marshall there was only one viceroy of the name of Patika.⁴ The Satrapal line of Kusuluka was intimately connected with the Satraps of Mathurā.⁵ The coins of Liaka Kusuluka show the transition of the district to which they belonged, i.e., a part of Eastern Gandhāra, from the rule of the Greek house of Eukratides to the Śakas.⁶ We learn from the Taxila, or the so-called Sirsukh, plate, dated in the year 78, that Liaka was a Satrap of the great king Moga and that Patika, his son, was a great gift-lord (*mahādānapati*).⁷

(b) **Manigul** and his son **Zeionises** or **Jihonika**.—Numismatists consider them to be Satraps of Pushkalāvati during the reign of Azes II. But the Taxila Silver

¹ *Corpus*, II. i. 103.

² *Bühler, Ep. Ind.*, IV, p. 51; Konow, *Corpus*, II. i. 25-29. Chuksha, according to Stein, is the present Chach in the north of the District of Attock. See also *AGI*, 63, 126.

³ *JRAS.*, 1907, p. 1035. The existence of at least two Liakas is, however, proved by the Taxila plate and the Zeda inscription (*Corpus*, II. i. 146). A Liaka appears also to be mentioned in the Mānsehra inscription of the year 68. He may have been identical with the father of Patika, *Ep. Ind.*, XXI, 257.

⁴ *JRAS.*, 1914, pp. 979 ff.

⁵ Cf. Inscription G on the Mathurā Lion Capital.

⁶ Rapson's *Ancient India*, p. 151.

⁷ *Ep. Ind.*, XXI, 257; *JRAS.*, 1932, 953a.

Vase Inscription of the year 191 discovered by Marshall in 1927¹ shows that Jihonika was a *Kshatrapa* in Cukhsha near Taxila in the year 191 of an era of Śaka (or Parthian ?) institution whose exact epoch is not known.² The successor of Zeionises was apparently Kuyula Kara.³

(c) **The House of Indravarman**⁴.—It consisted of Indravarman, his son Aspavarman, and Aspa's nephew Sasa(s) or Sasa(n). Aspavarman acted as governor of both Azes II and Gondophernes, while Sasa(s) served under Gondophernes and Pakores.

The Satraps of Mathurā

The earliest of this line of princes were once belived to be the rulers Hagāna and Hagāmasha. They were supposed to be succeeded by Rājuvula, who may have governed Śākala at an earlier stage. According to Allan⁵ he established himself in Mathurā late in life. The genealogical table of the house of Rājuvula or Rājula as arranged by Sten Konow⁶ is given below in a foot-note.

Rājuvula or **Rājula** is known from inscriptions as well as coins. An inscription in *Brāhmī* characters at

¹ *JRAS.*, 1928, January, 137 f. *Corpus*, II. i. 51 f.


² *Ep. Ind.*, XXI. 255f.

³ *CHI*, 582n, 588.

⁴ Indravarman has been identified by some scholars with Itravarma, son of Vijayamitra, who is known from certain coins. Vijayamitra is further regarded as identical with, or a successor of, Vijayamitra, a feudatory of Minedra (Menander). The importance of these identifications, in determining the chronological relation of the Indo-Greeks and the Śakas, is obvious, (Majumdar, *Ep. Ind.* xxiv, 1f; Sircar, *Select Inscriptions*, 102 ff; *Ep. Ind.* xxvi, 321 Mookerji, *IC*, XIV, 4, 1948, 205 D).

⁵ *CIC.*, AI. CNV.

⁶ *Corpus* II. i. 47.



Mora near Mathurā calls him a *Mahākshatrapa* or Great Satrap (viceroy). But the Greek legend on some of his coins describes him as "king of kings, the Saviour" showing that he probably declared his independence.

Rājuvula was apparently succeeded by his son Śuḍasa, Sonidāsa or **Śoḍāsa**. Inscription B on the Mathurā Lion Capital mentions him as a *Kshatrava* (Satrap) and as the son of the *Mahākshatrava* Rajula (Rājuvula). But later inscriptions at Mathurā written in *Brāhmī* characters call him a *Mahākshatrapa*. One of these inscriptions gives a date for him in the year 72¹ of an unspecified era. It is clear that during his father's lifetime he was only a *Satrap*. But on his father's death some time before the year 72, he became a Great Satrap. Sten Konow adduces grounds for believing that Śoḍāsa dated his inscription in the so-called *Vikrama* era.² Consequently the year 72, in his opinion, possibly corresponds to A. D. 15.

Dr. R. C. Majumdar refers the dates of the Northern Satraps (of Taxila and Mathurā) to the *Śaka* era, and places them in the middle of the second century A. D. But Ptolemy, who flourished about that time, places neither Taxila nor Mathurā within Indo-Scythia, *i.e.*, the *Śaka* dominion. This shows that neither Taxila nor Mathurā was a *Śaka* possession in the second century A. D. The principal Indo-Scythian possessions in Ptolemy's time were Patalene (the Indus Delta), Abiria (the Ābhira country in Western India), and Syrastrene (Kāthiāwād).³ This is exactly what we find in the Junāgaḍh

The genealogy, as reconstructed by Sten Konow, is not accepted by many scholars. An older view makes Kharaosta the son of a daughter of Rājuvula. For Rājuvula's connection with C. Pañjāb, see Allan, *CCAI*, 185. Cf. 438 *ante*.

¹ 42 according to Rapson. But 72 is preferred by most scholars.

Ep. Ind., Vol. XIV, pp. 139-141.

³ *Ind. Ant.*, 1884, p. 354.

inscription of the Śaka ruler Rudradāman I, who flourished in the middle of the second century A.D. In Ptolemy's time Taxila was included within the Arsa (*Sanskrit Uraśā*) territory,¹ and Mathurā belonged to the Kaspeiraioi.² Dr. Majumdar suggests that Ptolemy probably noticed the Śaka empire of Maues and his successors (which included Taxila, Mathurā and Ujjayinī) under the name of 'Kaspeiraioi.'³ But we should remember that far from including Taxila, Mathurā and Western India within one empire, Ptolemy sharply distinguishes the land of the Kaspeiraioi from Indo-Scythia which was the real Śaka domain in the middle of the second century A.D.⁴ Moreover, the territory of the Kaspeiraioi must have included the region below the sources of the Jhelum Chenab and the Ravi, *i.e.*, Kaśmīra and its neighbourhood;⁵ and there is no evidence that the dynasty of Maues ever ruled in Kaśmīra. It was only under the kings of Kanishka's dynasty that Kaśmīra and Mathurā formed parts of one and the same empire. As suggested by the Abbé Boyer the Kaspeiraioi of Ptolemy evidently referred to the Kushān empire.

We learn from the Mathurā Lion Capital Inscriptions that when Sudasa, *i.e.* Śoḍāsa, was ruling as a mere *Kshatrapa*, Kusuluka Patika was a *Mahākshatrapa*. As Śoḍāsa was a *Mahākshatrapa* in the year 72, he must have been a

¹ *Ind. Ant.*, 1884, p. 348.

² *Ind. Ant.*, 1884, p. 350.

³ *Journal of the Department of Letters*, University of Calcutta, Vol. I, p. 98 n.

⁴ Cf. Ptolemy, *Ind. Ant.*, 1884, p. 354, and the Junāgaḍh Inscription of the Śaka ruler Rudradāman.

⁵ Land of Kaśyapa? *Rājatarāṅgiṇī*, I, 27. IA. IV, 227. Stein accepts the identification of the territory of the Kaspeiraioi with Kaśmir, but rejects Wilson's assumption that Kaśmir was derived from Kaśyapa pura (*JASB.*, 1899, Extra 2, pp. 9-13). The evidence of Ptolemy seems to suggest that the city of Kaspeira stood close to Multan. Alberunī (I. 298) in a later age mentions Kaśyapapura as a name of Multan itself.

Kshatrapa before 72. Consequently Kusuluka Patika must have been reigning as a *Mahākshatrapa* contemporary of the *Kshatrapa* Śoḍāsa before the year 72. The Taxila plate of the year 78, however, does not style Patika as a *Kshatrapa* or *Mahākshatrapa*. It calls him *Mahādānapati* (great gift-lord) and gives the satrapal title to his father Liaka.¹ Dr. Fleet thinks² that we have to do with two different Patikas. Marshall and Sten Konow on the other hand, hold the view that the *Mahādānapati* Patika, who issued the Taxila plate, is identical with the *Mahākshatrapa* Kusuluka Patika of the Mathurā Lion Capital, but the era in which the inscription of Sam 72 is dated, is not the same as in the Taxila plate of Sam 78. In other words while Fleet duplicates kings, Marshall and Sten Konow duplicate eras. It is difficult to come to any final decision from the scanty data at our disposal. Fleet's theory is not improbable in view of the fact that we have evidence regarding the existence of at least two Liakas. But the duplication of kings is not absolutely necessary as the designation '*mahādānapati*' given to Patika in the Taxila plate does not preclude the possibility of his having been a *Mahākshatrapa* as well a few years back. We should remember in this connection that there are instances among the Western Kshatrapas of Chashtana's line, of *Mahākshatrapas* being reduced to a humbler rank³ while other members of the family held the higher office,⁴ and of a *Kshatrapa* (Jayadāman) being mentioned without the satrapal title.⁵ It is, therefore, not altogether improbable that the inscription of Sam 72 and

¹ Sten Konow, *Corpus*, Vol. II, Pt. I, 28; *Ep. Ind.* XIX, 257.

² *JRAS.*, 1913, 1001 n.

³ Cf. Majumdar, *The Date of Kanishka*, *Ind. Ant.*, 1917.

⁴ Rapson, *Coins of the Andhra Dynasty*, etc., cxxiv f.

⁵ Andhau Inscriptions.

that of *Sam* 78 are dated in the same era, and yet the two Patikas are identical.¹ If Sten Konow and Sir John Marshall are right in reading the name of Aja-Aya (Azes) in the Kalawān Copper-plate Inscription of the year 134 and the Taxila Inscription of 136, we have additional instances of a ruler of this age being mentioned without any title indicative of his rank.

Kharaosta was, according to S. Konow, the father-in-law, and according to Fleet, a grandson (daughter's son), of Rājuvula and consequently a nephew of Śoḍāsa.² The inscriptions A and E on the Mathurā Lion Capital mention him as the *Yuvaraya* Kharaosta. Sten Konow thinks³ that he was the inheritor to the position as "king of kings" after Moga. His known coins are of two types, presenting legends in Greek characters on the obverse and in *Kharoshthī* on the reverse. The *Kharoshthī* legend runs thus: *Kshatrapasa pra Kharaostasa Arṭasa putrasa*. 'Pra' according to Sten Konow, may be a reflex of *Prachakshasa*.⁴

The coins of the family of Rājuvula are imitated from those of the Stratos and also of a line of Hindu princes who ruled at Mathurā. This shows that in the Jumna valley Scythian rule superseded that of both Greek and Hindu princes.

¹ The *Rājatarānginī* furnishes an instance of a son being replaced by his father as king (cf. the case of Pārtha), and of a king abdicating in favour of his son and again resuming control over the kingdom; cf. the case of Kalasa who continued to be a co-ruler after the resumption of control by his father, and that of Rājā Mānsingh of Jodhpur (1804-43). The cases of Vijayāditya VII (*Eastern Chalukya*, D. C. Ganguli, p. 104) and of Zāfar Khān of Gujarāt may also be cited in this connection (*Camb. Hist. Ind.*, III, 295).

² JRAS, 1913, 919, 1009.

³ *Corpus*, 36.

⁴ *Corpus*, xxxv. 'prachakshasa' (=epiphanous, "of the gloriously manifest one"), occurs on coins of Strato I and Polyxanos. It is, however, possible that the Sanskrit equivalent of the name of the Satrap is *prakhara-ojas*, "of burning effulgence."

A fragmentary inscription found by Vogel on the site of Gaṇeśhrā near Mathurā revealed the name of Satrap of the Kshaharāta family called Ghaṭāka.¹

The Nationality of the Northern Satraps.

Cunningham held that the inscription P on the Mathurā Lion Capital—*Sarcasa Sakastanasa puyae*—gave decisive proof that Rājuvula or Rājula, Śoḍāsa and other connected Satraps were of Śaka nationality. Dr. Thomas shows, however, that the Satraps of Northern India were the representatives of a mixed Parthian and Śaka domination. This is strongly supported *a priori* by the fact that Patika of Taxila, who bears himself a Persian name, mentions as his overlord the great king Moga whose name is Śaka. The inscriptions on the Lion Capital exhibit a mixture of Persian and Śaka nomenclature.² Attention may, however, be called here to the fact that in the *Harivaṃśa* there is a passage³ which characterises the Pahlavas or Parthians as "*śmaśrudhāriṇaḥ*" (bearded).⁴ Judged by this test, kings of the family of Rājuvula and Nahapāna, who are not unoften taken to be Parthians, could not have belonged to that nationality as their portraits found on coins⁵ show no traces of beards and whiskers. They were, therefore, almost certainly Śakas.

¹ JRAS., 1912, p. 121.

² *Ep. Ind.*, Vol. IX, pp. 138 ff.; JRAS., 1906, 215 f. For Sten Konow's views see *Corpus*, II. I. xxxvii.

³ I. 14, 17.

⁴ The passage is also found in the *Vāyu Purāṇa*, Ch. 68, 141.

⁵ JRAS., 1913, between pp. 630-631.

SECTION II. THE PAHLAVAS OR PARTHIANS ¹

Already in the time of Eukratides, Mithradates I, King of Parthia (c. 171-138/37 B.C.), had probably conquered portions of the Pañjab or Sind, and in the days of the Śaka Emperors of the family of Maues-Moga, princes of mixed Śaka-Pahlava origin ruled as Satraps in Northern India. But it is important to note that Isidore of Charax, possibly a younger contemporary of Augustus, who wrote not earlier than 26 B.C. (reign of Phraates IV and the revolt of Tiridates) and is quoted by Pliny, does not include the Kābul Valley, Sind or the Western Pañjab within the empire of the Parthians or Pahlavas. The easternmost provinces of the Parthian empire mentioned by that writer are Herat (Aria), Farah (the country of the Anauoi, a segment of Aria (*i.e.*, the Herat Province), the districts between the Lake Hamun and the Helmund (Drangiana and Sakasthāna), and Kandahār (Arachosia or "White India"). Towards the middle of the first century A.D., however, Śaka sovereignty in parts of Gandhāra must have been supplanted by that of the Parthians. In 43-44 A.D., when Apollonios of Tyana is reputed to have visited Taxila, the throne was occupied by Phraotes, evidently a Parthian.² He was however independent of Vardanes, the great King of Babylon and Parthia (c. 39-47/48 A.D.),³ and himself powerful enough to exercise

¹ The Parthians (Pārthava, Pahlava) were an Iranian people established on the borders of the district that is today Mazandarsān and Khurāsān. About 249/8 B.C. they revolted against the Seleukids under the command of Arsakes (Arsaces), a leader of Scythia (Pope and Ackerman, *A Survey of Persian Art*, p. 71).

² *Apratihata* (Gondopernes) according to Herzfeld and Tarn (*Greeks*, 341).

³ Debevoise, *A Political History of Parthia*, 270.

suzerain power over the "Satrap of the Indus." Christian writers refer to a king of India named Gundaphar or Gūdnaphar and his brother Gad who are said to have been converted by the Apostle St. Thomas and who, therefore, lived in the first century A.D.¹ We have no independent confirmation of the story of the biographer of Apollonios. But the "so-called" Takht-i-Bāhī record of the year 103 (of an unspecified era) shows that there was actually in the Peshāwar district a king named **Guduvhara (Gondophernes)**. The names of Gondophernes and, in the opinion of some scholars, of his brother Gad, are also found on coins.² According to Rapson the two brothers were associated as sub-kings under the suzerainty of Orthagnes (Verethragna). Sten Konow, however, identifies Orthagnes with Guduvhara himself, while Herzfeld suggests that he was the "unnamed son of Vardanes, mentioned by Tacitus, who claimed the throne against Volagases I about A.D. 55."³ Dr. Fleet referred the date of the Takht-i-Bahāī (Bāhī) inscription to the Mālava-Vikrama era, and so placed the record in A.D. 47.⁴ He remarked "there should be no hesitation about referring the year 103 to the established Vikrama era of B.C. 58; instead of having recourse, as in other cases too, to some otherwise unknown era beginning at about the same time. This places Gondophernes in A.D. 47 which suits exactly the Christian tradition

¹ The original Syrian text of the legend of St. Thomas belongs probably to the third century A.D. (JRAS., 1913, 634). Cf. *Ind. Ant.*, 3, 302.

² Whitehead, pp. 95, 155. Gondophernes = Vindapharna, "Winner of glory" (Whitehead, p. 146, Rapson and Allan). The king assumed the title of Devavrata. S. Konow, following Fleet, takes the word Guḍana on the coins to refer to the tribe of Gondophernes (*Corpus*, II, i, xlyi).

³ *Corpus*, xlv; *The Cambridge Shorter History of India*, 70.

⁴ JRAS., 1905, pp. 223-235; 1906, pp. 706-710; 1907, pp. 169-172; 1913-1940; 1915, pp. 909-1003. Cf. the views of Cunningham and Dowson (IA, 4, 307), the discovery of the Khalatse and the Taxila silver vase inscriptions, however

which makes him a contemporary of St. Thomas, the Apostle."

The power of Gondophernes did not probably in the beginning extend to the Gandhāra region. His rule seems to have been restricted at first to Southern Afghanistan.¹ He succeeded, however, in annexing the Peshāwar district before the twenty-sixth year of his reign. There is no epigraphic evidence that he conquered Eastern Gandhāra (Taxila) though he certainly wrested some provinces from the Azes family. The story of the supersession of the rule of Azes II by him in one of the Scythian provinces is told by the coins of Aspavarman. The latter at first acknowledged the suzerainty of Azes (II) but later on obeyed Gondophernes as his overlord. Evidence of the ousting of Śaka rule by the Parthians in the Lower Indus Valley is furnished by the author of the *Periplus* in whose time (about 60 to 80 A.D.) Minnagara, the metropolis of Scythia, i.e., the Śaka kingdom in the Lower Indus Valley, was subject to Parthian princes who were constantly driving each other out. If Sten Konow and Sir John Marshall are right in reading the name of Aja-Aya or Azes in the Kalawān Inscription of 134 and the Taxila Inscription of 136, then it is possible that Śaka rule survived in a part of Eastern Gandhāra,² while Peshāwar and the Lower Indus Valley passed into the hands of the Parthians. But

makes the theory of Fleet less plausible unless we believe in the existence of a plurality of Śaka-Pahlava eras. Dr. Jaysawal was inclined to place Gondophernes in 20 B.C. But this date is too early to suit the Christian tradition.

¹ JRAS, 1913, 1003, 1010.

² For Fleet's interpretation of "Sa 136 ayasa ashaḍasa masasa, etc.," see JRAS, 1914, 995 ff.; also *Calcutta Review*, 1922, December, 493-494. S. Konow thought at one time that *ayasa* stood for *ādyaśa* (=the first). He took the word as qualifying *ashaḍasa*. But he changed his views after the discovery of the Kalawān Inscription of 134. He now thinks that the addition *ayasa*, *ajasa* does not characterise the era as instituted by Azes, but simply as 'connected with Parthian rulers' (*Ep. Ind.*, xxi, 255 f.). He refers the dates 134, 136 to the era of 38 B.C.

the absence of an honorific title before the name of Aja-Aya and the fact that in the record of the year 136 we have reference to the establishment of relics of the Buddha in Takshaśilā "for the bestowal of health on the *Mahārāja Rājātirāja Devaputra* Khushapa," probably suggest that the years 134 and 136 belong, not to the *pravardhamāna-vijayarājya* (the increasing and victorious reign) of Azes, but to a period when his reign was a thing of the past (*atitarājya*), though the reckoning was still associated with his honoured name. The dating in the Jānibighā inscription (*Lakshmana-senasy = atitarājye* sam 83) possibly furnishes us with a parallel.¹

The Greek principality in the Upper Kābul Valley had apparently ceased to exist when Apollonios travelled in India. We learn from Justin that the Parthians gave the *coup de grace* to the rule of the Bactrian Greeks. Marshall says² that the Kābul valley became a bone of contention between the Parthians and the Kushāns. This is quite in accordance with the evidence of Philostratos who refers to the perpetual quarrel of the "barbarians" with the Parthian king of the Indian borderland in 43-44 A.D.

With Gondophernes were associated as subordinate rulers his nephew Abdagases (in S. Afghanistan), his generals Aspavarman and Sasa(s) or Sasa(n), and his governors Sapedana and Satavastra (probably of Taxila).

After the death of the great Parthian monarch his empire split up into smaller principalities. One of these (probably Sīstan) was ruled by Sanabares, another (probably embracing Kandahār and the Western Pañjāb) by Pakores, and others by princes whose coins Marshall recovered for the

¹ Raychandhuri, *Studies in Indian Antiquities*, pp. 165 f.

² *ASI*, AR, 1929-30, 56 ff.

first time at Taxila. Among them was Sasa(s) or Sasa(n) who acknowledged the nominal sway of Pakores. The internecine strife among these Parthian princelings is probably reflected in the following passage of the *Periplus* :—

"Before it (Barbaricum) there lies a small island and inland behind it is the metropolis of Scythia, Minnagara; it is subject to Parthian princes who are constantly driving each other out."

Epigraphic (and in some cases numismatic) evidence proves that the Pahlava or Parthian rule in Afghanistan, the Panjāb and Sind was supplanted by that of the Kushāna, Gushapa, Khushapa or **Kushān**¹ dynasty. We know that Gondophernes was ruling in Peshāwar in the year 103 (A.D. 47 according to Fleet, somewhat earlier according to others). But we learn from the Panjtār inscription that in the year 122 the sovereignty of the region had passed to a Gushapa or Kushān king.² In the year 136 the Kushān suzerainty had extended to Taxila. An inscription of that year mentions the interment of some relics of the Buddha in a chapel at Taxila "for bestowal of perfect health upon the *Mahārāja, rājātirāja devaputra* Khushapa." The Sui Vihār and Mahenjo Daro Kharoshthi Inscriptions prove the Kushān conquest of the Lower Indus Valley. The Chinese writer Pan-ku, who died in A.D. 92, refers to the Yueh-chi occupation of Kao-fou or Kābul. This shows that the race to which the Kushāns belonged took possession of Kābul before A. D. 92. It is, no doubt, asserted by a later writer that Kao-fou is a mistake for Tou-mi. But the mistake

¹ For a note on the dynastic nomenclature, see R. Schafer, *JAOS*, 67, 4 p. 296 ff.; cf. *AOS*, 65, 71 ff.

² We learn from Philostratos that already in the time of Apollonios (A.D. 43-44) the barbarians (Kushāns?) who lived on the border of the Parthian kingdom of Taxila were perpetually quarrelling with Phraotes and making raids into his territories (*The Life of Apollonius*, Loeb Classical Library, pp. 183 ff.).

in Kennedy's opinion would not have been possible, had the Yueh-chi not been in possession of Kao-fou in the time of Pan-ku.¹ The important thing to remember is that a Chinese writer of 92 A.D., thought Kao-fou to have been a Yueh-chi possession long before his time. If Sten Konow is to be believed, the Kushāns had established some sort of connection with the Indian borderland as early as the time of Gondopheres. In line 5 of the Takht-i-Bāhī inscription Sten Konow reads "*erjhuṇa Kapasa puyae*,"² "in honour of prince Kapa," i.e., Kujūla Kadphises, the Kushān king, who is said to have succeeded Hermaios in the Kābul valley. Kujūla Kadphises has been identified with the Kuei-shuang (Kushān) prince K'iu-tsiu-k'io who took possession of Kao-fou (Kābul), Po-ta and Ki-pin. It appears from numismatic evidence that this Kushān chief³ was possibly an ally of Hermaios with whom he appears to have issued joint coins.⁴ Kadphises seems also to have been at first on friendly terms with the Parthian rulers of Gandhāra. But the destruction of

¹ JRAS, 1912, pp. 676-678. Note also Pan-ku's reference to a man's head on the coins of Ki-pin (JRAS, 1912, p. 685 n.) which possibly suggests an acquaintance with the coinage of Kujūla Kaphsa (or Kasa?).

² *Ep. Ind.*, XIV, p. 294; XVIII (1926), p. 282. *Corpus*, II, i. 62. Some regard this "Kapa" as a phantom. It is interesting to recall in this connection a statement of Philostratos (*The life of Apollonius of Tyana*, Loeb Classical Library, p. 185) that in A.D. 43-44, the Parthian king of Taxila had enlisted the services of certain "barbarians" to patrol his country so that instead of invading his dominions they themselves kept off the "barbarians" that were on the other side of the frontier and were difficult people to deal with. Prince "Kapa" (if the reading and interpretation be correct) may have been at first one of these friendly barbarian chiefs. His date is indicated by his (?) imitation of a Roman emperor's head of a style not later than about A.D. 60 (JRAS, 1913, 913).

³ Or one of his ancestors? Cf. Tarn, *The Greeks*, pp. 329, 343.

⁴ Pedigree coins according to Tarn.

Hermaios' kingdom by the Parthians' probably supplied him with a *casus belli*. He made war on the latter and eventually destroyed their power in the north-west borderland of India.

¹ Before the Parthian conquest, Kāpiśi apparently had to obey, for a time, the rule of Maues and Spaliriesca (CHI, 590 I.). The Kushāns, the "barbarian" enemies of "Phraates", may have had a hand in the restoration of Greek rule before its final disappearance in the Kābul valley.

SECTION III. THE GREAT KUSHĀNS.

We are informed by the Chinese historians that the Kushāns (chiefs of the Kuei-shuang or Kouei-chouang principality) were a section of the Yueh-chi (Yüe-chi) race. The modern Chinese pronunciation of the name according to Kingsmill is said to be Yué-ti. M. Lévi and other French scholars write Yue-tchi or Yué-tchi.

We learn from Ssū-ma-ch'ien (the Chinese annalist, who recorded the story of the travels of Chang-k'ien, the famous envoy), that between B.C. 174 and 165 the Yueh-chi were dwelling between the Tscenn-hoang (Tun-huang) country and the K'i-lien mountains, or Tien-chan Range, south and east of Lake Issykul in Chinese 'Turkestan.' At that date the Yueh-chi were defeated and expelled from their country by the Hiung-nū who slew their king and made a drinking vessel out of his skull. The widow of the slain ruler succeeded to her husband's power. Under her guidance the Yueh-chi in the course of their westward migration attacked the Wu-sun whose king was killed.¹ After this exploit the Yueh-chi attacked the Śakas on the upper Ili and in the plains of the Jaxartes or the Syr Darya and compelled their king or 'lord' to seek refuge in Kipin (Kāpiśa-Lampāka-Gandhāra).²

Meantime the son of the slain Wu-sun king grew up to manhood and, with the assistance of the Hiung-nū drove the

¹ Smith says (EHI⁴, p. 265) that they occupied land in the Kansuh Province in North-Western China. See also CHI, 365; Halphen, *J. Am. Or. Soc.* 65, pp. 71 ff. For the Hiung-nū-Hun Problem, cf. Stein, *IA*, 1905, 73 f. 84.

² The main section of the Yueh-chi passed on westwards beyond Lake Issykul, the rest diverged to the South and settled on the frontier of Tibet. The latter came to be known as the "Little Yueh-chi". Eventually they established their capital at Purushapura in Gandhāra. Smith, EHI⁴, 264; S. Konow, *Corpus*, II. i. lxxvi.

³ A part of the Śaka hōrde apparently seized Ferghana (Ta Yunn) c. 128 B.C. (Tarn, *Greeks*, 278 n. 4, 279).

Yueh-chi further west into the Ta-hia territory washed by the Oxus. The Ta-hia, who were devoted to commerce, unskilled in war and wanting in cohesion, were easily reduced to a condition of vassalage by the Yueh-chi who established their capital or royal encampment to the north of the Oxus (Wei), in the territory now belonging to Bukharā (in ancient Sogdiana). The Yueh-chi capital was still in the same position when visited by Chang-kien in or about B.C. 128-26.¹

The adventures of Chang-k'ien as related by Ssū-ma-ch'ien in the *Sse-ke* or *Shi-k'i* (completed before B.C. 91) were retold in Pan-ku's *Ts'ien Han-shu* or *Annals of the First Han Dynasty* that dealt with the period B.C. 206—A.D. 9 or 24, and was completed by Pan-ku's sister after his death in A.D. 92, with three important additions, namely :—

1. That the kingdom of the Ta-Yueh-chi had for its capital the town of Kien-chi (Kien-she), to the north of the Oxus,² and Kipin lay on its southern frontier.

2. That the Yueh-chi were no longer nomads.

3. That the Yueh-chi kingdom had become divided into five principalities, viz., Hi (co)u-mi (possibly Wakhān³ between the Pamirs and the Hindukush), Chouangmi or Shuang-mi (Chitral, south of Wakhān and the Hindukush) Konei-chouang or Kuei-shuang, the Kushān principality, probably situated between Chitral and the Panjshir

¹ *JRAS*, 1903, pp. 19-20; 1912, pp. 668 ff.; *PAOS*, 1917, pp. 89 ff.; Whitehead, 171; *CHI*, 459, 566, 701; Tarn, *Greeks*, 84, 274 n, 277; S. Konow, *Corpus*, II, i. xxii-xxiii, liv, lxi.

² Cf. *Corpus*, II, i. liv.

³ A *Bakanapati*, apparently lord of Wakhān, figures in the inscription of *Mohārāja vājātirāja devaputra Kashānaputra Shāhi* Vamataksha(ma?) whose identity is uncertain. The title *devaputra* connects him with the Kanishka Group of Khān kings, and not the Kadphises Group. *ASI*, 1911-12, Pt. 1, 15; 1930-34, Pt. 2, 286.

country, Hit(h)um (Parwān on the Panjshir) and Kao-fou (Kābul).¹

We next obtain a glimpse of the Yueh-chi in Fan-Ye's *Hou Han-shu* or *Annals of the Later Han Dynasty* which cover the period between A.D. 25 and 220. Fan-Ye based his account on the report of Pan-young (cir. A.D. 125) and others.² He himself died in 445 A.D. The capital of the Yueh-chi was then probably the old Ta-hia (Bactrian) city of Lan-shi, variant Ch'in-shi³, to the north of the Oxus. Fan-Ye gives the following account of the Yueh-chi conquest :

"In old days the Yue-chi were vanquished by the Hiung-nū. They then went to Ta-hia and divided the kingdom among five *Hsi-h(e)ou* or *Yabgous*,⁴ viz., those of Hsiumi, Shuang-mi, Kuei-shuang, Hsitun and Tumi. More than hundred years after that, the *hsi-hou* or *Yabgou* (*Yavuga*) of Kuei-shuang (Kushān) named K'iu-tsiu-k'io attacked and annihilated the four other *hsi-hou* and made himself king or lord (*Wang*); he invaded Ngan-si (the Arsakid territory, i.e., *Parthia*) and took possession of the territory of Kao-fou (Kābul), overcame Po-ta⁵ and Ki-pin and became complete

¹ A later historian regards Kao-fou as a mistake for Tou-mi which, however, was probably not far from Kābul, *JRAS*, 1912, 669. For the proposed identifications see *Corpus*, II. i. lvi. Cf. *JRAS*, 1903, 21; 1912, 669. In *Ep. Ind.*, XXI, 258, S. Konow suggests the identification of Kuei-shuang with Gandhāra or the country immediately to its north.

² Cf. S. Konow, *Corpus*, liv: "It is accordingly the events of the period A.D. 25-125 which are narrated by Fan-Ye, though there are some additions referring to a somewhat later time in the case of countries which were near enough to remain in contact with China after the reign of emperor Ngan" (107-25). See also *Ep. Ind.*, XXI, 258.

³ Alexandria = Zariaspa or Bactria. (Tarn, *Greeks*, 115, 298). *JAOS*, 61 (1941), 242 n.

⁴ According to one view the five *hsi-hou* existed already in Ta-hia when the Yueh-chi invaded Bactria (*JAOS*, 65. 72 f.).

⁵ Perhaps identical with the country of Po-tai which, in the time of Sung-yun, sent two young lions to the King of Gandhāra as present (Beal, *Records of the Western World*, Vol. I, ci). S. Konow (*Ep. Ind.*, XVIII) identified P'u-ta with Ghazni, but later on (*Ep. Ind.*, XXI, 258) suggested its identification with Butkhak, ten miles east of Kābul.

master of these kingdoms. K'iu-tsiu-k'io died at the age of more than eighty. His son Yen-kao-tchen succeeded him as king. In his turn he conquered T'ien-tchou (lit. 'India,' on the banks of a great river, apparently the kingdom of Taxila referred to by Philostratos), and established there a chief for governing it. From this time the Yue-chi became extremely powerful. All the other countries designated them Kushān after their king, but the Han retained the old name, and called them Ta-Yue-chi."

"K'iu-tsiu-k'io" has been identified with **Kujula¹ Kadphises (I),²** or Kozola Kadaphes, the first Kushān king who struck coins to the south of the Hindukush. Numismatic evidence suggests that he was the colleague or ally,³ and afterwards the successor, of Hermaios, the last Greek prince of the Kābul valley. The former view that Kadphises conquered Hermaios is, in the opinion of Marshall, wrong. Sten Konow finds his name mentioned in the Takht-i-Bāhī inscription of the year 103 belonging to the reign of Gondophernes.⁴ The inscription probably belongs to a period when the Kushān and Parthian rulers were on friendly terms. But the Parthian attack on the kingdom of Hermaios apparently led to a rupture which ended in war. The result was that the Parthians were ousted by Kadphises I.

¹ Cf. Kusuluka. The expression probably means 'strong' or beautiful (S. Konow, *Corpus*, 1). According to Burrow (*The Language of the Kharoshthi Documents*, 82, 87) Kujula=Gusura=Vazir. Dr. Thomas (possibly) thinks that the word Kujula has the sense of 'Saviour'.

² Pahlavi *Kad*=chief+*pises* or *pēs*=form, shape, *JRAS*, 1913, 632 n.

³ Fleet and Thomas, *JRAS*, 1913, 967, 1034; in the opinion of some scholars Hermaios was dead at the time of the Kushān conquest. Coins bearing his name continued, according to this view, to be struck long after he had passed away. Tarn regards the Hermaios-Kadphises coins as "pedigree coins". His view is not accepted by Bachhofer (*JAOS*, 61, 240 n). Supporters of the 'alliance' theory may point to the gold dollars circulating in Chungking engraved with relief portraits of Marshal Chiang Kaishek and President Roosevelt of the United States (*A. B. Patrika*, 29-3-1945).

⁴ The interpretation of S. Konow is not accepted by Professor Rapson, *JRAS*, 1930, p. 189.

Marshall identifies Kadphises I with the Kushān king of the Panjtar record (of the year 122) and the Taxila scroll of the year 136.¹ We should, however, remember that in the Taxila inscription of 136 the Kushān king is called *Devaputra*, a title which was characteristic of the Kanishka group and *not* of Kadphises I or II unless we identify Kadphises I with Kuyula Kara Kaphsa.² The monogram on the scroll is by no means characteristic only of coins of the Kadphises group, but it is also found, in Marshall's and S. Konow's opinion, on the coins of Zeionises and Kuyula Kara Kaphsa. If, however, S. Konow and Marshall are right in reading the name of Uvima Kavthisa in the Khalatse inscription of the year 184 or 187, and in identifying him with Vima Kadphises, the king of the Panjtar and Taxila records of 122 and 136 may have been a predecessor of Wema (Vima), and should preferably be identified with Kadphises I. But the reading 'Uvima Kavthisa' and his identification with Kadphises II are by no means certain.

Kadphises I probably coined no gold but only copper. His coinage shows unmistakable influence of Rome.³ He

¹ *JRAS*, 1914, pp. 977-78; Rapson, *CHI*, 582, identifies the Kushān king of 136 with Vima (i.e., Kadphises II).

² Mentioned by R. D. Banerji, *Prāchīna Mudrā*, p. 85. I cannot vouch for the correctness of the reading.

³ In one class of his copper coins appears a Roman head which was palpably imitated from that of Augustus (B.C. 27-A.D. 14), Tiberius (A.D. 14-37), or Claudius (A.D. 41-54). *JRAS*, 1912, 679; 1913, 912; Smith, *Catalogue*, 66; *Camb. Short Hist.* 74. Rome and its people, Romakas, first appear in the *Mahābhārata* (II, 51, 17) and occur not unfrequently in later literature. Diplomatic relations between Rome and India were established as early as the time of Augustus who received an embassy from king 'Pandion' (*JRAS*, 1860, 309 ff. *Camb. Hist. Ind.* I, 597.) about B.C. 27-20. An Indian embassy was also received by Trajan (A.D. 98-117) shortly after A.D. 99. Strabo, Pliny and the *Periplus* refer to a brisk trade between India and the Roman Empire in the first century A.D. See *JRAS*, 1904, 591; *IA*, 5, 281; 1923, 50. Pliny deplores the drain of specie (*JRAS*, 1912, 986; 1913, 644-1031).

copied the issues of Augustus or those of his immediate successors preferably Claudius (A. D. 41-54),¹ and used the titles *Yavuga* (chief), *Mahārāja*, *Rājātirāja* (the great king, the king of kings) and "*Sachadhrama thita*", "Steadfast in the True Faith" (of the Buddha?).²

"K'in-tsiu-k'io," or Kadphises I, was succeeded by his son **Yen-kao-tchen**, the Vima, Wima or Wema Kadphises of the coins, who is usually designated as **Kadphises II**. We have already seen that he conquered Tien-tchou or the Indian interior, probably Taxila, and set up a chief who governed in the name of the Yueh-Chi. According to Sten Konow³ and Smith⁴ it was Kadphises II who established the Śaka Era of A.D. 78. If this view be accepted then he was possibly the overlord of Nahapāna, and was the Kushān monarch who was defeated by the Chinese between A.D. 73 and 102 and compelled to pay tribute to the emperor Ho-ti (A.D. 89-105). But there is no direct evidence that Kadphises II established any era. No inscription or coin of this monarch contains any date which is referable to an *era* of his institution. On the contrary we have evidence that Kanishka did establish an era, that is to say, his method of dating was continued by his successors, and we have dates ranging probably from the year 1 to 99.⁵

The conquests of the Kadphises kings opened up the path of commerce between China and the Roman Empire and India. Roman gold began to pour into this country in payment for silk, spice and gems. Kadphises II began to issue gold coins.⁶ He had a bilingual gold and copper

¹ *The Cambridge Shorter History*, 74, 75.

² Smith, *Catalogue*, 67 n.; S. Konow, *Corpus*, II. i. lxiv f.; Whitehead, 181.

³ *Ep. Ind.*, XIV, p. 141.

⁴ *The Oxford History of India*, p. 128.

⁵ For criticism of the "Omitted hundreds theory," see *JRAS*, 1913, 380 f.

⁶ A gold coin of Wima or Vima (*NC*, 1934, 232), gives him the title *Basileus Basilewn Soter Megas* (Tarn, *Greeks*, 354 n 5). This throws welcome light on the problem of the identification of the nameless king Soter Megas.

coinage.¹ The obverse design gives us a new lifelike representation of the monarch. The reverse is confined to the worship of Śiva, which was gaining ground since the days of the *Śiva-Bhāgavatas* mentioned by Patañjali.² In the *Kharoshthī* inscription Kadphises II is called "the great king, the king of kings, lord of the whole world, the *Mahiśvara*, the defender."³

We learn from Yu-Houan, the author of the *Wei-liao*⁴ which was composed between A.D. 239-265 and covers the period of the Wei down to the reign of the emperor Ming (227-239),⁵ that the Yueh-chi power was flourishing in Kipin (Kāpiśa-Gandhāra), Ta-hia (Oxus valley), Kao-fou (Kābul) and Tien-tchou (India) as late as the second quarter of the third century A.D. But the early Chinese annalists are silent about the names of the successors of Yen-kao-tchen (Kadphises II). Chinese sources, however, refer to a king of the Ta-Yueh-chi named Po-tiao or Puā-d'ieu (possibly Vāsudeva) who sent an embassy to the Chinese emperor in the year 230.⁶ Inscriptions discovered in India have preserved the names with dates of the following great Kushān sovereigns besides the Kadphises group, viz., **Kanishka I**(1-23),⁷ Vāsishka (24-28),⁸ Huvishka

¹ A silver piece resembling the ordinary small copper type of Vima Kadphises is also known (Whitehead, *Indo-Greek Coins*, 174). Other silver coins of the monarch are apparently referred to by Marshall (*Guide to Taxila*, 1918, 81). A silver coin of Kanishka is also known (*ASI, AR*, 1925-26, pl. 1xf). Smith (*EHI*⁴, p. 270) and others make mention of silver coins of Huvishka.

² V. 2. 76; cf. Saiva, Pāṇini, IV. 1. 112.

³ As already stated Sten Konow finds the name of Vima (Uvima) Kavthian (Kadphises?) in the Khalatse (Ladakh) inscription of the year 187(?). *Corpus*, II. i. 81. The identity of the King in question is, however, uncertain.

⁴ *A History of the Wei Dynasty* (A.D. 220-264).

⁵ *Corpus*, II. i. lv.

⁶ *Corpus*, II. i. lxxvii.

⁷ See *JRAS*, 1913, 960; 1924, p. 400. "Three Mathurā Inscriptions and their bearing on the Kushān Dynasty" by Dayāram Sahnī; and *IHQ*, Vol. (II (1927), p. 853, "Further Kanishka Notes" by Sten Konow. *Ep. Ind.*, XXIV. 210.

⁸ If Vāsishka be identical with Vas Kshāga of a Sācchī epigraph, his reign

(28-60),¹ Kanishka II, son of Vā-jheshka (41), and Vāsudeva (67-98).² Huvishka, Vā-jheshka and Kanishka II are probably referred to by Kalhapa as Hushka, Jushka and Kanishka who apparently ruled conjointly. It will be seen that Kanishka II ruled in the year 41, a date which falls within the reign of Huvishka (28-60). Thus the account of Kalhapa is confirmed by epigraphic evidence.

In the chronological order generally accepted by numismatists, the Kanishka group succeeded the Kadphises group. But this view is not accepted by many scholars. Moreover, there is little agreement even among scholars who place the Kanishka group after the Kadphises kings. The more important theories of Kanishka's date are given below :

1. According to Dr. Fleet, Kanishka reigned *before* the Kadphises group, and was the founder of that reckoning, commencing B.C. 58, which afterwards came to be known as the Vikrama Samvat.³ This view (held at one time by Cunningham and Dowson, and maintained by

(as sub-king) commenced not later than the year 22 as we learn from an inscription of that year on the pedestal of an image of the Buddha (*Proc. of the Seventh Session of the I. H. Congress*, Madras, p. 135).

¹ See *Ep. Ind.*, XXI, 55 ff.—Mathurā Brāhmi Inscription of the Year 28. Cf. *Ep. Ind.*, xxiii, 35—Hidda Inscription of 28.

² *Hyd. Hist. Cong.*, 164.

³ For discussions about the origin of the so-called Vikrama era see *JRAS*, 1913, pp. 637, 994 ff.; Kielhorn in *Ind. Ant.*, ix, (1891), 124 ff.; 397 ff.; *Bhand. Com. Vol.*, pp. 187 ff. *CHI*, pp. 168, 638, 671; *ZDMG*, 1922, pp. 250 ff. *Ep. Ind.* xxiii, 48 ff.; xvi, 119 ff.; Kielhorn (and now Altekar) adduce evidence which seems to show that the early use of the era, as may be inferred from records with dates that may be recognised to refer to this reckoning, was mainly confined to Southern and Eastern Rājputāna, Central India and the Upper Ganges Valley. The name of the era found in the earliest inscriptions recalls designations like that of king KRITA of Penzer, *The Ocean of Story*, III, 19. Kṛitya rulers are mentioned by Fleet, *JRAS*, 1913, 998n. Kṛita may also have reference to the inauguration of a Golden Age after a period of toil and moral. From the fifth to the ninth century the reckoning was believed to be used

Franke) was accepted by Kennedy, but was ably controverted by Dr. Thomas, and can no longer be upheld after the discoveries of Marshall.¹ Inscriptions, coins as well as the testimony of Hiuen Tsang clearly prove that Kanishka's dominions included Gandhāra, but we have already seen that according to Chinese evidence Yin-mo-fu, and not the Kushāns, ruled Kipin (Kāpiśa-Gandhāra) in the second half of the first century B.C. Allan thinks that "the gold coinage of Kanishka was suggested by the

especially by the princes and people of Malava. The connection of the name **Vikrama** with the era grew up gradually and was far from being generally adopted even in the ninth century A.D. The phraseology employed in the poems and inscriptions of the next centuries shows a gradual advance from the simple *Samrat* to *Vikrama Samrat*, *Srinripa Vikrama Samrat* and so on. The change in nomenclature was probably brought about by the princes and people of Gujara, whose hostility to the Mālavas is well known. The Śātavāhanas could not have founded this or any other era because they always used regnal years, and Indian literature distinguishes between *Vikrama* and *Śālivahana*. As to the claims of Azes, see *Calcutta Review*, 1922, December, pp. 493-494. Fleet points out (*JRAS*, 1914, 995 ff.) that even when the name of a real king stands before the statement of the years, so that the translation would be "in the year of such and such a king" he is not necessarily to be regarded as the actual founder of that particular reckoning. The nomenclature of an era, current in a comparatively late period, more than a century after its commencement, is no proof of origin. Therefore, the use of the terms *Ayasa* or *Ajasa* in connection with the dates 184 and 186 of the Kalawan and Taxila inscriptions, does not prove that Azes was the founder of the particular reckoning used. His name may have been connected with the reckoning by later generations in the same way as the name of the Valabhi family came to be associated with the Gupta era, that of Śātavāhana with the Saka era, and that of Vikrama with the "Kṛita". Mālava reckoning itself which commenced in 58 B.C. Regarding the claims of Vikrama see Bhand. *Com. Vol. and Ind. Ant.*, cited above. The *Purāṇas* while mentioning Gārdabhilla are silent about Vikramāditya. Jaina tradition places Vikramāditya after Nahavāhana, or Nahapāna. Regarding the contention of Fleet that the Vikrama era is a northern reckoning attention may be invited to the observations of Kielhorn and to a note on *Chola-Pāṇḍya Institutions* contributed by Professor C. S. Srinivasachari to *The Young Men of India*, July, 1926. The Professor points out that the era was used in Madura in the 5th century A.D. Kielhorn proves conclusively that the area where the era of 58 B.C. was used in the earliest times did not include the extreme north-west of India.

¹ Thomas, *JRAS*, 1913; Marshall, *JRAS*, 1914.

Roman *solidus*" and that the Kushān monarch can hardly be placed before Titus (79-81 A.D.) and Trajan (98-117 A.D.).¹

2. According to Marshall, Sten Konow, Smith and several other scholars Kanishka's rule began about 125 or 144 A.D.,² and ended in the second half of the second century A.D.³ Now, we learn from the Sui Vihār inscription that Kanishka's dominions included a portion at least of the Lower Indus Valley. Again we learn from the Junāgaḍh inscription of Rudradāman that the *Mahākshatrapa*'s conquests extended to Sindhu and Sanvīra (which included Multān according to the Purāṇas and Alberuni) and even to the land of the Yaudheyas in the direction of the Sutlej. Rudradāman certainly flourished from A.D. 130 to A.D. 150. He did not owe his position as *Mahākshatrapa* to anybody else (*svayam adhigata Mahākshatrapa nāma*).⁴ If Kanishka reigned in the middle of the second century A.D., how are we to reconcile his mastery over the Sui Vihār region in the Lower Indus Valley with the

¹ Camb. Short History, p. 77.

² Recently Ghirshman suggested the period A.D. 144-72 for Kanishka (Begram, *Recherches Archéologiques et Historiques sur les Kouchans*). The argument that India was still in A.D. 125 governed by a Viceroy (and therefore, not by Kanishka or Huvishka) is effectively disposed of by Thomas in *JRAS*, 1913, 1924. He points out that the historian of the Later Han is obviously referring to the conditions at the time of the invasion of Wima Kadphises, and not to the state of things in A.D. 125.

³ Dr. Sten Konow's views are difficult to ascertain. In the *Indian Studies in honour of C. R. Lanman* (Harvard University Press), p. 65, he mentions A.D. 134 as the initial point of the Kanishka reckoning which he and Dr. Van Wijk "have tried to establish" (cf. *Acta Orientalia*, III, 54 ff.). But in *IHQ*, III (1927), p. 351, he, along with Dr. Van Wijk, shows a predilection for A.D. 128-29 (cf. *Corpus*, lxxvii; *Acta Orientalia*, V, 168 ff.). Professor Rapson (in *JRAS*, 1930, 196 ff.) points out the conjectural and inconclusive character of the two Doctors' calculations. "The year 79," says he, "seems to be out of the running and a dark horse, the year 128-9, is the favourite."

⁴ *Ep. Ind.*, VIII, 44.

contemporary sovereignty of Rudradāman?¹ Again Kanishka's dates 1-23, Vāsishka's dates 24-28, Huvishka's dates 28-60, and Vāsudeva's dates 67-98, suggest a continuous reckoning. In other words, Kanishka was the originator of an era. But we know of no era ever current in, or known to, North-West India, which commenced in the second century A.D.

3. Dr. R. C. Majumdar thought that the era founded by Kanishka was the Traikutaka-Kalachuri-Chedi era of 248 A.D.² Prof. Jouveau-Dubreuil points out that this is not possible.³ "In fact, the reign of Vāsudeva, the last of the Kushāns, came to an end 100 years after the beginning of the reign of Kanishka. Numerous inscriptions prove that Vāsudeva reigned at Mathurā. It is certain that this country, over which extended the empire of Vāsudeva, was occupied about 350 A.D. by the Yaudheyas and the Nāgas and it is probable that they reigned in this place nearly one century before they were subjugated by Samudragupta. The capitals of the Nāgas were Mathurā, Kāntipura and Padmāvati." The Kushān (?) realm in the Indian borderland was, in A.D. 360, ruled by Grumbates.⁴ The theory of Dr. Majumdar cannot, moreover, be reconciled with the Tibetan tradition which makes Kanishka a contemporary of king Vijaya-kīrti of Khotan,⁵ and the Indian tradition which makes Huvishka a contemporary of Nāgārjuna, and hence of a king of the Imperial Śātavāhana line, who can hardly be placed later than the second century A.D., as he is described as 'lord of the three seas' and sovereign of

¹ See *IHQ*, March, 1930, 149.

² For this era see *JRAS*, 1905, pp. 566-68.

³ *Ancient History of the Deccan*, p. 31.

⁴ *EHIA*, p. 290. The Chionitai identified by Cunningham with Kushans.

⁵ *Ep. Ind.*, XIV, p. 142.

(South) Kośala (in the Upper Deccan).¹ Lastly, the catalogues of the Chinese *Tripitaka* state that An-Shih-Kāo (148-170 A.D.) translated the *Mārgabhūmi Sūtra* of Saṅgharaksha who was the chaplain of Kanishka.² This shows conclusively that Kanishka flourished before 170 A.D.³ The arguments against the theory of Dr. Majumdar are equally applicable to the surmise of Sir R. G. Bhandarkar who placed Kanishka's accession in A.D. 278.

4. According to Fergusson, Oldenberg, Thomas, Banerji, Rapson, J. E. Van Lohuizen-De Leeuw, Bachhofer and many other scholars Kanishka was the founder of that reckoning commencing A.D. 78, which came to be known as the *Śaka* era.⁴ This view is not accepted by Prof. Jouveau-Dubreuil on the following grounds:—

¹ *Rājatarāṅginī*, I. 173; *Harsha-charita* (Cowell), p. 252; Watters, *Yuan-Chuang*, II, p. 200. The epithet *trisamudrādhipati* which the *Harsha-charita* (Book VIII) applies to the Śātavāhana friend of Nāgārjuna cannot fail to remind one of Gautamīputra Śātakarṣi 'whose chargers drank the water of the three oceans' (*trisamudratayapitarāhana*), or one of his immediate successors.

² Eliot, *Hinduism and Buddhism*, II, p. 64n. Bunyiu Nanjio's *Catalogue*, App. II, 4.

³ According to the theory of Dr. Majumdar, Vāsudeva I ruled from (249+74) 323 to (249+98) 347 A.D. But Chinese evidence places a Po-t'iao (Vāsudeva?) in 230 A.D. The Khalatse Ins. also presents difficulties.

⁴ For the origin of the *Śaka* era see Fleet, *GII*, preface 56; *JRAS*, 1913, pp. 635, 650, 987 ff.; Dubreuil, *AHD*, 26; Rapson *Āndhra Coins*, p. cv; S. Konow, *Corpus*, II. i. xvi f. Nahapāna, who was not even a *Mahākshatrapa* in the years 42-45, and who never became a paramount sovereign, could not possibly have been the founder of the era. The theory which represents Nahapāna as the founder of the era used in his inscriptions (dated 42-46) is also contradicted by a Jaina tradition (relied on by Sten Konow, *Corpus*, II. i. xxxviii) which assigns to him (Nahavāhana) a period of only 40 years. Chashtana has no better claims and the evidence of the *Periplus* shows that he could not have ruled at Ujjain in 78 A.D. As to the theory that Kadphises II founded the reckoning in question, it may be pointed out that no inscription or coin of this monarch contains any date which is referable to an era of his institution. The only Scythian king who did establish an era in the sense that he used a regnal reckoning that was continued by his successors, is Kanishka. And the only reckoning that is attributed by Indian writers, since the days of the early Chalukyas, to a Scythian king is the *Śaka* era of 78 A.D.

(a) If we admit that Kujāla-Kadphises and Hermaios reigned about 50 A.D. and that Kanishka founded the Śaka era in 78 A.D. we have scarcely 28 years for the duration of the end of the reign of Kadphises I and the whole of the reign of Kadphises II.

(But the date, A.D. 50, for Kadphises I is uncertain. Even if we accept it as correct, the period of 28 years is not too short in view of the fact that Kadphises II succeeded an octogenerian. When Kadphises I died "at the age of more than eighty" his son must have been an old man. It is, therefore, improbable that "his reign was protracted.")

(b) Marshall, says Prof. G. Jouveau-Dubreuil, has discovered at Taxila in the Chir Stūpa a document dated 136 which, in the *Vikrama* era, corresponds to 79 A.D., and the king mentioned therein is probably Kadphises I, but certainly not Kanishka.

(Now, the epithet *Devaputra* applied to the Kushān king of the Taxila scroll of 136, is characteristic of the Kanishka group, and not of the Kadphises kings.¹ So

Regarding the objection that the Śaka era was foreign to the north it may be pointed out that the era of 58 B.C., was equally foreign to the extreme north-west of India. The assertion that the Śaka era was never used in the north-west simply begs the question. It assumes what it has got to prove, viz., that the reckoning used by the house of Kanishka does not refer to the Śaka era. The very name Śaka points to its foreign, and possibly north-western, origin, as the imperial Sakas resided in that region, and it is only the viceroys who dwelt in Mālwa Kāthiāwar and the Deccan. On the analogy of every famous Indian regnal reckoning it may be confidently asserted that the Śaka era, too, originated with a sovereign and not with a mere viceroy.

¹ I am glad to note that a somewhat similar suggestion is now made by Dr. Thomas in Dr. B. C. Law Volume, II, 312. It is, however, by no means clear why it is said that the possibility of the identification of *Devaputra* with Kanishka 'has been ignored'. The Kadphises kings meant here are Kujāla (Kadphises I), and Vima (Wema) and not Kuyula Kara Kaphsa whose identification with Kadphises I is a mere surmise. Kara or Kala probably means a Mahārājaputra, a prince (Burrow, *The Language of the Kharoshthi Documents*, 52). Even if Kuyula Kara be identical with Kujāla (cf. *Corpus*, II, i, lxxv) and the Kushān king of the Taxila inscription of 136, it may be pointed out that it is by no means certain that the date 136 refers to the *Vikrama* era.

the discovery need not shake the conviction of those that attribute to Kanishka the era of 78 A.D. The omission of the personal name of the Kushān monarch does not necessarily imply that the first Kushān is meant. In several inscriptions of the time of Kumāra Gupta and Budha Gupta, the king is referred to simply as *Gupta nripa*.)

(c) Professor Dubreuil says : " Sten Konow has shown that the Tibetan and Chinese documents tend to prove that Kanishka reigned in the second century."

(This Kanishka may have been Kanishka of the Ārā Inscription of the year 41 which, if referred to the Śaka era, would give a date in the second century A.D. Po-t'iao of Sten Konow,¹ the king of the Yueh-chi who sent an ambassador to China in A.D. 230, may have been one of the successors of Vāsudeva I. " Coins bearing the name of Vāsudeva continued to be struck long after he had passed away." ² Dr. Smith, Mr. R. D. Banerji and Dr. S. Konow himself clearly recognise the existence of more than one Vāsueva.) ³

(d) Sten Konow has also shown that the inscriptions of the Kanishka era and those of the Śaka era are not dated in the same fashion. (But the same scholar also shows that all the inscriptions of the Kanishka era are also not dated in the same fashion. In the *Kharoshthī* inscriptions, Kanishka and his successors recorded the dates in the same way as their Śaka-Pahlava predecessors, giving the name of the month and the day within the month. On the other hand, in their *Brāhmī* records Kanishka and his successors usually adopted the Ancient

¹ Vāsudeva? *Ep. Ind.*, XIV, p. 141. *Corpus*, II, i. lxxvii; cf. *Acta*, II, 133.

² *EHI*, 3rd ed., p. 272.

³ *Ibid*, pp. 272-78. *Corpus*, ii, I. lxxvii.

Indian way of dating.¹ Are we to conclude from this that the *Kharoshthi* dates of Kanishka's inscriptions are not to be referred to the same era to which the dates of the *Brāhmī* records are to be ascribed?—If Kanishka adopted two different ways of dating, we fail to understand why he could not have adopted a third method to suit the local conditions in Western India. Sten Konow himself points out that in the Śaka dates we have the name of the month as in the *Kharoshthi* records with addition of the *Paksha*. "The Śaka era which (the Western *Kshatrapas*) used was a direct imitation of the reckoning used by their consins in the north-west, the additional mentioning of the '*paksha*' being perhaps a concession to the custom in the part of the country where they ruled." It is not improbable that just as Kanishka in the borderland used the old Śaka-Pahlava method, and in Hindusthān Proper used the ancient² Indian way of dating prevalent there, so in Western India his officer added the '*paksha*' to suit the custom in that part of the country.)³

¹ *Ep. Ind.*, XIV, p. 141. For an exception see *ibid.*, XXI, 60.

² As to the statement of Fleet endorsed by S. Konow, *Corpus*, lxxvii, that the use of the Śaka era was foreign to Northern India attention may be invited to Kielhorn's *List of Ins. of Northern India*, Nos. 351, 352, 362, 364-365, 368, 379, etc. So far as North-West India is concerned there is as little positive proof of the early use of the *Vikrama* era as of the era of 78 A.D. The paucity of early records dated in the Śaka era in the valley of the Upper Ganges and its tributaries is possibly due to the fact that the era of 58 B.C. already held the field. Later eras of undoubtedly northern origin, like those of the Guptas and Harsha, have practically been forgotten, but the era of 58 B.C. is still in use. In Southern India the case is different. The use of regnal years in the records of the Mauryas (many of which are located in the south) and those of the Śātavāhanas, Chetas, and other early dynasties, proves beyond doubt that there was no early reckoning in use that could compete with the new era that was introduced by the Śaka satraps. The story of the foundation of the Chālukya *Vikrama* era suggests that the Śaka reckoning was at times deliberately sought to be discontinued because of its foreign association. This might have happened in the north as well as in the south.

According to Sten Konow Kanishka came from Khotan¹ and belonged to the Little Yüeh-chi. The theory presents many difficulties.² It is certain that his successors in 230 were still known as the Ta (Great?) Yüeh-chi. The family name according to Kumāralāta's *Kalpanāmaṇḍitikā* was Kiu-sha.³

Kanishka completed the Kushān conquest of Upper India and ruled over a wide realm which extended from Kāpiśa,⁴ Gandhāra and Kāśmīra to Benares. Traditions of his conflict with the rulers of Soked (Sāketa) and Pāṭaliputra in Eastern India are preserved by Tibetan and Chinese writers.⁵ Epigraphic records give us contemporary notices of him, with dates, not only from Peshāwar and possibly from Zeda (near Uṇḍ) in the Yuzufzai country, but also from Mānikiala near Rāwalpindi, from Sui Vihār about 16 miles south-west of Bahāwalpur (north of Sind), from Mathurā and Śrāvastī, and from Sārnāth near Benares.⁶ His coins are found in considerable quantities as far eastwards as Ghāzipur and Gorakhpur.⁷ The eastern portion of his empire was apparently governed by the *Mahā-Kshatrapa* Kharapallāna and the *Kshatrapa* Vanashpara. In the northern portion we find the general Lala and the Satraps Vespasi and Liaka. He fixed his own residence at Peshāwar (Puruṣha-

¹ *Corpus*, II, i. lxxvi; cf. lxi; JRAS, 1903, 334.

² *Ibid.*, p. lxxvii.

³ Cf. Kuśa of *Kanika lekha* and Kuśadvīpa of the *Purāṇas*. See now Shafer. *Linguistics in History*, JAOS, 67, No. 4, pp. 296 ff.

⁴ Cf. The story of the Chinese hostage mentioned by H. Tsang.

⁵ *Ep. Ind.*, xiv, p. 142; *Ind. Ant.*, 1903, p. 382; *Corpus*, II, i, pp. lxxii and lxxv. The reference may be to Kanishka II.

⁶ In recent years Mr. K. G. Goswami has drawn attention to a Brāhmī Inscription of Kanishka, dated in the year 2 (?), which he found in the Municipal Museum at Allahabad (*Calcutta Review*, July, 1934, p. 83).

⁷ A gold coin from Mahāsthāna (Bogra) represents the standing bearded figure of Kanishka—possibly an imitation of the coinage of the great Kushān king.

pura) and possibly established Kanishkapura¹ in Kaśmīra. It is, however, more probable that Kanishkapura was established by his namesake of the Ārā inscription. After making himself master of the south (*i.e.*, India) Kanishka turned to the west and defeated the king of the Parthians.² In his old age he led an army against the north and died in an attempt to cross the Tsung-ling mountains (Tāghdumbāsh Pāmīr) between the Pāmīr Plateau and Khotan. The Northern expedition is apparently referred to by Hiuen-Tsang who speaks of his rule in the territory to the east of the Tsung-ling mountains, and of a Chinese Prince detained as a hostage at his court.

It is not improbable that Kanishka was the Kushān king repulsed by general Pan-ch'ao during the reign of the Emperor Ho-ti (A.D. 89-105). It has no doubt been argued that Kanishka "must have been a monarch of some celebrity and if the Chinese had come into victorious contact with him, their historians would have mentioned it." But if we identify Pan-ch'ao's Kushān contemporary with Kadphises II, the silence of the Chinese becomes still more mysterious and inexplicable because he was certainly well-known to the annalists. On the other hand, Kanishka was not known to them and the non-mention of his name, if he were Pan-ch'ao's contemporary, cannot be more surprising than that of his predecessor, Wema. In favour of Kanishka's identity with Pan-ch'ao's antagonist we may urge that Kanishka is known to have come into conflict with the Chinese, but the same cannot be said with regard to Wema, the events of whose reign, as recorded by Chinese annalists, do not

¹ Cunningham (AGI², 114) located it near Śrīnagar. Stein and Smith identify it with Kānispur, "situated between the Vitastā river and the high road leading from Varāhamūla to Śrīnagar" (EHI⁴, p. 275).

² *Ind. Ant.*, 1903, p. 382.

include a first class war with China. The legend of Kanishka's death published by S. Lévi contains a significant passage which runs thus:—"I have subjugated three regions; all men have taken refuge with me, the region of the north alone has not come in to make its submission."¹ Have we not here a covert allusion to his failure in the encounter with his mighty northern neighbour?

Kanishka's fame rests not so much on his conquests, as on his patronage of the religion of Śākyamuni. Numismatic evidence and the testimony of the Peshāwar Casket inscriptions show that he actually became a convert to Buddhism possibly at the commencement of his reign, if not earlier. He showed his zeal for his faith by building the celebrated relic tower and *Śaṅghārāma* at Purushapura or Peshāwar which excited the wonder of Chinese and Muslim travellers.² He convoked the last great Buddhist council which was held in Kaśmīra or Jālandhar.³ But though a Buddhist, the Kushān monarch continued to honour the Greek, Sumerian, Elamite, Mithraic, Zoroastrian and Hindu gods worshipped in the various provinces of his far-flung empire.⁴ The court of Kanishka was adorned by Pārśva, Vasumitra,

¹ EHI⁴, p. 285; JRAS, 1912, 674.

² The fame of the *Kanishka Mahāvihāra* remained undiminished till the days of the Pāla Kings of Bengal as is apparent from the Ghoshrāvan Inscription of the time of Devapāla. Kanishka's *Chaitya* is referred to by Alberuni.

³ One account possibly mentions Gandhāra as the place where the Assembly met. The earliest authorities seem to locate it in Kashmīr. *Kundalavana vihāra* appears to be the name of the monastery where the theologians assembled probably under the presidency of Vasumitra. The chief business of the Synod seems to be the collection of canonical texts, and the preparation of commentaries on them (Smith, EHI⁴, pp. 283 ff; Law, *Buddhist Studies*, 71).

⁴ See JRAS, 1912, pp. 1003, 1004. The Elamite (Sumerian? Hastings, 5, 827) goddess Nana possibly gave her name to the famous Nāpaka coins (cf. Bhand., *Carm. Lec.*, 1921, p. 161). For the influence of the Mithra (Mīhr, Mihra, Mīro) cult on Kushān India, see Sir R. G. Bhandarkar, *Vaishnavism, Saivism and Minor Religious Systems*, p. 151. According to Professor Rapson

Āsvaghosha,¹ Charaka, Nāgārjuna,² Saṃgharakṣa, Māthara, Agesilaos the Greek and other worthies who played a leading part in the religious, literary, scientific, philosophical and artistic activities of the reign. Excavations at Māt near Mathurā have disclosed a life-size statue of the great king.³

After Kanishka came **Vāsishka**, Huviṣhka and Kanishka of the Ārā inscription. We have got inscriptions of Vāsishka dated 24 and 28 which possibly prove his control over Mathurā and Eastern Mālwa.⁴ He may have been identical with Vājṣhka, the father of Kanishka of the Ārā inscription, and Jushka of the *Rājatarāṅginī*, the founder of the town of Jushkapur, modern Zukur to the north of Śrīnagar.⁵

Huviṣhka's dates range from 28 to 60. A Mathurā Inscription⁶ represents him as the grandson of a king who has the appellation "*Saśa dharmatṛita*," i.e., steadfast or abiding in the true Law, which occurs on the coins of Kuyula Kaphsa.⁷ Kalhana's narrative leaves the impression that Huviṣhka ruled simultaneously with

(*Andhra Coins*, xi) the diversity of coin-types does not show religious eclecticism, but reflects the different forms of religion which prevailed in the various districts of the vast empire of the Great Kushāns. Cf., *Asṣrārī* and *Bednūr* types of coins of the time of Ilutmiṣh and of Hyder Ali.

¹ For the legend about Kanishka and Āsvaghosha see a recent article by H. W. Bailey (JRAS, 1942, pt. I)—trans. with notes of a fragment of a Khotan Ms. The king's name is spelt Cadrā (*Chandra*) Kanishka.

² It is possible that Nāgārjuna was a contemporary, not of Kanishka I, but of Kanishka II and Huviṣhka.

³ EHI⁴, p. 272. Cf. Coin-portrait, JRAS, 1912, 670.

⁴ As the Saśchi images may have been brought from Mathurā, the find-spots need not be regarded as forming necessarily a part of the empire of the king mentioned on the pedestals.

⁵ EHI⁴, p. 275.

⁶ JRAS, 1924, p. 402.

⁷ The epithet is also applied to Amogha in the Kharoṣṭhī documents (Barrow, p. 125).

Jushka and Kanishka, i.e., Vā-jheshka and **Kanishka of the Ārā inscription** of the year 41. The Wardak vase inscription possibly proves the inclusion of Kābul within his dominions. But there is no evidence that he retained his hold on the Lower Indus Valley which was probably wrested from the successors of Kanishka I by Rudradāman I. In Kaśmīra Huvishka built a town named Hushkapura.¹ Like Kanishka I, he was a patron of Buddhism and built a splendid monastery at Mathurā.² He also resembled Kanishka in his taste for a diversity of coin-types. Besides a medley of Greek, Persian and Indian deities we have, on one of his coins, the remarkable figure of Roma.³ A Mathurā inscription refers to the restoration during his reign of a delapidated *Devakula* of his grandfather.

Smith does not admit that the Kanishka of the Ārā inscription of the year 41 was different from the great Kanishka. Lüders, Fleet, Kennedy and Sten Konow, on the other hand, distinguish between the two Kanishkas.⁴ According to Lüders, Kanishka of the Ārā inscription was a son of Vāsishka and probably a grandson of Kanishka I. Kanishka II had the titles *Mahārāja*, *Rājātirāja*, *Devaputra* and possibly *Kaisara* (Caesar). It is probable that he, and not Kanishka I, was the founder of the town of Kanishkapura in Kaśmīra.

¹ It is identified with Ushkūr inside the Bāramūla Pass (EHI⁴, p. 287).

² Cf. Lüders, List No. 62.

³ *Camb. Short Hist.*, 79. Numismatic evidence possibly suggests that the 'Non-standard' was to some of the Great Kushāns what the *Garuda-dhvaaja* was to their Gupta successors. Cf. Whitehead, 196.

⁴ Cf. *Corpus*, II. i. lxxx; 163. Ep. Ind., XIV, p. 143. JRAS, 1913, 98. The mention of a distinguishing patronymic in the record of the year 41, and the fact that no inscriptions of Kanishka are known that are referable to the period 24 to 40 of the era used by the family (when the Kushān throne was occupied by Vāsishka and, possibly Huvishka as a junior partner), suggest that Kanishka of the year 41 is not to be identified with Kanishka of the years 1-23.

The last notable king of Kanishka's line was **Vāsudeva I**. His dates range from the year 67¹ to 98, *i.e.*, A.D. 145 to 176 according to the system of chronology adopted in these pages. He does not appear to have been a Buddhist. His coins exhibit the figure of Śiva attended by Nandi. There can be no doubt that he reverted to Śaivism, the religion professed by his great predecessor Kadphises II. A king named Vāsudeva is mentioned in the *Kāvya Mīmāṃsā* as a patron of poets and a *Sabhāpati*, apparently 'President of a Society' (of learned men). That the Kushān Age was a period of great literary activity is proved by the works of Aśvaghosha, Nāgārjuna and others. It was also a period of religious ferment and missionary activity. It witnessed the development of Śaivism and the allied cult of Kārttikeya, of the *Mahāyāna* form of Buddhism and the cults of Mihira and of Vāsudeva-Krishṇa, and it saw the introduction of Buddhism into China by Kāśyapa Mātāṅga (*c.* 61-68 A.D.).

"The dynasty of Kanishka opened the way for Indian civilization to Central and Eastern Asia."

The inscriptions of Vāsudeva have been found only in the Mathurā region. From this it is not unreasonable to surmise that he *gradually* lost his hold over the north-western portion of the Kushān dominions.

About the middle of the third century A.D., we hear of the existence of no less than four kingdoms all 'dependent on the Yueh-chi,' and ruled probably by princes of the Yue-chi stock.²

¹ Mr. M. Nagor makes mention of an inscription incised on the base of a stone image of the Buddha acquired from Pālikherā (Mathura Museum, No. 2907; which records the installation of the image in the year 67 during the reign of Vāsudeva.

² Cf. Kennedy, JRAS, 1913, 1060 f. Among the successors of Vāsudeva I may be mentioned Kanishka (III); Vasu (Whitehead, *Indo-Greek Coins*, pp. 211-12; cf. RDB, JASB, Vol. IV (1908), 81 ff; Altekar, NHIP, VI. 14 n) or Vāsudeva II.

These were Ta-hia (the Oxus region, *i.e.*, Bactria), Ki-pin (Kāpīśa), Kao-fou (Kābul) and 'Tien-tehou' (lit. India, meaning probably the country on either side of the Indus with a vague suzerainty over a wider area). In 230 the Ta Yueh-chi, *i.e.*, the Great (?) Yueh-chi king Po-tiao sent an embassy to the Chinese Emperor. The Yueh-chi kingdom of 'Tientchou' began to fall to pieces some time after this date and probably disappeared as an important power in the fourth century A.D. having already lost some of the remotest provinces to the Nāgas. Those nearer the Indus emerged as petty states. Śakasthāna and parts of North-West India were conquered by the Sassanians in the days of Varhrān II (A.D. 276-93). During the early part of the reign of Shāpūr II (A.D. 309-79) the Sassanian suzerainty was still acknowledged in those regions.

who is apparently to be identified with Po-tiao, A.D. 230 (*Corpus*, II. i. lxxvii); and Grumbates(?), A.D. 360 (Smith, *EHJ*⁴, p. 290f. Kings claiming to belong to the family of Kanishka continued to rule in Ki-pin and Gandhāra long after he had passed away (*Itinerary of Oukong*, Cal. Rev., 1922, Aug.-Sept., pp. 193, 489). The last king of Kanishka's race was, according to tradition, Lagatūrmān who was overthrown by his Brāhmaṇa minister Kallar (Alberuni, II, 13). For an alleged invasion of India in the later Kushān period by Ardeshir Bābagān (A.D. 226-41), the founder of the Sassanian dynasty, see Ferishta (Elliot and Dowson, VI, p. 557). Varhrān II (A.D. 276-93) conquered the whole of Śakasthāna and made his son Varhrān III Governor of the conquered territory. Śakasthāna continued to form a part of the Sassanian empire down to the time of Shāpūr II. A Pahlavi Inscription of Persepolis, which Herzfeld deciphered in 1923, dated probably in A.D. 310-11, when Shāpūr II (309-79) was on the throne, refers to the Sassanian ruler of Śakasthāna as "Śakānsāh, minister of ministers (*dabīrān dabīr*) of Hind, Śakasthāna and Tukhāristhān" (*MASI*, 38, 36). The Paikuli Inscription mentions the Śaka chiefs of North-Western India among the retainers of Varhrān III, Governor of Śakasthāna in the last quarter of the third century A.D. (*JRAS*, 1933, 219). The Ābhiras of Western India seem also to have acknowledged the sway of the Sassanians (Rapson, *Andhra Coins*, cxxxiv). J. Charpentier points out (*Aiyangar Com.*, Vol. 16) that at the time of Kosmas Indiko-pleustes (c. 500 A.D.) the right side of the Indus Delta belonged to Persia. Persians figure also in early Chalukya epigraphs and the *Raghuvamśa* of Kalidāsa.

SECTION IV. THE NĀGAS AND THE LATER KUSHĀNS

The successors of the Great Kushāns in Mathurā and certain neighbouring tracts were the Nāgas.¹ The prevalence of Nāga rule over a considerable portion of northern and central India in the third and fourth centuries A.D., is amply attested by epigraphic evidence. A Lahore copper seal inscription of the fourth century A.D. refers to a king named Maheśvara Nāga, the son of Nāgabhaṭṭa.² The Allahabad Pillar inscription refers to King Ganapati Nāga, while several Vākāṭaka records mention **Bhava Nāga** sovereign of the **Bhāraśīyas** whose grandson's grandson Rudrasena II was a contemporary of Chandra Gupta II, and who accordingly must have flourished before the rise of the Gupta Empire. Some idea of the great power of the rulers of Bhava Nāga's line and the territory over which they ruled may be gathered from the fact that the dynasty performed ten *Aśvamedha* sacrifices and "were besprinkled on the forehead with the pure water of (the river) *Bhāgirathi* (Ganges) that had been obtained by their valour."³ The valiant deeds of the family culminating in the performance of ten *Aśvamedha* sacrifices indicate that they were not a feudatory line owing allegiance to the Kushāns. We learn from the *Purāṇas* that the Nāgas established themselves at Vidiśā (Besnagar near Bhilsa), Padmāvati

¹ A Yūpa Inscription from Barnāla (in the Jaipur State) discloses the existence of a line of kings, one of whom bore a name that ended in—*Varādhana*. They belonged to the Sohartta or Sohartṛi *gotra*. But the dynastic designation is not known (*Ep. Ind.*, xxvi, 120). The record is dated in *Kṛita* 284 corresponding to A.D. 227-28.

² Fleet, CII, p. 233.

³ CII, p. 241; AHD, p. 72.

(Padam Pawāyā, "in the apex on the confluence of the Sindhu and Pāra)," ¹ Kāntipuri (not satisfactorily identified), ² and even Mathurā which was the southern ³ capital of Kanishka and his successors. The greatest of the Nāga Kings was perhaps Chandrāmśa, ⁴ 'the second Nakhavant,' whose name reminds us of the great king **Chandra** of the Delhi Iron Pillar inscription. *It is by no means clear that the two are identical.* ⁵ But if Chandra preceded the rise of the Gupta empire, it is natural to seek a reference to him in the Purāṇic texts which were not compiled till the Gupta-Vākāṭaka age.

The hand of a Nāga princess was sought by Chandra Gupta II in the fourth century, and a 'Nāga' officer governed the Gangetic Doāb as late as the time of Skanda Gupta. ⁶ The Kushāns, however, continued to rule in the Kābul

¹ Coins of a *Mahārāja* or *Adhirāja* named Bhavanāga have been found at this place. His identity with Bhavanāga of Vākāṭaka epigraphs proposed by Dr. Altekar (J. Num. S. I, V. pt. II) must await future discoveries.

² Mention is made of a Kāntipuri in the *Skanda Purāṇa* (Nāgarakhaṇḍa, ch. 47, 4ff). In the story narrated in the text a petty prince of Kāntipuri 'marries a princess of Daśārṇa, the valley of the Dhasan, in Eastern Malwā which, in the time of the *Meghadūta*, included Vidiśā. Kāntipuri probably lay not far from the last-mentioned city.

³ JRAS, 1905, p. 233.

⁴ "Nṛpān Vidiśakāmśa c=āpi bhaviṣyāmstu nibodhata
Seṣasya Nāga-rājasya putraḥ para purañjayaḥ
Bhogi bhaviṣyate (?) rājā nṛpo Nāga-kul ōdvahah
Sadācandras tu Chandrāmśo dvitīyo Nakhavāms tathā."

—*Dynasties of the Kali Age*, p. 49.

⁵ Devotion to Viṣṇu may suggest identification with Chandra-Gupta I, or preferably, Chandra II. But then we have to explain the significant omission of the termination -gupta in this memorable *prāśasti* and the epithet Dhāva, especially as Chandra-Gupta II is known as Devagupta or Devarāja and not Dhāva. One should note also the claim to have acquired *adhirājya* and victory over a Trans-Indus people by his own prowess and not as a sequel to the power and prestige won by a line of distinguished ancestors. The Viṣṇuite association of this great King precludes the possibility of identification with Chandra Kanishka. Identification with the first Maurya is fantastic in view of the date of the epigraph and recorded achievements of the hero which do not include the overthrow of the Nandas and clash with the Yavanas.

⁶ For later traces of Nāga rule, see *Born. Gaz.*, 1. 2, pp. 281, 292, 313, 574; *Ep. Ind.*, X, 25.

valley and parts of the Indian borderland. One of them gave his daughter in marriage to Hormisdas (or Hormuzd) II, the Sassanian King of Persia (A.D. 301-09). As already stated Varhrān II (A.D. 276-93) and his successors up to the time of Shāpūr II seem to have exercised suzerainty over their Scythic neighbours. "When Shāpūr II besieged Amida in A.D. 350, Indian elephants served under his command."¹ Shortly afterwards the Sassanian supremacy was replaced by that of the Guptas, and the "*Daivaputra Shāhi Shāhānushāhi*," i.e., the Kushān monarch or monarchs of the North-West sent valuable presents to Samudra Gupta.² In the fifth century³ the **Kidāra Kushāns** established their rule over Gandhāra and Kaśmīra.⁴ In the sixth century the Kushāns had to fight hard against the Huns and in the following centuries, against the Muslims. In the ninth century A.D. a powerful Muslim dynasty, that of the Saffārids, was established in Sīstān (Seistan) and the sway of the family soon extended to Ghazni, Zābulistān, Herat, Balkh and Bamiyan.⁵ The later kings of the race of Kanishka seem to have had one residence in Gandhāra at the city of Uṇḍ, Ohind, Waihand or Udabhāṇḍa, on the Indus. Another capital was situated in the Kābul valley. The family was finally extinguished by the Brāhmaṇa Kallār or Lalliya who founded the Hindu Shāhiyya dynasty towards the close of the ninth century A.D. A part of the kingdom of Kābul fell into the hands of Alptigin in the tenth century.⁶

¹ JRAS, 1913, p. 1062. Smith (EHI⁴, p. 290) and Herzfeld (MASI, 38, 36) give the date A. D. 360.

² Cf. also JASB, 1908, 93.

³ Or probably earlier (about the middle of the fourth century according to Altekar, NHIP, VI. 21).

⁴ JRAS, 1913, p. 1064. Smith, *Catalogue*, 64, 89. R. D. Banerji JASB, 1908, 91.

⁵ Nazim, *The Life and Times of Sultan Mahmud*, 186.

⁶ Nazim, *op cit*, p. 26.

CHAPTER IX. SCYTHIAN RULE IN SOUTHERN AND WESTERN INDIA

SECTION I. THE KSHAHARĀTAS

We have seen that in the second and first centuries B.C., the Scythians possessed Ki-pin (Kāpiśā-Gandhāra) and Śakasthāna (Seistan) and soon extended their sway over a large part of Northern India. The principal Scythic dynasties continued to rule in the north. But a Satrapal family, the Kshaharātas, extended their power to Western India and the Deccan, and wrested parts of Mahārāshṭra from the Śātavāhanas. The Śātavāhana king apparently retired to the southern part of his dominions, probable to the *Janapada* of the Bellary District which came to be known as Śātavāhanibhāra, and was at one time under the direct administration of a military governor (*mahāsenāpati*) named Skanda-nāga.¹ The waning power of the indigenous rulers of the Deccan and the waxing strength of the invaders seem to be hinted at in the following lines of the *Periplus* :

“The city of Calliena (Kalyāna) in the time of the elder Saraganus (probable Śātakarṇi I) became a lawful market town; but since it came into the possession of Sandanes (possible Sunandana Śātakarṇi)² the port is much obstructed, and Greek ships landing there may chance to be taken to Barygaza (Broach) under guard.”

¹ Ep. Ind. XIV, 155.

² Wilson in JASB, 1904, 272; Smith ZDMG, Sept., 1903; IHQ, 1932, 234; JBORS, 1932, 7f. The adjective ‘elder’ becomes pointless unless the passage mentions a younger Saraganus, and this person can only refer to Sandanes from whom the elder king is distinguished.

The name of the Scythian conquerors of the Broach region and of Mahārāshṭra, Kshaharāta, seems to be identical with "Karatai," the designation of a famous Saka tribe of the north mentioned by the geographer Ptolemy.¹

The known members of the Kshaharāta, Khakharāta, or Chaharata family are Liaka, Patika, Ghaṭāka, Bhūmaka and Nahapāna. Of these Liaka, Patika, and Ghaṭāka belonged to the Taxila and Mathurā regions respectively. Bhūmaka was a *Kshatrapa* of Kāthiāwār. Rapson says that he preceded Nahapāna. His coin-types are "arrow, discus and thunderbolt." These types have been compared with the reverse type "discus, bow and arrow" of certain copper coins struck conjointly by Spalirises and Azes (I).

Nahapāna was the greatest of the Kshaharāta Satraps. Eight Cave Inscriptions discovered at Paṇḍulena, near Nāsik, Junnar and Karle (in the Poona district) prove the inclusion of a considerable portion of Mahārāshṭra within his dominions. Seven of these inscriptions describe the benefactions of his son-in-law Ushavadāta (Rishabhādatta) the Śaka, while the eighth inscription specifies the charitable works of Ayama, the *Amātya* (minister or district officer). Ushavadāta's inscriptions indicate that Nahapāna's political influence probably extended from Poona (in Mahārāshṭra) and Sūrpāraka (in North Konkan) to Prabhāsa in Kāthiāwār, Mandasor (Daśapura) and Ujjain in Mālwa and the district of Ajmer including Pushkara, the place of pilgrimage to which Ushavadāta resorted for consecration after his victory over the Mālayas or Mālavas.

¹ *Ind. Ant.*, 1884, p. 400. Mr. Y. R. Gupta points out (*Ind. Ant.*, 1926, 178, that among the shepherds of the Deccan we have the surname Kharāta which he considers to be a 'shortened form of Khakharāta' (Kshaharāta).

The Nāsik records give the dates 41, 42, and 45, of an unspecified era, and call Nahapāna a *Kshatrapa*, while the Junnar epigraph of Ayama specifies the date 46 and speaks of Nahapāna as *Mahākshatrapa*. The generally accepted view is that these dates are to be referred to the Śaka era of 78 A.D. The name Nahapāna is no doubt Persian, but the Kshaharāta tribe to which Nahapāna belonged was probably of Śaka extraction and Ushavadāta, son-in-law of Nahapāna, distinctly calls himself a Śaka. It is, therefore, probable that the era of 78 A.D. derives its name of *Śaka* era from the Śaka princes of the House of Nahapāna. Rapson accepts the view that Nahapāna's dates are recorded in years of the Śaka era, beginning in 78 A.D., and, therefore, assigns Nahapāna to the period A.D. 119 to 124.¹ Several scholars² identify Nahapāna with Mambarus (emended into Nambanus)³ of the *Periplus* whose capital was Minnagara in Ariake. According to one theory Minnagara is modern Mandasor,⁴ and Ariake is Aparāntika.⁵

¹ Allan thinks that the coins of Nahapāna cannot be assigned to so late a date in the second century A.D. He points among other things to the similarity of the bust on the obverse of Nahapāna's silver coins and that on the coins of Bhājuvāla. But he admits that this may be due to derivations from a common prototype such as the coins of Strato I. *Camb. Short Hist.* 80 f.

² E. g., M. Boyer in *Journal Asiatique*, 1897; JASB, 1904, 272. In JRAS, 1918, 108, Kennedy points out that the name certainly ends in *-baros-baros*, and not in *banos*.

³ JRAS, 1912, p. 785.

⁴ This is the view of D. R. Bhandarkar who apparently follows *Bomb. Gaz.*, I. 1, 15 n.; *Cf.*, however, *Ind. Ant.*, 1926, p. 143, *Capital of Nahapāna* (=Junnar). Fleet identifies Minnagara with Debad in the Pañch Mahāla (JRAS, 1912, p. 788; 1913, 993a). In a paper read at the sixth conference of Orientalists at Patna Dr. Jayaswal referred to a Jaina work which mentions Broach as the capital of Nahapāna (See now *Āraṇyaka sūtra*, JBORS, 1930, Sept. Dec., 299). For a different tradition see IHQ, 1929, 256. Vasudhara (?) nagari.

⁵ *Cf.* also IA, 7, 259, 263: Ariake may also be Aryaka of Varāhamihira's *Bṛhat Samhita*.

R. D. Banerji and G. Jouveau-Dubreuil are of opinion that Nahapāna's dates are not referable to the Śaka era. They say that if we admit that the inscriptions of Nahapāna are dated in the Śaka era, there will be only an interval of five years between the inscription of this king, dated 46 and the inscriptions of Rudradāman, dated 52. Within these years must have taken place :

- (1) The end of Nahapāna's reign ;
- (2) The destruction of the Kshaharātas ;
- (3) The accession of Chashtana as *Kshatrpa*, his reign as *Kshatrpa* his accession as a *Mahākshatrpa*, and his reign as *Mahākshatrpa* ;
- (4) The accession of Jayadāman as *Kshatrpa*, his reign as *Kshatrpa*, and perhaps also his reign as *Mahākshatrpa* ;
- (5) The accession of Rudradāman and the beginning of his reign.

There is no necessity, however, of crowding the events mentioned above within five years (between the year 46, the last known date of Nahapāna, and the year 52, the first known date of Rudradāman). There is nothing to show that Chashtana's family came to power *after* the destruction of the Kshaharātas. The line of Chashtana may have been ruling in Cutch and perhaps some adjacent territories, as the Andhau inscriptions of the year 52 suggest, while the Kshaharātas were ruling in parts of Mālwa and Mabārāshtra. Moreover, there is no good ground for believing that a long interval elapsed from the accession of Chashtana to that of Rudradāman. Drs. Bhandarkar and R. C. Majumdar have pointed out that the Andhau inscriptions clearly prove that Chashtana and Rudradāman ruled conjointly in the year 52. Professor J. Dubreuil rejects their view on the ground that

there is no "cha" after Rudradāman in the text of the inscription: *Rājā Chashtanasa Ysāmotika-putrasa rājā Rudradāmasa Jayadāma-putrasa varshe dvipachāse*, 50, 2. Professor Dubreuil translates the passage thus :

"In the 52nd year, in the reign of Rudradāman, son of Jayadāman, grandson of Chashtana and great-grandson of Ysāmotika."

The Professor who objects to a 'cha' himself makes use not only of "and" but also of the words "grandson" and "great-grandson" no trace of which can be found in the original record. Had his translation been what the writer of the Andhau inscriptions intended, we should have expected to find the name of Ysāmotika first, and then the name of Chashtana followed by those of Jayadāman and Rudradāman—*Ysāmotika prapautrasa Chashtana putrasa Jayadāma-putrasa Rudradāmasa*.¹ Moreover, it is significant that in the text of the inscription there is no royal title prefixed to the name of Jayadāman who ruled between Chashtana and Rudradāman according to Dubreuil. On the other hand, both Chashtana and Rudradāman are called *Rājā*. The two are mentioned in exactly the same way—with the honorific *rājā* and the patronymic. The literal translation of the inscriptional passage is "in the year 52 of king Chashtana son of Ysāmotika, of King Rudradāman son of Jayadāman," and this certainly indicates that the year 52 belonged to the reign both of Chashtana and Rudradāman.² The conjoint rule of two kings was known to ancient Hindu writers on polity.³ The theory of the conjoint

¹ Cf. the Junnāgaḍh, Guṇḍa and Jasḍhan inscriptions.

² Cf. the coin legends "*Heramayasa Kaliyapaya*," "*Guduphurasas Sasasa*," "*Khatapāna Hagānasa Hagāmashasa*", etc., where, too, we have no *cha* after the second name. Whitehead, *Indo-Greek Coins*, 86, 147; *CHI*, 538.

³ Cf. *Dvairāja* in the *Atharva Veda* (V. 20, 9); *Dvairājya* in the *Kaṭhiliya Arthashastra*, p. 325; *Dorajja* of the *Āyāraṅga Sutta*; the classical account of Patalene, p. 259 *ante*; the case of Dhṛitarāshṭra and Duryodhana in the *Great*

rule of Chashtāna and his grandson is supported by the fact that Jayadāman did not live to be a *Mahākshatrāpa* and must have predeceased his father, Chashtāna, as unlike Chashtāna and Rudradāman, he is called simply a *Kshatrāpa* (not *Mahākshatrāpa* and *Bhadramukha*) even in the inscriptions of his descendants.¹ We have already noticed the fact that the title *Rājā*, which is given to Chashtāna and Rudradāman in the Andhau inscriptions, is not given to Jayadāman.

Mr. R. D. Banerji says that the inscriptions of Nahapāna cannot be referred to the same era as used on the coins and inscriptions of Chashtāna's dynasty because if we assume that Nahapāna was dethroned in 46 S. E., Gautamīputra must have held Nāsik up to 52 S. E. (from his 18th to his 24th year), then Pulumāyi held the city up to the 22nd year of his reign, i.e., up to at least 74 S. E. But Rudradāman is known to have defeated Pulumāyi and taken Nāsik before that time. Banerji's error lies in the tacit assumption that Rudradāman twice occupied Nāsik before the year 73 of the Śaka era. There is no clear evidence to suggest that the Śātavāhanas lost Poona and Nāsik to that great satrap though they may have lost Mālwa and the Konkan. Another untenable assumption of Mr. Banerji is that Rudradāman finished his conquests before the year 52 or A. D. 130, whereas the Andhau inscriptions merely imply the possession of Cutch and perhaps some adjoining tracts by the House of Chashtāna.

The theory of those who refer Nahapāna's dates to the Śaka era, is confirmed by the fact pointed out by

Epic; of Eukratides and his son in Justin's work; of Strato I and Strato II; of Azes and Azilises, etc., etc. The *Mahāvastu* (III. 432) refers to the conjoint rule of three brothers:—"Kaliṅgeshu Sīṃhapuraṃ nāma nagaraṃ tatra trayo bhātāro ekamātrikā rajyaṃ kārayaṃti." See also IA, 6, 29. Cf. Nilkanta Sastri, *Pandyan Kingdom*, 120, 122, 180.

¹ Cf. the Guṇḍa and Jasdhan inscriptions.

Professor Rapson, and Dr. Bhandarkar after him, that a Nāsik inscription of Nahapāna refers to a *gold* currency, doubtless of the Kushāns who could not have ruled in India before the first century A. D.¹

The power of Nahapāna and his allies, the Uttamabhadras,² was threatened by the Mālavas (**Mālavas**) from the north, and the Śātavāhanas from the south. The incursion of the Mālavas was repelled by Ushavādāta. But the Śātavāhana attack proved fatal to Śaka rule in Mahārāshṭra.

We know very little about Chakora and Śivasvāti mentioned in the Purāṇas as the immediate successors of Sunandana during whose reign Śātavāhana prestige had sunk very low and marauders from Barygaza had been harrying the ports that had once enjoyed the protection of the elder Śātakarṇi, probably Śātakarṇi I. But the king whose name occurs next in the list, *viz.*, Gautamīputra, regained the lost power of the house and dealt a severe blow at the power of the intruders from the north. The Nāsik *praśasti* calls him the "uprooter of the Kshaharāta race," and the "restorer, of the glory of the Śātavāhana family". That Nahapāna himself was overthrown by Gautamīputra is proved by the testimony of the Jogalthembi hoard (in the Nāsik district) which consisted of Nahapāna's own silver coins and coins restruck by Gautamīputra. In the

¹ Rapson, *Coins of the Andhra Dynasty, etc.*, pp. lviii, clxxxv; Bhandarkar, *Ind. Ant.*, 1918-1919, 'Deccan of the Śātavāhana Period'.

² The Uttamabhadras may have been a section of the Bhadra tribe mentioned in a list of *gaṇas* along with the Rohitakas (*cf.* Rohtak in south-east Punjab), the Āgreyas (*cf.* Agra?) and the Mālavas (*Mbh.* III. 253.20). In *Mbh.* VI. 50.47 the Pra-bhadras are associated with the *gaṇas* or corporations of the Dāserakas, apparently of the desert region of Rājputāna (Monier Williams, *Dic.* 405).

restruck coins there was not a single one belonging to any prince other than Nahapāna as would certainly have been the case if any ruler had intervened between Nahapāna and Gautamīputra.

SECTION II. THE RESTORATION OF THE ŚĀTAVĀHANA EMPIRE.

Gautamīputra's victory over the Kshaharātas led to the restoration of the Śātavāhana power in Mahārāshṭra and some adjoining provinces. The recovery of Mahārāshṭra is proved by a Nāsik inscription, dated in the year 18,¹ and a Karle epigraph addressed to the *Amātya* or the king's officer in charge of Māmāla (the territory round Karle, modern Māval in the Poona district). But this was not the only achievement of Gautamīputra. We learn from the Nāsik record of queen Gautamī Balaśrī that her son destroyed the Śakas (Scythians), Yavanas (Greeks) and Pahlavas (Parthians), and that his dominions extended not only over Asika,² Asaka (Aśmaka on the Godāvarī, a part of Mahārāshṭra),³ and Mūlaka (the district around Paiṭhan), but also over Surasṭha (South Kāṭhiāwār), Kukura (in Western or Central India, possibly near the Pāriyātra or the Western Vindhyas),⁴ Aparānta (North Koṅkan), Anupa (district around Māhiśmatī on the Narmadā), Vidarbha (Greater Berar), and Ākara-Avanti (East⁵ and west Mālwa). He is further styled lord of all the mountains from

¹ The Nāsik Edict was issued from the camp of victory of the Vejayanti army (*Ep. Ind.*, VIII. 72) and was addressed to the *Amātya* or the king's officer in charge of Govardhana (Nāsik). According to Sircar 'Vejayanti' is not a city but an epithet of *Senā* (army).

² On the *Kṛṣṇaveṇā*, i.e., the river *Kṛṣṇā* (Khāravēla's ins., *IHQ.* 1938 275); cf. *Ārabika*, Patañjali, IV, 2.2.

³ Shamasāstry's translation of the *Arthaśāstra*, p. 143, n. 2. Its capital Potana probably corresponds to Bodhan in the Nizam's dominions.

⁴ *Bṛihat Samhitā*, XIV, 4.

⁵ Eastern Mālwa was possibly under Vāsishka, the successor of Kanishka I, in the year 28 of the Kushān Era which corresponds to A.D. 106 according to the system of chronology adopted in these pages. Ākara has been identified with Āgar, 35 miles north-east of Ujjain, Bomb. Gaz., Gujarat, 540; *Ep. Ind.*, xliii. 102.

the Vindhyas to the Malaya or Travancore hills, and from the Eastern (Mahendra) to the Western (Sahya) Ghāṭs. The possession of Vejayanti in the Kanarese country is possibly hinted at in the Nāsik inscription of the year 18. The names of the Andhra country (Andhrāpatha) and South Kosala are, however, conspicuous by their absence. Inscriptions, coins and the testimony of Hiuen Tsang prove that both these territories were at one time or other included within the Śātavāhana empire. The earliest Śātavāhana king whose inscriptions have been found in the Andhra region is Pulumāyi, son of Gautamīputra. It is, however, possible that some vague claim of suzerainty over the areas in question is implied in the boast that Gautamīputra was lord of the Vindhyas and the Eastern Ghāṭs (Mahendra) and that his chargers "drank the water of the three oceans" (*tisamudatoya-pīta-vāhana*). Moreover "Asika" seems to have included a considerable portion of the valley of the Kṛishṇā.

In the Nāsik *praśasti* Gautamīputra figures not only as a conqueror, but also as a social reformer. "He crushed down the pride and conceit of the Kshatriyas, furthered the interest of the twice-born, apparently the Brāhmaṇas, as well as the lowest orders (*Dvijāvarakuṭubavivadhana*)¹ and stopped the contamination of the four *varṇas* (castes)."

According to Sir R. G. Bhandarkar and Dr. D. R. Bhandarkar, Gautamīputra reigned conjointly with his son Pulumāyi. They give the following reasons in support of their theory:—

¹ *Kuṭumba* means 'a household', 'a family' and *avara-kuṭuba* may be taken to mean 'households or families of the lowly'. The use of the word *kuṭuba* may suggest that the 'lowly' order or orders, whose families or households are referred to, are the traders and agriculturists (*kuṭumbika*).

(1) In Gautamī's inscription (dated in the 19th year of her grandson Pulumāyi) she is called the mother of the great king and the grandmother of the great king. This statement would be pointless if she were not *both* at one and the same time.

(2) If it were a fact that Gautamīputra was dead when the queen-mother's inscription was written, and Pulumāyi alone was reigning, we should expect to find the exploits of the latter also celebrated in the inscription. But there is not a word in praise of him. A king dead for 19 years is extolled, and the reigning king passed over in silence.

(3) The inscription dated in the year 24, engraved on the east wall of the Veranda of the Nāsik Cave No. 3, which records a grant made by Gautamīputra and the "king's mother whose son is living", in favour of certain Buddhist monks "*dwelling in the cave which was a pious gift of theirs,*" presupposes the gift of the Nāsik Cave No. 3 in the 19th year of Pulumāyi. Consequently Gautamīputra was alive after the 19th year of his son.

As regards point (1), it may be said that usually a queen sees only her husband and sometimes a son on the throne. Queen Gautamī Balaśri, on the other hand, was one of the fortunate (or unfortunate) few who saw grandchildren on the throne. Therefore, she claimed to be the mother of a great king and the grandmother of a great king.

As to point (2), is the silence satisfactorily explained by the theory of conjoint rule? Those who prefer the opposite view may point out that although it is not customary for an ordinary subject to extol a dead king and pass over a reigning monarch in silence, still it is perfectly natural for a queen-mother in her old age to recount the glories of a son who was associated with her in a previous gift.

As to point (3), it is not clear that the gift referred to in the postscript of the year 24 was identical with the grant of the year 19 of Pulumāyi. The donors in the postscript were king Gautamīputra and the *rājamātā*, the king's mother, apparently Balaśrī, while the donor in the year 19 of Pulumāyi was the queen-mother *alone*. In the inscription of the year 24, the queen-mother is called *Mahādevī Jīvasutā Rājamātā*, the great queen, the king's mother; whose son is alive. In Pulumāyi's inscription the epithets *Mahādevī* and *Rājamātā* are retained but the epithet "*Jīvasutā*," "whose son is alive," is significantly omitted. The donees in the former grant were the *Tekirasi* or *Triraśmi* ascetics in general, the donees in the latter grant were the monks of the *Bhadavāntya* school. The object of grant in the former case may have been merely the *Veranda* of Cave No. 3, which contains the postscript of the year 24, and whose existence before the 19th year of Pulumāyi is attested by an edict of Gautamīputra of the year 18. On the other hand, the cave given away to the *Bhadavāntya* monks was the whole of Cave No. 3.

If Gautamīputra and his son reigned simultaneously, and if the latter ruled as his father's colleague in Mahārāshtra, then it is difficult to explain why Gautamīputra was styled "*Govadhanasa Benākaṭakasvāmi*," "lord of Benākaṭaka in Govardhana" (Nāsik),¹ and why he addressed the officer at Govardhana directly, ignoring his son who is represented as ruling over Mahārāshtra, while in the record of the year 19, Pulumāyi was considered as

¹ The use of the expression "*Govadhanasa*" suggests that there were other localities named Benākaṭaka from which this particular place is distinguished. A Benākaṭa in the eastern part of the Vākāṭaka kingdom is mentioned in the Tiroḍi plates of Pravarasena II (? III) (IHQ, 1935, 293; Ep. Ind. XXII, 167 ff). Beṇā or Bennā is apparently the name of a small stream in each case.

so important that the date was recorded in the years of his reign, and not in that of his father who was the senior ruler.¹

The generally accepted view is that Pulumāyi came after Gautamīputra.

The date of Gautamīputra Śātakarṇi is a matter regarding which there is a wide divergence of opinion. There are scholars who believe that the epithets *paravāraṇa-vikrama*, *chāru-vikrama*, "whose gait was beautiful like the gait of a choice elephant," and *śaka-nishūdāna*, destroyer of Śakas, suggest that he was the original of *Rājā Vikramāditya* of legend who founded the era of 58 B.C. But, as already pointed out, the use of regnal years by Gautamīputra and his descendants indicates that no era originated with the dynasty. Further, Indian literature clearly distinguishes between Vikramāditya of Ujjain and Śālivāhana or the Śātavāhanas of Pratiśṭhāna. The view accepted in these pages is that Gautamīputra was the conqueror of Nabapāna and that his 18th year fell after the year 46 of the Saka era, the last recorded date of his vanquished opponent. In other words the conquest of Nāsik by Gautamīputra took place some time after A. D. $78+46=124$, and his accession after A. D. $124-18=106$. As he ruled for at least 24 years, his reign must have terminated after A. D. 130.

In the Purāṇic lists compiled by Pargiter the immediate successors of Gautamīputra are Pulomā, his son, and Śātakarṇi. Pulomā is doubtless identical with Siro P(t)olemaios of Baithana mentioned by Ptolemy and Vāsishṭhīputra Svāmi Śrī **Pulumāvi** of inscriptions and

¹ Cf. R. D. Banerji, JRAS, 1917, pp. 281 et seq. Note also the epithet (*Dakṣiṇā*) *pathafrara* 'lord of the Deccan,' applied to Pulumāyi in the *prafarī* of the year 19.

coins. Śātakarṇi is perhaps to be identified with **Vāsishṭhīputra Śrī Śātakarṇi** of a Kanheri Cave Inscription, or with Vāsishṭhīputra Chatarapana Śātakarṇi of a Nānāghaṭ record. His exact position in the genealogical list cannot be determined with precision. The Kanheri epigraph represents Vāsishṭhīputra Śrī Śātakarṇi as the husband of a daughter of the *Mahākshatrpa* Ru(dra). Rapson identifies this Rudra with Rudradāman I. There can hardly be any doubt that the Śātavāhana king mentioned in the Kanheri record, or one of his close relations who bore a similar name, was identical with Śātakarṇi, lord of the Deccan, whom Rudradāman "twice in fair fight completely defeated, but did not destroy on account of the nearness of their connection." Dr. Bhandarkar's identification of Vāsishṭhīputra Śrī Śātakarṇi of Kanheri with Vāsishṭhīputra Śiva Śrī Śātakarṇi of coins and Śiva Śrī of the *Matsya Purāṇa* cannot be regarded as more than a conjecture. The ruler mentioned in the Kanheri Inscription may have been a brother of Pulumāyi.

We have seen that the capital of **Pulumāyi** was Baithan, *i.e.*, Paiṭhan or Pratiśṭhāna on the Godāvarī identified by Bhandarkar with Navanara or Navanagara, *i.e.*, the new city. Inscriptions and coins prove that the dominions of this king included the Krishṇā-Godāvarī reign as well as Mahārāshṭra. It has already been pointed out that the Andhra country is not clearly mentioned in the list of territories over which Gautamīputra held his sway. It is not altogether improbable that Vāsishṭhīputra Pulumāyi was the first to establish the Śātavāhana power firmly in that region. Sukṭhankar identifies him with Siri Pulumāyi, king of the Śātavāhanas, mentioned in an inscription discovered in the Adoni tāluk of the Bellary district. But the absence of the distinguishing metonymic makes the identification uncertain and probably

indicates that the king referred to in the inscription is Pulumāyi I of the Purāṇas or some other prince of the dynasty who bore the same name. D. C. Sircar identifies him with the last king of Pargiter's list. Numismatic evidence suggests that the political influence of a Pulumāyi extended to the Coromandel coast, and possibly to the Chanda district of the Central Provinces. But in the absence of epigraphic corroboration the matter cannot be regarded as definitely proved. Moreover, the absence of the metronymic *Vāsishṭhīputra* makes it uncertain in some cases as to whether the son of the great Gautamīputra is meant.

Vāsishṭhīputra Pulumāyi must have come to the throne some time after A. D. 130. He is known from a Karle epigraph to have ruled for at least 24 years, so that his reign terminated after A.D. 154.

The successors of Pulomā according to the Purāṇic lists compiled by Pargiter are Śiva Śrī¹ Pulomā and Śivaskanda (or Śivaskandha)² Śātakarṇi.

Yajñaśrī Śātakarṇi.³

The immediate successor of Śivaskanda according to the collated text of Pargiter was Yajña Śrī. If the Purāṇas are to be believed his accession took place more

¹ Mirashi in the *Journal of the Num. Soc.* II(1940), p. 88 attributes to him the coins of "Śivaśrī Pulumāyi III" of the Tarhāla hoard. He draws a distinction between this king (who was a Pulumāyi) and Vāsishṭhīputra Śivasrī Śātakarṇi who is known to Rapson's Catalogue. The *Vishṇu Purāṇa*, however, represents Śivaśrī as a Śātakarṇi (and not a Pulumāyi). The matter must, therefore, be regarded as *sub judice*.

² Mirashi (*ibid.* 89) identifies him with King Sirikhada or Skanda Śātakarṇi of the Tarhāla hoard (Akola district) and other coins whose name was wrongly read as Chada Śātakarṇi by Smith and Rudra Śātakarṇi by Rapson. This "Rudra" was represented as a ruler of the Andhra-deśa.

³ In *JRAS*, July, 1934, 560ff, Dr. D. C. Sircar suggests that the name of this king was Śrī Yajña Śātakarṇi as stated in inscriptions, and not Yajña Śrī (as stated in the Purāṇas). It should, however, be remembered that Śrī is here an honorific

than 35 years after the close of the reign of Gautamīputra Śātakarṇi, i.e., after A. D. 165 and ended after A.D. 194. Yajña Śrī's inscriptions, which prove that he reigned for at least 27 years, are found at the following places, viz., Nāsik in Mahārāshṭra, Kanheri in Aparānta, and China in the Kṛishṇā district. His coins are found in Gujrāt, Kāthiāwār, Aparānta, the Chanda District in the Central Provinces, and the Kṛishṇā district of the Madras State. There can be no doubt that he ruled over both Mahārāshṭra and the Andhra country and recovered Aparānta (N. Koṅkan) from the successors of Rudradāman I. Smith says that his silver coins imitating the coinage of the Śaka rulers of Ujjain probably point to victories over the latter, and that the coins bearing the figure of a ship suggest the inference that the king's power extended over the sea. He thus anticipated the naval ventures of the Kadambas of Goa, of Sivājī and of the Angriās.¹

Yajñaśrī was the last great king of his dynasty. After his death the Śātavāhanas probably lost North-Western Mahārāshṭra to the **Ābhīra** king Īśvarasena.² The later

and it is frequently used as a suffix in the names of members of the Śātavāhana royal house (cf. Veda or Skanda-Siri, Haku-Siri, Bala-Sri, Siya-Sri, etc.; Rapson, *Andhra Coins*, pp. xlvii, l, lii). The mere fact that in certain documents Śrī precedes the name of a king does not prove conclusively that it was never used as a suffix. In the famous inscription of Khāravela the king is called both Siri Khāravela and Khāravela-Siri. In the *Mudrārākshasa* Śrīmat Chandragupta is also styled Chanda-Siri. Cf. Aśoka Śrī in *Parīkṣhṭa-parvan*, IX. 14.

¹ Rapson, however, says (*Coins of the Andhra Dynasty*, p. 22) in reference to certain lead coins (of the Coromandel coast): "ohv Ship with two masts. Inscr. not completely read, but apparently *Siri-Pu (lumā) rīsa*."

² The earliest reference to the *Ābhīras* to which an approximate date can be assigned is that contained in the *Mahābhāshya* of Patanjali. The *Mahābhāshya* as well as the *Mahābhārata* connects them with the *Sūdras*—the *Sodrai* of Alexander's historians. Their country—*Ābiria*—finds mention in the *Periplus* and the geography of Ptolemy. In the third quarter of the second century A. D., *Ābhīra* chieftains figured as generals of the Śaka rulers of Western India. Shortly afterwards a chief named *Īśvaradatta*, probably an *Ābhīra*, became

Sātavāhana princes—Vijaya, Chaṇḍa Śrī (variant Chandra Śrī) and Pulomāvi of the Purāṇas—seem to have ruled in Berar, the Eastern Deccan and the Kanarese country.¹ The existence of Vijaya seems now to be confirmed by numismatic evidence.² Chaṇḍa Śrī may have been identical with Vāsisthī-putra “*Sāmi-siri Chaṇḍa Sāta*” of the Kodavali rock-cut well Inscription discovered near Piṭhāpuram in the Godāvarī region, while Pulomāvi is, in the opinion of Dr. D. C. Sircar, to be identified with the king of the same name mentioned in the Myakadoni inscription of the Bellary District. Coins disclose the existence of a few other Kings of the line who must be assigned to the latest Sātavāhana period. Sātavāhana rule in the

Mahākshatrapa. His relation to the Ābhīra king Mādhariputra Išvara Sena, son of Śiva Datta, remains doubtful. But some scholars are inclined to identify the two chiefs. It is also suggested that this dynasty of Išvara Sena is identical with the Traikūṭaka line of Aparānta, and that the establishment of the Traikūṭaka era in A.D. 248 marks the date at which the Ābhīras succeeded the Sātavāhanas in the Government of Northern Mahārāshṭra and the adjoining region. The last known rulers of the Traikūṭaka line were Indradatta, his son Dahrasena (455-56 A. D.), and his son Vyāghrasena (489-90), after whom the kingdom seems to have been conquered by the Vākāṭaka king Harishepa.

¹ The Berar (Akola) group includes certain princes, not included in the Purāṇic lists, e.g., Śrī Kumbha Śātakarṇi, Śrī Karṇa Śātakarṇi (unless he is identified with the so-called Svātikarṇa, the fourteenth king of Pargiter's list) and Śrī Śaka Śātakarṇi (Mirashi, *J. Num. Soc.*, II, 1940). Mirashi thinks that the real name of the so-called Kṛishṇa (II) of the Chanda hoard was Karṇa. Among kings of uncertain identity mention may be made of Śrī Śivamaka Sāta of the Amarāvati inscription and Māthariputra Śrī Sāta of Kanheri.

² Mirashi, *Journal of the Num. Soc. of India*, II (1940), p. 90. The only clear letters are *ya-Sātakarṇi*. The ascription to Vijaya must be regarded as tentative.

Krishnā, Guṇṭūr and Bellary districts was eventually supplanted by the Ikshvākus¹ and the Pallavas.²

Provincial Government under the Śātavāhanas

A word may be said here regarding the internal organisation of the Śātavāhana empire. The sovereign

¹ The *Ikshvākus* are known from inscriptions discovered on the ruins of the Jagayyapeta stūpa in the Krishnā District and also at Nāgārjunikonda and Gurzala in the Guṇṭūr district (Ep. Ind., 1929, II.; 1941, 123 f.). They were matrimonially connected with the Kekayas, probably a ruling family of Ancient Mysore (Dubreuil, *AHD*, pp. 68, 101). The most well-known rulers of the Ikshvāku family of the Eastern Deccan are Chāntamūla, Sri-Vira-Purusha-datta, Ehuvala Chāntamūla II and possibly 'Hulupurisādāta' (Ep. Ind., xxvi, 125). The Ikshvākus were succeeded by the "Ānanda" kings of Guṇṭūr, the Brihat-phalāyanas of Kudurābāra (near Masulipatam), the Śālaṅkāyanas of Veṅḡ (cf. IA. 5, 175 and the *Salakruoi* of Ptolemy), and the Vishnukundins of Leṇḍulura (near Veṅḡ).

² The *Pallavas*—a people of unknown origin, claiming descent from Aśvatthāman and Nāga princesses, are the most important of all the dynasties that succeeded the Śātavāhanas in the Far South. The claim of descent from Brāhmanas of the Bharadvāja gotra, the performance of the *Aśvamedha* and patronage of Sanskrit learning, connect the dynasty with the Śuṅgas, while the Brāhmana-Nāga connection, (cf. *Saṅkīrṇa-jāti, Brāhma-khaṭra*, SII, Vol. xii, Nos. 7, 48) the performance of Vedic sacrifices including the horse-sacrifice, early association with the Śātavāhana Janapada in the Bellary district and the use of *Prākṛita* in their early records, connect the family with the Śātavāhanas. There is no question of any Parthian affinity as the genealogical lists of the family are singularly devoid of Parthian nomenclature. The elephant's scalp used as a crown is no test of race. The well-known hostility of the family to the Cholas and the decidedly northern character of their culture preclude the possibility of a pure Tamil extraction. The first great Pallava king, Śiva-Skanda-varman, is known from the inscriptions found at Mayidavolu (in Guṇṭūr) and Hirabadagalli (in Bellary) to have ruled over an extensive empire including Kāñchi, Andhrāpātha and Śātabani rājya, and performed the *Aśvamedha* sacrifice. About the middle of the fourth century A.D. the emperor Samudra Gupta invaded Southern India, defeated the reigning Pallava king, Viśhṇugopa, and gave a severe blow to the power and prestige of the empire of Kāñchi which, in the long run, probably led to its disruption. The evidence of the Pennakonda Plates, the Tālagunda inscription and the Hebbata grant (IHQ, 1927, 434) seems to suggest that the Pallava supremacy continued for some time to be acknowledged by the early Gaṅgas of Aconitapura and East Mysore and the early Kadambas of Vaijayanṭi (Banavāsi) and Mahiśa-Vishaya (Mysore). The history of the Pallavas

himself seems to have resided in Pratishthāna or in "camps of victory" in Govardhana (Nāsik district),

during the fifth and sixth centuries is obscure. Certain inscriptions disclose the names of the following kings, but little is known about them :—

Kings of Kṛishnā, Guṇṭūr and Nellore districts	King of Kāñchi	
	Vishṅugopa I Skandamūla Kāpagopa Virākūcha II* Skandavarman I (Skanda- śiṣya) Kumāraviśṅu I, re- covered Kāñchi. Boddhavarman, defeated Cholas. Skanda II Kumāraviśṅu II	Vayalūr, Veḍṛpulai- yam, Darsi and Chendalūr grants.
	Boddhavarman Skandavarman III Vishṅugopa II Vishṅudāsa Skandavarman IV Sinhavarman I ¹ Viravarman*	
	Skandavarman V Sinhavarman II A.D. 480? Skandavarman VI Nandivarman I Sinhavarman III, IV. (two kings of this name) Vishṅugopa III Sinhavarman V Sinhaviśṅu Mahendrarvarman I Narasinhavarman I Contemporary of Pula- keśin II.	
Odiḡoḡu I and II Uruvupalli, Maṅgalūr, Pikira, Viḷavatti and Chūra grants.	Kumāraviśṅu Skandavarman I Viravarman* (1) Vijaya Skandavarman II (Tāmbraṇa ²), (2) Yuva-mahārāja Vishṅugopa (Palakkada). (3) Sinhavarman (Daśa- napura, Menmātura and Veṅḡorāshṭra). (4) Vijaya-Vishṅugopa Varman (Vijay-Palotkata)	Udayendiram grant. Lokavibhāga A.D. 458 and Penukōḡa plates?

* Kings marked with asterisks may have been identical. But this is by no means certain. The settlement of early Pallava genealogy and chronology must still await future discoveries.

¹ A Sinhavarman is mentioned in the Palnād inscription. But his identity and date are uncertain.

² Tāmbraṇa is identified with Chembrolu.

Vaijayanti (in North Kanara) and other places.¹ The imperial dominions were divided into administrative units called *āhāra* or *janapada* and placed under rulers who fell into two classes, viz., (a) *amātyas* who were ordinary civil functionaries and (b) military governors and feudatories styled *mahāsenāpati*, *mahārāṭhi*, *mahābhoja*, and even *Rājan*. *Amātyas* are mentioned in connection with Aparānta (North Konkan), Govardhana (Nāsik), Māmāḍ(l)a (Poona), Banavāsī (North Kanara) and Khadḍavali (Godāvari region). *Mahārāṭhis* are found associated with Chitaldrug, Nānāghaṭ, Karle and Kanheri (in the North Konkan). They intermarried with the imperial family (and at times adopted its nomenclature) and also with the Chuṭu, Kauśika and Vāsishṭha² clans. The *Mahābhojas* had close relations with Chuṭu rulers of Banavāsī. *Mahāsenāpatīs* are found in Nāsik in the days of Yajña Śrī and in Bellary in the time of a Pulumāyi. The rule of these military governors, some of whom belonged to the Kauśika³ family or were matrimonially connected with it, was very much in evidence in the last days of the Śātavāhana empire. Potentates with the title of *rājā* ruled in the Kolhapur region. The most notable among these were: Vāsishṭhīputra Vilivāyakura, Mātharīputra Śivalakura and Gautamīputra Vilivāyakura (II). The Vilivāyakura group cannot fail to remind one of Balakouros of Hippokoura mentioned by the Greek geographer Ptolemy (c. 150 A. D.)

It is from the ranks of military governors and feudatories that the princes who carved out independent principalities on the dissolution of the Śātavāhana empire, evidently sprang. The Śālāṅkāyanas (Salakenoi), for

¹ E.g., Navnara—perhaps really identical with the port of Calliena (Kalyāṇa, an ancient name of which, according to the *Bombay Gazetteer*, XIV, 114, is Navānagar).

² Vāsishṭhas figure as rulers of Kālīṅga in later times.

³ A Kauśikīputra Śātakarṇi is known from a coin (*Bibliography of Indian coins*, Part I, 1950, p. 36).

example, who appear to have been a feudatory family in the Andhra country, afterwards set up an independent sovereignty. The Pallavas were doubtless connected with the military governors of the Bellary district.

The Śātakarṇis of Kuntala.

In the days of the great Gautamīputra, son of Bala Śrī, Banavāsi or Vaijayantī (Kanara) seems to have been the capital of an imperial province under an *amātya* named Śivagupta. By an obscure transition the sovereignty of the territory passed into the hands of a family, possibly styled Chuṭu in inscriptions,¹ whose connection with the Śātavāhana-Śātakarṇis is not known. The evidence of the Myakadoni inscription and notices in the *Kāmasūtra* of Vātsyāyana, the *Gāthāsaptasatī* and the *Kāvya Mīmāṃsā*, probably suggest that a group of Śātavāhanas preceded the so-called Chuṭu *kula* in Kuntala or the Kanarese country. Some of them were great patrons of Prākṛit learning. The most famous amongst them was Hāla. Another king of the group was Kuntala Śātakarṇi, mentioned in the *Kāmasūtra* whom the Purāṇas regard as a predecessor of Hāla. The Chuṭu line is represented by Hāritīputra Viṣṇukaṇḍa-Chuṭu kulānanda Śātakarṇi, Rājā of Vaijayantīpura, and his daughter's son Śiva-Skandanāga Śrī who is identified by Rapson with Skandanāga Sātaka of a Kauheri Inscription, and also with Hāritīputra Śiva-[Skanda]-varman, lord of Vaijayantī, mentioned in a Malavalli record (in the Shimoga district of Mysore). The last identification seems to be doubtful as the mother and daughter of Viṣṇukaṇḍa could hardly

¹ Some scholars do not accept the theory that Chuṭu is a dynastic designation. They regard it as a personal name. *Prog. Rep. of the ASI. W. Circle, 1911-12, p. 5.*

have belonged to the same *gotra*. Hārītiputra Śivarman was apparently succeeded by the Kadambas.¹

¹ The Kadamba line was founded by Mayūrasarman, a Brāhmaṇa, who rose against the Pallavas and helped by "Vṛihad Bāṇa" and other kings, compelled the lord of Kañchi to confer on him the *Paṭṭabandha* of military governorship. He soon pushed his conquests to the western ocean. His great-grandson Kakustha varman gave his daughters in marriage to the Gupta and other kings. Krishṇa varman I performed the *Aśvamedha*. Mṛigēśa varman defeated the Gaṅgas and Pallavas and had his capital at Vaijayanṭi. Junior branches of the family ruled at Palāṣikā, Uchchaśṛīṅgī and Tripārvata. The Kadambas were finally overthrown by the Chalukyas. See Moras, *Kadamba-Kula*; Sircar, *JIH*, 1936, 301 ff.

SECTION III. THE ŚAKAS OF UJJAIN AND KATHIAWAR.

The greatest rivals of the restored Śātavāhana Empire were at first the Śaka *Kshatrapas* of Ujjain. The progenitor of the Śaka princes of Ujjain was Ysamotika who was the father of Chashtāna, the first *Mahākshatrapa* of the family. The name of Ysamotika is Scythic.¹ His descendant, who was killed by Chandra Gupta II, is called a Śaka king by Bāṇa in his *Harsha-charita*. It is, therefore, assumed by scholars that the *Kshatrapa* family of Ujjain was of Śaka nationality.

The proper name of the dynasty is not known. Rapson says that it may have been Kārddamaka. The daughter of Rudradāman boasts that she is descended from the family of Kārddamaka kings; but she may have been indebted to her mother for this distinction. The Kārddamaka kings apparently derive their name from the Kārdama, a river in Persia.²

According to Dubreuil, **Chashtāna** ascended the throne in A.D. 78, and was the founder of the Śaka era. But this is improbable in view of the fact that the capital of Chashtāna (Tiastanes) was Ujjain (Ozene of Ptolemy), whereas we learn from the *Periplus* that Ozene was not a capital in the seventies of the first century A.D.³ The *Periplus* speaks of Ozene as a former capital, implying that it was not a capital in its own time.

¹ *JRAS*, 1906, p. 211. Lévi and Konow (*Corpus*, II. i. lxx) identify Ysamotika with Bhūmaka on the ground that the Śaka word "Ysama" means earth. But identity of meaning of names need not necessarily prove identity of persons. Cf. the cases of Kumāra Gupta and Skanda Gupta.

² Pārasika. Shamasastri's translation of the *Kautiliya*, p. 86. See also *IHQ*, 1933, 37 ff. Cf. the Artamis of Ptolemy, VI. 11. 2, a tributary of the Oxus.

³ The *Periplus* mentions Malichos (Maliku), the king of the Nabataeans, who died in A. D. 75, and Zoscales (Za Hakale), king of the Auxumites, who reigned from A. D. 76 to 80 (*JRAS*, 1917, 827-830).

The earliest known date of Chashtana is S. E. 52, i.e., A.D. 130. We learn from the Andhau inscriptions that in the year A.D. 130 Chashtana was ruling conjointly with his grandson Rudradāman. Professor Rapson and Dr. Bhandarkar point out that his foreign title *Kshatrapa*, and the use of the *Kharoshthī* alphabet on his coins, clearly show that he was a viceroy of some northern power—probably of the Kushāns. Jayadāman, son of Chashtana, seems to have acted merely as a *Kshatrapa* and to have predeceased his father, and the latter was succeeded as *Mahākshatrapa* by Rudradāman.

Rudradāman¹ became an independent *Mahākshatrapa* some time between the years 52 and 72 (A.D. 130 and 150). We learn from the Junāgaḍh Rock Inscription of the year 72 that men of all castes chose him as protector and that he won for himself the title of *Mahākshatrapa*. This probably indicates that the power of his house had been shaken by some enemy (possibly Gautamīputra), and he had to restore the supreme satrapal dignity by his own prowess.

The place names in the inscription seem to show that the rule of Rudradāman extended over Purv-āpar-Ākar-Āvanti (East and West Mālwa), Anupa-nivrit or the Mābishmatī region (Māndhātā in Nimād, or Maheśvara),² Ānartta³ (territory around Dwārakā), Surāshṭra (district

¹ For references to Rudradāman in literature, see Chatterjee, *Buddhist Studies* (ed. Law), pp. 384 f.

² IA, 4, 346.

³ Ānartta may according to some, however, designate the district around Vaḍaragara (*Bom. Gaz.* 1, i, 6). In that case Kukura may be placed in the Dwārakā region. The *Bhāgavata Purāṇa* refers to Dwārakā as "Kukur-Andhaka-Vṛishṇibhiḥ guptā" (I, 11, 10). The *Vāyu Purāṇa* (ch. 96. 131) represents Ugrasena, the Yādava rājā as *Kukuredbhava*, of Kukura extraction. In Mbh. III. 183. 32, too, Kukuras are closely associated with Daśārhas and Andhakas who are known to have been Yādava clans. In II. 52. 15 they

around Junāgaḍh), Svabhira (the country on the banks of the Sāharmatī), Maru (Mārwar), Kachehha (Cutch), Sindhu-Sauvira (the Lower Indus Valley),¹ Kukura (probably between Sind and the Pāriyātra Mt.),² Aparānta (N. Koṅkan),³ Nishāda (in the region of the Sarasvatī and the Western Vindhya),⁴ etc. Of these places Surāshṭra, Kukura, Aparānta, Anupa and Ākarāvanti formed part of Gautamīputra's dominions, and must have been conquered either from that king or one of his immediate successors. The Junāgaḍh inscription gives the information that Rudradāman twice defeated Śātakarṇi, lord of the Deccan, but did not destroy him on account of their near relationship. According to Dr. D. R. Bhandarkar this Śātakarṇi was Gautamīputra himself, whose son Vāsishṭhīputra Śātakarṇi was Rudradāman's son-in-law. According to Rapson the lord of the Deccan defeated by the Śaka ruler

are associated with the Ambashṭbas and the Pahlavas. A branch of the people may have lived in the lower valley of the Chenab and the Indus, while another branch occupied a portion of Kāthiāwār.

¹ Sindhu is the inland portion lying to the west of the Indus (Watters, *Yuan Chwang*, II. 252, 253, read with 255; Vātsyāyana, *Kāmasūtra*, Benares Ed. 295). Sauvira includes the littoral (*Milinda Pañho*, S. B. E., XXXVI, 269), as well as the inland portion lying to the east of the Indus as far as Multān (Alberuni, I, 302; IA, 7, 259). The Jaina *Pravachanasūroddhāra* names Vitabhaya as the capital.

² *Bṛihat Samhitā*, V, 71; XIV, 4.

³ Aparānta in its extended sense (cf. Aśoka, RE, V) no doubt embraces not only Sūrpāraka but Nāsik, Bharukachchha, the Mahi valley, Cutch, Surāshṭra, Anartta, Abu, etc. (*Vāyu*, 45, 129 f., *Matsya*, 114. 50-51; *Mārk.* 57, 49 f.—the Purāṇic text is corrupt and Sūrpārakāḥ Kachehiyāḥ and Anarttāḥ should be substituted for Sūryārakāḥ, Kāśmīrāḥ and Āvantiyāḥ). But as the Junāgaḍh record distinguishes Aparānta from Surāshṭra, Anartta, etc., it is clearly used here in its restricted sense.

⁴ Cf. *Nishāda-rāshṭra*, Mbh., III. 130. 4 (the place of the disappearance—*Vināśana*—of the river Sarasvatī is described as the *deśa* of *Nishādarāshṭra*): note also *Pāriyātracharāḥ*, Mbh., XII, 135, 3-5. In Mbh. ii. 31. 4-7 a Nishādabhūmi is placed between the Matsyas (of Jaipur) and the Chambal. The Vedic commentator Mahidhara explains the word Nishāda as meaning a Bhil (*Vedic Index*, I. 454). According to Bühler (IA, 7, 263) Nishāda probably corresponded with Hissar and Bhatolr.

was Pulumāyi. It is more probable that the defeated ruler was Vāsishṭhīputra Śātakarṇi himself, who may have been a brother and a predecessor of Pulumāyi.

The Great Satrap also conquered the Yaudheyas, possibly of Johiya-bār along the Sutlej, who are known, from a stone inscription, to have occupied also the Bijayagaḍh region in the Bharatpur state. If the Kushān chronology accepted by us be correct, then he must have wrested Sindhu-Sauvīra from one of the successors of Kanishka I.

Rudradāman apparently held his court at Ujjain, which is mentioned by Ptolemy as the capital of his grandfather Chasṭana, placing the provinces of Ānarta and Surāshṭra under his Pahlava (Parthian) *Amātya*¹ Suviśākha. The *Amātya* constructed a new dam on the famous Sudarśana Lake which owed its origin to the "care bestowed by the Maurya government upon question of irrigation, even in the most remote provinces."

The Great *Kshatrapa* is said to have gained fame by studying grammar (*śabda*), polity (*artha*), music (*gandharva*), logic (*nyāya*), etc. As a test of the civilised character of his rule it may be noted that he took and kept to the end of his life, the vow to stop killing men except in battle. The Sudarśana embankment was rebuilt and the lake reconstructed by "expending a great amount of money from his own treasury, without oppressing the people of the town and of the province by

¹ With this bureaucratic designation is to be contrasted the title *Rājā* applied to Tushāspa, the local ruler of Surāshṭra in the days of Aśoka, who "was more than a mere official" (*IA*, 7, 257 n). While some of the Śaka provinces or districts were placed under *amātyas* or officers whose functions were mainly of a civil character, others seem to have been governed by generals (*Mahādanda-nāyaka*). The name of such a military governor is disclosed by a Sāñchi inscription (*JASB*, 1923, 343).

exacting taxes (*Kara*), forced labour (*Vishṭi*) benevolences (*Pranaya*), and the like.¹ The king was helped in the work of government by an able staff of officials, who were "fully endowed with the qualifications of ministers" (*amātya-guṇa samudyuktaiḥ*) and were divided into two classes, viz., *Matisachiva* (Counsellors) and *Karma-sachiva* (Executive Officers).

Rudradāman had at least two sons and one daughter. The princess was given in marriage to Vāsishṭhiputra Sri Śātakarṇi of the Śātavāhana family of the Deccan. A Nāgārjunikoṇḍa inscription² refers to a princess from Ujjain named Rudradhara Bhaṭṭārikā who was the queen (*Mahādevī*) of an Ikshvāku ruler of the Guṇṭūr district and some adjoining regions in the lower Krishṇā valley. It has been surmised by Vogel that she probably belonged to the house of Chashtana. Her father is styled a *Mahārāja*, a title which seems to have been formally assumed by one of the latest successors of Rudradāman I, viz., Svāmī-Rudrasena III, who ruled from c. A.D. 348 to 378, and was, apparently, a contemporary of Samudra-Gupta. It is, however, difficult to say if the Ikshvāku queen was a daughter of Rudrasena III or of some earlier prince.

Rudradāman I, was succeeded by his eldest son **Dāmaghsada I**. After Dāmaghsada there were, according to Rapson, two claimants for the succession: his son Jivādāman and his brother Rudra Śiṃha I. The struggle was eventually decided in favour of the latter. To **Rudra Śiṃha's** reign belongs the Guṇḍa inscription of the year 103 (= A. D. 181) which records the digging of a tank by an Ābhira general named Rudradhūti, son of the general Bāpaka or Bāhaka. The Ābhiras afterwards

¹ *Bomb. Gaz.* I, 1, 39.

² *Ep. Ind.*, XX, 1 ff.

possibly usurped the position of *Mahākshatrapa*. According to Dr. Bhandarkar an Ābhira named Īśvara-datta was the *Mahākshatrapa* of the period 188-90 A. D. But Rapson places Īśvaradatta after A.D. 236.

Rudra Siṃha I was followed by his sons **Rudrasena I**,¹ Saṅghadāman and Dāmasena. Three of Dāmasena's sons became *Mahākshatrapa*, viz., Yaśodāman, Vijaysena and Dāmajada Śrī. This last prince was succeeded by his nephew Rudrasena II who was followed by his sons Viśvasiṃha and Bharṭṛidāman. Under Bharṭṛidāman his son Viśvasena served as *Kshatrapa*.

The connection of Bharṭṛidāman and Viśvasena with the next *Mahākshatrapa* **Rudradāman II** and his successors cannot be ascertained. The last known member of the line was **Rudra Siṃha III** who ruled up to at least A.D. 388.

Rapson points out that from A.D. 295 to c. 340 there was no *Mahākshatrapa*. The elder branch of the family came to an end after 305 and passed by an obscure transition to a new line of Satraps and Great Satraps. The rulers from A.D. 295 to 332 held only the subordinate title of Satrap, and the higher title was not revived till a few years before A.D. 348, when Rudrasena III styled himself *Rājā Mahākshatrapa* and *Mahārāja Kshatrapa*. Now, it is precisely during the period when the old line passed away in obscurity, and the office of *Mahākshatrapa* remained in abeyance, that we find Śakasthāna and portions of Hind annexed to the Sassanian empire and dominated by Sassanian viceroys. The Sassanian conquest began before the end of the reign of Varhrān (Bahrām) II (A. D. 293) and the Sassanian suzerainty

¹. To Rudrasena's reign belong the Mulwasar tank inscription, and the Jashdan Pillar Inscription of A. D. 205. In the latter epigraph we have the title *Bhadrāmukha* applied to all the ancestors of Rudrasena, excepting Jayadāma.

was maintained till the early part of the reign of Shāpūr II (A.D. 309-79). The hold of the Persians on the distant Indian provinces became weak in the middle of the fourth century A.D. when Rudrasena III assumed the title of *Mahārāja*, and Samudra Gupta, the prototype of the Raghu of Kālidāsa, forced the foreign potentates of the north-west borderland to do him homage.


The revived power of the Śakas of Western India did not last long, being finally destroyed by the Guptas. Already in the time of Samudra Gupta the Śakas appear among the peoples who hastened to buy peace by the offer of maidens and other acts of respectful submission. The Udayagiri Inscriptions of Chandra Gupta II testify to that monarch's conquest of Eastern Mālwa. One of the Inscriptions commemorates the construction of a cave by a minister of Chandra Gupta who "came here, accompanied by the king in person, who was seeking to conquer the whole world." The subjugation of western Mālwa is probably hinted at by the epithet "*Simha-vikrānta-gāmini*," resorting to (as a vassal of) Simha Vikrama, i.e., Chandra Gupta II, applied to Naravarman of Mandasor.¹ Evidence of the conquest of Surāshṭra is to be seen in Chandra Gupta's silver coins which are imitated from those of Śaka Satraps. Lastly, Bāṇa in his *Harsha-charita* refers to the slaying of the Śaka king

¹ *Ind. Ant.*, 1913, p. 162. The small copper coins of Chandra Gupta II bearing a vase as type were probably struck by him in the Mālava territory which may have been under Śaka domination in the second century A.D. (Allan, *CICAI*, cvi).

by Chandra Gupta : *Ar(l ?) ipure cha para-kalatra kāmukam
kāmīni-veśaguptaścha Chandra Guptaḥ Śaka-palim
aśātayaditi.*¹

¹ According to the commentator Saṅkara, the *Parakalatra* and *Kāmīni* referred to above was Dhruva-devī, and the ruler of the Śakas was secretly killed by Chandragupta disguised as Dhruva-devī while the former was making advances of love. The *Śṛīṅgāraprakāśa* by Bhoja throws additional light on the point quoting passages from the *Devichandraguptam* (see *Aiyangar Com. Vol.*, 359 ff; also Lévi, J. A., 1923, 271 ff; *Devichandraguptam* by A. Rangaswami Sarasvatī, *Ind. Ant.*, 1923, p. 181 ff.) The last mentioned work is a play by Viśākhadatta, the author of the *Mudrārākṣasa*. Quotations from the *Devichandraguptam* are also found in the *Nāṭya darpaṇa* of Rāmachandra and Guṇachandra.

GENEALOGICAL TABLE OF THE SAKAS OF UJJAIN



SECTION IV. ADMINISTRATIVE MACHINERY OF THE SCYTHIAN PERIOD.¹

The little that we know about the administration of the Scythian Epoch leaves no room for doubt that the institutions of the age were not haphazard improvisations of military upstarts, having no relations with the past, but a highly developed and organised system—the fruit of the labours of generations of political theorists and practical statesmen (*Vakṭri-Prayokṭri*).

The influence of political thinkers (*Arthachintakas*) on Indo-Scythian Polity is evident. The ablest among the princes of the time assiduously studied the science of polity (*Arthavidyā*);² and the care taken to train the occupant of the throne, the employment of officers endowed with ministerial qualifications (*Amātyaguna*), the classification of ministers and other high officials (*Sachivas*), abstention from oppressive imposition of *Pranaya* (Benevolences), *Viśṭi* (forced labour) etc., and the solicitude for the welfare of the *Pauras* and *Jānapadas*, people of cities as well as country parts, clearly show that the teaching of the writers of treatises on polity (*Arthasāstra*) was not lost upon the Scythian conquerors of India. There was no great cleavage with the past,

¹ The expression "Scythian Period" has been used in this section in a broad sense to denote the epoch of all the Post-Mauryan dynasties that ruled in India during the centuries immediately preceding and succeeding the Christian era. During the greater part of this period the most powerful potentate in India was the Scythian "King of Kings" who had his metropolis in the North-West, but whose commands were not unoften obeyed on the banks of the Ganges and the Godāvari. See *Cal. Rev.*, Sept., 1925.

² The Junāgaḍh Inscription of Rudraśāman (*Ind. Ant.*, 1978, p. 261; *Ep. Ind.*, VIII, 36 f.).

and the references to *Mahāmātras*,¹ *Rajjukas*,² and *Samcharamtaka* or *Sañchārin*³ spies, indicate that the official machinery of the Maurya period had not ceased to function at least in Southern India.

But we must not suppose that the entire administrative structure of the period was a replica of the Maurya constitution. The foreign conquerors of North-Western India brought with them several institutions which had been prevalent for ages in the countries through which they passed. Thus the Persian system of government by Satraps was introduced in several provinces of Northern, Western and Southern India, and officials with the Greek titles of *Meridarch*⁴ (probably District Officer) and *Strategos* (general or governor) ruled contemporaneously with functionaries having the Indian designation of *Amātya* (minister or civil officer in charge of a district) and *Mahāsenāpati* (great general or military governor).

The tide of Scythian invasion could not sweep away the **tribal republics** which continued to flourish as in the days of Buddha and Alexander. Inscriptions and coins testify to the existence of many such communities,⁵ and like the *Licchhavis* and *Sākya*s of old, the most powerful among them were found very often ranged against their aggressive royal neighbours who were now mostly Scythian. Unfortunately, the contemporary records do not throw much light

¹ Lüders' Ins., Nos. 937, 1144. Note the employment of a *Śramanya* as *Mahāmātra* (High Officer) by a Śātavāhana ruler.

² Ins. Nos. 416, 1195. The *Rajjukas* were Surveyors and Judges in the country parts.

³ Ins., No. 1200; cf. IA, 5, 52, 155.

⁴ A *Meridarkha* Theōdora is mentioned in a Swāt Kharoshthi epigraph. Another *Meridarkha* is mentioned in a Taxila Kharoshthi inscription. The two *meridarchs* are mentioned as establishing Buddhist relics and sanctuaries (*Corpus*, II. i. xv).

⁵ E.g., the Mālavas (Mālayas), Yaudheyas, Ārjunāyanas and possibly the Audumbaras, Kulūtas, Kunindas (see *Camb. Hist.*, 528, 529), and Uttamabhadras. Cf. Smith, *Catalogue of Coins*, Sec. VII.

on their internal organisation, and it serves no useful purpose to ascribe to them institutions which really belong to their predecessors or successors.

Though the Scythians could not annihilate the republican clans, they did destroy many monarchies of Northern and Western India, and introduce a more exalted type of kingship. The exaltation of monarchy is apparent from two facts, namely, the assumption of high-sounding semi-divine honorifics by reigning monarchs, and the apotheosis of deceased rulers. The deification of rulers, and the use of big titles are not unknown to ancient Indian literature, but it is worthy of note that a supreme ruler like Aśoka, whose dominions embraced the greater part of India and possibly Afghanistan, was content with the titles of "*Rājā*" and "*Devānampiya Piyadasi*."¹ The great rulers of the Scythian age, on the other hand, were no longer satisfied with those modest epithets, but assumed more dignified titles like *Chakravartin* (emperor of a circle of states), *Adhirāja* (super-king), *Rājātirāja* (supreme king of kings), and *Devaputra* (the son and not merely the beloved of the gods).

In Southern India we come across titles of a semi-religious character like *Kshemarāja*,² *Dharma-Mahārājā-dhirāja* and *Dharma-Yuvamahārāja*,³ assumed by pious defenders of Indian faiths, engaged in upholding *dharma* as practised by the ancient teachers and law-givers, and

¹ 'Of Gracious Mien, Beloved of the Gods.'

² Lüders' Ins., No. 1345. 'The beneficent or propitious king', 'prince of peace'.

³ "The Righteous King of Kings", "the Righteous Crown Prince". Lüders' Ins., Nos. 1196, 1200. For the significance of the title, cf. IA, 5, 51, "*Kalinuga-doshāśānna-dharmodधारणा-nitya sannaddha*." Cf. also the epithets *Manvādi-pragīta-vidhi-vidhānadharma Dharma-rāja iva*, "prakhālita-kali-kalāṅkah" applied to the Maithaka Kings of Valabhi (*Bhaenagar Inscriptions*, 31). Sometimes even Śaka rulers and generals posed as *Dharmarājāyī* (JASB, 1923, 343).

purging it of the evils of the Kali Age, probably to distinguish themselves from the unbelieving foreigners and barbarian outcastes of the North-West.

The assumption of big titles¹ by kings and emperors was paralleled by the use of equally exalted epithets in reference to their chief consorts. Aśoka's queens appear to have been styled merely *Devī*. The mother of Tivara, for instance, is called "*Dutīā Devī*" (the second queen) and the implication is that the elder queen was *Prathamā Devī*. But in the Scythian epoch we come across the titles of *Agra-Mahishī* and *Mahādevī* which distinguished the chief queen from her rivals. Among such chief consorts may be mentioned Ayasi-Kamnia, Nāganikā, and Balasrī.

The apotheosis of deceased rulers is strikingly illustrated by the practice of erecting *Devakulas* or "Royal galleries of portrait statues." The most famous of these structures was the *Devakula* of the *Pitāmaha* (grandfather) of Huvishka referred to in a Mathurā inscription.² The existence of royal *Devakulas* as well as ordinary temples,

¹ It is a characteristic of Indian history that imperial titles of one period became feudatory titles in the next. Thus the title *Rājā* used by Aśoka became a feudatory title in the Scythian and Gupta periods, when designations like *Rājarājā*, *Rājādhirāja*, *Mahārājādhirāja*, *Parama-Bhaṭṭāraka* and *Parama-Rājādhirāja* (Allan, 63), came into general use. But even *Mahārājādhirāja* became a feudatory designation in the age of the Pratihāras when the loftier style of *Paramabhaṭṭāraka*, *Mahārājādhirāja*, *Paramesvara* was assumed by sovereign rulers.

² JRAS, 1924, p. 402. For images of later kings, cf. *Beginnings of South Indian History*, 144, 153; Raverty, *Tabaqāt*, I, 622 (effigy of Bikramajit); C. S. Srinivasachari, *The Evolution of Political Institutions of South India*, Section IV ("The Young Men of India," June and July, 1924), p. 5. Images of Sundara Chola and one of his queens were set up in the Tanjore temple and deified. C. V. Vaidya (*Medieval Hindu India*, I, 98) refers to the prevalence of the custom of raising some temples at the place of burning the dead body of the kings. But it is not clear if the temples contained images of the dead king and his queens. The deification and worship of the dead kings may be compared to *decapitapūjā* referred to in the *Kautilya* (II, 6).

and the presence of the living *Devaputra* probably earned for Mathurā its secondary name of "The city (?) of the gods."¹

The exaltation of royalty in the epoch under review had the sanction of certain writers on kingly duty (*Rājadharmā*) who represented the king as a "*mahati devatā*," a great divinity, in human shape. But it was probably due in the first instance to the Scythians² who acted as carriers of Persian, Chinese and Roman ideas of kingship. The title *Rājātirāja*, supreme king overpassing other kings, as Rapson points out, is "distinctively Persian." "It has a long history from the *Xshāyathiyānām Xshāyathiya*" of the inscriptions of Darius down to the *Shāhān Shāh* of the present day." The Kushān epithet "*Devaputra*" is apparently of Chinese origin, being the literal translation of the Chinese emperors' title "Son of Heaven" (*Tien-tze* ; *tien tzu*).³ If Lüders is to be believed, one at least of the Indo-Scythian sovereigns (Kanishka of the *Ārā* Inscription)

¹ For a different suggestion see Tarn, *The Greeks in Bactria and India*, 252. Tarn prefers to translate Ptolemy's phrase as 'daughter of the gods'. But see Lévi, *JA*, 1915, p. 91.

² The titles '*Theos*' and '*Theotopos*' were used by certain Indo-Greek rulers, but their example does not seem to have been widely followed. Gondophares, it is true, calls himself *Deosarata*, but not yet *Deos* or *Devaputra*. As to the theory that the Kushāns had been invested competitively with the title "son of the gods" in opposition to the Hsiungnu rather than to the Chinese, it has to be admitted that there is no definite evidence that the title in question originated with the Hsiungnu, and was not borrowed in ancient times from the Chinese. Pace B. C. Law Volume, II, 505 ff. The Kushāns had direct contact with the Chinese in the time of Panchao.

³ Cf. the use of the term '*Kshapayitā*' in connection with the subversion of the Śuṅga sovereignty by Simuka. The expressions *Kshatrasya Kshatra* (*Bṛhad Aranyaka Upanishad*, I. 4. 14), *Adhirāja*, *Chakrapartin*, etc., are, no doubt, known to our ancient literature. But there is no proof of the use of the last two as formal styles of sovereigns till the Post-Mauryan period, while the first is never so used.

⁴ JKAS, 1897, 203; 1912, 671, 682. Allan, *Coins of the Gupta Dynasties* xvii. Artabanes (I or II) called himself 'son of a God' (Tarn, *The Greeks*,

assumed the Roman title of "*Kaisar*," and the dedication of temples in honour of emperors on the banks of the Tiber may have had something to do with the practice of erecting *Devakulas* on the banks of the Jumna.

A remarkable feature of the Scythian Age was the wide prevalence of the system of *Dvairājya* or Diarchy in Northern and Western India and *Yauvarājya* (rule of a crown-prince) in N. W. India and the Far South. Under both these forms of government the sovereign's brother, son, grandson, or nephew had an important share in the administration as co-ruler or subordinate colleague. In a *Dvairājya* or Diarchy the rulers appear to have been of equal status, but in a *Yauvarājya* (rule of a crown-prince) the reigning prince was apparently a vicegerent. As instances of *Dvairājya* may be mentioned the cases of Lysias and Antialkidas, Agathokleia and Strato I, Strato I and Strato II, Spalirises and Azes, Hagāna and Hagāmasha, Gondophernes and Gad, Gondophernes and Abdagases, Chashtana and Rudradāman, Kanishka II and Huvishka etc., etc. Among ruling *Yavarājas* may be mentioned Kharaosta and the Pallava *Yuva-Mahārājas* Siva-Śkanda-varman, Vijaya-Buddha-varman¹ and Vishnugopa of Palakkada.

The king or viceroy, resided in cities called *Adhishthāna*. The number of such *Adhishthānas* and various other kinds of cities (*Nagara*, *Nagarī*), was fairly numerous. But regarding their administration our information is very meagre. We hear of "*niḡama-sabhās*"

p. 92). This may suggest Greek influence too. Some writers fail to distinguish between occurrence of similar royal epitheta in literature and their formal use in contemporary epigraphic records in the time of the Kings themselves (*B. C. Law* Volume, II, pp. 305 ff).

¹ IHQ, 1933, 211.

or town councils and of a city official called *Nagarākshadarsa*¹ whose functions are nowhere distinctly stated in the inscriptions but seem to have been similar to those of the *Nagara-vyāvahārikas*, or city judges, of the Maurya Age.

Regarding general administration, and the government of provinces, districts and villages, we have more detailed information. The designations of some of the highest officers of state did not differ from those in vogue during the Maurya period. *Mahāmātras*, and *Rajjukas* play an important part in the days of the *Śātavāhanas* and Scythians as in the time of Aśoka. But side by side with these functionaries we hear of others who do not figure in inscriptions of the Maurya Epoch although some of them appear in the *Arthasāstra* attributed to Kautilya.

The officers most intimately associated with the sovereign were the privy councillors,—the *Matissachivas* of the Junāgaḍh epigraph and the *Rahasyādhipikṛta* of the Pallava grants. Among other prominent court officials must be mentioned the *Rāja Vaidya*,² Royal Physician, and the *Rāja Lipikara*, Royal Scribe.³

No less important than the privy councillors were the high military officials—the *Mahāsenāpati*,⁴ the *Daṇḍanāyaka* and the *Mahādaṇḍa-nāyaka*⁵ who probably

¹ EHI⁴, 226; Lüder's Ins., No. 1351 (Udayagiri Cave Inscription). Cf. *Akshadarśa*, Patañjali, *Index of Words*. Oka, *Amarakośa*, 123; *Agni Purāṇa*, 366, 3; *Vin.* iii. 47. According to the last mentioned text the '*akshadarsas*' constituted a class of *Mahāmātras*, like their prototypes in the time of Aśoka. In later ages the *Akshadarśa* might have had revenue functions. Cf. Kahtia's comment on the passage from the *Amarakośa* referred to above. The duties of the *Akshapāṭalika*s of the Gupta period may be mentioned in this connection.

² Ins., 1190-93.

³ Ins., 271; Kauṭ., II, 10.

⁴ 1124, 1146.

⁵ 1329, cf. Majumdar's *List of Kharoshthi Ins.* No. 36. For the duties of a *Daṇḍanāyaka*, cf. IA, 4, 106, 276n; 5, 49; Fleet, CII, 16. *Daṇḍanāyakas* sometimes carved out principalities (*rājya*) for themselves (JASB, 1923, 343).

correspond to the *Senāpati* and *Nāyaka* ¹ of the *Kauṭīliya Arthaśāstra*. These important functionaries had probably under them subordinates like *Senāgopas* (captains), *Gaulmikas* ² (commanders of platoons), *Ārakshādhikṛitas* ³ (guards), *Aśvavārakas* ⁴ (troopers), *Bhaṭamanushyas* ⁵ (mercenaries), etc.

We have already referred to one class of civil officers (*Amātyas* or *Sachivas*), viz., the *Matī sachivas* (counsellors). There was another class of *Amātyas* who served as executive officers (*Karma sachivas*). From them were chosen governors,⁶ treasures,⁷ superintendents,⁸ and secretaries⁹ as in the days of Megasthenes.

Among treasury officials mention is made of the *Gaṁjavara*,¹⁰ the *Koṣṭhāgārika* ¹¹ and the *Bhāṇḍāgārika* ¹² who was one of the principal ministers of state (*Rājāmātya*). But we have no epigraphic reference to the *Sannidhātṛi* (lit. piler) or the *Samāharṭṛi* (collector) till the days of the "Śaila" kings of the Vindhyas and the Somavaṁśi kings of Kosala. The main heads of revenue received into the *Bhāṇḍāgāra* or *Kośa* (treasury) were, as enumerated in the Junāgaḍh Inscription, *Bali* (extra tribute), *Śulka* (duty), and *Bhāga* (customary share of the king). These sufficed to fill the exchequer of a benevolent prince like Rudradāman with

¹ Kauṭ., Bk. X. Ch. 1, 2, 5.

² Lüders' Ins., 1200; Ep. Ind., XIV, 155; cf. Manu, VII, 190.

³ Lüders, 1200.

⁴ Lüders, 331, 728.

⁵ Lüders, 1200.

⁶ Lüders' Ins., 965.

⁷ 1141.

⁸ 1186.

⁹ 1126.

¹⁰ Lüders, 82; *Rājatarāṅginī*, V. 177. Note the employment of a Brāhmaṇa treasurer by a Scythian ruler.

¹¹ Ep. Ind., XX, 23.

¹² Lüders, 1141.

kanaka (gold), *rajata* (silver), *vajra* (diamond), *vaidūryaratna* (beryl), etc. Rulers less scrupulous than the *Mahākshatrapa* doubtless oppressed the people with arbitrary imposts, forced labour and benevolences (*kara-vishṭi-praṇaya-kriyā-bhiḥ*). Besides the *Bhāṇḍāgāra* whose existence is implied by Lüders' Ins., No. 1141, we have reference to the storehouse, *Koṣṭhāgāra*,¹ which is described in Book II, Chapter 15, of the *Kauṭīliya Arthaśāstra*. The inscriptions afford us glimpses of the way in which the revenue was spent. The attempts to provide for " *pāniya* " or drinkable water are specially noteworthy. The Junāgaḍh Inscription tells us how " by the expenditure of a vast amount of money from his own treasury " a great Scythian ruler and his *amātya* restored the Sudarśana lake. References to the construction or repair of tanks, wells, lakes and other reservoirs of water, *Pushkariṇis*, *udapānas*, *hradas* or *taḍāgas*, are fairly common. Lüders' Ins., No. 1137, makes mention of makers of hydraulic engines (*Audayantriḥ*), while another epigraph² refers to a royal official called *Pāṇiyagharika* or superintendent of waterhouses. Inscription No. 1186, after recording the gift of a *taḍāga* (pond), a *nāga* (statue of a serpent deity) and a *vihāra* (pleasance, monastery), refers to the *Amātya Śkandasvāti* who was the *Karmāntika* (superintendent of works), an official designation known to the *Arthaśāstra*.³

In the department of Foreign Affairs we have the *Dūta* (envoy or messenger), but we do not as yet hear of dignitaries like the *Sāmdhivigrahika* (officer in charge

¹ In Ins. No. 937.

² Lüders, 1279.

³ Bk. I, Ch. 12.

of peace and war) and *Kumārāmātya*¹ who figure so prominently in inscriptions of the Gupta and Post-Gupta periods.

Inscriptions of the period under review refer also to officials like the *Mahāsāmiyas* who preserved records,² and others whose exact functions and status are nowhere indicated. Amongst these may be mentioned the *Abhyamtaropasthāyaka*, 'servant of the interior (harem ?)', *Māḍabika*,³ *Tūthika* and *Neyika*.⁴

The big empires of North Western India were split up into vast satrapies and smaller provinces ruled by *Mahākshatrapas* and *Kshatrapas*. The satrapies as well as the kingdoms outside the limits of the Scythian Empire, were divided into districts called *Rāshṭra*, *Āhāra*, *Janapada*, *Deśa* or *Vishaya*. We do not as yet hear of the organisation into *Bhuktis* (lit. allotments, administrative divisions) so widely prevalent in Post-Scythian times. *Rāshṭra*, *Āhāra* (or *Hāra*) and *Janapada* seem to have been synonymous terms in this age, as is proved by the case of the *Sātahani-ratṭha* (*rāshṭra*) or *Sātavāhani-hāra* which is styled a *janapada* in the Myakadoni Inscription. The chief officer in a *Rāshṭra* or *Āhāra* was the *Rāshṭrapati*, *Rāshṭrika* (*Raṭhika*) or *Amātya*. The *Amātya Suviśākha*, for instance, governed *Surāshṭra*

¹ *Kumāra* means 'a youth', 'a prince'. Hence *Kumārāmātya* may mean 'junior minister', or 'prince's minister'. The word *Kumāra* as the opposite of *Proudhā* may correspond to *Chikka*, *Chenna* or *Immaḍi* of the South. Another interpretation is also possible. *Kumārāmātya* may mean an *amātya* from one's youth just as *Kumāra-sevaka* means *ākaumārāparichārakah*.

² For another interpretation see JBBRAS, N.S., IV, 1928, pp. 64, 72; IHQ, 1933, 221. In the opinion of V. S. Bakhle the *Mahāsāmiya* "seems to refer to the resolution of the corporate assembly of the city or to that body itself."

³ The word *Māḍabika* may perhaps be connected with *Māḍamba* of the *Jaina Kaipāsūtra*, 89. Para. 62 refers to an official styled *Māḍambiya* (Burgomaster). For a tax *Maṇḍapikā* see *Ep. Ind.*, XXIII, 137.

⁴ Sircar equates *Neyika* with *Naiyogika*.

under the *Mahākshatrapa* Rudradāman. The *Amātyas* Vishnupālita, Śyāmaka, and Śiva-skanda-datta successively governed the *Āhāra* or district of Govardhana (Nāsik) in the time of Gautamīputra Śātakarṇi and Pulumāyi, while the neighbouring *Āhāra* of Māmāla (Poona District) was under an *Amātya* whose name ended in—Gupta. In the Far South the chief officer of the *Āhāra* seems to have been called '*Vyāpṛita*.' The *Janapadas*, particularly those on vulnerable frontiers, were sometimes placed under the charge of military governors (*Strategos*, *Mahāsenāpati*, *Mahādaṇḍanāyaka*, etc.). The *Janapada* of Śātavāhani-hāra was, for instance, under the *Mahāsenāpati* Skandanāga.² Part of Eastern Mālwa seems to have been governed by a Śaka *Mahādaṇḍanāyaka* shortly before its annexation by the Imperial Guptas and portions of the Indian borderland, were governed by a line of *Strategoi* (Aspavarman, Sasa)³ under Azes and Gondophernes.

Deśa, too, is often used as a synonym of *Rāshṭra*, or *Janapada*. It was under a *Deśādihikṛita*, the *Deshmukh* of mediaeval times, an officer mentioned in the Hīrahadagalli grant of Śiva-Skanda-varman. The next smaller unit was apparently the *Vishaya* governed by the *Vishayapati*.⁴ But sometimes even '*Vishaya*' was used as a synonym of *Deśa* or *Rāshṭra*, and there were cases in the Post-Gupta period of the use of the term to designate a larger area than a *Rāshṭra*.⁵

The smallest administrative units were the villages called *Grāma* or *Grāmāhāra*,⁶ and the smaller towns or

¹ Lüders, 1327, 1328.

² Cf. the Myakadoni Inscription.

³ For an *amātya* named Sasa, see the Koḍavali Rock Inscription of the Śātavāhana king Siri Chamiḍa Śāti or Śāta (Ep. Ind., XVIII, 318).

⁴ 929n (Lüders).

⁵ Fleet, CII, 32 n.

⁶ Lüders, Ins. No. 1195.

emporia called *Nigama*.¹ The affairs of a *Grāma* were controlled by officers styled *Grāmeyika Āyutta*² who were apparently headed by the *Grāmaṇi*,³ *Grāmika*,⁴ *Grāmabhōjaka*⁵ or (*Grāma*) *Mahattaraka*. Lüders' (Mathurā) Inscription, No. 48, gives the names of two such *Grāmikas*, Jayadeva and Jayanāga. In Southern India we have the curious title "*Muluḍa*" applied to the head of a village.⁶ The chief men of the *Nigamas* were the *Gahapatis*,⁷ the counterparts of the *Grāmaṇṛiddhas* of villages. In Lüders' Inscription, No. 1153, we have evidence of the corporate activity of a *dhamma-nigama* headed by the *Gahapati*. The *Grāma* and *Nigama* organisation was the most durable part of the Ancient Indian system of government, and centuries of Scythian rule could not wipe it out of existence. The village and the *Nigamas* were also the nurseries of those ideas of associate life which found vent in the organisation of societies, committees, assemblies and corporations styled *Goshṭhīs*,⁸ *Nikāyas*,⁹ *Parishads*,¹⁰ *Samghas*,¹¹ etc., about which the inscriptions of the period speak so much. Not the least interesting of these institutions was the "*Goshṭhī*" which

¹ In Pali literature *Nigamas* are distinguished from *grāmas*, villages, as well as from *nagaras*, cities which had strong ramparts and gateways (*drīḍha prākāra toraṇa*).

² 1327.

³ 1333.

⁴ 48, 69a.

⁵ 1200.

⁶ Ins., 1194. Cf. *Muruḍa*=lord (Śaka). For the presence of Śakas in the Far South, see Ep. Ind., XX, 37.

⁷ *Gahapati*, house-lord, was a designation specially applied to the leading men of the gentry, the wealthy middle class, *Kalyāna-bhattiko*, men accustomed to a good dietary. They are often distinguished from priests and nobles (Rhyas Davids and Stede).

⁸ Lüders' Ins., 273, 1332, 1335, 1338.

⁹ 1133.

¹⁰ 125, 925.

¹¹ 5, 1137.

afforded a field for co-operation between kings and villagers. Lüders' Ins., Nos., 1332 to 1338, speak of a *Goshṭhī* which was headed by the *Rājan*, and which counted among its officials the son of a village headman.

A less pleasing feature of ancient Indian polity in the Scythian, as in other times, was the employment of spies, particularly of the "*Samcharamtakas*," or wandering emissaries, whose functions are described with gruesome details in the *Arthaśāstra*. The evidence of foreign witnesses in Maurya and Gupta periods seems, however, to suggest that political morality did not actually sink so low as a study of the *Arthaśāstra* would lead us to think. Vatsyāyana probably voices the real feelings of his countrymen when he says that every single maxim for which there is provision in a theoretical treatise need not be followed in actual practice, because theoretical manuals have to be comprehensive, but practical application should have a limited range. No sane man will think of eating dog's flesh simply because its flavour, tonic power, dressing, etc., are discussed in medical treatises.

*Na śāstramastītye tāvat prayoge kāranam bhavet
śāstrārthān vyāpīno vidyāt prayogāmstrvekadeśikān
rasa-vīrya vipākā hi śvamāmsasyāpi vaidyake
kīrtitā iti tat kiṃ syād bhakṣaṇīyaṃ vicakṣaṇaiḥ.*

CHAPTER X. THE GUPTA EMPIRE: THE RISE OF THE GUPTA POWER.

*Imām sāgaraparyantām Himavad-Vindhya-kunḍalām
mahīm ekātapatrāṅkāṁ Rājasinhā¹ praśāstu naḥ
—Dūtavākyaṁ.*

SECTION I. THE FOUNDATION OF THE GUPTA DYNASTY

We have seen that the tide of Scythian conquest, which was rolled back for a time by the Śātavāhanas, was finally stemmed by the Gupta Emperors. It is interesting to note that there were many Guptas among the officials of the Śātavāhana conquerors of the Śakas *e.g.*, Śiva Gupta of the Nāsik Inscription of the year 18, (Pura or Puru?) Gupta of the Karle inscription, and Śiva-Skanda Gupta of the same epigraph. It is difficult to say whether there was any connection between these Guptas and the Imperial Gupta family of Northern India, two of whom actually bore the names of Skanda Gupta and Puru Gupta.²

¹ With *Rājasinhā* may be compared the epithet *Narendrasinhā* occurring on coins of Chandragupta II (Allan, *Gupta Coins*, 43). All the letters here are not clearly legible (*ibid.*, cxiii), but on many coins we find the analogous epithet *Siṃha-vikrama* (pp. 38 ff.). The reference in the *Dūtavākya* must be to a paramount ruler of Northern India, bounded by the seas and the Himālayan and Vindhyan ranges, who had the epithet 'lion-like king.' The ruler who answers best to the description is Chandra Gupta II. The author of the *Dūtavākya* possibly refers to this monarch. If he is identical with Bhāsa, a distinguished predecessor of Kālidāsa, his career as a poet may have begun *before* the accession of Chandra Gupta II, Vikramāditya, 'Narendra-Siṃha,' *i.e.*, in the time of the great patron and 'king of poets' (*Kavirāja*) Samudra Gupta.

² In the *Modern Review* (November), 1929, p. 499 f., it has been suggested that the Guptas are of *Kāraskara* origin. But the evidence on the point is hardly conclusive. The identification of the "accursed" Chapaḍasena of the *Kaumudīmahotsava* (adopted son of Sundaravarman), whose family was

Scions of the Gupta family are not unoften mentioned in old *Brāhmī* Inscriptions. The Ichchhāwar¹ Buddhist Statuette Inscription² mentions the benefaction of Mahādevī, queen of Śrī Hariḍāsa, sprung from the Gupta race (*Gupta-vamśodita*). A Bharhut Buddhist Pillar Inscription³ of the Śuṅga period refers to a "Gaupṭi" as the queen of Rājan Visadeva, and the grandmother of Dhanabhūti, probably a feudatory of the Śuṅgas.

Traces of "Gupta" rule in Magadha proper, or some neighbouring tract down the Ganges, are found as early as the second century A.D. I-Tsing, a Chinese pilgrim, who travelled in India in the seventh century A.D., mentions a Mahārāja Śrī Gupta who built a temple near Mṛigasikhāvana "which was about forty yojanas

uprooted (p. 500) with Chandra Gupta I, son of Mahārāja Śrī Ghaṭotkacha whose dynasty ruled gloriously for centuries, is clearly untenable. The mere fact that Lichchhavis helped Chaṇḍasena is not enough to prove that the prince in question is identical with Chandra Gupta I. Lichchhavis appear as enemies of Magadha as early as the fifth century B.C. For a summary of the plot of the drama, which is attributed by some to a female writer, see *Aiyangar Com. Vol.*, 361f. If Sundaravarman, and his son Kalyānavarman are real historical figures, and if they actually ruled over Magadha, they must be placed either before Mahārāja Śrī Gupta or after Bālāditya (6th century A.D.). The memory of Varman ādhipatya over Magadha was fresh at the time of the Sirpur Stone Inscription of Mahāśīva Gupta (*Ep. Ind.*, XI, 191). Cf. also Pūrṇavarman and Devavarman mentioned by Chinese writers, as well as kings of the Maukhari line. The origin of the Imperial Gupta family is wrapped up in obscurity. We only know that they probably belonged to the Dhārṇa gotra (*IHQ*, 1930, 565). They may have been related to Queen Dhārīnī, the chief consort of Agnimitra. Dr. R. C. Majumdar points out (*IHQ*, 1933, 980 ff.) that according to a Javanese text (*Tantri Kāmandaka*) Mahārāja Aśvavaryapāla of the Ikshvāku race traced his genealogy to the family of Samudra Gupta. Little reliance can, however, be placed on the uncorroborated assertions of late writers. Even more unreliable is the testimony of works like the *Bharishyottara Purāṇa* which, according to some critics, 'is a palpable modern forgery' (*NHIP*, VI. 133a). Cf. *Proceedings of the I. H. Congress*, 1944, pp. 119 ff.

¹ Bāndā District.

² Lüders, No. II.

³ Lüders, No. 687.

to the east of Nālandā, following the course of the Ganges.'¹ I-Tsing's date would place him about A.D. 175.² Allan rejects the date, and identifies Śrī Gupta, with Gupta the great-grandfather of Samudra Gupta, on the ground that it is unlikely that we should have two different rulers in the same territory, of the same name, within a brief period. But have we not two Chandra Guptas and two Kumāra Guptas within brief periods? There is no cogent reason for identifying Śrī Gupta of *cir.* A.D. 175, known to tradition, with Samudra Gupta's great-grandfather who must have flourished about a century later.

The names of Śrī Gupta's immediate successors are not known. The earliest name of a member of the Gupta family of Magadha which appears in inscriptions is that of *Mahārāja Gupta* who was succeeded by his son *Mahārāja Ghaṭotkacha*.

¹ Dr. Majumdar in *A New History of the Indian People*, VI, 129; Dr. D. C. Ganguli, *IHQ*, XIV (1938), 332.

² Allan, *Gupta Coins*, Introduction, p. xv. *Cf. Ind. Ant.*, X (1881), 110.

SECTION II. CHANDRA GUPTA I.

The first independent sovereign (*Mahārājadhīrāja*)¹ of the line was Chandra Gupta I, son of Ghaṭotkacha, who *may have* ascended the throne in 320 A.D., the initial date of the Gupta Era.² Like his great fore-runner Bimbisāra he strengthened his position at some stage of his career, by a matrimonial alliance with the Lichchhavis of Vaiśālī or of Nepāl,³ and laid the foundations of the Second Magadhan Empire. The union of Chandra Gupta I with the Lichchhavi family is commemorated by a series of coins⁴ having on the obverse standing figures of Chandra Gupta and his queen, the Lichchhavi princess Kumāradevī, and on the reverse a figure of Lakshmī, the goddess of luck with the legend "*Lichchhavayah*" probably signifying that the prosperity of Chandra Gupta was due to his Lichchhavi alliance. Smith suggests that the Lichchhavis were ruling in Pāṭaliputra as tributaries or feudatories of the Kushāns and that through his marriage Chandra Gupta succeeded to

¹ In the Riddhapur plates (JASB, 1924, 58), however, Chandra Gupta I and even Samudra Gupta are called (carelessly) simply *Mahārājas*.

² JRAS, 1893, 80; Cunningham, Arch. Sur. Rep., Vol. IX, p. 21. The identity of the Gupta king with whom the era (*Gupta prakāśa*, *Guptānaṁ kāla*) of 320 A.D. originated, is by no means clear. The claims of Mahārāja Gupta (IHQ, 1942, 273 n) or even (less plausibly) of Samudra Gupta, cannot be altogether disregarded.

³ It is not suggested that the marriage took place *after* 320 A.D. The chronology of the Guptas before A.D. 380 is still in a stage of uncertainty. Nothing definite can be stated about the relative date of the marriage till we know more about the length of Chandragupta I's reign, and the exact date of his accession, and that of his son and successor, Samudra Gupta. Some scholars think that Chandragupta I's alliance was with the ruling family of Nepāl (JRAS, 1889, p. 35) or of Pāṭaliputra (JRAS, 1893, p. 81).

⁴ There is difference of opinion among scholars regarding the attribution of these coins, see Altekar in *Num. Suppl.* No. XLVII, JRASB, III (1937), No. 3, 346. It is difficult to come to any final conclusion till the discovery of coins whose attribution to Chandragupta I is beyond doubt.

the power of his wife's relatives. But Allan suggests that Pāṭaliputra was in the possession of the Guptas even in Śrī Gupta's time.¹

From the record of Samudra Gupta's conquests it has been deduced that his father's rule was confined to Magadha and the adjoining territories. In the opinion of Allan the Purāṇic verses defining the Gupta dominions refer to his reign :

*Anu-Gaṅgā-Prayāgamcha Sāketam Magadhāmstathā
Etān janupadān sarvān bhokshyante Guptaramśajāḥ.*

"Kings born of the Gupta family will enjoy all these territories viz., Prayāga (Allahabad) on the Ganges,² Sāketa (Oudh), and Magadha (South Bihār)."

It will be seen that Vaiśālī (North Bihār) is not included in this list of Gupta possessions. Therefore, it is difficult to concur in Allan's view that Vaiśālī was one of Chandra Gupta's earliest conquests. Nor does Vaiśālī occur in the list of Samudra Gupta's acquisitions, though the reference to Nepāl as a border state in the famous Allahabad inscription may suggest that North Bihār was included within his dominions. It first appears definitely as a Gupta possession in the time of Chandra Gupta II, and constituted a viceroyalty under an imperial Prince. Prāyaga (Allahabad) may have been conquered from a line of kings whose existence is disclosed in certain inscriptions discovered at Bhīṭā.³ Two of these kings, Mahārāja Gautamiputra Śrī Śivamagha and Rājan Vāsishṭhiputra Bhīmasena are

¹ Kielhorn's North Indian Inscription, No. 541, however, suggests some connection between the Lichchhavis and Pushpapura (Pāṭaliputra).

² Cf. *Anu-Gaṅgāḥ Hastinapuram, Anu-Gaṅgāḥ Vārāṇasī, Anu-Saṅgam Pāṭaliputram—Palaśjali*, II. 1. 2.

³ And Bandhogarh (Rewa)—*Amrita Bazar Patrika*, II-10-38, p. 2; *NHIP*, VI, 41 ff. The Magha kings are also known from coins (Pāṭchpur hoard).

assigned by Marshall to the second or third century A.D. The name Śivamegha (or Śivamagha) reminds us of the 'Meghas' (Maghas) who ruled in Kosalâ in the third century A.D.¹ Another king, Mahārāja Gautamîputra Vṛishadhvaṇa, is assigned to the third or fourth century A.D.

One of the most memorable acts of Chandra Gupta I was the selection, before the assembled councillors (*Sabhyas*) and princes of the blood, of Samudra Gupta as his successor.

¹ JRAS, 1911, 132; Pargiter, DKA, p. 51; see also a note on the Kosam Stone Inscription of Mahārāja Bhimacarman, by Mr. A. Ghosh in *Indian Culture*, 1936, 177 ff; see also IC, I. 694, 715.

SECTION III. SAMUDRA GUPTA PARĀKRAMAṆKA.

The exact date when Chandra Gupta I was succeeded by his son, Samudra Gupta, is not known. If the evidence of the spurious Nālandā plate (issued from Nṛipura) has any value the event may have happened before the year 5 of the Gupta Era, *i.e.*, A.D. 325. But this is doubtful. It is clear not only from the Allahabad *Praśasti* but from the epithet "*tatpādaparigrihīta*," applied to Samudra Gupta in the Riddhapur inscription, that the prince was selected from among his sons by Chandra Gupta I as best fitted to succeed him. The new monarch may have been known also as Kācha.²

It was the aim of Samudra Gupta to bring about the political unification of India (*dharani-bandha*) and make

¹ The titles *Parākrama*, *Vyāghraparākrama*, and *Parākramāṇka* are found on coins (Allan, *Catalogue*, pp. cxi, 1f) and in the Allahabad *Praśasti* (CII, p. 6). Recently a coin has been found with the legend *Śrī Vikramaḥ* on the reverse (Bamnālā hoard, Nimar district, *J. Num. Soc. Ind.*, Vol. V, pt. 2, p. 140, December, 1943).

² The epithet *Sarva-rājo-chchhettā* found on Kācha's coins shows that he was in all probability identical with Samudra Gupta. Cf. Smith, *Catalogue*, 96; IA, 1902, 259f. For another view see Smith, JRAS, 1897, 19; Rapson, JRAS, 1893, 81; Heras, *Annals of the Bhandarkar Oriental Research Institute*, Vol. IX, p. 83f. To us it is unthinkable that the style "uprooter of all kings" could have been assumed by a Gupta monarch other than the one who is actually credited with that achievement by a contemporary inscription, before the events presupposed by the expression had actually happened. In the Poona plates we find the epithet applied to Chandra Gupta II, son of Samudra Gupta, along with many other designations of the latter. But it should be remembered that the plates in question are not official records of the Guptas themselves. In no official epigraph of the Imperial Guptas is the style "*Sarva-rājo-chchhettā*" applied to any other king except Samudra Gupta. The application of the term to Chandra Gupta II in the Poona Plates is due to the same carelessness which led the writer to describe Chandra Gupta I as a mere *Māhārāja* (and not *Māhārājādhirāja*). A comparison of the Āmgaḥbhi record with the Bānagaḍ Inscription shows that writers of *Praśastis* not unoften carelessly applied to a later king enologies really pertaining to a preceding ruler.

himself an *Ekarāt* or sole ruler like Mahāpadma. But his only permanent annexation was that of portions of *Āryāvarta* in the upper valley of the Ganges and its tributaries, together with certain districts in Central and Eastern India. Following his "*Sarvakshatrāntaka*" predecessor, this *Sarva-rājo-chchhettā*, "exterminator of all kings," uprooted Rudradeva, Matila, Nāgadatta, Chandravarman, Gaṇapati Nāga, Nāgasena, Achyuta, Nandi, Balavarman, and many other **kings of Āryāvarta**,² captured the scion of the **family of Kota** and made all the kings of forest countries (*ātavika-rāja*) his servants. Rudradeva has been identified by Mr. Dikshit with Rudrasena Vākātaka. But the Vākātakas can hardly be regarded as rulers of Āryāvarta, and they were far from being uprooted in the time of Samudra Gupta.³ Equally untenable is the identification of Balavarman with a prince of Assam, a province that was then looked upon as a border state (*Pratyanta*) and not as a part of Āryāvarta. Matila has been identified with a person named "Mattila" mentioned in a seal found in Bulandshahr in the **Central Doāb**. The absence of any honorific title on the seal leads Allan to suggest that it was a private one. But we have already come across several instances of princes being mentioned without any honorific. Chandravarman has been identified with the king of the same name mentioned in the Susunia⁴ inscription, who was the ruler of Pushkarana and was

¹ Destroyer of all Kshatriyas, an epithet of Mahāpadma.

² Father Heras thinks (*Ann. Bhā. Ind.*, IX, p. 88) that Samudra Gupta undertook two campaigns in *Āryāvarta*. But his theory involves the assumption that Achyuta and Nāgasena were "violently exterminated" in the second campaign after being "uprooted" in the first. To obviate the difficulty he takes "uprooted" to mean "defeated". This is, to say the least, unconvincing.

³ Cf. IHQ, I, 2, 264. Rudrasena is connected with Deotek in the Chanda Dist. of C. P. *Eighth Or. Conf.* 613 ff. *Ep. Ind.*, xxvi, 147, 160.

⁴ "A sandstone hill 12 miles to the north-west of Bankura."

possibly the founder of Chandravarman-koṣa mentioned in the Ghugrahātī grant. Some scholars identify Pushkarapa with Pokran or Pokurna in Mārwar, and further equate Simhavarman, the name of the father of Chandravarman, with Simhavarman of the Mandasor family. But there is very little to be said in support of this conjecture. No mention of Chandravarman, or reference to his exploits, is found in any epigraphic record of the Varman family of Western Mālwa. Pushkarapa is really to be identified with a village named Pokharan on the Dāmodar river in the **Bankura** District, some 25 miles to the north-east of Susunia Hill.¹

Ganapati Nāga, Nāgasena and Nandi seem to have been Nāga princes. That Ganapati Nāga was a Nāga prince is evident. This ruler is also known from coins

¹ Cf. Dikshit, *ASI, AR*, 1927-28, p. 188; S. K. Chatterji, "The Origin and Development of the Bengali Language," II, 1061; *IHQ*, I, 2, 255. Pandit H. P. Sāstri believed that this local ruler who bore the modest title of *Mahārāja* was identical also with the mighty emperor (*bhūmipati prāpta aikādhirājya*) Chandra of the Mehrauli Iron Pillar Inscription who "in battle in the Vaṅga countries turned back with his breast the enemies who uniting together came against him and by whom having crossed in warfare the seven mouths of the Indus the Vāhlikas were conquered." Others suggest the identification of the great Chandra with one or other of the famous Chandra Guptas of the Imperial Gupta Dynasty. But Chandra is never styled either Chandravarman or Chandra Gupta and, unlike the court poets of the Varmans and Guptas, the panegyrist of the mighty Chandra, who is said to have carried his arms to the distant corners of India, never gives the slightest hint about his pedigree. He does not even mention the name of his father. It may be noted here that the *Purāṇas* represent the Nāgas as ruling in the Jammu Valley and Central India early in the fourth century A.D. We learn from the *Viṣṇu Purāṇa* that Nāga dynasties ruled at Padmāvati and Mathurā. A Nāga line probably ruled also at Vidiśā (Pargiter, *Kali Age*, p. 49). Two kings named Sadā-Chandra and Chandrāśāśa, "the second Nakhavant," are mentioned among the post-Andhran kings of Nāga lineage. One of these, preferably the latter, who was obviously a ruler of note, may have been the Chandra of the Mehrauli Inscription. The Vāhlikas beyond "the seven mouths of the Indus" are apparently the Baktrioi occupying the country near Arachosia in the time of the geographer Ptolemy (*Ind. Ant.*, 1884.

found at **Mathurā**,¹ at Pawāyā near Narwar and at Besnagar.² Nāgasena, who met his doom at **Padmāvati**³ near Narwar on the Sindhu river between Gwalior and Jhansi, is mentioned as a scion of the Nāga family in the *Harsha-charita* (*Nāga-kula-janmanah sārīkāśrāvita mantrasya āsīdnāśo Nāgasēnasya Padmāvatyām*).⁴ Nandi was also probably a Nāga prince. In the *Purāṇas* Śiśu Nandi and Nandiyāśas are connected with the Nāga family of Central India. (We know also the name of a Nāga prince named Śivanandi.⁵ Achyuta was probably a king of **Ahichchhatrā**, modern Rāmanagar in the Bareilly District. To him has been attributed the small copper coins bearing the syllables 'achyu' found at Ahichchhatrā.⁶ As to the *Kota-kula* Rapson⁷ draws our attention to certain coins bearing the inscription *Kota*. These resemble the "Śruta coins" attributed to a ruler of

p. 406). An inscription of *Mahārājadhīrāja Śrī Chandra* has been discovered on a Jaina image at Vaibhāra hill (ASI, AR, 1936-26, p. 125). The identity of this Chandra is not clear.

¹ Altekar, *NHIP*, vi, 37.

² IHQ, I, 2, 255. Note the importance of the name of this king from the point of view of religious history. Cf. *Gajamukha* of the *Bṛhat Saṃhita*, 68, 58. A reference to king Ganapati Nāga in the *Bhāsa Sataka*, a late work, is more than doubtful. *Gajasektra Śrī* of that work is a misreading for *Gata Vaktra Śrī* (IHQ, 1936, 135ff *Kāryamālā*, IV, pp. 46f, 60).

³ Padmāvati—"Padam Pawāyā (25 miles n. e. of Narwar) in the apex of the confluence of the Sindhu and the Pārā. Nāga coins have been found here; also a palmleaf capital with an inscription of the first and second century B.C." EHI², p. 300, ASI, AR, 1916-16, pp. 101 ff.

⁴ "In Padmāvati Nāgasena, born in the Nāga family, whose confidential deliberations were divulged by a sārīkā bird, met his doom."

⁵ Dubrenil, *Ancient History of the Deccan*, p. 31. It is interesting to note that Garuḍa was the emblem of the Gupta kings who did much to curb the power of the Nāgas. Cf. the passage of the Junāgaḍh Inscription of Skanda Gupta:

*Narapati bhujagānām mānadarpot phanānām
pratīkṛtī Garuḍājñām nirvāṣikīm chācākarā*

In the *Purāṇas* Kṛishṇa, the deity honoured by the Guptas, crushes the head of the serpent, nāga, Kālīya. ()

⁶ Allan, *Gupta Coins*, xxii; *CCAI*, lxxix.

⁷ JRAS, 1898, 449 f.

Śrāvastī and should apparently be referred to the upper Gangetic region.¹

The conquered territories were constituted as *Vishayas* or Imperial sub-provinces. Two of these *vishayas* are known from later inscriptions of the family, namely, Antarvedī or the Gangetic Doab and **Airikina** in Eastern Mālwa. It is significant that a **Nāga** styled the *Vishayapati* Śarva-nāga, figures as a ruler of **Antarvedī** as late as the time of Skanda Gupta.

The annexation of the northern kingdoms named above was not the only achievement of Samudra Gupta. He made the rulers of the *Āṭavika rājyas*, or forest states, his servants. But his most daring exploit was an expedition to the south, which made his power felt by the potentates of the Eastern Deccan. We perceive, however, a difference between his northern and southern campaigns. In the north he played the part of a "*digvijayī*" or "conqueror of the quarters," of the Early Magadhan type.² But in the south he followed the Epic and Kauṭilyan ideal of a "*dharmavijayī*" or "righteous conqueror," i.e., he defeated the kings but did not annex their territory. He may have realised the futility of attempting

¹ Smith (*Coins in the Indian Museum*, 258) points out that the Kota coins are common in the Eastern Panjāb and the Delhi bazaar. A Kota tribe is said to exist also in the Nilgiris (JRAS, 1897, 863; Ind. Ant., iii, 36, 96, 205). The passage in the Allahabad Inscription that "Samudra Gupta caused the scion of the Kota family to be captured by his armies and took pleasure at Pushpāhvaya" has been taken by some scholars to suggest that the *Kotas* were at the time the ruling family of Pāṭaliputra (cf. Jayaswal, *History of India*, c. 150 A.D. to 350 A.D., p. 113). The identification of the *Kota kula*, with the *Māgadha* family of the *Kaumudī-mahotsava* lacks proof.

² This kind of *Vijaya* or conquest is termed *Asura-vijaya* "demon's conquest" in the *Arthasāstra* (p. 382). The name may have been derived from the Assyrians, the ruthlessness of whose warfare is well-known. For a discussion regarding the possible derivation of *Asura* from *Aśūr*, see JRAS, 1916, 355; 1924, 265ff. Conquest of this type is first met with in India in the sixth century B.C. (cf. Ajātaśatru's subjugation of the Lichchhavis and Viṇḍubha's conquest of the Sākya) when Persia served as a link between Assyria and India.

to maintain effective control over these distant regions in the south from his remote base in the north-east of India. His successor tried to maintain his hold on the Deccan by a system of marriage alliances.

The **Āṭavika** *rājyas* undoubtedly included the realm of Ālavaka (Ghāzipur) as well as the forest kingdoms connected with **Dabhālā** or the Jabbalpur territory.¹ The conquest of this region by Samudra Gupta is suggested also by his Eraṇ inscription.

The **Kings of Dakṣiṇāpatha** who came into conflict with the great Gupta were Mahendra of Kosala, Vyāghra-rāja of Mahākāntāra, Maṇṭarāja of Kaurāla, Svāmidatta of Koṭṭūra, a chieftain of Piśṭapura whose precise name is uncertain,² Damana of Eraṇḍapalla, Viśṇugopa of Kāñchī, Nīlarāja of Avamukta, Hastivarman of Veṅgī, Ugrasena of Palakka, Kubera of Devarāshṭra, Dhanam-jaya of Kusthalapura and others.

Kosala in *Dakṣiṇāpatha*, i.e., South Kosala, comprised the modern Bilāspur, Raipur and Sambalpur districts, and occasionally possibly even a part of Gañjām.³ Its capital was Śrīpura, the modern Sirpur, about forty miles east

¹ Fleet, CII, p. 114; *Ep. Ind.*, VIII, 284-287. In the latter part of the fifth and early part of the sixth century A.D., the Dabhālā country was governed by the *Parivrajaka Mahārājas* as feudatories of the Guptas. The Mbh. ii. 31, 13-15, like the Allahabad Prāsaṣti, distinguishes the Āṭavikas from the Kāntārakas. One of the Āṭavika states may have been Koṭāṭavi mentioned in the commentary on the *Rāma-charita* of Sandhyākara Nandi (p. 36). In one epigraphic record, *Ep. Ind.*, VII, p. 126, we have a reference to a place called Vaṭāṭavi, while another, Lüder's List, No. 1195, mentions Sabalāṭavi.

² For the various interpretations of the passage "*Paiśṭapuraka Mahendragiri Kauṭṭuraka Svāmidatta*," see Fleet, CII, Vol. 3, p. 7; JRAS, 1897, pp. 420, 868-870; IHQ, 1925, 252; Barua, *Old Brāhmī Inscriptions*, 224. It is not improbable that Mahendragiri in this passage is a personal name. Cf. the name Kunāra-giri given to a chief of Koṇḍaviḍu whose territories included a portion at least of the Godāvarī district (Kielhorn, S. Ins., 596). In JRAS, 1897, 870, we have reference to Kamtagir, an ally of Sindhia.

³ Inclusion of Ratnapur, *Ep. Ind.*, X, 26; of Koṅgoda, *Ep. Ind.*, VI, 141, unless Kosala is a misreading for Tosala.

by north from Raipur.¹ Mahākāntāra is apparently a wild tract of the Central Provinces (Madhya Pradesh) which probably included Kāntāra which the *Mahābhārata* places between Venvātata (the valley of the Waingāṅgā) and Prāk-Kosala, the eastern part of Kosala mentioned above.²

Kaurāla cannot be Kolleru or Colair which must have been included within the territory of Hastivarman of Veṅgī mentioned separately. Dr. Barnett suggests its identification with one of the villages that now bears the name Korāḍa³ in South India. There is a place named Kolāḍa near Russelkonda in Gañjām.

Koṭṭūra has been identified with Kothoor, 12 miles south-east of Mahendragiri in Gañjām.⁴ Piṣṭapura is Piṭhāpuram in the Godāvari district. Eraṇḍapalla is identified by Fleet with Eraṇḍol in Khandesh, and by Dubreuil with Eraṇḍapali, "a town probably near Chicacole" in the Gañjām district.⁵ But G. Ramdas⁶ suggests the identification of Eraṇḍapalla

¹ Fleet, *CII*, p. 223. Cf. *Ep. Ind.*, xxiii. 118f.

² Mbh. II. 31. 12-13. G. Ramdas (*IHQ*, I. 4, 684) identifies Mahākāntāra with the 'Jhād-khaṇḍ' Agency tracts of Gañjām and Vizagapatam. The sway of the rājā of Mahākāntāra or "Greater Kāntāra", may have extended northwards as far as Nachna in the Ajaygarh (not Jaso) state (Smith, *JRAS*, 1914, 320). The identification of many of the southern kingdoms suggested by Mr. R. Sathianathan (in his *Studies in the Ancient History of Tamiṇamāṇḍalam*) does not carry conviction. His conclusion that Samudragupta "first emerged on the east coast at Piṭhāpuram and conquered the Western Deccan" is based upon evidence that is clearly inadequate.

³ *Cal. Rev.*, Feb., 1924, 253 n. Cf. Kurālām, Tj. 590 (*A Topographical List of Inscriptions of the Madras Presidency*, by V. Rangacharya). The identification with Yayātinagarī (*Ep. Ind.*, XI. 189), which Dboyi connects with the sports of the Keralas, was suggested in some editions of this work. But the reading Kerali in the *Paranadīpta* is not beyond doubt. For Kolāḍa see *Ep. Ind.*, XIX. 42.

⁴ There is another Koṭṭūra 'at the foot of the Hills' in the Vizagapatam district (*Vizag. District Gaz.*, I. 137). See also Koṭṭūra (*IA*, 4, 323) and Kottūr-nāḍu, MS. 338, Rangacharya's *List*.

⁵ Dubreuil, *AHD*, pp. 55-60. A place called Eraṇḍavallī is mentioned in an inscription of Govinda III (*Bhārata Itihāsa Sam. Mañjala*, AR, XVI).

⁶ *IHQ*, I. 4, p. 683. There is an Eraṇḍī *firṭha* in *Padma*, Svarga khaṇḍa, 45, 57, 61.

with Yenḍipalli in Vizagapatam or Enḍapilli in Ellore Tāluk. Kāñchī is Conjeeveram near Madras. Avamukta cannot be satisfactorily identified. But the name of its king Nilarāja reminds us of Nilapalli, "an old seaport near Yanam" in the Godāvarī district.¹ Veṅgī has been identified with Vegi or Pedda-Vegi, 7 miles north of Ellore between the Krishnā and the Godāvarī. Its king Hastivarman was identified by Hultzsch with Attivarman (of the Ānanda family).² But the more probable view is that he belonged to the Śālaṅkāyana dynasty.³ Palakka is probably identical with Palakkada, (or Pālatkaṭa) a Pallava royal residence or seat of a viceroy in Guntur or Nellore in South India. Allan and G. Ramdas locate it in the Nellore district.⁴ Devarāshṭra is the Yellamañchili tāluk of the Vizagapatam district.⁵ Kusthalapura is, according to Dr. Barnett, probably Kuttalur, near Polur, in North Arcot.⁶

The capture and liberation of the southern kings, notably of the ruler of Koṭṭūra near Mt. Mahendragiri remind us of the following lines of Kālidāsa's *Raghuvamśam* :—

*Gṛihīta-pratimuktasya sa dharma-vijayī nṛipaḥ
Śriyaṁ Mahendra-nāthasya jahāra natu medinīm*

¹ Gazetteer of the Godāvarī District, Vol. I, p. 213. Curiously enough, the *Brahma Purāṇa* (ch. 113. 22f) mentions an *Avimukta-kshetra* on the bank of the Gantami, i.e., the Godāvarī. Cf. Avimuktesvara, Anantapur, 164 of Rangacharya's List.

² Attivarman was wrongly assigned to the Pallava race. Cf. IHQ, 1, 2, p. 253; *Ind. Ant.*, IX, 102. But he is actually described as born in the lineage of the great saint Ānanda (*Bomb. Gaz.*, I. ii. 334; Kielhorn, S. Ins., 1015; *IA*, IX, 102; *ASI*, 1924-25, p. 118).

³ The name Hastivarman is actually found in a Śālaṅkāyana *Vamśāvali* (IHQ, 1927, 429; 1933, 212; Pedavegi plates of Nandivarman II).

⁴ IHQ, I. 2, 686. Cf. *Ep. Ind.*, xxiv. 140.

⁵ Dubreuil, AHD, p. 160; ASR, 1908-09, p. 123; 1934-35, 43, 65.

⁶ *Cal. Rev.*, 1924, p. 253 n. Cf. Kutalapattu, MS. 179 of Rangacharya's List.

"The righteous conqueror (Raghu) took away from the lord of the Mahendra Mountain, who was made captive and then released, his glory but not his territory."

It is not a little surprising that the Allahabad *Prasasti* contains no clear reference to the Vākāṭakas who are known to have dominated part of the region between Bundelkhand and the Penguṅgā in the fifth century A.D. The earliest reference to the Vākāṭakas occurs in certain inscriptions of Amarāvati.¹ The dynasty rose to power under Vindhyaśakti I and his son Pravarasena I. Pravara-sena appears to have been succeeded in the northern part of his dominions by his grandson Rudrasena I. Prithivishena I, the son and successor of Rudrasena I, may have been a contemporary of Samudra Gupta and perhaps also of his son Chandragupta II, inasmuch as his son Rudrasena II married the daughter of the last-mentioned Gupta emperor. Prithivishena I's political influence extended over a fairly wide territory. The Nach-nē-kī-talāi and Ganj regions² were in all probability ruled by his vassal Vyāghra-deva. Professor Dubreuil, however, says that the Nāchnā and Ganj inscriptions, which mention Vyāghra, belong, not to Prithivishena I, but to his great-grandson Prithivishena II. This is improbable in view of the fact that from the time of Prithivishena II's great-grandfather, if not from a period still earlier, down to at least A.D. 528, the princes of the region which intervenes between Nāchnā and Ganj and the proper Vākāṭaka territory,³ owned the sway of the Gupta empire.

¹ Ep. Ind., XV, pp. 261, 267.

² Fleet, CII, p. 233; Ep. Ind., XVII, 12. Cf. Ind. Ant., June, 1926.

³ This was Berar with the adjoining regions (cf. Ep. Ind., xxvi, 147). That Nāchnā and Ganj were in the Gupta Age apparently included within Dakṣiṇāpatha is suggested by the *Bṛhat Saṃhitā* (xiv, 13) which places even Chitrakūta in the Dakṣiṇa or Southern Division. A recent Vākāṭaka Inscription discovered in the Drug District contains an interesting reference to Padmapura which Professor Mirashi identifies with the ancestral home of Bhavabhūti

Now as Vyāghra of the Nāchnā and Ganj records acknowledges the supremacy of the Vākāṭaka Prithivishēṇa, this Prithivishēṇa can only be Prithivishēṇa I, who ruled before the establishment of the Gupta supremacy in Central India by Samudra Gupta and Chandra Gupta II¹ and not Prithivishēṇa II during whose rule the Guptas, and not the Vākāṭakas, were apparently the acknowledged suzerains of the Madhya Pradeśa as we learn from the records of the Parivrājaka *Mahārājas*.²

The absence of any clear reference to Prithivishēṇa I in Harishēṇa's *Praśasti* is explained by the fact that Samudra Gupta's operations were actually confined to the eastern part of Trans-Vindhyan India. There is no reliable evidence that the Gupta conqueror carried his arms to the central and western parts of the Deccan proper, i.e., to the territory ruled by Prithivishēṇa I himself. Professor Dubreuil has shown that the identification of Devarāshṭra with Mahārāshṭra and of Eraṇḍapalla with Eraṇḍol in Khandesh is probably wrong.³

Though Samudra Gupta did not invade the Western Deccan it is clear from his Eraṇ Inscription that he did deprive the Vākāṭakas of their possessions in Central India. These territories were not, however, directly governed by the Vākāṭaka monarch, but were under a vassal prince. In the time of Prithivishēṇa this prince was Vyāghra. We should naturally expect a conflict between the Vākāṭaka feudatory and the Gupta

and with the modern Padampur near Amgaon in the Bhaṇḍārā District of the Central Provinces. *IHQ*, 1935, 299; *Ep. Ind.*, xxii, 207 ff. The Basim grant implies control of a branch of the family over the part of Berar south of the Ajanta range.

¹ The Eraṇ and Udayagiri Inscriptions. For evidence of Palaeography see *JRASEB*, xii. 2, 1946, 73.

² *Cf. Modern Review*, April, 1921, p. 475. For Dubreuil's views, see *Ind. Ant.*, June, 1926.

³ *Cf. Modern Review*, 1921, p. 457.

conqueror. Curiously enough, the Allahabad *Prasasti* refers to Samudra Gupta's victory over Vyāghrarāja of Mahākāntāra.¹ It is probable that this Vyāghrarāja is identical with the Vyāghra of the Nāchnā inscription who was the Central Indian feudatory of Prithivishēṇa. As a result of Samudra Gupta's victory the Guptas succeeded the Vākātakas as the paramount power in parts of Central India. Henceforth the Vākātakas appear in fact as a purely southern power.

The victorious career of Samudra Gupta must have produced a deep impression on the **Pratyanta**² *nṛipatis* or frontier kings of North-East India and the Himālayan region, and the tribal states of the Pañjāb, Western India, Mālwa and the Central Provinces, who are said to have gratified his imperious command (*prachanḍa śāsana*) "by giving all kinds of taxes, obeying his orders and coming to perform obeisance." The most important among the eastern kingdoms which submitted to the mighty Gupta Emperor were **Samatāṭa** (part of Eastern Bengal bordering on the sea, having its capital probably at Karmmānta or Baḍ-Kamta near Comilla),³ **Ḍavāka** (not yet satisfactorily identified)⁴ and **Kmāārūpa** (in Lower Assam). We learn from the Dāmodarpur plates that the major portion of Northern Bengal, then known as Puṇḍravardhana-bhukti, formed an integral part

¹ Has the title *Vyāghra-parākrama*, found on a type of Samudra Gupta's coins that represents the king as trampling on a tiger, anything to do with the emperor's victory over *Vyāghra-rāja*? It is not a little curious that the next sovereign, conqueror of Rudrasinhha III, the last Satrap, assumed the title of *Siṃha-vikrama*.

² For the significance of the term, see *Divyāvadāna*, p. 22.

³ Bhattachali, *Iconography*, pp. 4f. JASB, 1914, 85 ff. Cf. the position of Mahārāja Rudradatta under the emperor Vainya Gupta early in the sixth century A.D. (Gunaighar Ins.).

⁴ Cf. Dekaka (Dacca), Hoyland, *The Empire of the Great Mogol*, 14. Mr. K. L. Barua identifies Davāka with the Kopili Valley in Middle Assam (*Early History of Kāmarūpa*, 42 n). For the alleged use of Gupta era in the Dabokā region, see Ep., xxvii, 18f.

of the Gupta Empire from A.D. 443 to A.D. 543, and was governed by a line of *Uparikas* as vassals of the Gupta Emperor. The identification of *Ḍavāka* with certain districts of North Bengal is, therefore, probably wrong. The Northern *Pratyantas* were Nepāl and Kārtripura. The latter principality comprised probably Katārpur in the Jālandhar district, and the territory of the Katuria or Katyur *rāj* of Kumaun, Garhwāl and Rohilkhand.¹

The **tribal states** which paid homage were situated on the western and south-western fringe of Āryāvarta proper. Among these the most important were the Mālavas, Ārjunāyanas, Yaudheyas, Madrakas, Ābhīras, Prārjunas, Sanakānīkas, Kākas and Kharaparikas.

The Mālavas occupied part of the Pañjāb in the time of Alexander. They were probably in Eastern Rājaputāna² when they came into conflict with Ushavadāta. Their exact location in the time of Samudra Gupta cannot be determined. In the time of Samudra Gupta's successors they were probably connected with the Mandasor regiōn. We find princes of Mandasor using the reckoning, commencing B.C. 58, handed down traditionally by the Mālava-gaṇa (*Mālava-gaṇ-āmnāta*).

The Ārjunāyanas and the Yaudheyas are placed in the northern division of India by the author of the *Bṛihat-Samhitā*. They may have been connected with the Pandoooi or Pāṇḍava tribe mentioned by Ptolemy as settled in the Pañjāb.³ The connection of the Ārjunāyanas

¹ EHI⁴, 302n; JRAS, 1898, 198. *Ep. Ind.*, XIII, 114; cf. J. U. P. Hist. Soc., July-Dec., 1945, pp. 217 ff, where Mr. Powell-Price suggests 'some sort of connection between the Kuṇindas and the Katyurs.'

² Cf. Smith, *Catalogue*, 161. Allan, *CCAI*, p. cv. Mālava coins have been found in vast numbers in the Jaipur State (JRAS, 1897, 883).

³ *Ind. Ant.*, XIII, 331, 349.

with the Pāṇḍava Arjuna is apparent.¹ Yaudheya appears as the name of a son of Yudhishtira in the *Mahābhārata*.² The *Harivaṃśa*, a later authority, connects the Yaudheyas with Uśinara.³ A clue to the locality of this tribe is given by the Bijayagaḍh inscription.⁴ The hill-fort of Bijayagaḍh lies about two miles to the south-west of Byānā in the Bharatpur state of Rājaputāna. But the Yaudheya territory must have extended beyond the limits of this area and embraced the tract still known as Johiyabār along both banks of the Sutlej on the border of the Bahāwalpur state.⁵

The Madrakas had their capital at Śākala or Śiālkoṭ in the Pañjab. The Ābhīras occupied the tract in the lower Indus valley and western Rājaputāna, near Vinaśana⁶ in the district called Abiria by the *Periplus*⁷ and the geography of Ptolemy. We have already seen that an Ābhīra possibly became *Mahākshatrapa* of Western India and probably supplanted the Śātavāhanas in a part of Mahārāshṭra before the middle of the third century A.D. A section of the tribe apparently settled in Central India and gave its name to the Āhirwār country between Jhansi and Bhilsa.⁸ The territories of the Prāṛjunas, Sanakānīkas, Kākas and Kharaparikas lay probably in Mālwa and the Central Provinces. The Prāṛjunakas are mentioned in the *Arthaśāstra* attributed

¹ Their coins are found in the Mathurā region (Smith, *Catalogue*, 160). The *Abhidhāna-chīntāmaṇi*, p. 434, identifies a river called Arjunī with the Babudā (Rāmgaṇḡ?).

² Ādi., 95, 76. Yaudheyas are already known to Pāṇini, V. 3, 117.

³ Pargiter, *Mārkandeya Purāṇa*, p. 380.

⁴ Fleet, CII, p. 251, Yaudheya votive tablets have been found in the Ludhiana District (JRAS, 1897, 867). Coins have been found in the area extending from Saharanpur to Multan (Allan, *CCAI*, cli).

⁵ Smith, JRAS, 1897, p. 30. Cf. Cunningham, AGI, 1924, 281.

⁶ *Sūdrābhirān prati dveshād yatra nashīā Sarasvatī*, Mbh., IX, 37. 1.

⁷ Cf. *Ind. Ant.*, III, 226 f.

⁸ JRAS, 1897, 891. Cf. *Ain-i-Akbari* II, 165; Malcolm, *CI*, I. 20.

to Kauṭilya¹ and are located by Smith² in the Narsinhapur District of the Central Provinces. A clue to the locality of the Sanakānikas is given by one of the Udayagiri inscriptions of Chandra Gupta II discovered in Eastern Mālwa. The Kākas find mention in the *Mahābhārata*³—*Ṛishikā Vidabhāḥ Kākās Taṅganāḥ Parataṅganāḥ*. In the *Bombay Gazetteer* Kāka is identified with Kākūpur near Bithur. Smith suggests that the name may be locally associated with Kākanāda (Sāñchī). The Kharaparikas may have occupied the Damoh District of the Central Provinces.⁴

The rise of a new indigenous imperial power could not be a matter of indifference to the **foreign potentates** of the North-West Frontier, Mālwa and Surāshtra (Kāthiāwār) who hastened to buy peace "by the acts of homage, such as offer of personal service, the bringing of gifts of maidens,⁵ begging for seals marked with the Garuḍa sign (*Garutmadāṅka*) to allow them to rule over their respective districts and provinces (*svavishaya bhukti*)."⁶ The foreign powers that thus established diplomatic relations with Samudra Gupta were the *Daivaputra*⁷—*Shāhi-Shāhānushāhi* and the Śaka *Muruṇḍas*⁸

¹ P. 194.

² JRAS, 1897, p. 892.

³ Mbh. VI, 9. 64.

⁴ Bhandarkar, IHQ, 1925, 258; Ep. Ind., XII, 46. H. C. Ray, *DPNI*, I, 586, mentions a Kharpara *padraka* apparently in Mālwa. A Beṇṇākārpara-*bhāga* is mentioned in the Siwani plate.

⁵ The presence of Scythian maidens in the Hindu imperial harem is not surprising in view of the known facts about Chandra Gupta Maurya's alliance with Seleukos and the marriage of a Śātakarpi with the daughter of a great satrap. Cf. also Penzer, II. 47; III. 170.

⁶ Cf. Nilakanta Sastri, *The Paṇḍyan Kingdom*, 145. "The victor restored the crown and country of the Chola in the form of a religious gift, which was confirmed by the issue of a royal rescript with the Paṇḍyan seal on it."

⁷ As to the form *Daira*, see Achaemenian inscriptions of Xerxes, and forms like Bhaimarathī (instead of Bhimarathī).

⁸ Note the imitation by Samudra Gupta of coins of Kushān type with *Ardochsho reverse* (Allan, xxviii, xxxiv, lxvi). Such coins were, according to scholars, issued by Scythians of the North-West.

as well as the people of Sindhala and all other dwellers in islands.¹

The *Daivaputra-Shāhi-Shāhānushāhi* belonged apparently to the Kushān dynasty of the north-west, which derived its origin from the *Devaputra* Kanishka.² The Śaka *Muruṇḍas* must have included the northern chiefs of Scythian nationality who issued the *Ardochsho* coins as well as the Śaka chieftains of Surāshṭra and Central India, the representatives of a power which once dominated even the Ganges valley. Sten Konow tells us that *Muruṇḍa* is a Śaka word meaning lord, Sanskrit *Svāmin*. The epithet *Svāmin* was used by the *Kshatrapas* of Surāshṭra and Ujjain. A Sāñchī inscription discovered by Marshall discloses the existence of another Śaka principality or province which was ruled about A.D. 319 by the *Mahādaṇḍanāyaka* Śrīdharavarman, son of Nanda.³ A *Muruṇḍa Svāminī* (noble lady) is mentioned in a Khoh Inscription of Central India. To Scythian chiefs of the Vindhyan region should perhaps be attributed the so-called "Puri Kushān" coins which are found in large numbers in the neighbourhood of the Eastern Vindhyas and some adjoining tracts. The

¹ Some control over the islands in the neighbouring seas is possibly hinted at in the epithet *Dhanada-Varuṇendrāntakasama*, the equal of Dhanada (Kuvera, lord of wealth, guardian of the north), *Varuṇa* (the Indian Sea-god, the guardian of the west), Indra, king of the celestials and guardian of the east, and Antaka (Yama, god of death, and guardian of the south). The comparison of Samudra Gupta with these deities is apposite and possibly refers not only to his conquests in all directions, but to his possession of immense riches, **suzerainty over the seas**, the spread of his fame to the celestial region and his extirpation of various kings. Inscriptions discovered in the Trans-Gangetic Peninsula and the Malay Archipelago testify to the activities of Indian navigators (e.g., the *Mahānāvika* from Raktapittikā mentioned in a Malayan epigraph) and military adventures in the Gupta Age.

² Smith (JRAS, 1897, 32) identified him with Grumbates. Some scholars take the expression to refer to different kings and chieftains. Cf. Allan, xxvii. There may also be a reference to the Saasanids as well.

³ Ep. Ind., xvi, p. 232; JRAS, 1923, 337 ff.

existence of a Muṛuṇḍa power in the Ganges valley a couple of centuries before Samudra Gupta is vouched for by Ptolemy.¹ The Jaina *Prabhāvaka-charita* testifies to the control that a Muṛuṇḍa family once exercised over the imperial city of Pāṭaliputra.²

Samudra Gupta's Ceylonese contemporary was Meghavarna. A Chinese writer, Wang Hsien ts'e, relates that Chi-mi-kia-po-mo (i.e., Śrī Meghavarmā or Meghavarna) sent an embassy with gifts to Samudra Gupta and obtained his permission to erect a splendid monastery to the north of the holy tree at Bodh Gayā for the use of pilgrims from the Island.³

Allan thinks that it was at the conclusion of his campaigns that the Gupta conqueror celebrated the horse-sacrifice⁴ which, we are told in the inscriptions of his successors, had long been in abeyance. But it should be noted that the *Aśvamedha* was celebrated by several kings during the interval which elapsed from the time of Pushyamitra to that of Samudra Gupta, e.g., Pārāśarīputra Sarvatāta, Śātakarṇi, the husband of Nāyanikā, Vāsishṭhīputra Ikshvāku Śrī-Chāritamūla, Devavarman Śālaṅkāyana, Pravarasena I Vākāṭaka, Śiva-skandavarman Pallava and the Nāga kings of the house of Bhāraśiva. It is probable, however, that the court poets

¹ Ind. Ant., 1884, 377; Allan, xlix; cf. *India Antiqua* (Vogel Volume, 1947), 171 f., Muṛuṇḍas in the Ganges Valley c. 245 A.D. mentioned by the Chinese.

² C. J. Shah, *Jainism in N. India*, p. 194; Cf. *Indian Culture*, III, 49.

³ Geiger, the *Mahāvastu* (trans.), p. xxxix; Lévi, *Journ. As.*, 1900, pp. 316 ff., 401 ff.; Ind. Ant., 1902, 194.

⁴ Cf. Divekar, *Annals of the Bhendarkar Institute*, VII, pp. 164-65, "Allahabad *Pratistā* and *Aśvamedha*." In the Poona plates Samudra Gupta receives the epithet *aśvakāśvamedhavyājīn*. He was believed to have celebrated more than one horse-sacrifice. Some of the campaigns described in the Allahabad panegyric may have been actually conducted by Princes or officers who kept guard over the sacrificial horse that was allowed to roam at large. In the inscription of Harishapa the credit for capturing some of the vanquished chieftains is given to the army. Among the great commanders were men like Tilabhata and Harishapa himself, who was the son of Dhruvabhāti.

of the Guptas knew little about these monarchs. After the horse-sacrifice Samudra Gupta apparently issued coins bearing the legend *Aśva-medha-parākramah*, 'whose prowess was demonstrated by the performance of the horse-sacrifice.'

If Harishena, the writer of the Allahabad *Prasasti*, is to be believed, the great Gupta was a man of versatile genius. "He put to shame the preceptor of the lord of Gods and Tumburu² and Nārada and others by his sharp and polished intellect and choral skill and musical accomplishments. He established his title of *Kavirāja* by various poetical compositions."³ "He alone is worthy of the thoughts of the learned. . . His is the poetic style which is worthy of study, and his are the poetic works which multiply the spiritual treasures of poets." Unfortunately none of these compositions have survived.⁴ But the testimony of Harishena to his musical abilities finds corroboration in the lyrist type⁵ of his coins. Himself a poet like Harsha, Mahendravarman and other kings of a later age,

¹ Rapson and Allan refer to a seal bearing a horse and the legend *Parākrama*, and the stone figure of a horse, now in Lucknow, which are probably reminiscent of the *Aśvamedha* of Samudra Gupta. (JRAS, 1901, 102; Gupta Coins, xxxi.)

² For 'Tumburu' see *Adbhuta-Rāmāyaṇa*, VI, 7; EI, I, 236.

³ According to the *Kāśya Mīmāṃsā* (3rd ed., GOS, pp. xv, xxii, 19) a "*Kavirāja* is one stage further than a *Mohākavi*, and is defined as one who is unrestrained in various languages, various sorts of poetical compositions and various sentiments." For the intellectual activities of the Gupta Age see Bhandarkar, "*A Peep into the Early History of India*," pp. 61-74 and Bühler, *IA*, 1913. The son and successor of Samudra Gupta had the title *Rūpakṛiti*, 'maker of plays'.

⁴ A poetical work called the *Kṛishṇa-charitam* is attributed to Vikramāditya Mahārājādhirāja Paramabhāgavata Śri Samudra Gupta (IO, X, 79, etc.). But the ascription has been doubted by competent critics (cf. Jagannāth in *Annals*, BORI, and others).

⁵ A late-player (*Vṛṇḍ-gāthīn*) plays an important part in the *Aśvamedha*.

the Gupta monarch associated with men of letters who were none too prosperous and "put an end to the war between good poetry and plenty" (*satkāvyasrīvirodha*). As a result "he enjoyed in the world of the learned, a far-extending sovereignty whose shining glory endured in many poems."

Samudra Gupta favoured poetry as well as the *Sāstra*, while Aśoka seems to have specialised in scriptural studies alone. The former undertook military campaigns with the object of *sarva-prithivī-jaya*, conquest of the whole earth, as known to his panegyrist, the latter eschewed military conquest after the Kalinga war and organised missions to effect *Dhamma-vijaya*, conquest of the hearts of men, in three continents. Yet inspite of these differences there was much that was common to these remarkable men. Both laid stress on *parākrama*, ceaseless exertion in the cause in which they believed. Both expressed solicitude for the people committed to their care, and were kind even to vanquished enemies. And both laid emphasis on *Dharma*. Samudra Gupta, no less than Dharmāśoka, made firm the rampart of the true law (*Dharma-prāchīra-bandhaḥ*).

The attribution of the coins bearing the name Kācha to Samudra Gupta may be accepted. But the emperor's identification with *Dharmāditya* (sun of the true faith) of a Faridpur grant is clearly wrong. The titles used by this monarch were *Apratiratha*, 'unrivalled car-warrior' *Aprativāryavīrya*, 'of irresistible valour,' *Kritānta-paraśu*, 'axe of death,' *sarva-rāj-ochchhettā*, 'uprooter of all kings,' *Vyāghra-parākrama*, 'possessed of the strength of a tiger,' *Aśva-medha-parākrama*, 'whose might was demonstrated by the horse-sacrifice,' and *Parākramāṅka*, 'marked with prowess,'

¹ Cf. the epithet "*sarva-kṣatirāntaka*" applied to his great fore-runner, Mahāpadma Nanda.

but not *Dharmāditya*. Most of these epithets are connected with particular types of coins issued by the emperor. Thus *Parākrama* is found on the reverse of coins of the standard type, *Apratiratha* on coins of the archer type, *Kṛitānta-parāśu* on coins of the battle-axe type,¹ *sarva-rājochchhetta* on coins of the Kācha type, *Vyāghra-parākrama* (*Rājā*) on the tiger type of coins, and *Aśvamedha-parākrama* on the *Aśvamedha* type.² The appearance of a goddess seated on a lion (*simha-vāhinī*, i.e., *Durgā* or *Pārvatī*, *Vindhya-vāsinī* or *Haimavatī*) may point to the extension of the Gupta dominions to the Vindhya and the Himavat.³ The tiger and river-goddess (*makaravāhinī*) type may indicate that the sway of Samudra Gupta spread from the Ganges valley to the realm of the 'Tiger king' in Mahākāntāra. The figures of Gaṅgā and Yamunā occur frequently in door jambs of the Gupta Age. It has been surmised that they symbolise connection with the Gangetic Doāb.

Samudra Gupta's 'virtuous and faithful wife,' possibly Datta Devī, appears to be mentioned in an *Eran* inscription referable to the period of his rule. We possess no genuine dated documents for the reign of the great emperor. The Nālandā⁴ and Gayā grants profess to be dated in the years 5 and 9 respectively, but no reliance can be placed on them and the reading of the numeral in the Gayā record is uncertain. Smith's date (A.D. 330-375) for Samudra Gupta is conjectural. As the earliest known date of the next sovereign is A.D.

¹ The battle-axe appears also on coins of the Uḍumbaras, *CHI*, 539; and Jayadāman, Rapson (Andhra, etc.), 76.

² Cf. 'Horse facing post' which appears also on a square coin attributed to Chashtana (Rapson *ibid*, 76) whose dynasty was overthrown by the Guptas.

³ Nana on lion of Huvishka's coins (Whitehead, 207) may have suggested this type.

⁴ ASI, AR, 1927-28, p. 138.

380-381¹ it is not improbable that his father and predecessor died some time after A.D. 375.² One of the last acts of Samudra Gupta was apparently the selection of his successor. The choice fell on Chandra Gupta, his son by Datta Devī.

¹ An inscription of Chandra Gupta II, dated in the year 61, corresponding to A.D. 380-81 was discovered in the Mathura District (*Ep. Ind.*, XXI, 1 ff.).

² Sircar (*IHQ*, 1942, 272) reads the dated portion of the inscription of the year 61 as *Sri Chandra Guptasya vijaya-rājya samvatsare pañchame*—the fifth regnal year of Chandra Gupta (II). Therefore, his first year may be taken to be A.D. 376-77.

CHAPTER XI. THE GUPTA EMPIRE—(continued): THE AGE OF THE VIKRAMĀDITYAS.

*Kāmaṁ nṛipāḥ santu sahasraśo' nye
rājanvatīmāhuranena bhūmim
nakshatra-tārā-groha saṅkulāpi
jyotishmatī Chandramasaiva rātriḥ.*

—*Raghuvamśam.*

SECTION I. CHANDRA GUPTA II VIKRAMĀDITYA.

Epigraphic evidence indicates that Samudra Gupta was succeeded by his son Chandra Gupta II, Vikramāditya, also called Narendra Chandra, Siṃha Chandra, Narendra Siṃha and Siṃha Vikrama,¹ born of queen Dattadevi. Chandra Gupta was chosen out of many sons by his father as the best fitted to succeed him.² Another name

¹ Cf. the name Vikrama Siṃha of Ujjayini, Penser, III. 11. The story narrated in *Viṣṇuśaṭa Lumbaka*, has for its hero Vikramāditya, son of Mahendrāditya, who is apparently to be identified with Skanda Gupta. But some of the motifs such as *atritasha* (*Kathā Sar.* XVIII. 3, 42), visit to the enemy's own place with a *Vetāla* (5. 40 f) were probably taken from the cycle of legends associated with Chandra Gupta II, father of Mahendra.

² That Samudra Gupta had many sons and grandsons appears clear from the Erag epigraph. The theory of Dr. Altekar (*JBORS*, XIV. pp. 223-53; XV. pt. i-ii pp. 134 f.), and others that a king named Rāma (Śarma? Śeṣa?) Gupta intervened between Samudra Gupta and Chandra Gupta II is unsupported by any contemporary epigraphic evidence. The tradition that a Gupta king killed his brother and took his wife and crown, dates only from a ninth century epigraph. The literary evidence on the point is discrepant and hardly conclusive. The version given by Bāṇa in the seventh century differs in important respects from the story known to the author of the *Kārya-Mīmāṃsā*. Cir. 900 A.D. (*Cf. Ind. Ant.*, Nov., 1933, 201 ff.; *JBORS*, XVIII. 1, 1932, 17 ff.). The simple story, narrated in the *Harsha-Charita*, that Chandra Gupta, disguised as a female, destroyed a Śaka (not Khada) king, who coveted the wife of another, in the very city of the enemy, was doubtless embellished by later poets and dramatists, and (as is clear from certain data, to which Mr. V. V. Mirasbi draws attention in *IHQ*, March, 1934, 48 ff.) details, such as fratricide and association with ghouls, not found in the earlier account, continued to be

of the new monarch disclosed by certain Vākāṭaka inscriptions, several types of coins and the Sāñchī inscription of A. D. 412-3 was Deva Gupta, Deva-śrī or Deva-rāja.¹

For the reign of Chandra Gupta II, we possess a number of dated inscriptions so that its limits may be defined with more accuracy than those of his predecessors. His accession should be placed before A.D. 381, and his death in or about A.D. 413-14.

The most important external events of the reign were the emperor's matrimonial alliance with the Vākāṭaka king Rudrasena II, son of Prithivishena I, and the war with the Śaka Satraps which added Western Mālwa and Surāshṭra (Kāṭhiāwār) to the Gupta dominions.

Matrimonial alliances occupy a prominent place in the foreign policy of the Guptas. The Lichchhavi connection had strengthened their position in Bihār. After the conquest of the upper provinces they sought alliances with other ruling families whose help was needed to consolidate the Gupta power in the newly acquired territory and prepare the ground for fresh conquests. Thus Samudra Gupta received presents of girls (*kanyopāyana*) from Śaka-Kushān chiefs and other foreign potentates. Chandra Gupta II married

added in the days of Amoghavarsha I (A. D. 315-78) and Govinda IV (A.D. c. 927-939). The *Devī Chandraguptam* and similar works are as much unsuited to form bases of the chronicles of Chandra Gupta II as the *Mudrārākshasam* and the *Aśokāvadāna* are in regard to the doings of the great Mauryas. The subject has been fully discussed by the present writer in an article entitled "*Vikramāditya in History and legend*" contributed to the Vikrama-volume, Scindhia Oriental Institute (1918), pp. 433-511. The story of Chandra Gupta's adventure in its developed form has absorbed a good deal of folklore, such as tales about ghouls, *Piśācha*. The motif of the wife leaving a mean-spirited husband is found in Penzer, *Kathā S. S.*, III. 290.

¹ Cf. Bhandarkar, *Ind. Ant.* 1913, p. 160.

Kuberanāgā, a princess of **Nāga** lineage,¹ and had by her a daughter named Prabhāvatī, whom he gave in marriage to Rudrasena II, the Vakāṭaka king of Berar and the adjoining districts. According to Dr. Smith² "the Vakāṭaka *Mahārāja* occupied a geographical position in which he could be of much service or disservice to the northern invader of the dominions of the Saka satraps of Gujrāt and Surāshṭra. Chandra Gupta adopted a prudent precaution in giving his daughter to the Vākāṭaka prince and so securing his subordinate alliance."

The campaign against the Western Satraps is apparently alluded to in the Udayagiri Cave Inscription of Virasena-Śāba in the following passage "he (Śāba) came here (to Eastern Mālwa), accompanied by the king (Chandra Gupta) in person, who was seeking to conquer the whole world." Śāba was an inhabitant of Pāṭaliputra. He held the position, acquired by hereditary descent, of a *Sachiva* or minister of Chandra Gupta II, and was placed by his sovereign in charge of the Department of Peace and War. He naturally accompanied his master when the great western expedition was undertaken. Eastern Mālwa, which had already felt the might of Samudra Gupta, became the base of operations against the Śakas. Inscriptions at Udayagiri and Sāūchī suggest that the emperor Chandra Gupta II assembled at or near Vidiśā in East Mālwa many of his ministers, generals and feudatories, some of whom are

¹ *Nāga-kulotpannā*, cf. JASB, 1924, p. 56. It is possible, as urged by many writers, that Chandra Gupta Vikramāditya also entered into marriage alliances with the Kadambas of Valjayanti or Banavāsi in Kuntala, or the Kanarese, country. The sending of an embassy to Kuntala by Vikramāditya, is vouched for by Bhoja and Kshemendra. (*Proceedings of the Third Oriental Conference*, p. 6.) Kakusthavarmaṇ of the Kadamba dynasty gave his daughters in marriage to the Gupta and other kings in or about the fifth century (Talagunda Inscription, Ep. Ind., VIII, 33 ff. ; IHQ, 1933, 197 ff.).

² JRAS, 1914, p. 394.

mentioned in records dating from A.D. 402 to 413. The campaign against the Śakas was eminently successful. The fall of the Śaka Satrap is alluded to by Bāṇa. The annexation of his territory is proved by coins.¹

Chief Cities of the Empire.—The first important Gupta metropolis seems to have been at Pāṭaliputra—"the city named Pushpa" where Samudra Gupta is said to have "rested on his laurels" after one of his victorious campaigns, and from which a Gupta Minister for Peace and War went to East Mālwa in the company of his sovereign. From A.D. 402 Chandra Gupta seems to have had a residence in Mālwa, at first possibly at Vidiśā and later on, after his western conquests, at Ujjain. Certain chiefs of the Kanarese districts, who claimed descent from Chandra Gupta (Vikramāditya), referred to their great ancestor as *Ujjayini-puravar-ādhiśvara*, 'lord of Ujjain, the best of cities,' as well as *Pāṭalipuravar-ādhiśvara* 'lord of Pāṭali (putra), the best of cities.' Sir R. G. Bhandarkar identifies Chandra Gupta II with the traditional Vikramāditya *Śakāri*, "the sun of valour, the destroyer of the Śakas," of Ujjain.² The titles *Śrī*

¹ Silver coins of the Garuḍa type bearing the legend *Parama-Bhāgucata*, probably struck in Surāṣṭra (Allan, p. xciv). Some of the coins bear the date 90 (=A.D. 409, EHI, 4th ed., p. 345). It has been suggested that, like his father, Chandra Gupta, too, performed a horse sacrifice (IBQ, 1927, p. 725) and that a stone horse lying in a village named Nagawa near Benares, and bearing an inscription containing the letters Chandra-gu, commemorates the event. But there is no clear reference to such a sacrifice in the inscriptions or coins hitherto published.

² In literature Vikramāditya is represented as ruling at Pāṭaliputra (*Kathā-sarit-sāgara*, VII, 4, 3:—*Vikramāditya ityāsidrāja Pāṭaliputrake*) as well as Ujjayini and other cities. Śāhasāṅka of Ujjain is said to have ordered the exclusive use of Sanskrit in his realm *Kāya Mīmāṃsā*, 3rd. ed. p. 50). He thus reversed the policy of Aṣṭyaśāha (p. 197) or Śālavāha of Kuntala. Cf. the verse in *Sarvasatī Kaṣṭhābharaṇa* II, 15.

*Ke'bhunn Aṣṭyaśāha rājye prakṛta-bhāṣhinah
kūle Śrī Śāhasāṅkasya ke na Saṃskṛtitaśādinah.*

Among the *Kāya-kāras* tested in Ujjain mention is made of a Chandra Gupta along with Kālidāsa, Amara, Bhāravi and others (*Kāya M.*, p. 55).

Vikramah, Simha-Vikramah, Ajita-Vikramah, Vikramāṅka and *Vikramāditya* actually occur on Chandra Gupta's coins.¹

We have no detailed contemporary notice of Ujjayini (also called Viśālā, Padmāvati, Bhogavati, Hiranyavati)² in the days of Chandra Gupta. But Fa-hien who visited Mid India during the period A.D. 405 to 411, has left an interesting account of Pāṭaliputra. The pilgrim refers to the royal palace of Aśoka and the halls in the midst of the city, "which exist now as of old," and were according to him "all made by spirits which Aśoka employed, and which piled up the stones, reared the walls and gates, and executed the elegant carving and inlaid sculpture-work,—in a way which no human hands of this world could accomplish." "The inhabitants are rich and prosperous, and vie with one another in the practice of benevolence and righteousness. Every year on the eighth day of the second month they celebrate a procession of images... The Heads of the *Vaiśya* families

Paramārtha, the biographer of Vaṇḍanabha, refers to Ayodhya as the capital of a Vikramāditya while Hsien Tsang represents Śrāvastī as the seat of the famous king (EHI, 3rd Ed., pp. 332-33). Subandhu refers to the fame of Vikramāditya, but not to his capital city, "like a lake Vikramāditya hath left the earth, save indeed in fame" (Keith, *Hist. Sans. Lit.*, p. 312). Cf. Hāla, v. 64.

¹ Name, title or epithet.

Type of coin.

Śri Vikrama	Archer type (gold).
			Couch type (gold).
Vikramāditya	Chhatra (Parasol) type (gold).
Rūpakṛti	Couch type (gold).
Simha-Vikrama, Narendra Chandra,			Lion-Slayer (gold)
Narendra Simha, Simha Chandra			
Ajita-Vikrama	}	...	Horseman type (gold).
Paramabhāgavata		...	
Paramabhāgavata	}	...	Silver coins of the Garuḍa type.
Vikramāditya		...	
Vikramāṅka		...	
Vikramāditya, Mahārāja, Chandra		...	Copper coins (Garuḍa, Chhatra and Vase type).

² Meghadūta (I, 31) and *Kathā-sarit-sāgara*, Tawney's translation. Vol. II, p. 276. For an account of Ujjayini in the seventh century A.D., see Béal, H. Tsang, II, p. 270; and Ridding, *Kādambari*, pp. 310 ff.

establish houses for dispensing charity and medicines." The principal port of the empire on the east coast was Tāmralipti or Tamluk in West Bengal from which ships set sail for Ceylon, Java (then a centre of Brāhmaṇism), and China.

Much light is thrown on the character of Chandra Gupta Vikramāditya's **administration** by the narrative of Fa-hien and the inscriptions that have hitherto been discovered. Speaking of the Middle Kingdom, the dominions of Chandra Gupta in the upper Ganges Valley, the Chinese pilgrim says: "the people are numerous and happy; they have not to register their households, or attend to any magistrates and their rules; only those who cultivate the royal land have to pay a portion of the gain from it. If they want to go, they go: if they want to stay on, they stay. The king governs without decapitation or other corporal punishments. Criminals are simply fined, lightly or heavily, according to the circumstances of each case. Even in cases of repeated attempts at wicked rebellion they only have their right hands cut off. The king's bodyguards and attendants all have salaries. Throughout the whole country the people do not kill any living creature, nor drink intoxicating liquor, nor eat onions or garlic. The only exception is that of the *Chāṇḍālas*. In buying and selling commodities they use *cowries*."¹ The last statement evidently refers to such small transactions as Fa-hien had occasion to make.² The pilgrim does not seem to have met with the gold coins which would only be required for large transactions. That they were actually in currency, we know from the references to "*dīnāras*" and "*suvarṇas*" in inscriptions.³

¹ Legge.

² Allan.

³ Chandra Gupta II also issued silver and copper coins. The silver coins were mainly intended for the western provinces conquered from the Śaka satrapa

That Chandra Gupta II was a good monarch may be inferred also from the inscriptions. Himself a devout *Vaishṇava* (*Parama-bhāgavata*), he appointed men of other sects to high offices. His general *Āmrakārdḍava*, the hero of a hundred fights, *anēkasamar-āvāpta-vijaya-yaśas-patākāḥ*, appears to have been a Buddhist or at least a pro-Buddhist, while his Minister of Peace and War, *Sāba-Vīrasena*, and perhaps also his *Mantrin* or High Counsellor, *Śikharasvāmin*, were *Saivas*.

Regarding the machinery of Government we have no detailed information. But the following facts may be gleaned from the inscriptions. As in Maurya times, the head of the state was the *Rājā* who was at times nominated by his predecessor. The king is now regarded as a divinity—*Achintya Puruṣa*, 'the Incomprehensible Being' *Dhanada-Varuṇendrāntaka-sama*, the equal of Kuvera, Varuṇa, Indra and Yama, *loka-dhāma deva*, 'a god dwelling on earth,' *Paramadaivata*, 'the supreme deity.' He was assisted by a body of High Ministers whose office was very often hereditary as is suggested by the phrase "*anvaya-prāpta sāchivya*" 'acquirer of the post of minister by hereditary descent', of the Udayagiri Inscription of *Sāba*.¹ The most important among the High Ministers were the *Mantrin*, 'High Counsellor,' the *Sāṁdhi-vigrahika*, 'Minister for Peace and War,' and the *Akshapaṭal-ādhikṛita*, 'the Lord

but they are also mentioned in the time of his son in inscriptions of Northern Bengal. The Baigram inscription of the year 128 (448 A.D.) for instance refers to *rūpakas* along with *dīnāras* (cf. Allan, p. cxxvii). The copper coins issued by Chandra Gupta II are commonly found around Ayodhyā (Allan, p. cxxxi).

¹ The *Mahā-daṇḍa-nāyaka* Harisheṣa was the son of the *Mahādaṇḍa-nāyaka* Dhruva-bhūti. The *Mantrin* Prithivishēṣa was the son of the *Mantrin* Śikharasvāmin. Cf. also the hereditary governors (*gopṭṛi*), of Mandsor, Surāshṭra, etc. Things were somewhat different in the Maurya Period. Pushya Gupta, *Rāshṭriya* of Surāshṭra in the time of Chandra Gupta Maurya, was quite unconnected by blood with Tushāṣṭra, governor or feudatory in the time of Aśoka.

Keeper of State Documents.¹ Like the Kauṭilyan *Mantrin*, the Gupta *Sāmdhi-vigrahika* accompanied the sovereign to the battle-field. As in the case of most of the *Pradhānas* of Śivājī there was no clear-cut division between civil and military officials. The same person could be *Sāmdhi-vigrahika*, *Kumārāmātya* (cadet-minister), and *Mahā-daṇḍa-nāyaka*, 'great commandant of the army,' and a *Mantrin* could become a *Mahā-bal-ādhikṛita* 'chief commander of forces.'²

It is not clear whether the Guptas had a central council of ministers (*Mantri-parishad*).¹ But the existence of local *parishads* (e.g., the *Parishad* of Udānakūpa) is proved by a Basārḥ seal discovered by Bloch.

The empire was divided into a number of provinces styled *Deśas*, *Bhuktis*, etc., sub-divided into districts called *Pradeśas* or *Vishayas*.² Among *Deśas* the Gupta inscriptions mention Śukuli-deśa. Śurāshṭra (Kāthiāwāḍ), Dab-hālā (the Jubbulpore region, Dāhala or Chedi of later times) and "Kālīndī Narmadayor Madhya,"² the territory lying between the Jumna and the Nerbudda, and embracing, no doubt, Eastern Mālwa, are also perhaps to be placed under this category.

Among *Bhuktis* (*lit.* allotments) we have reference in inscriptions of the Gupta and early Post-Gupta Age to Puṇḍra-varḍhana *bhukti* (North Bengal), Vardhamāna *bhukti* (West Bengal) Tīrabhukti (North Bihār), Nagara *bhukti* (South Bihār), Śrāvastī *bhukti* (Oudh), and Ahichchhatra *bhukti* (Rohilkhand), all situated in the Ganges valley. Among *Pradeśas* or *Vishayas* mention is made of Lāṭa-*vishaya* (in continental Gujarāt), Tripurī-*vishaya* (in the Jubbulpore region), Airikīṇa in Eastern

¹ The Bilsāḍ Ins. (CII, 44) refers to a [Pa]rshad. But there is nothing to show that it was a central political assembly. The *Sabhyas* mentioned in connection with the nomination scene in the Allahabad Pillar Inscription may, however, have been members of a Central *Curia Regis* or Council.

² A territorial unit styled *Vithī* is also known.

Mālwa (called *Pradeśa* in Samudra Gupta's Eran inscription, and *Vishaya* in that of Toramāṇa), Antarvedī (the Gangetic Doāb), Vālavi (?) Gayā, Koṭivarsha (the Dinājpur region in North Bengal), Mahākhusāpāra (?), Khādātāpāra (?) and Kuṇḍādhāni.¹

The *Deśas* were governed by officers called *Goptris*, or Wardens of the Marches, as is suggested by the passage *Sarveshu Deśeshu vidhāya Goptrin* 'having appointed Goptris in all the *Deśas*.' The *Bhuktis* were usually governed by *Uparikas* or *Uparika Mahārājas* who were sometimes apparently princes of the Imperial family, e.g., *Rājaputra-deva-bhaṭṭāraka*, Governor of Puṇḍravardhana *bhukti* mentioned in a Dāmodarpur plate, Govinda Gupta, Governor of Tirabhukti mentioned in the Basārḥ seals² and possibly Ghaṭotkacha Gupta of Tumain in Central India. The office of *Vishaya-pati* or District Officer was held by Imperial officials like the *Kumār-āmātyas* and *Āyuktakas*,³ as well as by feudatory *Mahārājas* like Mātri-vishṇu of Eran. Some of the *Vishayapatis*, e.g., Sarvanāga of Antarvedī,⁴ were possibly directly under the Emperor, while others, e.g., those of Koṭivarsha, Airikīṇa and Tripurī, were usually under provincial Governors. The Governors and District Officers were no doubt helped by officials and dignitaries like the *Dāṇḍika*, *Chaur-oddharanika* and *Daṇḍapāśika*⁵ (apparently judicial and police officials), *Nagara Śreshṭhī* (President or Alderman of a city-guild), *Sārthavāha* (lit. caravan-leader or merchant), *Prathama-Kulika* (foreman of artisans) *Prathama-Kāyastha* (the

¹ Cf. Kuṇḍadhāna, a town mentioned in the *Book of the Gradual Sayings*, I. 18 n.

² Govinda Gupta is known also from the newly discovered Mandasor Ins. of the Mālava—Vikrama year 524 (noticed by Garde, *ASI. Annual Report*, 1922-23, p. 187; *Cal. Rev.*; 1926, July, 155; *Ep. Ind.*, xix, App. No. 7; xxvii, 12 ff.) which mentions his *Senādhipa* or captain Vāyurakṣita, and Vāyu's son Dattabhaṭa, Commander-in-chief of the forces of king Prabhākara (467-68 A.D.).

³ They are also known as officers apparently in charge of *vithis* or smaller units.

⁴ And Kulaviddhi of Pañchanagarī (in North Bengal), *Ep. Ind.*, xxi, 81.

⁵ Cf. Dandoāsi, Village Watchman, *JASB*, 1916. 30.

chief scribe), *Pusta-pāla* (record-keeper) and others. Every *Vishaya* consisted of a number of "grāmas" or villages which were administered by headmen and other functionaries styled *Grāmikas*, *Mahattaras* and *Bhojakas*.¹

Outside the limits of the Imperial provinces lay the vassal kingdoms and republics, mentioned in the Allahabad *prasaṣti* and other documents.

The Basārḥ seals throw some interesting sidelight on the provincial and municipal government as well as the economic organisation of the province of Tīrabhukti (Tirhut) in North Bihār. The province was apparently governed by prince Govinda Gupta, a son of the Emperor by the *Mahādevī* Śrī Dbruva-svāminī, who had his capital at Vaiśālī. The seals mention several officials like the *Uparika* (governor), the *Kumār-āmātya* (cadet-minister),² the *Mahā-pratihāra* (the great chamberlain),

¹ In the *Mṛichchhakatika* (Act IX), which may be a composition of the period between Bāṇa (who knew a king Sūdraka, but no poet of the same name) and Vāmana (8th century) the judge (*adhikaraṇika*) in a court of law is accompanied by a *śreṣṭhin* and a *Kāyastha*. Reference is also made to the *Adhikaraṇa-Bhojakas* and a *Mahattaraka* in connection with the arrangement of benches in the *Vyāvahāra-maṇḍapa* (the hall of justice) and the detection of people "wanted" by the city Police (*nagara-rakṣa-ādhiḥkṛta*.) The *Mudrārākṣha* of Viśākhadatta which is probably to be assigned to a period anterior to Rājaśekhara, the Dasarūpa and Bhoja, perhaps also to Vāmana but not to Avantivarman (of the Maukhari or Utpala dynasty) or Dantivarman (Rāshṭrakūṭa or Pallava) whose name or names occur in the *Bharata Vākya*, makes mention of *Kāyastha*, *Daṇḍapāśika*, etc. Village functionaries were ordinarily placed under officials of the *Vishaya* or district. But in exceptional cases they had direct dealings with the *Uparika* or governor of a *Bhukti* (*Ep. Ind.*, XV, 136).

² It has been taken to mean (1) minister of a Prince as distinguished from that of the King (*rājāmātya*), (2) minister in charge of Princes, C. V. Vaidya, *Med. Hind. Ind.*, I, 133, (3) a junior minister whose father is alive, or (4) one who has been a minister since the days of his youth. But cf. *Ep. Ind.*, X, 49; XV, 302 f. It will be seen that the *Kumārāmātyas* were, as stated by a previous writer, divided into two classes, viz., (i) *Yuvarājapādiya*, those serving the Crown Prince, and (ii) *Parama-bhṭārakapādiya*, those serving the Emperor himself. This perhaps makes the interpretation 'counsellor of, or in charge of the Prince' untenable. See, however, Penzer. I. 32; III. 136. The most probable view is that the term *Kumāra* in the expression *Kumārāmātya* corresponds to

Talavara (general or local chief),¹ the *Mahā-daṇḍa-nāyaka* (the great commandant), the *Vinayasthiti*² *sthāpaka*,³ the censor [?], and the *Bhaṭṭāśvapati* (lord of the army and cavalry), and the following offices, e.g., *Yuvarāja-pādīya Kumar-āmātya-ādhikaraṇa* (office of the Minister of His Highness the Crown Prince, according to Vogel), *Raṇabhāṇḍāgār-ādhikaraṇa*⁴ (office of the chief treasurer of the war department), *Balādhikaraṇa* (war office), *Daṇḍapāś-ādhikaraṇa* (office of the chief of Police), *Tīra-bhukty-Upārik-ādhikaraṇa* (office of the Governor of Tirhut), *Tīrabhuktau Vinayasthiti-sthāpak-ādhikaraṇa* (office of the censor [?] of Tirhut), *Vaiśāly-ādhishtān-ādhikaraṇa* (office of the government of the city of Vaiśālī), *Srī-parama-bhaṭṭāraka-pādīya Kumār-āmātya-ādhikaraṇa* (office of the cadet-minister waiting on His Majesty).⁵

The reference to the *Parishad* (Council or Committee) of Udānakūpa shows that the *Parishad* still formed an important element of the machinery of local government. The mention of the 'mote-hall of aldermen of guilds, caravan-leaders and foremen of artisans' (*Śreṣṭhī-sārthavāha-kulika-nigama*) is of interest to students of economics.

Pina, *Chikka*, *Immadi*, *Ilaya*, of the south, and is the opposite of *Peda* (*Praṇḍha*), *Piriya*. In the Gupta Age the Kumārāmātyas often served as district officers. The office was also combined with that of a general, counsellor and foreign secretary.

¹ Cf. *talāra* of the Chirwā Inscription of Samara Siṃha.

² Dr. Basak takes *Vinaya-sthiti* in the sense of law and order (*The History of North-Eastern India*, p. 312).

³ In the *Nāṭya-śāstra*, *Sthāpaka* is the designation of the introducer of a play (Keith, *Sanskrit Drama*, p. 340). Here a different functionary may be meant.

⁴ The mention of *Raṇa-bhāṇḍāgāra* suggests that the finance department had its military as distinguished from the civil side.

⁵ A distinction is drawn between imperial officials and those connected with viceregal administration and amongst the latter officers of the province of *Tīra-bhukti* are clearly distinguished from the public servants in charge of the subordinate administration of the *ādhishtāna* of *Vaiśālī*.

Chandra Gupta II had at least two queens, Dhruvadevi and Kubera-nāgā. The first queen was the mother of Govinda Gupta and Kumāra Gupta I.¹ The second queen had a daughter named Prabhāvatī who became queen of the Vākāṭakas. The latter was the mother of the Princes Divākarasena, Dāmodarasena and Pravarasena II (or III). Certain mediaeval chiefs of the Kanarese country claimed descent from Chandra Gupta. The origin of these chiefs is probably to be traced to some unrecorded adventures of Vikramāditya in the Deccan.²

¹ A son of Chandra Gupta styled *bhūpati* (king) Chandraprakāśa is mentioned in a verse quoted by Vāmana in his *Kāryālaṅkāra-Sātraṭṭhi* (JASB, Vol I, No. 10, [N.S.], 1905, 253 ff.). But the identity of this Chandra Gupta is uncertain. His identification with Vikramāditya (i.e., Chandra Gupta II) rests on the vexed problem of the date of Vasubandhu (or Sobandhu ?) alleged to be mentioned by Vāmana, and the question as to whether the personage mentioned may be identified with the Buddhist scholar whose biographer was Paramārtha (A.D. 500-59). Paramārtha was a Brāhmaṇa of the Bhādrarāja family of Ujjayini who stayed for a time in Magadha and then went to China (A. D. 546-60.) According to his account Vasubandhu was born at Purushapura or Peśāwār, of the Brāhmaṇa family of Kauśika. He went to Ayodhyā at the invitation of Bālāditya, son of Vikramāditya (JRAS, 1905, 89 ff.). For some recent views about the date of Vasubandhu, see *Indian Studies in Honour of G. R. Lanman*, 79 ff.

² Rājasekhara in his *Kāryamīmāṃsā* and Bhoja, in his *Śrīṅgāra Prakāśikā*, mention that Kālidāsa was sent on an embassy to a Kuntala king by Vikramāditya. "Kṣemendra, in the *Aucitya Vicāra Carcā*, refers to Kālidāsa's *Kuntalacara Dantya*" (*Proceedings of the Third Oriental Conference*, 1924, p. 6). That the Guptas actually established contact with Kuntala appears clear from the Talagund Inscription which states that a Kadamba ruler of the Kanarese country gave his daughters in marriage to the Gupta and other kings. An important indication of Gupta influence in the South Western Deccan is possibly afforded by the coins of Kumāra Gupta I found in the Satara District (Allan, p. cxix.) The rôle assigned to Kālidāsa by Rājasekhara, Bhoja and Kṣemendra is not unworthy of credence as tradition points to a date for him in the early Gupta Age. For traditions about his synchronism with Mahārājādhirāja Vikramāditya (*Sakārditi*) and Dignāga and with king Pravarasena who is held to be the author of the poem *Sobandha* written in *Mahārāṣṭri* Prakṛita and is, therefore, presumably identical with one of the kings bearing the same name in the Vākāṭaka family, (recorded in Abhinanda's *Rāmacharita*, ch. 32, Hala, *Gāthāślokaśatī*, Bhūmika, p. 8 and other works) see *Proceedings of the Seventh Oriental Conference*, 29 ff.; Mallikarāja's comment on *Meghadūta*, I. 14; *Ind. Ant.*, 1912, 267; JRAS, 1918, 118f. It has recently been

✓ SECTION II. KUMĀRA GUPTA I MAHENDRADITYA.

Chandra Gupta II's successor was Kumāra Gupta I¹ surnamed Mahendrāditya² whose certain dates range from A.D. 415 to A.D. 455.³ His extensive coinage, and the wide distribution of his inscriptions show that he was able to retain his father's empire including the central and western provinces.⁴ One of his viceroys, Chirātadatta, governed Puṇḍravardhana *Bhukti* or roughly North

¹ The Mandasor inscription of the Mālava year 524 suggests that Kumāra may have had a rival in his brother prince Govinda Gupta. In the record Indra (*vinadhā dhīpa*, Kumāra?), who is styled Śrī Mahendra and Mahendrakarmā on coins) represented as being suspicious of Govinda's power. *Ep. Ind.*, XIX, App. No. 7 and n. 5; *Ep.* xxvii. 15.

² Also called *Śrī Mahendra* (on coins of the Archer type), *Aśvamedha Mahendra* (on coins of the *Aśvamedha* type), *Mahendrakarmā*, *Ajita Mahendra* (on coins of the horseman type and sometimes on the lion-slayer type), *Siṃha Mahendra* (on coins of the lion-slayer type), *Śrī Mahendra Siṃha* (also on coins of the lion-slayer type), *Mahendra Kumāra* (on coins of the peacock type) *Mahendra-kalpa* (Tumain Ins.), *Siṃha Vikrama* (on coins of the lion-slayer type; Allan, *Gupta Coins*, p. 80). *Vyāghra bala-parākrama* (on coins of the tiger-slayer type) and *Śrī Pratāpa*. On the swordman type of gold coins and on copper coins of the Garuḍa and possibly *siṃha-sāhina* types the emperor is simply called Śrī Kumāra Gupta. The title Mahendrāditya with the epithet *Parama bhāgavata*, 'devoted worshipper of the Bhagavat (Viṣṇu-Kṛishṇa),' is found on silver coins, apparently struck in Surāshṭra.

³ The date 96 (=A.D. 415) is found in the Bilsar Inscription and the date 136 (=A.D. 455) on silver coins (*EHI*, 4th ed., pp. 345-46). The Erag inscription of Samudra Gupta refers to his 'virtuous and faithful wife' and many sons and son's sons of the royal pair. From this it seems probable that Kumāra Gupta and his brothers were already born during the reign of their grandfather, and that Kumāra had seen not less than some thirty five summers before his accession. As he reigned for at least forty years, he could not have died before the age of 75 (approximately).

⁴ The possession of the central districts in the Ganges valley is, according to Allan, confirmed by the silver coins of the peacock type (cf. the Ayodhyā coins of Āryamitra, *CHI*, I. 638 and Meghadūta I. 45.) and the inclusion of the western province by those of the Garuḍa type. Silverplaited coins with a copper core were intended for circulation in the Valabhi area, and coins of small thick fabric resembling the Traikutaka coinage were apparently struck in South Gujarāt (Allan, pp. xciii ff.)

Bengal,¹ another viceroy, prince Ghaṭotkacha Gupta, held office in the province of Erap (in Eastern Mālwa) which included Tumbavana²; a third viceroy or feudatory, Bandhuvarman, ruled at Daśapura in western Mālwa.³ The Karamadāṇḍe inscription of A. D. 436 mentions Prithivishena who was a *Mantrin* and *Kumārāmāya*, and afterwards *Mahā-balādhikṛita* or general under Kumāra Gupta, probably stationed in Oudh. The panegyrist of a Mālwa viceroy claims that the suzerainty of Kumāra Gupta extended over "the whole earth which is decked with the rolling seas as with a rocking girdle, which holds in its breast-like mountain altitudes the

¹ Cf. the Dāmodarpur plates of the years 124 and 128. (*Ep.* xvii. 193). The Baigram inscription of the year 128 (A. D. 447-48) refers to a *Kumārāmāya* named Kulaviddhi who governed a *vishaya* with its headquarters at Pañchagari, possibly Pañchabibi or Pañchgaḍ on the Karatoyā, *H. Standard* 14-10-47 in N. Bengal. *Ep. Ind.*, XXI, 78 ff. Year Book, ASB, 1950, 200. The Sultanpur or Kalaikudi Inscription (Bangaśrī 1350 B. S. *Baīākhya*, pp. 415-51 and *Bhādra*; IHQ XIX. 12) of the year 126=A. D. 439 in the Bogra district, makes mention of another officer, the *Āyuktaka*, Achyutadāsa of Purgakauṣikā in Śrīgavera-vīthi. The Natore Inscription of A. D. 432 (JPASB, 1911) is another record of Kumāra's reign found in N. Bengal.

² Tumain in the Guna district of the Gwalior state, about 50 miles to the north-west of Erap. M. B. Garde, *Ind. Ant.*, xlix 1920, p. 114, *Ep. Ind.* xxvi (1911), pp. 115 ff: Tumain Inscription of the year 116, i.e. A. D. 435. The identity of the prince mentioned in the record, with Śrī Ghaṭotkacha Gupta of seals and Ghaṭo Kramāditya of coins is uncertain (Allan, xvi, xi, liv) Hema Chandra (in the *Parīkṣita parvaṇ*, xii, 2-3) places Tumbavana in the Avantideśa, 'the ornament of the western half of Bhārata' in Jambūdvīpa.

Ihaiva Jambūdvīpe 'pūy Bhoratārdha vibhūṣaṇam

Avantirīti deśo 'sti vṛgodeśiya riddhibhiḥ

tatra Tumbavanamīti vidyate sanniveśanam

³ Mandasor Inscription of A. D. 437-38. Bhāde suggests (*JBOAS*, VII, March, 1921, pp. 33 f) that Viśva-varman of Gupta Ins. No. 17 is an independent king, who flourished a century before his namesake of ins. No. 18, who is a governor (*Goptrī*) of the Guptas. S. Majumdar points out that even Viśva-varman of Ins. No. 17 must be later than Naravarman of V. S. 461 (=A. D. 404-05). In the Bihar Kotra (Rāīgaḍh state, Mālwa) Ins. (*Ep. Ind.* xxvi. 130 ff) of Mahārāja Naravarman of the year 474 (i.e., A. D., 417-18) the king is styled 'auṭhara', thus establishing his connection with Viśhuvardhana of the Mālava Era 580 (A. D. 532-33)

founts of the vivifying liquid, and smiles with the flowers of its forest glens.¹

Like his father, Kumāra was a tolerant king. During his rule the worship of *Svāmī* Mahāsena (Kārttikeya), of Buddha, of Śiva in the *līṅga* form and of the sun, as well as that of Viṣṇu, flourished peacefully side by side.¹

The two notable events of Kumāra's reign are the celebration of the horse sacrifice, evidenced by the rare *Aśva-medha* type of his gold coinage, and the temporary eclipse of the Gupta power by the **Pushyamitras**. The reading Pushyamitra in the Bhitari inscription is, however, not accepted by some scholars because the second syllable of this name is damaged.² Mr. H. R. Divekar in his article—“*Pushyamitras in the Gupta Period*”³ makes the plausible emendation *Yudhy = amitrāś = ca* for Dr. Fleet's reading *Pushyamitrāś = ca* in the Bhitari Pillar Inscription.⁴ It is admitted on all hands that during the concluding years of Kumāra's reign the Gupta empire “had been made to totter.” Whether the reference in the inscription is simply to *amitras* (enemies), or to Pushyamitras, cannot

¹ Cf. the Bilsad, Menkuwar, Karamadāṇḍe and Mandasor inscriptions. Śiva appears to have been the favourite deity of many high ministers, Viṣṇu of the most powerful ruling race and the son of traders and artisans in the early Gupta period. The expression *Jitam Bhagavata* appears to have been popularised by the king. His example seems to have been followed by Mādhava Gaṅga of Penukonda plates (Ep. Ind. XIV. 331), Viṣṇuvarman I Kadamba of Hebbata grant (Mys. A. S., A. R., 1925. 98), Nandivarman Pallava of Udayendiram (Ep. Ind., III. 145) and other kings of the south. The popularity of the cult of Kārttikeya is well illustrated not only by the sanctuaries erected in his honour, but also by the names Kumāra and Skanda assumed by members of the imperial family, and the issue of the peacock type of coins by the emperor Kumāra Gupta I. The Gupta empire reached the zenith of its splendour before its final decline in the time of the originator of the ‘peacock’ coins, as a later empire did in the days of the builder of the peacock-throne.

² Cf. Fleet, CII, p. 55 n.

³ *Annals of the Rhendarkar Institute*, 1919-20, 93 f.

⁴ CII, III, p. 55.

be satisfactorily determined. We should, however, remember in this connection that a people called Pushyamitra is actually referred to in the *Vishṇu Purāṇa* and a Pushyamitika-Kula in the Jain *Kalpasūtra*.¹ The *Purāṇa* text associates the Pushyamitras, Paṭumitras, Durmitras and others with the region of Mekalā near the source of the Nerbudda.² References to the warlike activities of Mekalā and the neighbouring realm of Kosalā that had once been overrun by Kumāra's grandfather, are found in inscriptions of the Vākāṭaka relations of Kumāra Gupta. Bāṇa relates the tragic story of a ruler of Magadha who was carried off by the ministers of the lord of Mekalā. A passage in the Mankuwar stone image inscription of the year 129 (A.D. 449) where the emperor Kumāra Gupta I is styled simply *Mahārāja Śrī* instead of *Mahārājādhirāja Śrī* has been interpreted by some scholars to mean that he was possibly deprived by his enemies of his status as paramount sovereign. But the theory is rendered improbable by the Dāmodarpur plate of about the same date where Kumāra is given full imperial titles. It may be noted in this connection that in several inscriptions, and on certain coins, his immediate predecessors, too, are simply called *Rājā* or *Mahārāja*.

The assumption of the title *Vyāghra-bala-parākrama* "displaying the strength and prowess of a tiger", on coins of the *tiger-slayer* type, by Kumāra may possibly indicate that he attempted to repeat the southern venture of his

¹ SBE, XXII, 292 *Cf.* the legend *Pushamitasa* found on Bhiṭṭa seals in characters of the Kushān period or a somewhat earlier date (JRAS, 1911, 138).

² Vish. IV, 24, 17; Wilson, IX, 213. "Pushyamitra, and Paṭumitra and others to the number of 13 will rule over Mekalā." The commentary, however, distinguishes the 13 Pushyamitra-Paṭumitras from the 7 Mekalās. But from the context it is apparent that the position of the Pushyamitras was between the Māhiśhyas (people of Māhiśmatī ?) and the Mekalās in the Nerbudda-Son valleys if not in a part of the country of the Mekalās themselves. *Cf.* Fleet, JRAS, 1889, 229, *cf.* also Bhiṭṭa seals. For Mekalā see also *Ep. Ind.* xxvii 138 f.

grandfather and penetrate into the tiger-infested forest territory beyond the Nerbudda. Expansion towards the south is also indicated by a find of 1,395 coins in the Satara District.¹ But the imperial troops must have met with disaster. The fallen fortunes of the Gupta family were restored by prince Skanda Gupta who may have been appointed his father's warden in the Ghāzīpur region, the Aṭavi or Forest Country of ancient times.²

The only queen of Kumāra I named in the genealogical portion of extant inscriptions is Anantadevī. He had at least two sons, viz., Puru Gupta, son of Anantadevī, and Skanda Gupta the name of whose mother is, in the opinion of some scholars, not given in the inscriptions. Sewell, however, suggests that it was Devakī.³ This is not an unlikely assumption as otherwise the comparison of the widowed Gupta empress with Kṛishṇa's mother in verse 6 of the Bhitari Pillar Inscription will be less explicable. Hiuen Tsang calls Buddha Gupta (*Fo-to-kio-to*) or Budha Gupta,⁴ a son (or descendant ?) of Śakrāditya.⁵ The only predecessor of Budha Gupta who had a synonymous title was Kumāra Gupta I who is called Mahendrāditya on coins. *Mahendra* is the same as *Śakra*.

¹ Allan, p. cxxx. Cf. also the Kadamba inscription referring to social relations between the Kadambas of the fifth century and the Guptas.

² Cf. the Bhitari Inscription.

³ *Historical Inscriptions of Southern India*, p. 343.

⁴ The name *Fo-to-kio-to* has been restored as Buddha Gupta. But we have no independent evidence regarding the existence of a king named Buddha Gupta about this period. The synchronism of his successor's successor Bālāditya with M hiraṇka indicates that the king meant was Budha Gupta, cf. also *Ind. Ant.*, 1886, 251 n.

⁵ That Śakrāditya was a reality is proved by a Nālandā seal (H. Sastri, *MAI*, No. 66, p. 38). To him is ascribed an establishment at Nālandā, the far-famed place, which grew into a great university in the seventh century A. D. The pilgrim was not indulging in mere fancy as suggested by Śri N. Śāstri in a treatise on Nālandā.

The use of terms conveying the same meaning as titles and epithets was not unknown in the Gupta period. *Vikramāditya* was also called *Vikramāṅka*. Skanda Gupta is called both *Vikramāditya* and *Kramāditya*, both the words meaning "puissant like the sun" or "striding like the sun." If Śakrāditya of Hiuen Tsang be identical with Mahendrāditya or Kumāra I, Buddha Gupta¹ was closely related to Kumāra. Another member of Kumāra's family was possibly Ghatotkacha Gupta.²

Recent discoveries show that Budha Gupta was really a grandson (not a son) of Kumāra Gupta I. The Chinese pilgrim may have failed to distinguish between a son and a grandson. Cf. The Koppāram plates where Pulakeśin II is represented as a grandson of Kirtivarman I. But he was really the son of the latter. It is also possible that Śakrāditya was an epithet of Purugupta, the father of Budha.

¹ The Tumain Inscription referred to by Mr. Garde; cf. also the Basārh seal mentioning Śrī Ghatotkacha Gupta. The exact relationship with Kumāra is, however, not stated in the inscription.

SECTION III. SKANDA GUPTA VIKRAMADITYA.

According to the evidence of the *Ārya-Mañjuśrī-mūla-kalpa*, confirmed by epigraphic testimony, the immediate successor of Mahendra, i.e., Kumāra Gupta I, was Skanda Gupta. In an interesting paper read at a meeting of the *Asiatic Society of Bengal*, Dr. R. C. Majumdar suggested that after Kumāra's death, which apparently took place while the struggle with the Pushyamitras was still undecided, there was a fratricidal war in which Skanda Gupta came off victorious after defeating his brothers including Puru Gupta, the rightful claimant, and rescued his mother just as Kṛishṇa rescued Devakī.¹ Dr. Majumdar observed that the omission of the name of the mother of Skanda Gupta in the genealogy given in the Bihār and Bhitari Stone Pillar Inscriptions indicated that she was not the chief queen and Skanda 'had no natural claim to the throne'. The rightful heir of Kumāra was Puru Gupta, the son of the *Mahādevī* Anantadevī.

We should, however, remember that there was no rule prohibiting the mention of ordinary queens in inscriptions. The mother of Princess Prabhāvatī, Kuberaṇāgā, was not the chief queen of Chandra Gupta II.² No doubt the title *Mahādevī* is once given to her in the Poona plates of her daughter in the year 13, but it is not repeated in the Riddhapur plates of the year 19, where she is called simply Kuberaṇāgā devī without the prefix *Mahādevī*, whereas Kumāra-devī, Datta-devī and even her own daughter, Prabhāvatī-guptā are styled *Mahādevīs*. The contrast is full of significance and we know as a matter of fact that the real *Mahādevī* (chief queen) of Chandra

¹ Cf. the Bhitari Inscription, JASB, 1921 (N. S. XVII), 253 ff. In IC. 1944, 171, Dr. Majumdar modified his views regarding the omission of the name of the queen mother in the Bihar ins. and finds the names of Mahādevī Anantadevī and her son Purugupta in the inscription.

² JASB, 1924, 58.

Gupta II was Dhruva-devī or Dhruva-Svāminī. Though Kubera-nāgā was not the principal consort (*agramahishī*) of her husband, she is mentioned in the inscriptions of her daughter. On the other hand the names of queens, the mothers of kings, are sometimes omitted.¹ In the *genealogical portion* of the Banskhera and Madhuban plates the name of Yaśomatī as *Harsha's mother* is not mentioned, but in the Sonpat and the Nālandā seals² she is mentioned *both* as the mother of Rājya-var dhana and as the mother of Harsha. Therefore it is not safe to draw conclusions from a comparison of genealogies given on seals and those given in ordinary praśastis. From a comparative study of the seals and plaques referred to above on the one hand and ordinary panegyric epigraphs on the other, two facts emerge, viz., (a) genealogies given by the records of the former class are fuller than those given in the others, and (b) names of mothers of reigning kings that are invariably given (even though this meant repetition) in documents of the first group are sometimes omitted by the writers of praśastis, even though they be the names of the chief queens. There is no real analogy between the genealogy on the Bhitari seal and that in the Pillar Inscriptions. A seal should be compared to another seal and an ordinary praśasti with another document of the same class.³

¹ The name of the father of a reigning king is also sometimes omitted (cf. Kielhorn's N. Ins. Nos. 464, 468).

² A. R. of the ASI. Eastern Circle, 1917-18, p. 44; *Ep. Ind.* XXI. 74 ff. *MASt.* No. 66, 68 f.

³ We have already seen that in the opinion of Sewall the name of Skanda's mother is actually mentioned in one epigraph. According to that scholar her name was Devaki. The comparison with Kṛishṇa's mother (who, with all her misfortunes, did not experience the pangs of widowhood) in the Bhitari Inscription would be less explicable, if not altogether pointless, if Devaki was not the name of the mother of Skanda Gupta as well as that of Kṛishṇa. Why were Kṛishṇa and Devaki thought of in connection with the victory over hostile powers, instead of, say, Skanda (Kārttikeya) and Pārvatī, Indra or Viṣṇu and Aditi,

As to the question of rightful claim to the succession, we should remember that the cases of Samudra Gupta and Chandra Gupta II suggest that the ablest among the princes was chosen irrespective of any claim arising out of birth.

There is nothing to show that the struggle at the end of Kumāra's reign, referred to in the Bhitari Pillar Inscription, was a fratricidal conflict. The relevant text of the inscription runs thus :

*Pitari divam upētē viplutām vaiṣṇa-lakṣmīm
bhūja-bala-cijit-ārīr-yyaḥ pratishṭhāpya bhūyaḥ
jītam-iti paritoshān mātaram sāsra-nettrām
hala-ripur-iva Kṛishṇa Devakīm-abhyupetaḥ*

"Who, when (his) father had attained heaven (i.e., died), vanquished (his) enemies by the strength of (his) arm, and steadied once more the drifting fortunes of his family; and then exclaiming 'the victory has been won' betook himself, like Kṛishṇa, when his enemies had been slain, to his weeping mother, Devakī"¹

The hostile powers (*arī*), who made the *Vaiṣṇa-lakṣmī*, goddess of family fortune, of Skanda Gupta "*vipluta*," 'convulsed,' after the death of his father, were apparently enemies of the Gupta family, i.e., outsiders not belonging to the Gupta line. As a matter of fact the antagonists expressly mentioned in the Bhitari Pillar

by the panegyrist of Skanda Gupta who is compared to Sakra (*Sakropama*, Kahaṇṇ Inscription) and Viṣṇu (*Śrīparīkṣīptacakṣa*, Junāgaḍh epigraph) ? A possible explanation is that the name of his mother coupled with her miserable plight suggested to the court poet comparison with Kṛishṇa and Devakī. Cf. Ep. Ind. I, 364; xii, 126, 131 (Hampe and Conjeeveram ins. of Kṛishṇadeva Rāya) where we have a similar play on the name Devakī :—

*śatcūṣṭhe Derakijānirddidipe Timma bhūpatih
pāṇṇavi Tuluvendroḥṇu Yadoh Kṛishṇa iṣṇvaye ..
sarasāḍadabhāttaśmān Narasāvanipālakaḥ
Devakīnanḍanāt tear. 'nāndanoh) Kāmo Devakī nāndanādita.*

The problem, however, is not free from difficulties and its final solution must await fresh discoveries.

¹ For the reference to Devakī, see *Viṣṇu Purāṇa*, V, 72.

Inscription were outsiders, *e.g.*, the Pushyamitras¹ and the Hūpas. There is not the slightest reference to a fratricidal war. There is no doubt a passage in the Junāgaḍh Inscription of Skanda which says that "the goddess of fortune and splendour (Lakshmī) of her own accord selected (Skanda) as her husband (*svayam varayam-chakāra*)...having discarded all the other sons of kings (*manujendra-putra*)."² But "*Seayameva śriyā grihīta*" "accepted by Śrī or Lakshmī of her own accord" is an epithet which is applied by Prabhākara-varḍhana, shortly before his death, to Harsha whose devotion to his elder brother is well-known. That Skanda Gupta like Harsha was considered to be the favourite of the Goddess of Luck is well-known. Attention may be invited to the Lakshmī type of his coins³ and the epithet *Śrī-parikshipta-vakshāḥ* ("whose breast is embraced by Śrī, *i.e.*, Lakshmī"), occurring in the Junāgaḍh Inscription. The panegyrist of the emperor refers to a *seayambara* in the conventional style.⁴ A *seayambara* naturally presupposes an assemblage of princes, not necessarily of one particular family, in which all the suitors are discarded excepting one. But there is no inseparable connection between a *seayambara* and a fight, and, even when it is followed by a fight, the combatants are hardly ever princes who are sons of the

¹ Even if the reference be merely to "amitras" (see *ante*, p. 563), these amitras could not have included an elder brother, as the passage "*kakṣīpa-charaṇapīṭhe sthāpita vāma-pādah*," "placed (his) left foot on a foot-stool which was the king (of that hostile power himself)" clearly shows. The expression *samudita bāja kośa* ("whose power and wealth had risen") would be singularly inappropriate in the case of the rightful heir to the imperial throne of the Guptas with its enormous resources existing for several generations, and can only point to a *purseu* power that had suddenly leaped to fame.

² Allan, p. xcix.

³ Cf. *Ep. Ind.*, I. 25.

*Gārjjarāśvara-rājya-Śrīr
gaya jāyā seayambara*

The *Seayambara* of Lakshmī forms the subject of the drama which Urvashī acts before Indra with her sister nymphs (JASB, 59, 32).

same king. The epigraphic passage referring to Lakshmi's *svayambara*, therefore, does not necessarily imply that there was a *struggle* between the sons of Kumāra in which Skanda came off victorious. It only means that among the princes he was specially fortunate and was considered to be the best fitted to rule because of the valiant fight he had put up against the enemies of the family and empire. In the Allahabad *praśasti* we have a similar passage:—"who (Samudra Gupta) being looked at with envy by the faces, melancholy through the rejection of themselves, of others of equal birth...was bidden by his father,—who exclaiming 'verily he is worthy' embraced him—to govern of a surety the whole world." It may be argued that there is no proof that Skanda was selected by Kumāra. On the contrary he is said to have been selected by Lakshmi of her own accord. But such was also the case with Harsha. Skanda like Harsha was called upon to save the empire of his forbears at a time when the fortunes of the imperial family were at a low ebb, and both these eminent men owed their success to their own prowess. The important thing to remember is that the avowed enemies of Skanda Gupta mentioned in his inscriptions were outsiders like the Pushyamitras, Hūṇas,¹ and Mlechchhas.² The *manujendra-putras* of the Junāgaḍh Inscription are mentioned only as disappointed suitors, not as defeated enemies, comparable to the brothers of Samudra Gupta who were discarded by Chandra Gupta I. We are, therefore, inclined to think that as the tottering Gupta empire was saved from its enemies (*e.g.*, the Pushyamitras) by Skanda Gupta it was he who was considered to be the best fitted to rule. There is no evidence that his brothers disputed his claim

¹ Bhitari Ins.

² Junāgaḍh Ins.

and actually fought for the crown. There is nothing to show that Skanda shed his brothers' blood and that the epithets "*amalātmā*," 'pure-souled,' and "*parahitakārī*," 'the benefactor of others,' applied to him in the Bhitari Inscription and coin legends,¹ were unjustified.

The view that Skanda Gupta was the immediate successor of Kumāra Gupta I seems to be confirmed by a verse in the *Ārya-Mañjuśrī-mūla-kalpa*² which runs thus:—

*Samudrākhyā nṛipaśchaiva
Vikramaśchaiva kīrtitaḥ
Mahendranṛipavaro mukhyaḥ
Sakārādyam ataḥ param
Devarājākhyā nāmāsau yugādhamē*

It is impossible not to recognise in the kings (*nṛipa*) Samudra, Vikrama, Mahendra and "*Sākārādyā*" mentioned in the verse, the great Gupta emperors Samudra Gupta, Chandra Gupta II, Vikramāditya, Kumāra Gupta I Mahendrāditya, and Skanda Gupta.³

Skanda Gupta assumed the titles of *Kramāditya* and *Vikramāditya*.⁴ The passage from the *Mañjuśrī-mūla-kalpa* quoted above refers to his appellation *Devarāja*. The titles *Vikramāditya* and *Devarāja* were apparently assumed in imitation of his grandfather. The latter

¹ Allan, *Gupta Coins*, cxxi.

² Vol. I, ed. Ganapati Sāstri, p. 628. Cf. the Rewa Ins. of 141 = A.D. 460/61. Attention was drawn to this record by Mr. B. C. Chhabra at the Oriental Conference, Twelfth (Benares) Session, Summaries of Papers, part II, p. 39, and later by Drs. Majumdar and Sircar.

³ IHQ, 1932, p. 352.

⁴ Allan, *Catalogue*, pp. 117, 122; cf. Fleet, CII, p. 53:—

"*Vinaya-bala-sunitair-vvikrameṣa krameṣa
pratidinam-abhipyād ipsitam yena labdhvā.*"

The epithet *Kramāditya* is found on certain gold coins of the heavy Archer type as well as on silver issues of the Garuda, Bull and Altar types. The more famous title of *Vikramāditya* is met with on silver coins of the Altar type.

epithet reminds one further of the name Mahendra given to his father. It is also to be noted that in the Allahabad Pillar Inscription Samudra Gupta is extolled as the equal of Indra and other gods and in the Kaśhāum record Skanda Gupta is called *Sakropama*.

From the evidence of coins and inscriptions we know that Skanda ruled from A.D. 455 to c. 467. The first achievement of the monarch was the resuscitation of the Gupta Empire and the recovery of lost provinces. From an inscriptional passage we learn that while preparing to restore the fallen fortunes of his family he was reduced to such straits that he had to spend a whole night sleeping on the bare earth. Line twelve of the Bhitari Inscription tells us that when Kumāra Gupta I had attained heaven, Skanda conquered his enemies by the strength of his arms. From the context it seems that these enemies were the Pushyamitras "whose power and wealth had (suddenly) gone up."

The struggle with the Pushyamitras was followed by conflicts with the Hūṇas¹ and probably also with the Vākāṭakas in which the emperor was presumably victorious in the end. The invasion of the Hūṇas took place not later than A.D. 458 if we identify them with the *Mlechchhas* or barbarian uitlanders of the Junāgaḍh Inscription. The memory of the victory over the *Mlechchhas* is preserved in the story of king Vikramāditya, son of Mahendrāditya of Ujjain, in Somadeva's *Kathā-sarit-sāgara*.² Central India and Surāshṭra seem to have been the vulnerable parts of the Gupta empire. The Bālāghaṭ plates³ refer to Narendrasena

¹ The Hūṇas are mentioned not only in inscriptions, but in the *Mahā-bhārata*, the *Purāṇas*, the *Raghuvamśa* and later in the *Harsha-charita* and the *Nītirākhyāmṛita* of Somadeva. The *Lalita Vistara* (translated by Dharmaraksha, d. A. D. 813) mentions the *Hūṇalipi* (Ind. Ant., 1913, p. 266). See also W. M. McGovern, *The Early Empires of Central Asia*, 399ff, 455ff, 485f.

² Allan, *Gupta Coins*, Introduction, p. xlix.

³ *Ep. Ind.*, IX, p. 271.

Vākātaka, son of Skanda Gupta's cousin Pravarasena II (III?) as "*Kosalā-Mekalā-Mālav-ādhipatyabhyarchitaśāsana*" 'whose commands were treated with respect by the lords of Kosalā (Upper Mahānadī Valley), Mekalā (Upper Valley of the Nerbudda and the Son), and Mālava (probably Eastern Mālwa).' The Junāgaḍh Inscription tells us that Skanda "deliberated for days and nights before making up his mind who could be trusted with the important task of guarding the lands of the Surāshṭras." Allan deduces from this and from the words "*sarveshu deśeshu vidhāya goptrīn*" 'appointing protectors in all the provinces' that the emperor was at particular pains to appoint a series of Wardens of the Marches to protect his dominions from future invasion. One of these Wardens was Paṇḍadatta,¹ governor of Surāshṭra. In spite of all his efforts Skanda Gupta could not, however, save the westernmost part of his empire from future troubles. During his lifetime he no doubt, retained his hold over Surāshṭra, the Cambay coast and the adjoining portions of continental Gujarāt and Mālwa.² But his successors do not appear to have been so fortunate. Not a single inscription or coin has yet been discovered which shows that Surāshṭra and Western Mālwa formed parts of the Gupta empire after the death of Skanda Gupta. On the contrary Harishena Vākātaka, cousin of Narendrasena, claims victories over Lāṭa

¹ Persian Farna-dāta seems, according to Jarl Charpentier, to be the form underlying the name Paṇḍadatta (*JRAS*, 1931, 140; *Aiyangar Com. Vol.*, 151).

² The inclusion of Surāshṭra within his empire is proved by the Junāgaḍh Inscription and that of the Cambay coast by silver coins of the 'Bull type'. The type was imitated by Kṛishṇarāja (Allan, *ci*), who is to be identified with the king of that name belonging to the Kāṭacheburi family. Kṛishṇa's son and successor, Saṁkaragaṇa appropriates the epithets of the great Samudra Gupta. His son Buddharāja effected the conquest of Eastern Mālwa early in the seventh century A. D. (c. 603 A. D.; Vaḍner plates, *Ep. Ind.*, xii, 31 ff.; see also Marshall, *A Guide to Sāñchī*, p. 21n). The dynasty was overthrown by the early Chalukyas and it is interesting to note that three of the characteristic epithets of Samudra Gupta are applied to the Chalukya Vijaya-rāja in the Kaira grant; Fleet, CII, 14.

(South Gujarāt) and Avantī (district around Ujjain) besides Trikūṭa in the Kōṅkan, Kuntalā (the Kanarese country), Andhra (the Telugu country), Kalinga (South Orissa and some adjoining tracts), and Kosala (Upper Mahānadī Valley), while the Maitrakas of Valabhī (Wala in the peninsular portion of Gujarāt) gradually assume independence.

The later years of Skanda seem to have been tranquil.¹ The emperor was helped in the work of administration by a number of able governors like Parṇadatta, viceroy of the west, Sarvanāga, District Officer (*Vishayapati*) of Antardedī or the Gangetic Doāb and Bhīmavarman, the ruler of the Kosam region.² Chakrapālita, son of Parṇadatta, restored in A.D. 457-58 the embankment of the lake Sudarśana at Girnar which had burst two years previously.

The emperor continued the tolerant policy of his forefathers. Himself a *Bhāgarata* or worshipper of Kṛishṇa-Vishṇu, he and his officers did not discourage followers of other sects, *e.g.*, Jainas and devotees of the Sun. The people were also tolerant. The Kāhām inscription commemorates the erection of Jaina images by a person "full of affection for Brāhmaṇas."³ The Indore plate records a deed by a Brāhmaṇa endowing a lamp in a temple of the Sun.

¹ Cf. the Kāhām Ins. of 141=A.D. 460-1.


² The inclusion within Skanda's empire of provinces lying still further to the east is proved by the Bhitari and Dihar Pillar Inscriptions and possibly by gold coins of the Archer type struck on a standard of 144·6 grains of metal. Allan, p. xcvi, 118.

³ Cf. The Pāṣāḍpur epigraph of the year 159 (A.D. 479) which records a donation made by a Brāhmaṇa couple for the worship of the Divine Arkats, *i.e.*, the Jinas.

מחלקת המחקר והפיתוח
מספר 34/100

מספר 34/100
מספר 34/100

מספר 34/100



CHAPTER XII. THE GUPTA EMPIRE (continued): THE LATER GUPTAS.

*Vasvaukasārāmatibhūya sāhaṁ
saurājya vaddhotsavayā bibhūtyā
samagraśaktau tvayi Sūryavaṁśye
sati prapannā karuṇānavasthām*

—*Raghuvamśam.*

SECTION I. SURVIVAL OF THE GUPTA POWER AFTER SKANDA GUPTA.

It is now admitted on all hands that the reign of Skanda Gupta ended about A.D. 467.¹ When he passed away the empire declined,² especially in the west, but did not wholly perish. We have epigraphic as well as literary evidence of the continuance of the Gupta empire in parts of Central and Eastern India in the latter half of the fifth as well as the sixth and seventh centuries A.D. The Dāmodarpur plates, the Sārnāth Inscriptions³ and the Eran epigraph of Budha Gupta prove that from A.D. 477 to 496 the Gupta empire extended from Bengal to Eastern Mālwa. The Betul plates of the *Parivrājaka Mahārāja Saṁkshobha*, dated in the year 199 G. E., i.e., 518 A.D., 'during the enjoyment of sovereignty by the Gupta King,'⁴ testify to the fact that the Gupta sway at this

¹ Smith *The Oxford History of India*, additions and corrections, p. 171, end.

² For the probable causes of decline, see *Calcutta Review*, April, 1933, p. 36 ff; also *post.* 626 ff.

³ A.S.I. Report, 1914-15; *Hindusthan Review*, Jan., 1918; JBORS, IV, 344 f.

⁴ *Śrīmatī pravardhamāna vijaya-rājya saṁvatsara-śaite nava-navaty-uttare Gupta-nṛipa-rājya bhuktau.* "In the glorious, augmenting and victorious reign, in a century of years increased by ninety-nine, in the enjoyment of sovereignty by the Gupta King."

period was acknowledged in Dabhāla, which included the Tripuri *Vishaya* (Jabbalpur region).¹ Another inscription of Samkshobha found in the valley near the village of Khoh in Baghelkhand, dated in A.D. 528, proves that the Gupta empire included some of the central districts even in A.D. 528.² Fifteen years later the grant of a village in the Koṣivarsha *Vishaya* (Dinājpur District) of Puṇḍravar-dhana-bhukti (roughly North Bengal) 'during the reign of *Paramadaivata* (the Supreme Divinity) *Parama-bhaṭṭāraka* (the Supreme Lord) *Mahārājādhirāja* (King of Kings) *Śrī.....Gupta*,'³ shows that the Gupta dominions at this period included the eastern as well as the central provinces. Towards the close of the sixth century a Gupta king, a contemporary of Prabhākara-vardhana of the Pushyabhūti⁴ family of Śrīkaṇṭha (Thānēsar), was ruling in "Mālava."⁵ Two sons of this king, Kumāra Gupta and

¹ Ep. Ind., VIII, pp. 284-87. Dabhāla = later Dahala.

² Fleet, CII, III, pp. 113-16; Hoernle in JASB, 1889, p. 95.

³ Ep. Ind., XV, p. 113 ff. Corrected in Ep. Ind., XVII (Jan., 1924), p. 193.

⁴ This seems to be the correct spelling and not Pushyabhūti (Ep. Ind., I, 65).

⁵ "Mālava" was graced by the presence of the Guptas as early as the fifth century. This is proved by the Udayagiri inscriptions of Chandragupta II and the Tumain inscription of Ghatotkacha Gupta. In the latter part of the sixth and the commencement of the seventh century, it seems to have been under the direct rule of a line of Guptas whose precise connection with the Great Guptas is not clear. Magadha was probably administered by local rulers like Kumāramātya Mahārāja Nandana (A. D. 551-2?) of the Amara plate, Gayā Dist., Ep. Ind., X, 40, and the Varmanas (cf. Nagārjuni Hill Cave Ins., CII, 226; also Pūrnavarman mentioned by Huen Tsang and Deva-varman, IA, X, 110). For a detailed discussion see Ray Chaudhuri, JBORS, XV, parts iii and iv (1922, pp. 651 f.). The precise location and extent of the "Mālava" of the "later Guptas" cannot be determined. In Ep. Ind., V, 229, the Daṇḍanāyaka Anantapāla, a feudatory of Vikramāditya VI, is said to have subdued the *Sapta Mālava* countries up to the Himālaya Mountains. This suggests that there were as many as seven countries called Mālava (cf. also Rice, Mysore and Coorg, 46). These were probably: (1) The country of the 'Mālavas' in the Western Ghats (*Kanarese Districts*, p. 569), (2) Mo-la-po Mālavaka *śhōra* of Valabhi grants on the Mahi governed by the Maitrakas, (3) Avanti in the wider sense of the term ruled by the Kāṭachakuris or Kalachuris of the Abhona plates (sixth century) and by a Brāhmana family in the time of

Mādhava Gupta were appointed to wait upon the princes Rājya-var dhana and Harsha of Thānesar. From the Aphaṣṭ inscription of Ādityasena we learn that the fame of the father of Mādhava Gupta, the associate of Harsha,¹ marked with honour of victory in war over Śuśthitavarman, doubtless a king of Kāmarūpa, was constantly sung on the bank of the river Lohitya or Brabmaputra. This indicates that even in or about A.D. 600 (the time of Prabhākara-var dhana) the sway of kings bearing the name Gupta extended from "Mālava" to the Brahmaputra.²

In the sixth century Gupta suzerainty was no doubt successively challenged by the Huns and their conquerors belonging to the Mandasor and Maukhari families. In

Hsuen Tsang Chinese pilgrim, (4) *Pūrva Mālava* (round Bhilsa), (5) District round Prayāga, Kauśāmbī and Fatehpur in U. P. (Smith, EHI, 4th ed., p. 350n.; IHQ, 1931, 150f.; cf. JRAS, 1903, 561), (6) part of eastern Rājputāna, (7) Chittul district of the Pāñjāb together with some Himalayan territory. The later Guptas probably held (4) and (5) and at times, Magadha as well. The *Rhāṣṭra Purāṇa* (xii. 1, 36) whose date is not probably far removed from that of the later Guptas, associates Mālava with Arbuda (Abu) and distinguishes it from Avanti. The rulers of Mālava and Avanti are also distinguished from each other by Rājasekhara in his *Viddhaśāla bhāṣikā*, Act IV (p. 121 of Jivānanda Vidyāsāgara's edition). Early, in the seventh century the Guptas seem to have lost Eastern Mālwa to the Kaṭachchuris. In the Vajner plates issued from Vidiśā (Besnagar) in or about A. D. 608, a Kaṭachchuri king, Saṅkaragopa receives epithets that are palpably borrowed from the Allahabad *Prastāvi* of Samudra Gupta. The overthrow of the Kaṭachchuris was effected by the early Chalukyas of Badami and South Gujaraṭ. Fleet points out (CII, 14) that three of the epithets of Samudra Gupta are applied to the Chalukya chieftain Vijayarāja in the Kaira grant of the year 394 (IA. VII, 248). Ādityasena of the later Gupta family, who ruled in the second half of the seventh century A. D., seems to be referred to in Nepalese inscriptions as 'King of Magadha'. Magadha, now replaced Eastern Mālwa as the chief centre of Gupta power.

¹ Cf. Hoernle in JRAS, 1909, 561.

² An allusion to the later Guptas seems to occur in the *Kādambari*, Verse 10, of Bāṇa which says that the lotus feet of Kubera, the poet's great-grandfather, were worshipped by many a Gupta :—

*Babhūva Vāṭayāyana vāṇsa sambhava
deṣo jagadgītāgūṇo'grāṇiḥ satām
oneka Guptārchita pāda pañkajāḥ
Kubera nāmāṇḍa iva Śrāyambhuraḥ.*

the first half of the seventh century the Guptas lost Vidiśā to the Kāṭachchuris and their power in the Ganges Valley was overshadowed by that of Harsha. But, after the death of the great Kansuj monarch, the "Gupta" empire was sought to be revived by Ādityasena, son of Mādhava Gupta, who "ruled the whole earth up to the shores of the oceans," performed the *Aśvamedha* and other great sacrifices and assumed the titles of *Parama-bhaṭṭāraka* and *Mahārājādhirāja*.

SECTION II. PURU GUPTA AND NARASIṂHA GUPTA BALADITYA.

We shall now proceed to give an account of Skanda Gupta's successors. The immediate successor of the great emperor seems to have been his brother **Puru Gupta**. The existence of this king was unknown till the discovery of the Bhitari seal of Kumāra Gupta II in 1889, and its publication by Smith and Hoernle.¹ The seal describes Puru Gupta as the son of Kumāra I by the queen Anantadevī, and does not mention Skanda Gupta. The mention of Puru Gupta immediately after Kumāra with the prefix *tat-pād-ānudhyāta* "meditating on, or attached to, the feet of" (Kumāra), does not necessarily prove that Puru Gupta was the immediate successor of his father, and a contemporary and rival of his brother or half-brother Skanda Gupta.² In the Manahali grant Madanapāla is described as *Śri-Rāmapāla-Deva-pād-ānudhyāta*, although he was preceded by his elder brother Kumārapāla. In Kielhorn's Northern Inscription No. 39, Vijayapāla is described as the successor of Kshitipāla, although he was preceded by his brother Devapāla.³

¹ JASB, 1889 pp. 84-105.

² The omission of Skanda's name in the Bhitari seal of his brother's grandson does not necessarily imply that the relations between him and Pura's family were unfriendly as suggested by Mr. R. D. Banerji (*cf. Annals of the Bhand, Ins.*, 1918-19, pp. 74-75). The name of Pulakaśin II is omitted in an inscription of his brother and Yuvardja Viśhnavardhana (Śatārā grant, *Ind. Ant.*, 1890 pp. 227f). The name of Bhoja II of the Imperial Pratihāra dynasty is not mentioned in the Partabgarh Inscription of his nephew Mahendrapāla II, but it is mentioned in an inscription of his brother Viṣṇyakapāla, the father of Mahendrapāla. Besides, there was no custom prohibiting the mention of the name of a rival uncle or brother; Maṅgaleśa and Govinda II are mentioned in the inscriptions of their rivals and their descendants. On the other hand even an ancestor of a reigning king was sometimes omitted, e.g., Dharaṇapatta is omitted in his son's inscription (Kielhorn, *N. Ins.*, No. 454).

³ Kielhorn, *Ins.*, No. 31.

Smith and Allan have shown that Skanda ruled over the whole empire including the eastern and the central as well as many of the western provinces. He may have lost some of his districts in the Far West. But the coin-types of the successors of Kumāra Gupta, with the exception of Skanda Gupta and Budha Gupta, show that none of them could have held sway in the lost territories of Western India. Epigraphic and numismatic evidence clearly indicates that there was no room for a rival *Mahārājādhirāja* in Northern India including Bihār and Bengal during the reign of Skanda Gupta. He was a man of mature years at the time of his death *cir.* A.D. 467.¹ His brother and successor Puru Gupta, too, must have been an old man at that time. It is, therefore, not at all surprising that he had a very short reign and died some time before A.D. 473 when his grandson Kumāra Gupta II was ruling. The name of Puru Gupta's queen has been read by various scholars as Śrī Vatsadevi, Vainyadevī or Śrī Chandradevī.² She was the mother of Narasimha Gupta Bālāditya.

The coins of Puru Gupta are of the heavy Archer type apparently belonging to the eastern provinces of the empire of his predecessors.³ Some of the coins hitherto attributed to him have the reverse legend Śrī Vikramah⁴ and possible traces of the fuller title of Vikramāditya. Allan identifies him with king Vikramāditya of Ayodhyā,

¹ When sons succeed a father or mother after a prolonged reign they are usually well advanced in years. In the case of Skanda Gupta we know that already in A.D. 455 he was old enough to lead the struggle against all the enemies of his house and empire in succession. Cf. 564 n.3 ante.

² Ep. Ind., XXI, 77; ASI. AR, 1931-35, 63.

³ Allan, pp. Lxxx, xcvi.

⁴ Mr. S. K. Sarasvati attributes these coins to Budha Gupta (*Indian Culture*, I, (92). This view, however, is not accepted by Prof. Jagan Nath (*Summaries of papers submitted to the 13th All India Oriental Conference*, Nagpur, 1946, Sec. IX p. 11). According to Mr. Jagan Nath the reading is definitely Pura and not Budha. As to the title Vikramāditya, see Allan, p. cxvii, Dr. R. C. Majumdar (ASB, 4-4-49) adduces evidence in support of the view of Mr. Sarasvati.

father of Bālāditya, who was a patron of Buddhism through the influence of Vasubandhu. The importance of this identification lies in the fact that it proves that the immediate successors of Skanda Gupta had a capital at Ayodhyā probably till the rise of the Maukharis. If the spurious Gayā plate is to be believed Ayodhyā was the seat of a Gupta *jaya-skandhāvāra*, or 'camp of victory,' as early as the time of Samudra Gupta. The principal capital of Bālāditya and his successors appears to have been Kāśī.¹

The identification proposed by Allan also suggests that Puru Gupta could not have flourished much later than 472 A.D., for a Chinese history of the Indian patriarchs belonging to that year mentions "Ba-su-ban-da."²

The evidence of the Bharsar hoard seems to show that a king styled Prakāśāditya came shortly after Skanda Gupta. Prakāśāditya may be regarded as possibly a *biruda* or secondary epithet of Puru Gupta or of one of his immediate successors. Even if we think with Allan that Puru had the title Vikramāditya there is no inherent improbability in his having an additional *Āditya* title. That the same king might have two "*Āditya*" names is proved by the cases of Skanda Gupta (Vikramāditya and Kramāditya) and Śilāditya Dharmāditya of Valabhī. But the identification of Prakāśāditya still remains *sub judice*. His coins are of the combined horseman and lion-slayer type. The "horseman type" was associated with the southern provinces of the empire of the Guptas³ and the lion-slayer type with the north.⁴

¹ *CH*, 285.

² *JRAS*, 1905, 40. This is now confirmed by the seal which represents Puru as the father of Buddha (476-95.)

³ Allan, p. lxxxvi.

Ibid, xci.

Puru Gupta seems to have been succeeded by his son **Narasimha Gupta Bālāditya**. This king has been identified with king Bālāditya whose troops are represented by Hiuen Tsang as having imprisoned the tyrant Mihirakula. It has been overlooked that Hiuen Tsang's Bālāditya was the immediate successor of Tathāgata Gupta,¹ who was himself the immediate successor of Bud(d)ha Gupta,² whereas Narasimha Gupta Bālāditya was the son and successor of Puru Gupta who in his turn was the son of Kumāra Gupta I and the successor of Skanda Gupta. The son and successor of Hiuen Tsang's Bālāditya was Vajra³ while the son and successor of Narasimha was Kumāra Gupta II. It is obvious that the conqueror of Mihirakula was not the son of Puru Gupta but an altogether different individual.⁴ The existence of several kings of the eastern part of the *Madhyadēśa* having the *biruda* Bālāditya is proved by the Sārnāth Inscription of Prakāṣāditya.⁵ Narasimha Gupta must have died in or about the year

¹ *Life of Hiuen Tsang*, p. 111, *Si-yu-ki*, II, p. 168.

² *Foto-kiō-to*. Beal, Fleet and Watters render the term by Buddha Gupta, a name unknown to imperial Gupta epigraphy. The synchronism of his second successor Bālāditya with Mihirakula proves that Buddha Gupta is meant. We have other instances of corruption of names, e.g., Skanda is transformed into Skandha in several Purāṇic lists of the so-called Andhra dynasty.

³ *Yuan Chwang* II, p. 155.

⁴ Drs. Bhaṭṭasāli and Basū, who uphold the identification of Hiuen Tsang's Bālāditya with the son of Puru Gupta do not apparently attach due weight to the evidence of the *Life of Hiuen Tsang*, p. 111, which, as we shall see later on, is corroborated by the combined testimony of the Sārnāth inscription of Prakāṣāditya and the *Ārya-Mahju-śrī-māla-kalpa*. The evidence of these documents suggests that Hiuen Tsang's Bālāditya was identical with Bhānu Gupta and was the father of Prakāṣāditya and Vajra.

⁵ *CII*, p. 285. A Bālāditya is mentioned in the Nālandā Stone Inscription of Yaśovarman (*Ep. Ind.*, 1929, Jan., 38) and also a seal (*Śrī Nālandāyām Śrī Bālāditya Gandhakaḍḍi*, *MAI*, 66 38).

A.D. 473. He was succeeded by his son Kumāra Gupta II Kramāditya by queen Mitradevī.¹

The coins of Narasiṁha and his successor belong to two varieties of the Archer type. One class of these coins was, according to Allan, apparently intended for circulation in the lower Ganges valley, and the other may have been issued in the upper provinces. The inclusion of Eastern India within the dominions of Bālāditya (Bālākhya) and Kumāra (II) is vouched for by the *Ārya-Mañjuśrī-mūla-kalpa*.²

¹ It is suggested in *Ep. Ind.*, xxi, 77 (clay seals of Nalanda) and *ASI, AR*, 1934-35, 63, that the name of Kumāra Gupta's mother has to be read as Mitradevī and not Srimati devī or Lakshmidēvī.

² Ganapati Sāstri's ed., p. 630. Cf. Jaysawal, *Imperial History*, 35.

*Bālākhya nāmasau nṛpatīr bhavitā Pūrva-deśakah
tasyāpareṇa nṛpatīḥ Cauḍāṇām prabhaviṣṭhavaḥ
Kumārākhya nāmataḥ proktaḥ so'pīr atyanta dharmatān.*

SECTION III. KUMĀRA GUPTA II AND VISHNUGUPTA.

Kumāra Gupta II of the Bhitari seal, son of Narasimha Gupta, has been identified with Kramāditya of certain coins of the Archer type that are closely connected with the issues of Narasimha Bālāditya. He is also identified with king Kumāra Gupta mentioned in the Sārnāth Buddhist Image Inscription of the year 154 G. E., i.e., A.D. 473-74.¹ Drs. Bhaṭṭasālī, Basāk and some other scholars think that the Kumāra Guptas of the Bhitari seal and the Sārnāth epigraph were distinct individuals. The former places Kumāra, son of Narasimha, long after A.D. 500.² But his theory is based upon the doubtful identification of Narasimha, with the conqueror of Mihirakula. According to Dr. Basāk Kumāra of the Sārnāth Inscription was the immediate successor of Skanda. In his opinion there were two rival Gupta lines ruling simultaneously, one consisting of Skanda, Kumāra of Sārnāth and Budha, the other comprising Puru, Narasimha and his son Kumāra of the Bhitari seal. But there is not the slightest evidence of a partition of the Gupta empire in the latter half of the fifth century A.D. On the contrary inscriptions and coins prove that both Skanda and Budha ruled over the whole empire from Bengal to the West. We have already seen that according to the traditional account of the *Ārya-Maṇjuśrī-mūla-kalpa* the kingdom of Bālākhyā, i.e., Bālāditya and his successor Kumāra embraced the *Purva-deśa* (Eastern India) including Gauḍa (Western and part of Northern Bengal).³ How

¹ See *ASI, AR*, 1914-15, 124, *Hindusthan Review*, Jan., 1918, *Ann. Dharm. Inst.*, 1918-19, 67 ff. and *JBORS*, iv, 344, 412, for the views of Vaidya, Pathak, Pandey, Pannalal and others.

² *Dacca Review*, May and June, 1920, pp. 54-57.

³ *Ārya-Maṇjuśrī-mūla-kalpa*, G. Śāstrī's ed., pp. 630 f.

can we reconcile the rule of these kings with the contemporary sovereignty of a rival line represented by Skanda and Budha?¹ There is no cogent reason for doubting the identity of Kumāra of the Bhitari seal with his namesake of the Sarnāth inscription.

Kumāra II's reign must have terminated in or about the year A.D. 476-77, the first known date of Budha Gupta.² The reigns of Puru, Narasimha and Kumāra II appear to be abnormally short, amounting together to only ten years (A.D. 467-77). This is by no means a unique case. In Veṅgī three Eastern Chālukya monarchs, viz., Vijayāditya IV, his son Ammarāja I, and Ammarāja's

¹ The seal of Budha Gupta (*MASS*, No. 66, p. 64) proves conclusively that Budha, far from belonging to a rival line, was actually a son of Puru Gupta. It also negatives the late date for Puru Gupta suggested by Dr. Bhatṭasālī.

² One of the successors of Kumāra (II), son of Balāditya, is according to the *Ārya-Maṇjuśrī-mūla-kalpa*, a prince styled *Ukārākhya*. That appellation may according to Jayaswal apply to Prakāśāditya, for Allan finds the letters *cu* or *u* on his coins. But the identification of a prince whose designation was *u*, (*Ukārākhya*), with Budha Gupta (Jayaswal, *An Imperial History of India*, 38), does not seem to be plausible. The passage in the *Ārya-Maṇjuśrī-mūla-kalpa* suggests a name like Upagupta, Upendra. Though there is no direct epigraphic evidence for the name Upagupta, the existence of such a prince does not seem to be improbable in view of the fact that an Upaguptā is mentioned in Maukhari records as the mother of Isānavarman [Āśirgaḍh (Plect, *CII*, p. 220) and Nālandā (*Ep. Ind.*, xxi, p. 74) seals]. Cf. Bhānu Gupta and Bhānu Gupta, Harsha Gupta and Harsha Gupta, Mahāseṇa Gupta and Mahāseṇa Gupta. On the analogy of these cases it is possible that there was a prince named Upagupta, apparently the brother of Upaguptā. If this surmise be correct Upagupta may have to be placed in the same period as the mother of Isānavarman, i.e., in the first half of the sixth century A.D., sometime after Budha Gupta. If *u* is the initial of *Upendra* (Viṣṇu or Kṛishṇa) and not of *Upagupta*, it may refer to Viṣṇu Gupta or to Kṛishṇa Gupta, just as *Somākhyā* has reference to the Gauda king Śaśāṅka. The existence of a son of Kumāra Gupta II named *Mahārājādhirāja Śri Viṣṇu Gupta* has recently been disclosed by a fragmentary seal at Nālandā (*Ep. Ind.*, xxvi, 235; *I.H.Q.*, XIX, 19). It is difficult in the present state of our knowledge to say whether he was the immediate successor of his father, or had to wait till the death of his great uncle Budha Gupta. Those who place him and his father *after* Budha Gupta, have to dissociate Kumāra of the Bhitari and Nālandā seals from the homonymous prince of Sarnāth. This is not improbable but must await future discoveries for confirmation.

son, another Vijayāditya, ruled only for seven years and six and a half months.¹ In Kāśmīra six kings, Śūravarman I, Pārtha, Sambhuvardhana, Chakravarman, Unmattāvanti and Śūravarman II, ruled within six years (A.D. 933-39); and three generations of kings, viz., Yaśaskara, his uncle Varṇaṭa, and his son Saṁgrāmadeva ruled for ten years (A.D. 939-49). A fragmentary seal discovered at Nālandā refer to Kumāra's son **Vishṇu Gupta** who is probably to be identified with Chandrāditya of the coins.

¹ Holtzsch, *III*, Vol. I, p. 46.

SECTION IV. BUDHA GUPTA

For Budha Gupta, now known to have been a son of Puru Gupta¹ we have a number of dated inscriptions and coins which prove that he ruled for about twenty years (A.D. 477-c. 495).

Two copper-plate inscriptions discovered in the village of Dāmodarpur in the district of Dinājpur, testify to the fact that Budha Gupta's empire included Puṇḍravardhana *bhukti* (roughly North Bengal) which was governed by his viceroys (*Uparika Mahārāja*) Brahmadata and Jayadata.² The Sārnāth inscription of A.D. 476-77 and Benares Ins.³ of 479 prove his possession of the Kāśī country. In A.D. 484-85 the erection of a *dhvaja-stambha* or flag staff in honour of Janārdana, i.e., Viṣṇu, by the Mahārāja Mātṛivishṇu, ruler of Eraṇ, and his brother Dhanyaviṣṇu, while the *Bhūpati* (King) Budha Gupta, was reigning, and Mahārāja Surāśmichandra was governing the land between the Kālindī (Jumna) and the Narmadā (Nerbudda), indicates that Budha Gupta's dominions included part of Central India as well as Kāśī and North Bengal.

The coins of this emperor are dated in the year A.D. c. 495. They continue the peacock-type of the Gupta silver coinage that was meant, according to Allan, for circulation in the central part of the empire.⁴ Their

¹ Seal of Budha Gupta (*MASE*, No. 66, p. 64).

² To the reign of this Gupta king belongs also probably the Pāhāḍpur (ancient Somapura) (Rājshāhi District) plate of A.D. 478-79 (*Mod. Rev.*, 1931, 150; *Prabāsi* 1338, 671; *Ep. Ind.*, XX, 59 ff.) and also a copper-plate of A.D. 488-9 (*Ep. Ind.*, xxiii, 52), originally found at Nandapura (Monghyr District). For a possible reference to Budha Gupta in Purāṇic literature, see *Pro. of the Seventh Or. Conf.*, 576.

³ *JRASE*, 1949, 5 ff.

⁴ Cf. also *Mahābhārata*, ii. 32. 4; Kālidāsa, *Meghadūta*, I. 45.

legend is the claim to be lord of the earth and to have won heaven,—found on the coins of Kumāra Gupta I and Skanda Gupta.

SECTION V. SUCCESSORS OF BUDHA GUPTA

According to the *Life of Hiuen Tsang* Budha Gupta was succeeded by **Tathāgata** Gupta, after whom **Bālāditya** succeeded to the empire.¹ At this period the supremacy of the Guptas in Central India was challenged by the Hun king Toramāṇa. We have seen that in A.D. 484-85 a *Mahārāja* named Mātrivishṇu ruled in the Airikīṇa *Vishaya* (Eran in Eastern Mālwa, now in the Saugor District of the Central Provinces) as a vassal of the emperor Budha Gupta. But after his death his younger brother Dhanyavishṇu transferred his allegiance to Toramāṇa. The success of the Huns in Central India was, however, short-lived. In 510-11 we find a general named Goparāja fighting by the side of a Gupta king at Eran and king Hastin of the neighbouring province of Ḍabhālā to the south-east of Eran acknowledging the sovereignty of the Guptas. In A.D. 518-9 the suzerainty of the Guptas is acknowledged in the Tripurī *vishaya* (Jubbulpore District). In the year 528-29 the Gupta sway was still acknowledged by the *Parivrājaka-Mahārāja* of Ḍabhālā. The *Parivrājakas* Hastin and Saṁkshobha seem to have been the bulwarks of the Gupta empire in the northern part of the present Madhya Pradesh. The *Harsha-charita* of Bāṇa recognises the possession of Mālava, possibly Eastern Mālwa, by the Guptas as late as the time of Prabhākara-vardhana (*cir.* A.D. 600). There can be no doubt that the expulsion of the Huns from parts of Central India was final.² The recovery of the Central Provinces was probably

¹ Beal, *Si-yu-ki*, II, p. 168; the *Life*, p. 111.

² For the survival of the Huns in the Mālwa region, See *Ep. Ind.*, xxiii., 102.

effected in the time of Bālāditya whose troops are represented by Hiuen Tsang as having imprisoned Mibirakula, the son and successor of Toramaṇa, and set him at liberty at the request of the Queen Mother. The Hun king had to be content with a small kingdom in the north.¹ It is not improbable that Bālāditya was a *biruda* of the "glorious Bhānu Gupta, the bravest man on the earth, a mighty king, equal to Pārtha" along with whom Goparāja went to Eran and having fought a "very famous battle" died shortly before A.D. 510-11.²

Mihirakula was finally subjugated by the *Janendra*³ Yaśodharman of Mandaśor some time before A.D. 533.

¹ Beal, *Si-yu-ki*, I, p. 171.

² In a Nālandā Stone Inscription (*Ep. Ind.*, XX, 43-45) Bālāditya is described as a king of irresistible valour and conqueror of all foes. The last of the Bālādityas mentioned in a Sārnāth Inscription (Fleet, CII, 285 f.) had a son named Prakṣāditya by his wife Dhavalā. In the *Ārya-Manjūśrī-mūla-kalpa* (ed. G. Sāstrī, p. 637 ff.) *Pakṣārākhya* (Prakṣāditya) is represented as the son of *Bhākārākhya* (Bhānu Gupta). Buddhist tradition thus corroborates the identification, first proposed in these pages, of Bālāditya with Bhānu Gupta. Cf. now Jayaswal, *An Imperial History of India*, pp. 47, 53. An inscription found at Gopālighara near Comilla and certain seals at Nālandā disclose the existence of a king named (Yal)nya Gu(pta) who ruled in or about A. D. 507 and must have been also a contemporary of Mihirakula or of his father (*Probhāsi*, 1933, 675; *IHQ*, 1930, 53, 561). The seals give him the style *Mahārājādhirāja* (*ASI*, *AR*, 1930-34, Pt. I, 239, 249; *MAI*, 66, 67; *IHQ*, XIX, 275) and suggest relationship with the imperial Guptas. Dr D. C. Ganguly identifies him with the *Daddatāditya* of coins (*IHQ*, 1933, 784, 989). But owing to damaged condition of the Nālandā seal his parentage cannot be ascertained.

³ The ascription of the title of Vikramāditya to Yaśodharman of Mandaśor, and the representation of this chief as a ruler of Ujjain, the father of Śūlāditya of Mo-la-po and the father-in-law of Prabhākara-varḍhana are absolutely unwarranted. According to Father Heras (*JBORS*, 1927, March, 8-9) the defeat of Mihirakula at the hands of Bālāditya took place after the Hun king's conflict with Yaśodharman. It should, however, be remembered that at the time of the war with Bālāditya Mihirakula was a paramount sovereign to whom the king of Magadha had been tributary, and with whom he dared not fight, being only anxious to conceal his poor person (Beal, *Si-yu-ki*, Vol. I, p. 108). This is hardly possible after the *Janendra* of Mandaśor had compelled the Hun "to pay respect to his two feet". The victory of Bālāditya over Mihirakula was certainly not decisive. The "loss of the royal estate" was only temporary, and the tyrant soon placed himself on the throne of Kāśmīra and conquered

Line 6 of the Mandaśor Stone Pillar inscription¹ leaves the impression that in the time of Yaśodharman Mihirakula was the king of a Himālayan country ("small kingdom in the north"), i.e., Kāśmīra and that neighbourhood, who was compelled "to pay respect to the two feet"² of the victorious *Janendra* probably when the latter carried his arms to "the mountain of snow the tablelands of which are embraced by the Gāṅgā."

Yaśodharman claims to have extended his sway as far as the Lauhitya or Brabmaputra in the east. It is not improbable that he defeated and killed *Vajra*, the son of *Bālāditya*,³ and extinguished the viceregal family of the Dattas of Puṇḍra-varḍhana. Hiuen Tsang mentions a king of Central India as the successor of *Vajra*. The Dattas, who governed Puṇḍra-varḍhana from the time of Kumāra Gupta I, disappear about this time. But Yaśodharman's success must have been short-lived,

Gandhāra (Beal, *Si-yu-ki*, I, p. 171). To the court-poet of Yaśodharman Mihirakula was pre-eminently a king of the Himālayan region. This is clear from the following passage which was misunderstood by Fleet whose interpretation has been followed by Father Hervas (p. 8 n) :—


"He (Yaśodharman) to whose feet respect was paid—by even that (famous) king Mihirakula, whose head had never previously been brought into the humility of obeisance to any other save (the god) Sthānu (and) embraced by whose arms the mountain of snow falsely prides itself as being styled an inaccessible fortress" (Kielhorn in *Ind. Ant.*, 1895, p. 219). Kielhorn's interpretation was accepted by Fleet. [The statement that Mihirakula's head 'had never been brought into the humility of obeisance to any other save (the god) Sthānu' shows that he refused to do homage to Bālāditya, and probably accounts for the order, given for his execution by that king.]

¹ CII, pp. 146-147; Jaysawal, *The Historical Position of Kalki*, p. 9.

² If the identification of Bālāditya with Bhānu Gupta first proposed in these pages is correct, his son *Vajra* may be identified with *Vakṛākhyā*, the younger brother (*anuja*) of the *Prakṛāditya* of the Sārnāth Inscription (Fleet, CII, 284 A.)—the *Pakṛākhyā* of the *Ārya-Maṇjuśrī-mūla-kalpa* who is represented as the son of *Bhukṛākhyā*, i.e., Bhānu Gupta (ed. G. Sāstri, pp. 637-44). *Prakṛāditya* is represented in the inscription named above as the son of Bālāditya by Dhavalā. Cf. now Jaysawal, *An Imperial History of India*, pp. 47, 53, 56, 63.

because in A.D. 543-44, ten years after the Mandaśor inscription which mentions the *Janendra* Yaśodharman as victorious, the son (?) and viceroy of a Gupta *parama-bhaṭṭāraka mahārājādhirāja prithivipati*, 'supreme sovereign, king of kings, lord of the earth,' and not any official of the Central Indian *Janendra*, was governing the Puṇḍra-vardhana-*bhukti*, a province which lay between the Indian interior and the Lauhitya.

THE EARLY IMPERIAL GUPTAS



Lalier Guptas

SECTION VI. THE LINE OF KRISHNA GUPTA

The name of the Gupta emperor in the Dāmodarpur plate of A.D. 543-44 is unfortunately lost. The Aphasā inscription, however, discloses the names of a number of "Gupta" kings,¹ the fourth of whom, Kumāra Gupta(III), was a contemporary of Īśānavarman Maukhari who is known from the Harāhā inscription to have been ruling in A.D. 554.² Kumāra Gupta III, and his three predecessors, viz., Kṛishṇa, Harsha and Jivita, should probably be placed in the period between A.D. 510, the date of Bhānu Gupta, and 554, the date of Īśānavarmān. It is possible, but by no means certain, that one of these kings is identical with the Gupta emperor mentioned in the

¹ Although the rulers, the names of most of whom ended in -*gupta*, mentioned in the Aphasā and connected contemporary epigraphs, who ruled over the provinces in the heart of the early Gupta empire, are called "Guptas" for the sake of convenience, their relationship with the early *Gupta-kula* or *Gupta-vamśa* is not known. It is, however, to be noted that some of them (e.g., Kumāra Gupta and Deva Gupta), bore names that are found in the earlier family, and Kṛishṇa Gupta, the founder of the line, has been identified by some with Govinda Gupta, son of Chandra Gupta II. But the last suggestion is hardly acceptable, because Govinda must have flourished more than half a century before Kṛishṇa Gupta. And it is surprising that the panegyrists of Kṛishṇa Gupta's descendants should have omitted all references to the early Guptas if their patrons could really lay claim to such an illustrious ancestry. In the Aphasā inscription the dynasty is described simply as *Sad-vamśa* 'of good lineage'. The designation *Gupta*, albeit not "*Early Imperial Gupta*," is possibly justified by the evidence of Bāṇa. The Guptas and the Gupta *Kulaputra* mentioned in Bāṇa's *Kādambarī* and *Harsha-charita* may refer to the family of Kṛishṇa, if not to some hitherto unknown descendants of the early imperial line. One of the princes of the early Gupta line, Ghaṭotkacha Gupta of the Tumain inscription is known to have ruled over Eastern Mālwa and it is not impossible that Kṛishṇa Gupta was, in some way, connected with him. We must, however, await future discoveries to clear up the point.

² H. Sāstri., *Ep. Ind.*, XIV, pp. 110 ff.

Dāmodarpur plate of A.D. 543-44.¹ The absence of high-sounding titles like *Mahārājādhirāja* or *Parama-bhaṭṭāraka* in the *Sloka*s or verses of the Aphaṣaḍ inscription does not necessarily prove that the kings mentioned there were petty chiefs. No such titles are attached to the name of Kumāra I in the Mandaśor inscription, or to the name of Budha in the Eraṇ inscription. On the other hand the queen of Mādhava Gupta, one of the least powerful kings mentioned in the Aphaṣaḍ inscription, is called *Parama-bhaṭṭārikā* and *Mahādevī* in the Dēo Baraṇārka epigraph.

Regarding **Kṛishṇa Gupta** we know very little. The Aphaṣaḍ inscription describes him as a hero whose arm played the part of a lion, in bruising the foreheads of the array of the rutting elephants of (his) haughty enemy (*dṛiptārāti*), (and) in being victorious by (its) prowess over countless foes. The *dṛiptārāti* against whom he had to fight may have been Yaśodharman. The next king **Deva Śrī Harsha Gupta** had to engage in terrible contests with those who were "averse to the abode of the goddess of fortune being with (him, her) own lord."² There were wounds from many weapons on his chest. The name of the enemies, who tried to deprive him of his rightful possessions, are not given. Harsha's son **Jivita Gupta I** probably succeeded in re-establishing the power of his family in the territory lying between the Himālayas and the sea, apparently in Eastern India. "The very terrible scorching fever (of fear) left not (his) haughty foes, even though they stood on seaside shores

¹ Mr. Y. R. Gupte (*Ind. Hist. Journal*) reads the name of Kumāra in the inscription of A. D. 543-44, but he identifies him with the son of Narasiṃha Gupta. The ruler whose name is missing may represent one or other of the "Gupta" lines already known to scholars or some new line. Cf. the cases of Vainya Gupta and the princes mentioned on pp. 214-15 of *Ep. Ind.*, xx, Appendix.

that were cool with the flowing and ebbing currents of water, (and) were covered with the branches of plantain trees severed by the trunks of elephants roaming through the lofty groves of palmyra palms; (or) even though they stood on (that) mountain (Himālaya) which is cold with the water of the rushing and waving torrents full of snow." The "haughty foes" on seaside shores were probably the Gaudas who had already launched into a career of conquest about this time and who are described as living on the sea shore (*samudr-āśraya*) in the Harāhā inscription of A. D. 554.¹ The other enemies may have included ambitious *Kumārāmātyas* like Nandana of the Amauna plate.

The next king, **Kumāra Gupta III**, had to encounter a sea of troubles. The Gaudas were issuing from their "proper realm" which was in Western Bengal as it bordered on the sea and included *Karṇasuvarṇa*² and *Rāḍhāpuri*.³ The lord of the Andhras who had thousands of three-fold rutting elephants, and the *Śūlikas* who had an army of countless galloping horses, were powers to be reckoned with. The Andhra king was probably *Mādhava-varman* (I, *Janāśraya*) of the Polamuru plates belonging to the *Vishṇukunḍin* family who "crossed the river *Godāvāri* with the desire to conquer the eastern region"⁴ and performed eleven horse-sacrifices. The *Śūlikas* were probably the *Chalukyas*.⁵ In the *Mahākūṭa* pillar

¹ Ep. Ind., XIV, p. 110 *et seq.*

² M. Chakravarti, JASB, 1908, p. 274.

³ *Prabodha-chandrodaya*, Act II.

⁴ Dubreuil, AHD, p. 92 and D. C. Sircar, IHQ, 1933, 276 ff.

⁵ In the *Bṛihat-Saṃhitā*, IX. 15; XIV. 8, the *Śūlikas* and *Saulikas* are associated with *Aparānta* (N. Kodkan), *Vanavāsī* (Kanara) and *Vidarbhā* (Berar). In *Bṛih. Saṃ.*, IX. 21, X. 7, XVI. 35, however, they are associated with *Gandhāra* and *Vokkāṇa* (Wakhan). A branch of the people may have dwelt in the north-west. In JRAS, 1912, 128, we have a reference to *Kulastambha* of the *Sulki* family. *Tāranātha* (*Ind. Ant.*, IV, 364) places the kingdom of "Sulik" beyond "Togara" (Ter in the Deccan ?).

inscription the name appears as Chalikya. In the Gujarāt records we find the forms Solaki and Solāṅki. Śūlika may have been another dialectic variant. The Mahākūṭa pillar inscription tells us that in the sixth century A.D., Kīrtivarman I of the "Chalikya" dynasty gained victories over the kings of Vaṅga, Aṅga, Magadha, etc. His father is known to have performed the *Aśvamedha* sacrifice, "the super-eminent touch-stone to test the might of warriors conquering the world and an indication of the conquest of all the warriors." Prince Kīrtivarman may have been entrusted with the guardianship of the sacrificial steed that had to roam about for a year in the territories of the rulers to whom a challenge was thrown by the performer of the sacrifice.

A new power was rising in the Upper Ganges Valley which was destined to engage in a death grapple with the Guptas for the mastery of Northern India. This was the Mukhara or **Maukhari**¹ power. The Maukharis claimed descent from the hundred sons whom king Aśvapati got from Vaivasvata, i.e., Yama² (not Manu). The family consisted of several distinct groups. The stone inscriptions of one group have been discovered in the Jaunpur and Bārā Bankī districts of the Uttara Pradeśa, while lithic records of another group have been discovered in the Gayā district of Bihār. A third family has left inscription at Baḍvā in the Kotah state in Rājputāna. The Maukharis of Gayā, namely, Yajñavarman, Śārdūlavarman and Anantavarman were a

¹ The family was called both Mukhara and Maukhari. "*Soma-Sūrya vaṁśā-viva Pushpabhūti* (sic) *Mukhara Vaṁśau*", "*sakalabhuvana namaskṛito Maukhari vaṁśaḥ*." (*Harsha-charita*, Parab's ed., pp. 141, 146). Cf. also CII, p. 229.

² Mbh., III. 296. 38 ff. The reference is undoubtedly to the hundred sons that Aśvapati obtained as a boon from Yama on the intercession of his daughter Śāvitri. It is surprising that some writers still identify the Vaivasvata of the Maukhari record with Manu.

feudatory family. Śārdūla is expressly called *sāmanta chūdāmaṇi*, 'crest-jewel of vassal chiefs' in the Barābar Hill Cave Inscription of his son.¹ The Baḍvā Maukharis held the office of general or military governor under some Prince of Western India in the third century A. D. The Maukharis of the Uttara Pradeśa² probably also held a subordinate rank at first. The earliest princes of this family, viz., Harivarman, Ādityavarman, and Īśvaravarman, were simply *Mahārājas*, Ādityavarman's wife was Harsha Guptā, probably a sister of king Harsha Gupta. The wife of his son and successor Īśvaravarman was also probably a Gupta princess named Upa-Guptā. In the Harābhā inscription Īśānavarman, son of Īśvaravarman and Upa-Guptā,³ claims victories over the **Andhras**,⁴ the **Śūlikas** and the **Gauḍas** and is the first to assume the Imperial title of *Mahārājādhirāja*. It was this which probably brought him into conflict with king Kumāra

¹ CII, p. 223. The connection of the Maukharis with Gayā is very old. This is proved by the clay seal with the inscription *Mokhalīśa*, or *Mokhalīṇam* (Fleet, CII, 14), to which attention has already been drawn above. A reference to the *Mokharis* seems also to occur in the Chandravalli Stone Inscription of the Kadamba king Mayūraśarman (*Arch. Survey of Mysore*, A. R. 1929, pp. 50 ff). Dr. Tripathi finds a possible reference in the *Mahābhāshya* (JBORS, 1934, March). For the Baḍvā ins., see *Ep. Ind.*, XXIII, 42 ff. (Altekar).

² In literature the Maukhari line of U. P. is associated with the city of Kanauj which may have been the capital at one time. Cf. C. V. Vaidya, *Medieval Hindu India*, I, pp. 9, 33; Aravamuthan, *the Kaveri, the Maukharis and the Sangam Age*, p. 101. Hiuen Tsang, however, declares Kanauj to have been included within the realm of the House of Pushyabhūti even before Harsha. A Gupta noble was in possession of Kuśasthala (Kanauj) for some time after the death of Rājyavardhana and before the rise of Harsha. (*Harsha-Charita*. Parab's ed., pp. 226, 249).

³ Fleet, CII. 220.

⁴ The victory over the Andhras is also alluded to in the Jaunpur stone inscription (CII, p. 230) which, according to Fleet, also seems to refer to a conflict with Dhārā, the capital of Western Mālava (?). Dr. Basāk thinks that Dhārā in this passage refers to the edge of the sword (*Hist. N. E. Ind.*, 109).

Gupta III.¹ Thus began a duel between the Maukharis and the Guptas which ended only when the latter with the help of the Gaudas wiped out the Maukhari power in the time of Grahavarman, brother-in-law of Harshavardhana.²

We have seen that Īśānavarman's mother and grandmother were probably Gupta princesses. The mother of Prabhākaravardhana, the other empire-builder of the second half of the sixth century, appears also to have been a Gupta princess. It seems that the Gupta marriages in this period were as efficacious in stimulating imperial ambition³ as the Lichchhavi marriages of more ancient times.

Kumāra Gupta III claims to have "churned that formidable milk-ocean, the cause of the attainment of fortune, which was the army of the glorious Īśānavarman, a very moon among kings."⁴ This is not an empty boast, for the Maukhari records do not claim any victory over the Guptas. Kumār Gupta III's funeral rites took place at Prayāga which probably formed a part of his dominions.

The son and successor of this king was **Dāmodara Gupta**. He continued the struggle with the Maukharis⁵ and fell fighting against them. "Breaking up the proudly stepping array of mighty elephants, belonging to the

¹ Any one acquainted with the history of Europe knows that enumeration as I, II, III etc. need not imply that the kings in question belonged to the same dynasty.

² The successors of Grahavarman may have survived as petty nobles. With them a "Later Gupta" king contracted a matrimonial alliance in the seventh century A. D.

³ Cf. Hoernle, JRAS, 1903, p. 557.

⁴ Aḥṣaḍ Ins.

⁵ The Maukhari opponent of Dāmodara Gupta was either Sūryavarman or Sarvavarman (both being sons of Īśānavarman), if not Īśānavarman himself. A Sūryavarman is described in the Sirpur stone inscription of Mahāśīva Gupta as "born in the unblemished family of the Varmans, great on account of their *ādhipatyā* (supremacy) over Magadha." If this Sūryavarman be identical with,

Maukhari, which had thrown aloft in battle the troops of the **Hūṇas** (in order to trample them to death), he became unconscious (and expired¹ in the fight).''

Dāmodara Gupta was succeeded by his son **Mahāsena Gupta**. He is probably the king of Mālava, possibly Eastern Mālwa, mentioned in the *Harsha-charita*, whose sons Kumāra Gupta and Mādhava Gupta were appointed to wait upon Rājya-var dhana and Harsha-var dhana by their father, king Prabhākara-var dhana of the Pushyabhūti family of Śrikanṭha (Thānesar). The intimate relation between the family of Mahāsena Gupta and that of Prabhākara-var dhana is proved by the Madhuban grant and the Sonpat copper seal inscription of Harsha which represent Mahāsena Gupta Devī as the mother of Prabhākara, and the Aphaṣ inscription of Ādityasena which alludes to the association of Mādhava Gupta, son of Mahāsena Gupta, with Harsha.

The Pushyabhūti alliance of Mahāsena Gupta was probably due to his fear of the rising power of the Maukharis.² The policy was eminently successful, and

or a descendant of, Śūryavarman, the son of Išānavarman, then it is certain that for a time the supremacy of Magadha passed from the hands of the Guptas to that of the Maukharis. The Deo-Baraṇār Inscription (Shāhābad District) of Jivita Gupta II also suggests (CII, pp. 216-218) that the Maukharis Sarvavarman and Avantivarman held a considerable part of Magadha some time after Bālāditya-deva. After the loss of Magadha the later Guptas were apparently confined to "Mālava," till Mahāsena Gupta once more pushed his conquests as far as the Laubhitya.

¹ Reference to *Mahābhārata* XII. 99, 46-47; *Raghuvamśa*, VII. 53; *Kāvyādarśa*, II, 119; *Rājatarāṅgiṇī*, I. 68, shows that the objections raised against the interpretation of Fleet are invalid. The significance of the touch of *Surabadhūsa* as distinct from a human being, is entirely missed by a writer in Bhand. Com. Vol. 181, and a reviewer of Dr. Tripathi's *History of Ancient India*.

² And perhaps of other aggressive states mentioned in the beginning of the fourth *Uchchhṛāsa* of the *Harsha-charita*. The Lāṭas of that passage may have reference to the Kaṭachchuris who finally ousted the Guptas from Vidiśā in or about A. D. 608. The Kaṭachchuri (Kalachuri) dominions included the Lāṭa

during his reign we do not hear of any struggle with that family. But a new danger threatened from the east. A strong monarchy was at this time established in **Kāmarūpa** by a line of princes who claimed descent from Bhagadatta. King *Susthitavarman*¹ of this family came into conflict with Mahāsena Gupta and was defeated. "The mighty fame of Mahāsena Gupta," says the Aṃśad inscription, "marked with honour of victory in war over the illustrious Susthitavarman.....is still constantly sung on the banks of the river Lohitya."

Between Mahāsena Gupta, the contemporary of Prabhākara-vardhana, and his younger or youngest son Mādhava Gupta, the contemporary of Harsha, we have to place a king named **Deva Gupta II**² who is mentioned by name in the Madhuban and Banskhera inscriptions of Harsha as the most prominent among the kings "who resembled wicked horses," who were all punished and restrained in their evil career by Rājya-vardhana. As the Gupta princes are uniformly connected with Mālava in the *Harsha-charita* there can be no doubt that the wicked Deva Gupta is identical with the wicked lord of Mālava who cut off Grahavarman Maukharī, and who was himself defeated "with ridiculous ease" by Rājya-vardhana.³ It is difficult

country in the latter part of the sixth and the first decade of the seventh century A.D. (Dubreuil, A.H.D., 82).

¹ See the Nidhanapur platea. A writer in the JRAS (1929) revives the theory that Susthitavarman was a Maukharī and not a king of Kāmarūpa. But no Maukharī king of that name is known. The association of Susthitavarman with the river Lohitya or Brahmaputra clearly shows that the king of that name mentioned in the Nidhanapur plates is meant.

² The Emperor Chandra Gupta II was Deva Gupta I.

³ It is difficult to believe, as does one writer, that the Mālava antagonist of Grahavarman and Rājya-vardhana was Buddharaja of the Kalachuri (Kaṭach-churi) family. Had that been the case then it is rather surprising that a shadowy figure like Devagupta, and not Buddha-rāja, would be specially selected in the epigraphic records of the time of Harsha, for prominent notice among "the kings who resembled wicked horses," who received punishment at the hands of Rājya-vardhana. It is the 'Guptas' who are associated with Mālava in the *Harsha-*

to determine the position of Deva Gupta in the dynastic list of the Guptas. He may have been the eldest son of Mahāsena Gupta, and an elder brother of Kumāra Gupta and Mādhava Gupta.¹ His name is omitted in the Aphaṣṭ list of kings, just as the name of Skanda Gupta is omitted in the Bhītārī list.

Shortly before his death, king Prabhākara-vardhana had given his daughter Rājyaśrī in marriage to Grahavarman, the eldest son of the Maukhari king Avantivarman. The alliance of the Pushyabhūti with the sworn enemies of his family must have alienated Deva Gupta, who formed a counter-alliance with the Gaṇḍas whose hostility towards the Maukharis dated from the reign of Iśānavarman. As soon as Prabhākara died the Gupta king and the Gaṇḍa king, Śaśāṅka,² seem to have made a joint attack on the Maukhari kingdom. "Graha-varman was by the wicked *rājā* of Mālava cut off from the living along with his noble deeds. Rājyaśrī also, the princess, was confined like a brigand's wife with a pair of iron fetters kissing her feet

charita which deals mainly with events till the rescue of Rājyaśrī. The rulers mentioned in connection with the tragic fate of the last of the Maukharis, the vicissitudes through which Rājyaśrī passed, and the struggles in which Rājya-vardhana engaged, include Guptas and Gaṇḍas but no Kaśāpachuri king.

¹ Hoernle, JRAS, 1909, p. 562. The suggestion, however, cannot be regarded as a well-established fact. Devagupta may have represented a collateral line of the Mālava family who continued to pursue a policy hostile to the Pushyabhūti and the Maukharis, while Kumāra, Mādhava, the Gupta *Kuloputras* who connived at the escape of Rājyaśrī from Kudasthala (Kananj), and Ādityasena, son of Mādhava, who gave his daughter in marriage to a Maukhari, may have belonged to a friendly branch.

² There is no reason to believe that Śaśāṅka belonged to the Gupta family (pace Allan, *Gupta Coins*, *loc. cit.*). Even if it be proved that he had a secondary name, Narendra Gupta, that by itself cannot establish a connection with the Gupta line in view of (a) the absence of any reference to his supposed Gupta ancestry in his own seal matrix ins. or in the record of his feudatories, (b) the use of the *Nandidhva* to the exclusion of the *Gaṇḍadhva*, (c) his Gaṇḍa connection. The epithet '*Samudrādhipa*' applied to the Gaṇḍas of the sixth century A. D., can hardly be regarded as an apposite characterisation of the Guptas of Magadha, Prayāga or Mālwa.

and cast into prison at Kanyakubja." "The villain, deeming the army leaderless purposes to invade and seize this country (Thanesar) as well." Rājya-vardhana, though he routed the Mālava army "with ridiculous ease," was "allured to confidence by false civilities on the part of the overlord of Gauḍa, and then weaponless, confiding and alone despatched in his own quarters."

To meet the formidable league between the Guptas and the Gauḍas, Harsha, the successor of Rājya-vardhana, concluded an alliance with Bhāskara-varman, king of Kāmarūpa, whose father Suśhita-varman Mṛigāṅka had fought against Mahāsenā Gupta. This alliance was disastrous for the Gauḍas as we know from the Nidhanapur plates of Bhāskara. At the time of the issuing of the plates Bhāskara-varman was in possession of the city of Karpasuvārṇa that had once been the capital of the Gauḍa king, Śaśāṅka, whose death took place some time between A.D. 619 and 637. The king overthrown by Bhāskara-varman may have been Jayanāga (*nāgarāja-samāheyaḥ Gauḍarāja*), the king of Gauḍa named Nāga, successor of *Somākhyā* or Śaśāṅka, whose name is disclosed by the Vappaghoshavāṭa inscription.² The Gauḍa people, however, did not tamely acquiesce in the loss of their independence. They became a thorn in the side of Kanauj and Kāmarūpa, and their hostility towards those two powers was inherited by the Pāla and Sēna successors of Śaśāṅka.

In or about A.D. 608 the Guptas seem to have lost Vidiśā to the Katachchuris. Magadha was held a little before A.D. 637 by Pūrṇavarman. **Mādhava Gupta**, the younger or youngest son of Mahāsenā Gupta, remained a subordinate ally of Harsha of Thanesar and Kanauj and

¹ *Harsha-charita*, Uchchheṣṭa 9, p. 183.

² *Ep. Ind.*, XVIII, pp. 69 ff; *Ārya-Manjudri-mūla-kalpa*, ed. G. Sāstri, p. 63b. The name *Jaya* is also given in the Buddhist work.

apparently resided at his court. In the period 618-27, Harsha "punished the kings of four parts of India" and in 641 assumed the title of King of Magadha.¹ After his death the Gupta sovereignty in Magadha was revived by **Ādityasena**, a prince of remarkable vigour and ability, who found his opportunity in the commotion which followed the usurpation of Harsha's throne by Arjuna (?). For this "Later Gupta" king we have a number of inscriptions which prove that he ruled over a wide territory extending to the shores of the oceans. The Aphsā, Shāhpur and Mandāra inscriptions recognise his undisputed possession of south and part of east Bihār. A Deoghar inscription, noticed by Fleet,² describes him as the ruler of the whole earth up to the shores of the seas, and the performer of the *Āśvamedha* and the other great sacrifices. He renewed contact with the Gauḍas as well as the Maukharis and received a Gauḍa named Sūkshamśiva in his service. A Maukhari chief, Bhogavarman, accepted the hands of his daughter³ and presumably became his subordinate ally. The Dēo-Baraṇārī inscription refers to the *Jayaskandhāvāra* of his great-grandson Jīvita Gupta II at Gomatīkoṭṭaka. This clearly suggests that the so-called Later Guptas, and not the Maukharis, dominated about this time the Gomatī valley in the *Madhya-deśa*. The Mandāra inscription applies to Ādityasena the imperial titles of *Parama-bhaṭṭāraka* and *Mahārājādhirāja*. We learn from the Shāhpur stone image inscription that he was ruling in the year A.D. 672-73. It is not improbable that he or his son Deva Gupta (III) is the *Sakalottarā-patha-nātha*, lord of the whole of North India,

¹ *Ind. Ant.*, IX, 19.

² CII, p. 213 n. Āditya is said to have performed three *Āśvamedha* sacrifices.

³ Kielhorn, INI, 541.

who was defeated by the Chalukya kings Vinayāditya (A.D. 680-96) and Vijayāditya.¹

We learn from the Dēo-Baraṇār̥k inscription that Ādityasena was succeeded by his son **Deva Gupta** (III), who in his turn was succeeded by his son **Vishṇu Gupta** (II).² The last king was **Jivita Gupta II**, son of Vishṇu. All these kings continued to assume imperial titles. That these were not empty forms appears from the records of the Western Chalukyas of Vātāpi which testify to the existence of a Pan-North Indian empire in the last quarter of the seventh century A. D. The only North Indian sovereigns, *Uttarāpatha-nātha*, who laid claim to the imperial dignity during this period, and actually dominated Magadha and the *Madhya deśa* as is proved by the Aphaṣṭ and Dēo-Baraṇār̥k inscriptions, were Ādityasena and his successors.³

The Gupta empire was probably finally destroyed by the Gauḍas who could never forgive Mādhava Gupta's desertion of their cause and who may have grown powerful in the service of Ādityasena. In the time of Yaśovarman of Kanauj, *i.e.*, in the first half of the eighth century A. D., a Gauḍa king occupied the throne of Magadha.⁴

¹ *Bomb. Gaz.* Vol. I, Part II, pp. 189, 368, 371; and Kendur plates.

² This king seems also to be mentioned in an inscription discovered at Mangraon in the Buxar subdivision.

³ For a curious reference to the Chalukyas and king Jih-kwan ('Sun army' *i.e.* Ādityasena), see IA, X, p. 110.

⁴ Cf. the *Gauḍacaho* by Vākpatirāja. Banerji confounds the Gauḍas with the later Guptas. In the Harāhā Inscription the Gauḍas are associated with the sea-coast, *Samudrāsraya*, while the later Guptas, as is well-known, had their centres in the hinterland including Magadha and Mālwa. The people on the seashore were, according to the evidence of the Aphaṣṭ Inscription, hostile to Jivita Gupta I. The *Prasastikāra* of the Aphaṣṭ record is expressly mentioned as a Gauḍa, a designation that is never applied to his patrons. The family of Kṛishṇa Gupta is simply characterised as *Sadvamśa* and there is not the slightest hint that the kings of the line and their panegyrist belonged to the same nationality. The fact that Gauḍa is the designation of the lord of Magadha

Petty Gupta Princes, apparently connected with the imperial line, ruled in the Kanarese districts during the twelfth and the thirteenth centuries A.D. and are frequently mentioned in inscriptions. Evidence of an earlier connection of the Guptas with the Kanarese country is furnished by the Tālagund inscription which says that Kākustha-varman of the Kadamba dynasty gave his daughters in marriage to the Gupta and other kings. In the fifth or sixth century A. D. the Vākāṭaka king Narendrasena, a descendant of Chandra Gupta II Vikramāditya through his daughter Prabhāvatī Guptā, is said to have married a princess of Kuntala, *i.e.*, of the Kanarese region.¹ Curiously enough, the Gutta or Gupta chiefs of the Kanarese country claimed descent from Chandra Gupta Vikramāditya,² lord of Ujjayinī.³


in the days of Yaśovarman early in the eighth century cannot be taken to prove that Gauḍa and later Gupta are interchangeable terms. In this period lordship of Magadha is not inseparably connected only with later Gupta lineage. Cf. the passage *Magadhātīpatyamahatām jāta kule varmaṇām*, which proves the existence of non-Gupta lines among rulers of Magadha in this age.

¹ Jouveau-Dubreuil, AHD, p. 76.

² *Bomb. Gaz.*, Vol. I, Part II, pp. 573-80. Sir R. G. Bhandarkar, "A Peep into the Early History of India," p. 60. I owe this reference to Dr. Bhandarkar.

³ The account of the Later Guptas was first published in the JASB, 1920, No. 7.

THE LATEST GUPTAS



¹ A. Ghosh, *Two Maukhari seals from Nalanda*, Ep. xxiv, 285. We have reference to another son of Avantivarman named Suva or Such.....who seems to have succeeded his father. Grahavarman too, has royal epithets in the *Harsha-charita* (pp. 149, 183). The order of succession is not, however, clear from available evidence.

APPENDIX A.

THE RESULTS OF AŚOKA'S PROPAGANDA IN WESTERN ASIA.¹

The vast region beyond the western frontiers of India came within the geographical horizon of Buddhist writers as early as the *Bāveru Jātaka*, and possibly the *Sussandi Jātaka*, and its princes figure not inconspicuously in Buddhist inscriptions of the third century B.C. The records of Aśoka show that the eyes of the imperial missionary of Magadha were turned more to the West than to the East; and even the traditional account of early Buddhist proselytising efforts given in the chronicles of Ceylon,² does not omit to mention the country of the Yonas where Mahārakkhita "delivered in the midst of the people the '*Kālakārāma suttanta*,' in consequence of which a hundred and seventy thousand living beings attained to the reward of the path (of salvation) and ten thousand received the *pabbajjā*." It will perhaps be argued that the Yona country mentioned in the chronicles is to be identified with some district in the Kābul valley, and is not to be taken to refer to the realm of "Antiochos," the Yona king, and the kings, the neighbours of that Antiochos, namely, Ptolemy, Antigonos, Magas and Alexander," mentioned in the second and the thirteenth rock edicts of Aśoka. Rhys Davids, in fact, is inclined to regard the declaration in these edicts about the success of Aśoka's

¹ Mainly an extract from an article published in the *Buddhist Studies* (ed. B. C. Law).

² *Mahāvamsa*, Ch. XII.

³ Dr. Jarl Charpentier has contributed a paper to *A Volume of Indian Studies presented to Professor E. J. Rapson* in which he revives the suggestion of Prinsep (Hultzsch, *Aśoka*, xxxi) that "Amūtiyaka" referred to by Aśoka is Antiochos Soter (281-61), and not his son Antiochos Theos (261-46). But his theory requires that Chandragupta ascended the throne in 327-25 B.C., that he was identical with Xandrames and that the story of his visit to Alexander (recorded by Justin and Plutarch) is a myth. The theory is opposed not only to the evidence of Justin and Plutarch, but to the known facts about the ancestry of Chandragupta. Unlike Xandrames, Chandragupta is nowhere represented as of barbaric origin. His paternal ancestors are described as rulers by Brāhmanical and Buddhist writers alike.

missionary propaganda in the realms of Yona princes as mere "royal rhodomontade". "It is quite likely," says he, "that the Greek kings are only thrown in by way of make-weight, as it were; and that no emissaries had been actually sent there at all."¹ Sir Flinders Petrie is, however, of opinion that in the Ptolemaic Period Buddhism and Buddhist festivals had already reached the shores of Egypt. He infers this from Indian figures found at Memphis. An epigraph from the Thebaid mentions as the dedicator "Sophon the Indian".²

Alberuni,³ writing in the eleventh century A. D. says, "In former times Khurāsān, Persis, Irāk, Mosul, the country up to the frontier of Syria, was Buddhistic, but then Zarathustra went forth from Ādharbaijān and preached Magism in Balkh (Baktra). His doctrine came into favour with king Gushtasp, and his son Isfendiyād spread the new faith both in East and West, both by force and by treaties. He founded fire-temples through his whole Empire, from the frontiers of China to those of the Greek Empire. The succeeding kings made their religion (*i.e.*, Zoroastrianism) the obligatory state-religion for Persis and Irāk. In consequence the Buddhists were banished from those countries, and had to emigrate to the countries east of Balkh Then came Islam." The above account may not be correct in all its particulars. The statement that Buddhism flourished in the countries of Western Asia before Zoroaster is clearly wrong. But the prevalence of the religion of Śākyamuni in parts of Western Asia in a period considerably anterior to Alberuni and its suppression by Zoroastrianism and Islam may well be based upon fact. The antagonism of Buddhism to the fire-cult is hinted at in the *Bhūridatta Jātaka*.⁴ It has even been suggested that Zoroastrian scriptures allude to disputes with the Buddhists.⁵

Four centuries before Alberuni, Hiuen Tsang bore witness to the fact that Lang kie(ka)-lo, a country subject to Persia, contained above 100 monasteries and more than 6,000 Brethren

¹ *Buddhist Indiā*, p. 238.

² Mahaffy, *A History of Egypt under the Ptolemaic Dynasty*, 155 f.

³ Sachau, *Alberuni's India*, Vol. I, p. 21.

⁴ No. 543.

⁵ Sir Charles Eliot, *Hinduism and Buddhism*, III, 450.

who applied themselves to the study of the Great and Little "Vehicles". Persia (Po-la-sse) itself contained two or three *Saṅghārāmas*, with several hundred priests, who principally studied the teaching of the Little Vehicle according to the Sarvāstivādin school. The *pātra* of Śākya Buddha was in this country, in the King's palace.¹

The Chinese pilgrim did not probably personally visit Persia. But no doubt need be entertained regarding the existence of Buddhist communities and *Saṅghārāmas* or monasteries in Irān. Stein discovered a Buddhist monastery in "the terminal marshes of the Helmund" in Seistān.² Mānī, the founder of the Manichæan religion, who was born in A.D. 215-16, at Ctesiphon in Babylonia and began to preach his gospel probably in A.D. 242, shows unmistakable traces of Buddhist influence.³ In his book *Shābūrqn̄* (*Shapurakhan*) he speaks of the Buddha as a messenger of God. Legge and Eliot refer to a Manichæan treatise which has the form of a Buddhist Sūtra. It speaks of Mānī as the *Tathāgata* and mentions *Buddhas* and the *Bodhisattva*. In Bunyiu Nanjio's *Catalogue of the Chinese translation of the Buddhist Tripiṭaka*, App., II, No. 4, we have reference to a Parthian prince who became a Buddhist *śramaṇa* or monk before A.D. 148. In his *History of Fine Art in India and Ceylon*,⁴ Dr. Vincent Smith refers to a picture of a four-armed Buddhist saint or *Bodhisattva* in the guise of a Persian with black beard and whiskers, holding a thunderbolt (*vajra*) in his left hand, which has been found at a place called Dandān-Uiliq in Turkistan. Such figures are undoubtedly the products of a type of Buddhism which must have developed in Irān, and enjoyed considerable popularity as late as the eighth century A.D. which is the date assigned by Dr. Smith to the fresco or distemper paintings on wood and plaster discovered at Dandān-Uiliq.

It is difficult to say to what extent Buddhist literature made its influence felt in Western Asia. Sir Charles Eliot points

¹ Beal, *Records of the Western World*, Vol. II, pp. 277-78; Watters *Yuan Ching*, II, 257.

² Sir Charles Eliot, *Hinduism and Buddhism*, III, 3.

³ *Ibid.*, p. 446; *The Dacca University Journal*, Feb., 1926, pp. 103, 111; JRAS, 1913, 89, 76, 81.

⁴ P. 310.

out the close resemblance between certain Manichæan works and the Buddhist *Suttas* and the *Pātimokkha*, and says that according to Cyril of Jerusalem, the Manichæan scriptures were written by one Scythianus and revised by his disciple Terebinthus who changed his name to Boddas.¹ He finds in this "jumble" allusions to Buddha Sākyamuni and the Bo-tree. It may further be pointed out that some *Jātaka* tales show a surprising similarity to some of the stories in the *Arabian Nights*. The *Samugga Jātaka*², for instance, tells the story of the demon who put his beautiful wife in a box and guarded her in this manner in order that she might not go astray.³ But this did not prevent her from taking pleasure with others. The tale in all its essentials recurs in the *Arabian Nights*.³

The *Jātaka* verse,

"He his true bliss in solitude will find,
Afar from woman and her treachery"

is comparable to the statement of the poet in the *Arabian Nights*:

"Never trust in women ; nor rely upon their vows ;
For their pleasure and displeasure depend upon their passions.
They offer a false affection ;
For perfidy lurks within their clothing."

Whatever may be the case at the present day, in times gone by Western Asia was clearly not altogether outside the sphere of the intellectual and spiritual conquests of Buddhism.

¹ Cf. McCrindle, *Ancient India as described in Classical Literature*, p. 185.

"Terebinthus proclaimed himself learned in all the wisdom of the Egyptians and gave out that his name was no longer Terebinthus but that he was a new Buddha (Boddas) and that he was born of a virgin. Terebinthus was the disciple of Scythianus, who was a Saracen born in Palestine and who traded with India."

² No. 436

³ Burton, *The Book of the Thousand Nights*, I. 12ff; Olcott, *Stories from the Arabian Nights*, p. 3; Lane's *Arabian Nights*, pp. 8-9. A similar story is found in *Lambaka X*, *tarāṅga* 8 of the *Kathā-sarit-sāgara*; Penzer, *The Ocean of Story*, Vol. V. pp. 151-52. "So attachment to women, the result of infatuation produces misery to all men. But indifference to them produces in the discerning emancipation from the bonds of existence."

APPENDIX B.

A NOTE ON THE CHRONOLOGICAL RELATION OF KANISHKA AND RUDRADĀMAN I.¹

Some years ago² Mr. Haricharan Ghosh and Professor Jayachandra Vidyalankar contributed two very interesting notes on the date of Kanishka. The latter upholds the theory of Dr. Sten Konow, fortified by the calculations of Dr. Van Wijk, that the great Kushān Emperor began his rule in A.D. 128-29, and criticises the view put forward in this work that Kanishka I's rule in the "Lower Indus Valley" (this and not "Sind," is the expression actually used) could not have synchronised with that of Rudradāman I, who, "did not owe his position as *Mahākshatrpa* to anybody else." The conclusions of Professor Konow and Dr. Van Wijk are admittedly hypothetical, and little more need be said about them after the illuminating observations of Professor Rapson in *JRAS*, 1930, January, pp. 186-202. In the present note we shall confine ourselves to an examination of the criticism of Professor Jayachandra Vidyalankar and Mr. Haricharan Ghosh of the views expressed in the preceding pages.

The Professor has not a word to say about the contention that Kanishka's dates 1-23, Vāsishka's dates 24-28, Havishka's dates 31³-60, and Vāsudeva's dates 67-98 suggest a continuous reckoning. In other words, Kanishka was the originator of an era. But we know of no era current in North-West India which commenced in the second century A. D. He only takes considerable pains to prove that Rudradāman's sway over Sindhu-Sauvīra (which he identifies with modern Sind) between 130 and 150 A. D. does not imply control over Sui Vihār and Multān, and consequently Kanishka's sovereignty over Sui Vihār in the year 11 of an era starting from 128-29 A.D., i. e., in or about 140 A.D., is not irreconcilable

¹ *IHQ*, March, 1930, pp. 149 ff.

² *IHQ*, V, No. 1, March, 1929, pp. 49-80, and *JBORS*, XV, parts I & II March-June, 1929, pp. 47-63.

³ The earliest recorded date of Havishka is now known to be the year 28

with the rule of the Great Satrap in Sindhu-Sauvīra at about the same time. He is not oblivious of the difficulty of harmonising this limitation of Rudradāman's power with the known fact of the Great Satrap's campaign against the Yaudheyas in the course of which he claims to have uprooted that powerful tribe "in their country proper which was to the north of Suē Vihār" and, according to the theory advocated by the Professor, "formed part of Kanishka's dominions" at that time. He meets the difficulty by saying that "the pressure of the Kausāna armies from the north had driven the Yaudheyas to the desert of Marwar". Such surmises to explain away inconvenient details, are, to say the least, not convincing, especially in view of the fact that Maru finds separate mention in the inscription of Rudradāman as a territory under the rule of the mighty Satrap.

But is the contention of the Professor that Sindhu-Sauvīra did not include the country up to Multān correct? Alberuni, who based his assertions on the geographical data of the *Purāṇas* and the *Bṛihatsaṃhitā*, made the clear statement that Sauvīra was equivalent to Multān and Jāhrāvār.¹ Against this Professor Vidyānāth quotes the evidence of Yuan Chwang who says that in his days "Mou-lo-san-po-lu," i.e. Mūla-sthāna-pura or Multān was a dependency of the "Che-ka" or Takka country in the C. Pañjāb. It should be noted, however, that the Chinese pilgrim is referring to political dependence, and not geographical inclusion. India was a dependency of Great Britain. But geographically it was not a part of the British Isles. On the other hand, Alberuni does not give the slightest hint that what he actually means by the equation "Sauvīra, i.e., Multān and Jāhrāvār" is political subjection of Multān to Sind. His account here is purely geographical, and he is merely giving the names of the countries, as taken from the *Samhitā* of Varāhamihira with his own comments. Far from making Multān a political dependency of Sind he carefully distinguishes "Sauvīra, i.e., Multān and Jāhrāvār" from "Sindhu" which is mentioned separately.

The view that ancient Sauvīra was confined to Southern Sind and that Sindhu and Sauvīra together correspond to

modern Sind, and nothing but Sind, is unsupported by any early evidence. Yuan Chwang went east from Sin-tu above 900 li and, crossing to the east bank of the Indus, came to the Mon-lo-san-pu-lu country.¹ This proves that Sin-tu lay to the west of Mou-lo-san-pu-lu (Multān), and was situated on the west side of the Indus. The commentator of the *Kāma-sūtras* of Vātsyāyana makes the clear statement² सिन्धुनामा नदस्तस्य पश्चिमेन सिन्धुदेशस्तस्य भवानाम् । The major part of modern Sind was clearly outside the geographical (as opposed to the political) limits of ancient "Sin-tu" or Sindhu and was, in the days of Yuan Chwang, included in the countries of A-tien-p'o-chih-lo, Pi-to-shih-lo, and A-fan-tu. Part of the modern territory of Sind may have been included in Sauvira whose southern limits undoubtedly reached the sea, because the *Milinda-Pañho* mentions it in a list of countries where "ships do congregate". We are informed by the author of the *Periplus* that "ships lie at anchor at Barbaricum" (at the mouth of the Indus). But the evidence of Alberuni leaves no room for doubt that the northern limits of Sauvira reached Multān. A scholar like Alberuni thoroughly conversant with Purāṇic lore, is not likely to make an unwarranted statement. In fact, the inclusion of Multān within Sauvira receives striking confirmation from some of the *Purāṇas*. The *Skandapurāṇa*, for instance,³ referring to the famous temple of the Sun at Mūla-sthāna or Multān, says that stood on the banks of the river Devikā (*Devikātata*):—

ततो गच्छेन्महादेवि मूलस्थानमिति श्रुतम् ।

देविकायास्तटे रम्ये भास्करं वारितस्करम् ॥

In the *Agnipurāṇa*⁴ the Devikā is brought into special relations with the realm of Sauvira:—

सौवीरराजस्य पुरा मैत्रेयोभुव पुरोहितः ।

तेन चायतनं विष्णोः कारितं देविकातटे ॥

According to Yuan Chwang, Sin-tu and Multān were neighbouring countries lying on opposite sides of the Indus.

¹ Watters, II. 254.

² Benares edition, p. 295.

³ *Prabhāsa-ka-cira-Mahātmya*, Ch. 279.

⁴ Ch. 200.

This is quite in accordance with the close association of Sindhu and Sauvīra in early literature.

पतिः सौवीरसिन्धूनां दुष्टभावो जयद्रथः ।¹

कच्चिदेकः शिवीनाढ्यान् सौवीरान् सह सिन्धुभिः ।²

शिविसौवीरसिन्धूनां विषादश्चाप्यजायत ।³

Rudradāman's mastery over Sindhu and Sauvīra (in the sense in which these terms were understood by the *Purāṇas*, the commentator on the *Kāmasūtras* of Vātsyāyana, Yuan Chwang and Alberuni) is clearly irreconcilable with the simultaneous sovereignty of Kanishka over Sui Vihār.

Apart from the identification of Sauvīra with Multān and Jāhrāvār, is it unreasonable to hold that a power which exercised sway over ancient Sindhu and Maru, and fought with the Yaudheyas of Johiyawār, had the Sui Vihār region under its control?

Mr. H. C. Ghosh asserts⁴ that it cannot be proved that Rudradāman held Sindhu and Sauvīra some time from 136 A.D. at least. He also thinks that the argument that Kanishka started an era "involves a *petitio principii*." Now, we know that by 150 A.D. Rudradāman was "the lord of the whole of eastern and western Ākarāvanti, Anupanīyid, Ānartta, Surāshṭra, Svabhra, Maru, Kachchha, Sindhu, Sauvīra, Kukura, Aparānta, Nishāda, and other territories gained by his own valour." The conquest of so many countries must have taken a long time, and the Andhan inscriptions show that one of the countries, at any rate, namely, Kachchha, had come under the sway of the Great Satrap as early as 130 A.D. On p. 277 of the *Political History of Ancient India* (second edition) it has been pointed out that "the name of the capital of Scythia (*i.e.*, the Lower Indus Valley) in the time of the Periplus was Minnagara, and this was evidently derived from the city of Min in Śakasthāna mentioned by Isidore. Rapson points out that one of the most characteristic features in the name of the western

¹ Mbh., III, Ch. 266.

² Mbh., III, Ch. 266.

³ Mbh., III, Ch. 270.

⁴ *IHQ*, 1929, p. 79.

Kshatrapas of Cashṭana's line, viz., 'Dāman' (-dama) is found also in the name of a prince of the Drangianian house of Vonones. Lastly, the Kārdamaka family, from which the daughter of the *Mahākshatrapa* Rudra claimed descent, apparently derived its name from the Kārdama river in Persia."

The facts noted above indicate that the Saka sept to which Chasṭana and Rudradāman belonged came from Sakasthāna in Irān through the Lower Indus Valley to Cutch and other places in Western India. In view of this and the contiguity of Cutch to the Lower Indus Valley, it is permissible to think that the date of the conquest of Sindhu and Sauvira could not have been far removed from, and may have even preceded, that of Cutch (Kachchha). As the great Satrap retained his hold on these provinces till 150 A.D. it stands to reason that he was their ruler from c. 136 A.D.

As to the second contention of Mr. Ghosh, it may be pointed out that Kanishka's dates 1-23, Vāsishka's dates 24-28, Huvishka's dates 28-60, and Vāsudeva's dates 67-98, do suggest a continuous reckoning. To deny that Kanishka started an era is tantamount to saying that the dates of his successors, Vāsishka, Huvishka, and Vāsudeva are regnal years. But no serious student will contend that Vāsudeva's dates 67-98 are to be taken as regnal years.

APPENDIX C.

A NOTE ON THE LATER GUPTAS.¹

It was recently urged by Professor R. D. Banerji that Mahāsena Gupta of the Aḥṣaḍ inscription, father of Mādhava Gupta, the associate of Harsha, could not have been a king of East Mālava, and secondly, that Susthitavarman whose defeat at the hands of Mahāsena Gupta, in the Lohita or Lauhitya region, is mentioned in the Aḥṣaḍ inscription, was not a Maukhari, but a king of Kāmarūpa.

The second proposition will be readily accepted by all careful students of the Aḥṣaḍ epigraph and the Nidhanapur plate inscription, though some western scholars are still, I know not why, of a contrary opinion.² As to the first point, *viz.*, whether Mahāsena Gupta was a direct ruler of East Mālava or of Magadhā, a student will have to take note of the following facts :—

- (i) In the Dēś-Baraṇārka Inscription of Jivita Gupta II, which records the continuance of the grant of a village³ in South Bihar, we have reference to Bālāditya-deva, and after him, to the Maukharis Sarva-varman and Avanti-varman. Not a word is said about their later Gupta contemporaries in connection with the previous grants of the village. The inscription is no doubt damaged, but the sovereignty of Sarva-varman and Avanti-varman undoubtedly precludes the possibility of the direct rule of their contemporaries of the later Gupta line.

¹ Mainly an extract from an article published in *JBORS*, Sept.-Dec., 1929, pp. 561 ff.

² *JRAS*, 1926, July, pp. 689f.

³ Dr. R. C. Majumdar's suggestion that the village in question may have been situated in U. P. has been commented upon by Dr. Sircar who points out that Fleet's reading of the name of the village (on which Dr. Majumdar bases his conclusions) is tentative and unacceptable.

- (ii) Inscriptions discovered in the Barābar and Nāgārjuni hill caves disclose the existence of another line of Maukhari "Varmans" who were feudatory (*sāmanta*) chiefs of the Gayā district in the time of the later Guptas.
- (iii) Yuan Chwang who visited Magadha in the time of Harsha mentions Pūrṇa-varman as the occupant of the throne of Magadha.¹ He does not say a word about Mādhava Gupta or his father in connection with Magadha.
- (iv) Bāṇa indeed, refers to Mādhava Gupta, the associate of Harsha, but he expressly mentions his father as the king of Mālava, and not of Magadha. The existence of two associates of Harsha, each bearing the name of Mādhava Gupta, one of whom was the son of a king of Magadha, is not known to the biographer of the great emperor.

From the evidence adduced above two facts emerge, *viz.*, that the father of the only Mādhava Gupta whom the biographer of Harsha knew to be the associate of his royal patron, was a king of Mālava, and that before Harsha's conquest of the province in A. D. 641,² direct control over Magadha was exercised, not by the Guptas, but by the "Varmans". The memory of "Varman" *ādhipatya* (supremacy) over Magadha had not died away even in the time of the Sirpur stone inscription of Mahāsiva Gupta.

The only relevant argument that Professor Banerji urged against the view that Mahāsena Gupta, the father of Mādhava Gupta, the associate of Harsha, was "*probably*"³ a king of Mālava, is that "it was impossible for a king of Mālava to reach the banks of the Laṅghitā without strenuous opposition from the kings" who governed the intervening region. But how did Professor Banerji solve the problem? By making Mahāsena Gupta king of Magadha, and assuming that "Assam

¹ Watters, III, 115.

² *Ind. Ant.*, IX, 19.

³ *Political History of Ancient India, Second Edition*, p. 373.

very probably lay on his frontier and Rādhā and Vanga or Mithilā and Varendra were included in his kingdom." Anything in the nature of a proof he failed to give, but we were asked to accept his surmise because "in this case only is it possible for Mahāsenā Gupta to have fought with Susthitarman of Assam."

Regarding the possibility of a king of Mālava carrying his arms to the banks of the Laubitya, attention may be invited to the Mandaśor inscription of Yaśodharman. In the case of Mahāsenā Gupta a careful student of the Aphaṣṭ inscription cannot fail to note that the way before him had been prepared by his immediate predecessors. Kumāra Gupta, his grandfather, had pushed to Prayāga, while Dāmodara Gupta, father of Mahāsenā Gupta, claims to have "broken up the proudly stepping array of mighty elephants, belonging to the Maukhari" —the same power which we have already seen, held control of Magadha a little before Harsha's conquest of the Province. The Gauḍa expansion had already been stopped for a time by the victories of Īśānavarman Maukhari. What was there to prevent the son of Dāmodara Gupta (who must have assumed command after the *death* of his father on the battle-field) ' from pushing on to the Laubitya ?

¹ Cf. Fleet Corpus III, pp. 203, 206. Cf. also *Viraśaṅgā motif ante*, 696 n 1.

APPENDIX D.

'THE DECLINE OF THE EARLY GUPTA EMPIRE.'

Towards the close of the fifth century A.D. the empire built up by the genius of Samudra Gupta and Vikramāditya was fast hastening towards dissolution. Skanda Gupta (A.D. 455- c. 467) was the last king of the Early Gupta line who is known to have controlled the westernmost provinces. After A.D. 467 there is no evidence that the Imperial Guptas had anything to do with Surāshṭra or the major part of Western Mālwa.¹ Budha Gupta (A.D. 476-77 to c. 495) was probably the last prince of the family to be implicitly obeyed on the banks of the Lower Ganges as well as the Narmadā. The rulers who came after him retained a precarious hold for some time on Eastern Mālwa and North Bengal. But they had to fight with enemies on all sides, and, if a tradition recorded

¹ First published in the *Calcutta Review*, April, 1880.

² The identity of the supreme lord (*Parama-rāḍmīn*) mentioned in connection with the consecration of the early Valabhi king Droṇasiṃha, is unknown. The surmise that he was a Gupta, though plausible lacks convincing proof. Some scholars lay stress on the fact that the era used is the Gupta era (IC, V. 409). But the use of an era instituted by a dynasty does not always indicate political subordination to that line. It may simply have a geographical significance, a continuation of a custom prevailing in a particular locality. Even undoubted Gupta vassals used the *Mālava-Vikrama Samvat* in Mandasor. Conversely the Gupta era is found used in regions, e.g., Shorkot, beyond the proper limits of the Gupta empire. Teipur, too, should possibly come under the category, as we are not sure as to whether it formed a part of the state of Kāmarūpa in the fourth century A. D. Equally conjectural is the identification of the ruler in question with a Hun or a sovereign of Mandasor. Theories and speculations in the absence of clear data are at best unprofitable. Some connection of the later kings of the Gupta line with the Mandasor region in W. Mālwa in the first quarter of the sixth century A. D. may possibly be hinted at by the expression *Guptanāthaḥ* 'by the Gupta lords' used in the Mandasor *pradasti* or panegyric of Yaśodharman. The term *nātha* may have reference to the fact that the Guptas were once overlords of Mandasor. But the analogy of *Hāṇadhipa* occurring in the same record may suggest that *nātha* simply means 'lord' or 'king' without reference to any special relations subsisting between Mandasor and the Guptas in or about 533 A.D.

CAUSES OF DECLINE OF GUPTA EMPIRE 627

by Jinasena,¹ is to be believed, their power collapsed in A.D. 551 (320+231) :

*Guptānām oha śata-deçyam
eka-trimśachcha varshāni
kāla-vidbhīr udāhṛitam.*²

The supremacy over Āryāvarta then passed to the houses of Mukhara (cir. A.D. 554)³ and Pushyabhūti (family of Harsha, A.D. 606-47) under whom the centre of political gravity shifted from Magadhā to Kanauj and that neighbourhood. Attempts were no doubt made by a line of so-called later Guptas to restore the fallen fortunes of their family, but these were not crowned with success till after the death of Harsha.

The causes of the decline of the early Gupta Empire are not far to seek, though a detailed presentation of facts is impossible in view of the paucity of contemporary records. The broad outline of the story is, however, perfectly clear. The same causes were at work which proved so disastrous to the Turki Sultanate of Delhi in the fourteenth century, and to the so-called Mughul Empire in the eighteenth, *viz*, outbreak of rebellions within, devastating invasions from without, the growth of a class of hereditary governors and other officials who commanded enormous influence in local centres, and assumed the titles of *Mahārāja* and *Mahārājādhirāja*, and dissensions in the imperial family itself.

Already in the time of Kumāra Gupta I, the stability of the empire was seriously threatened by a turbulent people whose name is commonly read as **Pushya-mitra**. The danger was averted by the crown prince Skanda Gupta. But a more formidable enemy appeared from the steppes of Central Asia. Inscriptions discovered at Bhitari, Kura, Gwalior and Eran, as well as the records of several Chinese pilgrims, prove that shortly after the

¹ *Harivamśa*, Ch. 80.

² *Ind. Ant.*, 1885, 142; *Bhand. Com.*, Vol., 193.

³ *Ep. Ind.*, XIV, pp. 110-20; *JRAS*, 1936, 843f. About this time (A.D. 554 or A.D. 564) as pointed out by Drs. Bhatiasali and Sircar, king Bhūti-varman of Assam is found arrogating to himself imperial titles by the performance of an *Aśvamedha* sacrifice. Cf. *Bhāratavarsha*, Ashājha, 1348, p. 83, etc. *Ep. Ind.*, xxvii, 18 l. Subsequently Sircar opines that he finds no Gupta year in the record.

death of Kumāra Gupta I, the fierce Huns swooped down upon the north-western provinces of the empire and eventually made themselves masters of the Pañjāb and Eastern Mālwa.

The newcomers were long known to the people of India as a race of Uitlanders closely associated with the Chinese. The *Mahāvastu*¹ mentions them along with the Chīnas, while the *Sabhāparva* of the *Mahābhārata*² includes them in a list of foreign tribes amongst whom the Chīnas occupy the first place:—

*Chīnān Sakāms tathā ch Odrān(?)³ Varvarān Vanavāsinaḥ
Vārshneyān(?) Hāra-Huṇāmścha Kṛishṇān Haimavataṁstathā.*

A verse in the *Bhīshmaparva*⁴ brings the Huns into relations with the Pārasikas or Persians:—

*Yavanās Chīna-Kāmbojā dāruṇā Mlecchchhajātayaḥ
Sakṛidgrahāḥ Kulatthāścha Huṇāḥ Pārasikāḥ saha.*

This verse is reminiscent of the period when the Huns came into contact with the Sassanian dynasty of Persia.⁵ Kālidāsa, too, places the Huns close to Persia—in the saffron-producing country watered by the river Vaṅkshu, the modern Oxus.⁶ Early in the reign of the Emperor Skanda Gupta they poured into the Gupta Empire, but were at first beaten back. The repulse of the Huns is mentioned in the Bhitari Inscription and is also probably alluded to by the grammarian Chandragomin as a contemporary event.⁷ With the passing away of Skanda Gupta, however, all impediments to the steady advance of the invaders seem to have been removed and, if Somadeva, a Jaina contemporary of Kṛishṇa III, Rāshṭrakūṭa, is to be

¹ I. 135.

² II. 51, 93-94

³ The mention of the Odras in this connection is odd. It is tempting to read in the epic verse Chaḍotāścha (instead of *tathāchodrān*). Chaḍota is the name of a territory in Central Asia near Khotan.

⁴ 9.65-86.

⁵ Smith. *EHI*. 4th edition, p. 339. See also W.M. McGovern, *The Early Empires of Central Asia*.

⁶ *Ind. Ant.*, 1912, 293f.

⁷ *Ind. Ant.*, 1896, 105.

believed, they penetrated into the Indian interior as far as Chitrakūṭa.¹ They certainly conquered the Eraṇ district (*Airikiṇa pradeśa*) in the northern part of the present Madhya Pradeśa. The principal centres of their power in India, in the time of their kings Toramāṇa and Mihirakula, were Pavvaiya on the Chināb² and Śākala, modern Siālkoṭ, between the Chenāb and the Degh, in the Upper Pañjāb.

Next to the Hun inroads must be mentioned the ambition of generals and feudatories. In the time of the Emperor Skanda Gupta, Surāshṭra was governed by a *Goptṛi* or Margrave named Parnadatta, who was appointed by the emperor himself to the Viceroyalty of the Far West. Shortly afterwards, Bhaṭārka, a chief of the **Maitraka** clan, established himself in this province as general or military governor, with his capital probably at Valabhi. He, as well as his immediate successor, Dharasena I, was satisfied with the title of *Senāpati* or general, but the next chief Droṇasimha, the second son of Bhaṭārka (A.D. 502-03) had to be installed as *Mahārāja* by his suzerain. A branch of the dynasty established itself in Mo-la-po (Mālavaka)³ or the westernmost part of Mālwa in the latter half of the sixth century, and made extensive conquests in the direction of the Sahya and Vindhya Hills.⁴ Another, and a junior, branch continued to rule at

¹ Bhand., *Com. Vol.*, 216. Chitrakūṭa may be Chitor in Rājaputāna, or more probably the equally famous Chitrakūṭa on the Mandākinī in Central India, where Rama lived for a short time during his banishment. A Hūga-mandala is mentioned in an inscription as being situated in the Mālwa region (*Ep. Ind.* XXIII. 102).

² JBORS. 1928, March, p. 33; C. J. Shah, *Jainism in Northern India*, 210, quoting *Kuvalayamālā* (? 5th century A. D.).

³ Smith. EHI, 4th edition, p. 343.

⁴ Dharasena II, king of Valabhi, left two sons, viz., Śilāditya II Dharmāditya and Kharagraha I. The account of Hiuen Tsang seems to suggest that in his time (i.e., shortly after Śilāditya) the Maitraka dominions split up into two parts, one part including Mo-la-po and its dependencies probably obeying the line of Śilāditya-Dharmāditya, the other part, including Valabhi, obeying Kharagraha and his sons, one of whom was Dhruvasena II, Bālāditya or Dhruva-bhaṭa, who married the daughter of Harsha of Kanauj. The account of the Chinese pilgrim seems to receive confirmation from the Alina plate of Śilāditya VII (Fleet, CII, 171 f. esp. 182n) which associates Derabhaṭa, the son of Śilāditya I Dharmāditya, with the region of the Sahya and Vindhya mountains, while the descendants of Kharagraha I are connected with Valabhi. The Navalakhi and Nogaṇā plates, however, suggest that occasionally the same

Valabhī. In the seventh century Dhruvasena II of Valabhī married the daughter of Harsha. His son Dharasena IV (A.D. 645-49) assumed the imperial titles of *Paramabhaṭṭāraka Paramēśvara Chakravartin*.

But the Maitrakas of Mo-la-po and Valabhī were not the only feudatories who gradually assumed an independent position. The rulers of Mandaśor pursued the same course, and their example was followed by the Maukharis of the Madhyadeśa and the kings of Navyāvakāśikā-Vardhamāna and Karṇasuvarṇa in Bengal.

Mandaśor, the ancient *Daśapura*, was one of the most important Viceregal seats of the Early Gupta Empire. It was the Capital of a long line of margraves belonging to the Aulikara family' who governed part of Western Mālwa on behalf of the Emperor Chandra Gupta II Vikramāditya and his son Kumāra Gupta I Mahendrāditya. With the sixth century A.D., however, a new scene opened. Yaśodharman, ruler of Mandaśor about A.D. 533, emboldened no doubt by his success over the Huns, defied the power of the Gupta lords (*Guptanātha*), and set up pillars of victory commemorating his conquests, which, in the words of his court panegyrist, embraced the whole of Hindusthān from the river Lauhitya, or the Brahmaputra, to the Western Ocean, and from the Himālayas to the mountain Mahendra or the Eastern Ghāṭs. After his death the Guptas figure again as lords of Mālava (Eastern Mālwa) in literature and possibly in inscriptions of the time of Harsha. But Western Mālwa could not be recovered by the family. Part of it was, as we have already seen, included within the dominions of the Maitrakas. Another part, viz., Avanti or the district round Ujjain, the proud capital of Vikramāditya and Mahendrāditya in the fifth century A.D.,² is found in the next centuries in the

ruler governed both Mālavaka and Valabhī. In the latter half of the seventh century A. D. the line of Kharagraha I became extinct, and the Maitraka dominions were once more united. For an alleged connection of the Valabhī dynasty with the Kanarese country, see Moraes, *Kodamba-kośa*, 84 f. The recently discovered Virḍi copperplate grant of Kharagraha I of the year 227 (= A.D. 616-17) shows that for a time that ruler held Ujjain (*Prā* of the 7th Or. Conf. 659 ff.). It is from the camp at Ujjain that the grant was issued.

¹ *Ep. Ind.* XXVI. 130 ff; *Prest.* CII, 163.

² Somadeva. *Kaṭhā-mṛit-sāgara*, Bk. XVIII; Allan. *Gupta Coins*, xlix n; *Bomb. Gaz.*, I, ii, 578.

IMPERIAL AMBITION OF THE MAUKHARIS 631

possession of Śaṅkaragaṇa of the Kaṭachchhūri or Kalachūri dynasty¹ and Kharagraha I of the Maitraka line which gave way to a Brāhmaṇa family in the days of Hiuen Tsang,² which in its turn, was replaced by the Rāshtrakūṭas, the Gurjara Pratihāras and other families.³

Another family which came to the forefront in the sixth century A.D., was the line of the Mukharas or **Maukharis**. The stone inscriptions of the princes of this dynasty prove their control over the Bārā Bankī, Jaunpur and Gayā districts of the Uttar Pradesh and Bihār. All these territories formed integral parts of the Gupta Empire in the fourth and fifth centuries A.D. In the next century they must have passed into the hands of the Maukharis. The feudatory titles of the earlier princes of the Mukhara line leave no room for doubt that they occupied a subordinate position in the first few decades of the sixth century A.D. In or about the year A.D. 554, however, Śānavarman Maukhari ventured to measure swords with the Guptas, and probably also with Huns, and assumed the Imperial title of *Mahārājādhirāja*. For a period of about a quarter of a century (A.D. 554-cir. A.D. 580) the Maukharis were beyond question the strongest political powers in the Upper Ganges Valley. They anticipated to some extent the glorious achievements of Harsha, the brother-in-law, and, apparently, the

¹ G. Jouveau Dubreuil, *Ancient History of the Deccan*, 82.

² Watters, *Yuan Chwang*, ii. 250. This family may have been connected with the viceregal line of Naigamas mentioned in the Mandasor Inscription of the Mālava year 589, of the time of Yaśodharman and Vishṇuvardhana. Abhayadatta of this family was the viceory (*Rājasthānīya*, *Sachiva*) of a district bounded by the Vindhya, the Pāriyātra (Western Vindhya including the Aravalli range) and the Sindhu (the sea or a Central Indian stream bearing the same name). His nephew is called a *nṛpati* (king). Dakṣa, the young brother of the ruler, excavated a well in the year 589 (= A. D. 583-34).

³ *Ind. Ant.*, 1886, 142; *Ep. Ind.*, XVIII, 1926, 239 (verse 9 of Sañjam grant); cf. *Ep. Ind.*, XIV, p. 177 (reference to a governor of Ujjain under the Pratihāra King Mahendrapāla II). In the Sañjam inscription it is claimed that at Ujjain an early Rāshtrakūṭa king made the Gurjara and other lords his door-keepers (Pratihāra). It is not improbable that, like the Paramāras, the Gurjara lords brought to Ujjain were for a long time feudatories of the Rāshtrakūṭas and the name Pratihāra had reference to their status under the Rāshtrakūṭas, before the theory of descent from Lakshmaṇa was adumbrated. Incidentally it may be pointed out that the home territory (*Savishaya*) of Nāgabhaṭa's line was in Marwar as is clear from the Jaina Kuvalayamāla and the Buchkala inscription.

successor (on the throne of Kanauj ?) of their last notable king Grahavarman.

Like the Maukharis, the **rulers of Bengal**, too, seem to have thrown off the Gupta yoke in the second half of the sixth century A.D. In the fourth and fifth centuries Bengal undoubtedly acknowledged the suzerainty of the Gupta Empire. The reference to Samatāṭa in Eastern Bengal as a *pratyanta* or border state in the Allahabad Pillar Inscription of the emperor Samudra Gupta proves that the Imperial dominions must have embraced the whole of western and central Bengal, while the inclusion of northern Bengal (Paṇḍravardhana *bhukti*) within the empire from the days of Kumāra Gupta I (A. D. 443-44) to A. D. 543-44¹ is sufficiently attested by the Dāmodarpur plates. Samatāṭa, though originally outside the limits of the Imperial provinces, had, nevertheless, been forced to feel the irresistible might of the Gupta arms. The Harāhā Inscription of Išānavarman, however, shows that the political situation had changed completely about the middle of the sixth century A.D. A new power, *viz.*, that of the **Gauḍas**, was fast rising to importance in the valley of the Lower Ganges. Gauḍa was already known to Pāṇini² and the *Kautilīya Arthaśāstra*.³ The grammarian seems to associate it with the East.⁴ A passage occurring in the *Matsya*, *Kūrma* and *Linga Purāṇas*⁵ has, however, been taken to mean that the Śrāvastī region was the cradle of the Gauḍa people. But the passage in question does not occur in the corresponding text of the *Vāyu* and *Brahma Purāṇas* and the *Mahābhārata*.⁶ In early literature the people of the Śrāvastī region are always referred to as the Kosalas. Vātsyāyana, the author of the *Kāmasūtra*, writing probably in the third or fourth century of the Christian era, refers to Gauḍa

¹ For the date, see *Ep. Ind.*, XVII, Oct., 1924, p. 345.

² VI. ii. 100.

³ ii. 13.

⁴ *Cf.* VI. ii. 99 (in regard to accentuation).

⁵ *Nirmītā yena Śrāvastī Gauḍa-deśe dojjottamāḥ.*
Matsya, XII, 30, *cf. Linga*, I, 65.

Nirmītā yena Śrāvastī Gauḍa-deśe mahāpuri (*Kūrma*, I. 20. 19).

⁶ *Yajñe Śrāvastako rājā Śrāvastī yena nirmītā* (*Vāyu*, 88. 27; *Brahma*, VII, 58).

Tasya Śrāvastako jñeyah Śrāvastī yena nirmītā (*Mbh.*, III. 201. 4).

and Kosala as names of distinct countries.¹ Gauḍa in the *Matsya-Kūrma-Liṅga* MSS. may have been inserted as a Sanskritised form of Goṇḍa in the same way as the term Madra-maṇḍala is employed to denote the Madras Presidency, by some modern paṇḍits of the Southern Presidency, as well as other scholars and journalists who are unacquainted with the topography of Ancient India.² In the Central Provinces the name "Gond" is very often Sanskritised into Gauḍa.³ Varāhamihira, writing in the sixth century A.D., places Gandaka in the Eastern division of India. He does not include Gauḍa in the list of countries situated in the *Madhyadeśa*. Mention is no doubt made of a place called Guḍa. But, if Alberuni⁴ is to be believed, Guḍa is Thanesar and not Oudh. The use of the term *Pañcha Gauḍa* as the designation of a territory embracing Northern India as far as Kanauj and the river Sarasvatī, is distinctly late and dates only from the twelfth century A.D. The term is possibly reminiscent of the Gauḍa empire of Dharmapāla and Devapāla, and cannot be equated with the ancient realm of the Gauḍas in the early centuries of the Christian era. The distinct statement in the Harāhā Inscription that the Gauḍas were on the seashore clearly suggests that the Bengal littoral and not Oudh, was the seat of the people in the sixth century A.D. In the next century, their king Śaśāṅka is found in possession of Karṇasuvarṇa near Murshidābād. In the century that follows a Gauḍa appears, in the *Gauḍa-vaḥo* of Vākpati-rāja, as the occupant of the throne of Magadha. The zenith of Gauḍa power is reached in the ninth century when the Gauḍa dominion extends over the Gangetic Doūb and Kanauj. About the early kings of the Gauḍas our information is meagre. Certain copper-plate inscriptions, discovered in the Faridpur and Burdwan⁵ Districts, disclose the existence of three kings—Dharmāditya, Gopachandra⁶ and Samāchāradēva, who are described as

¹ For Koslā, see *doṣaṇachchhedya-prakaranam*; for Gauḍa, see *nakha-chchhedya prakaranam* and *dāvarakshika-prakaranam*.

² Cf. Gieger's translation of *Mahāvaṃśa*, p. 62a.

³ Cf. *Imperial Gazetteer of India*, Provincial Series, Central Provinces, p. 158.

⁴ i. 300.

⁵ Mallasārula Plate (*S. P. Patrikā*, 1944, 17).

⁶ Gopachandra may be the Gopākhyā nripati who was apparently a contemporary and rival of Prakāśāditya, son of Bhānu Gupta (*Ārya-Mahājūri-mūla*).

overlords of Navyāvakāśikā, Vāraka-maṇḍala, and, in one case, of Vardhamāna-*bhukti* (Burdwan Division). The Vappaghoshavāta inscription introduces to us a fourth king, viz., Jayanāga, who ruled at Karpasuvarṇa. These kings are, however, not expressly referred to as Gaudas. The earliest king, to whom that epithet is applied is the famous Śaśāṅka, the great rival of Rājya-vardhana of Thanesar and his brother Harsha. The title *Mahārājādhirāja* assumed by the Bengal kings mentioned above, leaves no room for doubt that they no longer acknowledged the suzerainty of the Guptas and set themselves up as independent sovereigns.

The uprising of the Pushyamitras, the invasions of the Huns and the intransigentism of provincial governors and feudatories, were not the only sources of trouble to the Guptas in the last days of their sovereignty. Along with foreign inroads and provincial insubordination we should not fail to take note of the dissensions in the Imperial family itself. The theory of a struggle amongst the sons of Kumāra Gupta I may or may not be true, but there is evidence to show that the descendants of Chandra Gupta II did not pull on well together, and the later kings who bore the Gupta name sometimes took opposite sides in the struggles and convulsions of the period. The later Imperial Guptas do not seem to have been on friendly terms with their Vākāṭaka cousins. Narendrasena Vākāṭaka, a great-grandson of Chandra Gupta II through his daughter Prabhāvatī, seems to have come into hostile contact with the lord of Mālava. Narendrasena's cousin Harishena claims victories over Avantī. Inasmuch as the Guptas are associated with parts of Mālava as late as the time of Harsha, some of the victories gained by the Vākāṭakas must have been won over their Gupta cousins. In the seventh century A.D., Deva Gupta appears as an enemy of Harsha's family, while Mādhava Gupta was a friend.

Lastly, it is interesting to note that while the earlier Guptas were staunch Brāhmanists, some of whom did not scruple to

kalpa, ed., G. Śāstri, p. 637). It is not altogether improbable that *Dhakarākhyā* (*ibid.*, p. 644) is identical with *Dharmāditya*. Was he a younger brother (son) of *Vākārākhyā* (Vajra) and *Pakārākhyā* (Prakāṣāditya)? If this surmise turns out to be correct he may have belonged to the Gupta line.

engage in sacrifices involving the slaughter of living beings, the later kings, or at least some of them, e.g., Budha (Buddha) Gupta, Tathāgata Gupta and Bālāditya had Buddhist leanings. As in the case of Aśoka after the Kaliūga war and Harsha after his intimate relation with the Chinese Master of the Law, the change of religion probably had its repercussions on the military and political activities of the Empire. In this connection it is interesting to recall a story recorded by Hsuen Tsang. When "Mahirakula," the Hun tyrant ruling at Śākala, proceeded to invade the territory of Bālāditya, the latter said to his ministers, "I hear that these thieves are coming, and I cannot fight with them (their troops); by the permission of my ministers I will conceal my poor person among the bushes of the morass." Having said this he withdrew to an island with many of his subjects. Mihirakula came in pursuit but was taken alive as a captive. He was, however, set free and allowed to go away on the intercession of the Queen Mother.¹ We do not know how far the story is authentic. But it seems that Indians of the seventh century A.D. from whom the Chinese pilgrim must have derived his information, did not credit the later Pro-Buddhist rulers of the Gupta dynasty with the possession of much courage or military vigour, though they bear testimony to their kindness and piety. The misplaced clemency of Bālāditya and his mother helped to prolong the tyrannical rule of Mihirakula and gave Yaśodharman and the succeeding aspirants for imperial dominion, viz., Iśānavarman and Prabhākara-vardhana, an opportunity of which they were not slow to take advantage and thereby seal the doom not only of the Hun (Yetha), but also of the Gupta domination in Northern India.

¹ Beal, *Si-yu-ki*, I, 168 l. ; Watters, I, 288-89.

APPENDIX E

KINGDOMS, PEOPLES AND DYNASTIES OF TRANS-VINDHYAN INDIA CHRONOLOGICALLY ARRANGED.

- Brāhmaṇa Period** :—1. Nishadhas (capital Giriprastha, Mbh., III, 324. 12).
2. Vidarbhas (capital Kuṇḍina) and other Bhojas.
3. Dasyu tribes—Andhras, Sabaras, Pulindas and Mūtibas.

- Sūtra Period** :—1. Māhishmati (Māndhātā or Maheśvara, IA, 4, 346).
2. Bhṛigu-Kachchha (Broach).
3. Śūrpāraka (Sopara in the Koṅkan).
4. Aśmaka (capital Paudanya, Bodhan).
5. Mūlaka (capital Pratishṭhāna).
6. Kaliṅga (capital Dantapura).
7. (?) Ukkala (N. Orissa).

- Rāmāyaṇic Period** :—Aryan Expansion south of the Godāvarī—settlement on the Pampā—exploration of Malaya, Mahendra and Laṅkā.

- Maurya Period** :—
- | | |
|-----|---|
| 1. | Aparāntas proper (capital Śūrpāraka) |
| 2. | Bhojas (capital Kuṇḍina?). |
| 3. | Rāshṭrikas (capital Nāsik?). |
| 4. | Petenikas (of Pratishṭhāna?). |
| 5. | Pulindas (capital Pulinda-nagara). |
| 6. | Andhras (capital Bezvāḍa etc. ?). |
| 7. | Aṭavi. |
| 8. | Kaliṅgas (including Tosali and Samāpā). |
| 9. | Viceroyalty of Suvarṇagiri. |
| 10. | Āhāra of Isila. |
| 11. | Chojas. |
| 12. | Pāṇḍyas. |
| 13. | Keralaputra. |
| 14. | Satiyaputra (Satyabhūmi of Keralolpatti ?). |
| 15. | Tāmraparṇī (Ceylon). |
- Maurya Empire.**

- Early Post Maurya Period :—**
1. Kingdom of Vidarbha.
 2. Sātavāhanas of Dakṣiṇāpatha.
 3. Chetas of Kalinga.
 4. Kingdom of Pithuḍa near
Masulipatam.
 5. " " Chola.
 6. " " Pāṇḍya.
 7. " " Kerala.
 8. " " Ceylon (sometimes
ruled by Chola
princes).

- Age of the Periplus :—**
1. Southern part of Ariake under
Mambarus (or Nambanus ?).
 2. Dachinabades under Saraganus and his
successors (*i.e.*, the Deccan under
the Sātavāhana-Sātakarṇis).
 3. Damirica (Tamilakam, Draviḍa) includ-
ing :—
 - (a) Cerobothra (Keralaputra).
 - (b) The Pandian Kingdom.
 - (c) (Kingdom of) Argaru
(= Uragapura)
 4. Masalia (Masulipatam).
 5. Dosarene (= Tosali).

- Age of Ptolemy :—**
1. Kingdom of Baithana (Pratishṭhāna) ruled
by Pulumāyi (Sātavāhana).
 2. Kingdom of Hippokoura (Kolhapur),
ruled by Baleokouros (Vilivāyakura).
 3. Kingdom of Mousopalle (in the Kanarese
Country).
 4. " " Karoura ruled by
Kerobothros (Keralaputra).
 5. Pounnata (S. W. Mysore).
 6. Kingdom of the Aīoi (capital Kottiara in
S. Travancore).
 7. Kingdom of the Kareoi (Tāmraparṇī
Valley).
 8. Kingdom of Modoura (Madurā) ruled by
'Pandion' (Pāṇḍya).

9. Kingdom of the Batoi (capital Nikama)
10. Kingdom of Orthoura, ruled by "Sornagos" (Chola-Nāga ?).
11. Kingdom of Sora (Chola) ruled by Arkatos.
12. Kingdom of Malanga (Kāñchi ? Mavilangai ?), ruled by Basaronagas (=Nāga ?)
13. Kingdom of Pitundra (Pithuda).


- A. D. 150-350 :—
1. Abhīras (N. Mahārāshtra and W. India).
 2. Vākātakas (Berar and adjoining provinces) and chiefs of Mahākāntāra.
 3. Kingdoms of South Kosala, Kaurāla, Kottura, Eraṇḍapalla, Devārāshtra (under the Vaśiṣṭha family ?), Piṣṭapura (under the Māthara-kula ?), Avamukta, Palakka, Kusibhalapura.
 4. Kingdom of Andhrāpatha (and Veṅgī) :—
 - (a) Ikshvākus.
 - (b) Rulers of the Ānanda-gotra (Kandarapura).
 - (c) Brihatphalāyanas of Kudura, etc.
 - (d) Śālaṅkāyanas (Salakenoi of Ptolemy ?) of Veṅgīpura, one of whom was Hastivarman of Veṅgī.
 5. Pallavas of Kāñchī,
 6. Śātakarṇis of Kuntala.

- A. D. 350-600 :—
1. Traikutakas and Mauryas of the Koṅkan ; and Lāṭas, Nāgas and Gurjaras of South Gujarāt.
 2. Vākātakas (C. Deccan).
 3. Kaṭachchuris (N. Mahārāshtra and Mālwa).
 4. Kings of Śarabhapura (S. Kosala ?).
 5. Pāṇḍavas of Mekalā.
 6. Kingdoms of Uḍra, Koṅgoda, Kaliṅga [under the Vaśiṣṭha family, the Māthara-kula, the Muḍgala family (Ep. Ind. xxiii. 199ff) and Eastern Gaṅgas] ; Leṇḍulura (under Viṣṇu-kunḍins) in East Deccan.

7. Pallavas of Kāñchī (in Drāmila or Draviḍa).
8. Cholas, Pāṇḍyas, Mūshakas and Keralas of the Far South.
9. Gaṅgas and Ālupas of S. Mysore, Shimoga and S. Kanara.
10. Bāṇas of E. Mysore and N. Arcot, Kekayas of Dāvāṅgere tāluk, Kadambas of Vaijayanti, etc. and Sendrakas of Nāgarakhaṇḍa (N. W. Mysore), or of the Tumkur region.
11. Nalas of (a) Pushkarī who governed the Poḍāgaḍh region (Jeypore Agency), (b) Yeotmal in Berar and perhaps also (c) the Bellary District.
12. Early Chalukyas of Vātāpi.

After A. D. 600 :—1. Silāhāras of Koṅkaṇ.

2. Early Chālukyas, Rāshṭrakuṭas including the lines of Mānadeśa, etc., Later Chālukyas, Kalachuryas and Yādavas of W. Deccan.
3. Haihayas, Kalachuris or Chedis of Tripuri and Ratnapura, and Nāgas of Chakrakūṭa (C.P.).
4. Eastern Chālukyas, Chiefs of Velnāṇḍu, and Kākatiyas of the Telugu Country, Eastern Gaṅgas of Kaliṅga and Orissa, Karas, Śabaras (? Śaśādharma and Pāṇḍu family) and Somavaiṅśi Guptas of Mahānadi Valley (N. E. Deccan).
5. Western Gaṅgas, Sāntaras and Hoysalas (Mysore).
6. Pallavas of Kāñchī, Vaidumbas of Renāṇḍu, Kalabhras of the Tinnevely District, Cholas of Tanjore, Varmans of Kerala and Kolamba, and Pāṇḍyas of Madurā (Far South).



BIBLIOGRAPHICAL INDEX*

A

Abhidhāna Chintāmaṇi, 119, 482
 Abhidhānappadīpikā, 198
 Acta Orientalia, 373, 378, 418, 467
 Advance, 409
 Aelian, 275, 328
 Age of Imperial Unity, 295
 Age of Nandas and Mauryas, 229
 A Guide to Sācchi, Marshall, 267, 393, 416, 579
 A Guide to Taxila, Marshall, 60, 429, 464
 Ain-i-Akbari, 86
 Aivangar Commemoration Volume, 992, 274, 309, 314, 330, 479, 519, 528, 579
 Aivangar, S. K., 269, 328n, 329
 Aivikās, Barua, 323
 Alberuni, 5, 233, 475, 479, 615, 619, 632
 Alexander the Great, Tarn, 422
 Allan, 389, 527, *et passim*
 Allkar, 553
 Amarakodā, 391
 Oka, 391, 520
 Amṛta Bāzār Patrikā, 300, 393
 An Account of the Kingdom of Kabul, 149
 Ancient Geography of India, 94, 100, 127, 191, 193, 259, 423, 444, 474, etc.
 Ancient Hindu Polity, N. Law, 330
 Ancient History of the Deccan, G. Jonsson-Dubrenil, 64, 89, 468, 500, 536, 539f, 607n, 631n
 Ancient India, Aivangar, 328
 Ancient India, Rapson, 191, 246, 444
 Ancient India as described in Classical Literature, McCrindle, 240, 251, 276, 333
 Ancient Indian Historical Tradition, Pargiter, 8, 17, 18, 72, 81, 102, 255
 Ancient Mid-Indian Kshatriya Tribes, B. C. Law, 26, 145
 Ancient Persian Lexicon and the Texts of the Achaemenian Inscriptions, H. C. Tolman, 147, 240
 A New History of the Indian People, 396
 An Indian Ephemeris by Swami Kanna Pillai, 227
 Annals of the Bhandarkar Institute, 202, 205, 317, 391, 412
 Annals of the First Han Dynasty, 423, 459
 Annals of the Later Han Dynasty, 436, 460
 Anspach, 251
 Antigonas Gonatas, Tarn, 331
 Anukramāṇi, 66

Apadāna, 65
 Apastamba, 35
 A Peep into the Early History of India, R. G. Bhandarkar, 549, 612n
 A Political History of Parthia, Debevoise, 451
 Apollodorus of Artemita, 389
 Apollonios, 454
 Appianus, 273
 Arabian Nights (Burton), 617
 ——— Lane, 617
 ——— Olcott, 617
 Aranyaka Aitareya, 310
 ——— Kaushitaki (Śāṅkhāyana), 33, 35, 113
 ——— Taittiriya, 92, 41
 Aravamuthan, 413, 604
 Arch. Expl. Ind., Marshall, 129
 Archaeological Report, Cunningham, 28
 Archaeological Survey of Mysore, A. R., 604n
 Archaeological Survey of India, 126, 329, 402, 418, 418, 454, 503, 535, 540, 552, 573, 581, *et passim*
 Archaeological Survey of Western India, 405, 503
 Aristobolus, 250
 Arrian (Chinnock's translation), 239, *et passim*
 Arthaśāstra—Bābasaheb, Ed. by F. W. Thomas, 248, 253
 ——— Kautilya (Shama Sastry), 9, 277, *et passim*
 Arvabhata, 27
 Ārya Mañjunādi Mūlakalpa, 193, 214, 572, 577, 588f, *et passim*
 Arvonisation of India, N. Dutt, 19
 Aryan Rule in India, Havell, 345
 Aryans, V. Gordon Childe, 8
 Āryasūra, 10
 Ashtādhyāyī of Pāṇini, Ed. by S. C. Vasu, *passim*
 Āśoka, Bhandarkar, 303, 315
 Āśoka Edicts in a New Light, Barua, 337
 Āśoka, Macphail, 278
 Āśoka, Smith (3rd edition), ch. iv, *passim*
 Āśoka Text and Glossary, Woolner, 311
 Āśokāvadāna, 6, 222, 554
 Āśvaghosha, 63, 128
 A Survey of Persian Art, 239, 451
 Athetios, 277
 Atthakathā, 214
 Aucitya-Vidāra Carcā, 564

* This Index purports to give a general idea of the kind of literature that has been utilised in preparing the work. It may also be of some little use to students. In the case of the more well-known authorities no detailed reference has been deemed to be necessary; such references will ordinarily be found in the text itself.

Avadāna-kalpalatā, 281
 Avasyaka-Kāthānakas, 204
 A volume of Indian Studies presented to
 Prof. E. J. Rapson, 841, 432

B

Bābar-nāma (in English), A. S. Beveridge, 268
 Balhlo, V. S., 523
 Bāna, pt. II, *passim*
 Banerji, R. D., 223, 404, 471, 482, 485, 585, *et passim*
 Bārhaspatya Artha-Sāstra, 248
 Barnett, L. D., S. 218, 223, 270, 331, 378, 413, *et passim*
 Barua, B. M., 125, 236, 273, 336, 343, 375, 391, 420, *et passim*
 Barua, K. L., 543
 Basak, R. G., 563, 588, 604n
 Buddha Dharma Kosha, 236
 Beal, 63, 126, 215, 333, 460, 557, 595
 Beginnings of Buddhist Art, Foucher, 430
 Beginnings of South Indian History, 231, 269, 333, 517
 Beloch, 331
 Bevan, 253
 Bhandarker Commemoration Volume, 200, 409, 606n
 Bhandarkar, D. R., 162
 Bhandarkar, R. G., *passim*
 Bharata Mallika, 268
 Bhāratvarsha, 627n
 Bhāsa, 47, 131, 203
 Bhattachārya, N. K., 543, 568, 627
 Bhavabhūti, 56, 60, 171
 Bhavanagar, Inscriptions, 516
 Philas Topas, 238, 298
 Bhoja, 512, 564
 Bigandet, 295
 Black Yajna (Keith), 165, 168
 Bloch, 560
 Bloomfield, 13
 Bodhāyana, 309
 Bombay Gazetteer, see Gazetteer, Bombay
 Book of Kindred Sayings (where the volume is not specified, volume I is to be understood), Mrs. Rhys Davids, 120, 124, 156, 198, 206f, 210, 349
 Bose, A. K., 335
 Brāhmaṇa—
 —Aitareya, Part I, ch. i-iv, 3, *et passim*
 —Aitareya (Keith), 37, 157, 163
 —Aitareya (Trivedi's Trans.), 44
 —Gopatha, 39, 51, 55, 68, 100
 —Jaiminiya, 46, 51, 86
 —Jaiminiya Upanishad, 25, 44, 101, 102, 175
 —Kausītaki, 62, 73
 —Paśchaviśā or Tāpdyā, 36, 44, 46, 48, 81, 101, 359
 —Sākhitopanishad, 71
 —Satapatha, Eggeeling, pt. I, pt. II, ch. i-ii, 3, *et passim*
 —Vaiśā, 44, 50, 149, 370

Bṛihat Kathā, 202, 221
 Bṛihaddevatā, 25
 Bṛihat Saṁhitā (Varāhamihira, ed. Kero), 29, 249, 300, 330, 352, 386, 485, 491, 502, 619, *et passim*
 Buddha, Oldenberg, 24, 52, 72, 113, 131, 191
 Buddha Charita, 88, 193
 Buddhaghosha, 111, 207, 312
 Buddhist Conception of Spirits, Law, 133, 150, 289
 Buddhist India, Rhys Davids, 57, 100, 105, 108, 133, 147, 154, 191, 614
 Buddhist Studies (ed. Law), 221, 475, 506, 614
 Buddhist Suttas, see Suttas, Buddhist
 Bühler, *passim*
 Bunyū Nanjō, Catalogue, 3, 469, 616
 Bury, 121, 261

C

Caland, 1, 37, 48, 359
 Calcutta Review, 4, 8, 432, 453, 466, 473, 479, 514, 540, 581, 626
 Callimachus, 295
 Cambridge Ancient History, Vol. I, 139
 Cambridge History of India, Vol. I, 167, 240, 247, *et passim*
 Cambridge History of India, Vol. III, 449
 Cambridge Shorter History of India, 452, 463, 467, 477, 485
 Carl Cappeller, 5
 Carleyle, 127
 Carmichael Lectures (1918), 67, 74, 76, 117, 133, 143, 225, 253, 308, 397, 475
 Carr, 295
 Catalogue of Coins, Allan (Ancient India), 373, 391f, 393, 402, 511, 544
 Catalogue of Coins, Allan (Guptas), 377, 529, *et passim*
 —Gardner, 424
 —Rapson (Andhras and W. Khatrapas), 314, 404, 408, 415, 444, 448, 469, 475, *et passim*
 —Smith (Indian Museum), 402, 423, 463, 482, 515, *et passim*
 —Whitehead (Indo-Greeks and Indo-Scythians), 395, 420, 426, 436, 452, 459, 463, 477, 478, *et passim*
 Ceylonese Chronicles, *passim*
 Chakravarti, M., 602n
 Champā, R. C. Majumdar, 143
 Chandra, H. P., 213, 223, 224, 373f, 388, 404
 Chandragomin, 623
 Charpentier, 296, 340, 479, 579
 Chatterji, B. B., 148
 Chatterji, S. K., 538
 Chattopadhyaya, K. P., 409
 Chaucer, 383
 Chhavilākara, 309
 Coins of Ancient India, Cunningham, 321, 393
 Corporate Life in Ancient India, R. C. Majumdar, 140
 Corpus Inscriptionum Indicarum, Vol. I,

Hultzsch, *passim*
 Corpus Inscriptionum Indicarum, Vol. II,
 Konow, *passim*
 Corpus Inscriptionum Indicarum, Vol. III,
 Fleet, *passim*
 Cunningham, *passim*
 Curtius, 232, *et passim*
 Cyril, 617

D

Dacca Review, 390
 Dacca University Journal, 618n
 Dasa-kumāra-Charita, 107, 148, 263
 Deskar, S. S., 310
 Devibhāgavatam, 45
 Devi-Chandraguptam, 512, 554
 Devi-Mahātmya, 5
 Dey, N. L., 67, 108, 129, 330
 Dhammapada Commentary, 120, 124, 323
 Dhoyi, 92, 539
 Dhruva, 352
 Dialogues of the Buddha, 75, 87, 109, 124,
 126, 127, 128, 154, 198, 214, 256, 323,
 327, 341, 408
 Dictionary of Pali Proper Names, Malalase-
 kera, 36, 86, 88, 131, 192, 194, 195, 200,
 201, 202, 208, 211, 214
 Die Kosmographie Der Indier, 95, 330
 Dikshit, 409, 535
 Dikshitar, 413
 Diodorus, 237, *et passim*
 Dipavāṇsa, 331
 Divekar, 548, 568
 Divyāvadāna (Cowell and Neil), 66, 135,
 196, 267, *et passim*
 Dowson, 452, 465
 D. R. Bhandarkar Volume, 383
 Dubreuil, 64, 89, 378, 468, 469ff, 500, 536,
 539ff, 602n, 612n
 Dvātrīṣṭ-puttalikā, 219
 Dynasties of the Kali Age, Pargiter, 17,
 22, 29, 113, 114, 201, 220, 236, 355,
et passim
 —Kanarese Districts, Fleet, 23, 235

E

Early Empires of Central Asia, McGovern,
 628n
 Early History of Bengal, see Monahan
 Early History of the Dekkan, R. G.
 Bhandarkar, 401, 413, 417, *et passim*
 Early History of India, Vincent Smith,
passim
 Early History of the Vaisnavā Sect,
 Raychaudhuri, 31, 41, 141, 171, 263,
 420
 Early Pallavas, D. C. Sircar, 523
 Eggeling, I, 39, *et passim*
 Ehot (Hinduism and Buddhism), 108, 148,
 333, 469, 615f
 Elphinstone, 149
 Epigraphia Indica, *passim*
 Erskine, K. D. (Rājputāna Gazetteer), 266

Essay on Guṇādhyā, 117, 146, 147, 202,
 204, 221
 Excavations at Harappā, 122

F

Fa Hien, Legge, 194, 209, 558, *et passim*
 Fan-ye, 429, 460f
 Felix Lacote, 202
 Fergusson, 469
 Ferishta, 479n
 Fick, The Social Organization in North-
 East India, trans., S. Maitre, I, 146,
 177, 318
 Fillicot, 295
 Fleet, pt. II, *passim*
 Foreign Elements in the Hindu Popu-
 lation, 383
 Foucher, 60, 423, 430, 432
 Franke, 466
 Fundamental Unity of India, Radha-
 kumud Mookerjee, 163, 165

G

Gaṇapātha, 252
 Gaṇḍavyūha, 306
 Gangooly, O. C., 228
 Ganguly, D. C., 596n
 Garde, 561, 567, 571
 Gardner, see Catalogue of Coins
 Gārgi Samhitā, 217, 352, 360, 365
 Gaṇḍavaho, 611, 633
 Gazetteer—Amraoti, 67
 —Bombay, Vol. I, Pt. II, *passim*
 —Godāvari District, 540
 —Rājputāna, IIA, the Mewar
 Residency, 266
 —Vizagapatam, 539
 Geiger, *passim*
 Geographical Dictionary, 67, 129
 Ghosh, A., 613n
 Ghosh, Bhramar, 413
 Ghosh, Haricharan, 618, 621
 Ghoshal, U. N., see Hindu Revenue
 System
 Gita, 141, 395
 Ghirshman, 467
 Goldstücker, 34, 383
 Goswami, K. G., 473
 Great Epic of India, Hopkins, 4, 49, 142,
 171
 Greek World, 295
 Guṇādhyā, Essay on, see Essay on
 Guṇādhyā
 Guno, 202
 Gupta, Y. R., 484, 601

H

Hala, 407, 557, 564
 Hamilton and Falconer, Pt. II, Ch. iii-viii,
passim
 Hardy, Manual of Buddhism, 110
 Hariavāmin, 17, 69, 181

644 POLITICAL HISTORY OF ANCIENT INDIA

- Hārīt Krishna Dev, 76, 423
 Harivamśa, 15, 87, 91, 107, 131, 133, 141, 145, 193, 327, *et passim*
 Harsha Charita, ed. Parab, 6, 182, *et passim*
 ————Cowell and Thomas, 222, 469
 Harvard Oriental Series (23-30), 108, 136, *et passim*
 Hastings, 475
 Havell, 345
 Heaven and Hell in Buddhist Perspective, B. C., Law, 143, 155
 Hemchandra, 207, *et passim*
 Heras (JBORS), 596
 Hermann, 431
 Herodotus, 240
 Herzfeld, 182, 240, 428, 431, 482
 Hillebrandt, 164
 Hinduism and Buddhism, see Eliot
 Hindu Civilisation, Mookerji, 356
 Hindu Polity, Jayaswal, 258
 Hindu Revenue System, Ghoshal, 283
 Hindusthan Review, 581, 590
 Historical Inscriptions of Southern India, 570
 Historical Position of Kalki, Jayaswal, 597
 History of Ancient India, Tripathi, 606n
 History of Bengal (D. U.), 256
 History of Buddhist Thought, E. J. Thomas, 96
 History of Central and Western-India, Ghosh, 391, 418
 History of Egypt under the Ptolemaic Dynasty (Mahaffy), 615n
 History of Fine Art in India and Ceylon, Smith, 345, 430
 History of Greece for Beginners, Bury, 121, 261
 History of Hindu Political Theories, Ghoshal, 160
 History of India, K. P. Jayaswal, 537, 589, 597n
 History of Indian and Indonesian Art Coomaraswami, 308, 430
 History of Indian Literature, Weber, 49, 65, 69, 113
 History of Indian Literature, Winternitz, 11
 History of Mediaeval India, C. V. Vaidya, 24
 History of Sanskrit Literature, Keith, 391, 490
 History of Sanskrit Literature, Macdonell, 3, 54
 History of Sanskrit Literature, Max Müller, 356
 Hsuen-Tsang, *passim*
 Hoernle, 199, 583, 605n, 608n
 Hoey, 193
 Hoffmann, 442
 Holdich, 247
 Hopkins, 2, 4, 40, 171, 430
 Hoyland (The Empire of the Great Mogol), 543
 Hultzsch, see Corpus Inscriptionum Indicarum, I
 I
 Iconography, Bhattasali, 543
 Illustrated London News, 242
 Imperial Gazetteer, the Indian Empire, 94, 430
 ————C. P., 633
 Imperial History of India, Jayaswal, *et passim*
 India in 1932-33, 441
 India, What it can teach us, 430
 Indian Antiquary, *passim*
 Indian Culture, 10, 87, 99, 109, 125, 155, 171, 199, 265, 269, *et passim*
 Indian Cultural Influence in Cambodia, 148
 Indian Historical Journal, 507
 Indian Historical Quarterly, *passim*
 Indian Studies in Honour of C. R. Lanman, 467, 564
 Indica, see Megasthenes
 Indrāji, Bhagwanlāl, 374
 Intercourse between India and Western World, Rawlinson, 384
 Introduction to the Pratimānāṭaka, 316
 Introduction to the Kalpa Sūtra of Bhadrabāhu, Jacobi, 350
 Invasion of India by Alexander, McCrindle, 232, 237, *et passim*
 Isidor of Charax, 382, 431
 I-Tsing, 108, 305
 Iyengar, Srinivāsa, 92
 J
 Jackson, 182, 202
 Jacobi, 1, 11, 213, 350
 Jaina Canon, 11
 Jainism in North India, C. J. Shah, 295, 548, 629 n
 Jātaka, Camb. ed.; also Fausbøll, 11, 99, 107, *et passim*
 ————Ārāmadūsa (268), 96
 ————Asātarūpa (100), 154
 ————Assaka (207), 98, 144
 ————Aṭṭhāna (425), 76
 ————Bāvera (339), 614
 ————Bhaddasāla (465), 97, 99, 128, 209,
 ————Bhallaṭṭiya (504), 98
 ————Bhojajāniya (23), 98
 ————Bhūridatta (543), 96, 149, 615
 ————Brahāchatta (336), 97, 153
 ————Brahmadatta (323), 135
 ————Champeyya (506), 107, 110
 ————Chatta (336), 105
 ————Chetiya (422), 129
 ————Chullakālīṅga (301), 124, 143, 144
 ————Chulla Sutasoma (525), 173
 ————Darīmukha (378), 76, 161
 ————Dasa Brāhmaṇa (495), 41, 133
 ————Dasappaka (401), 161
 ————Daśaratha (461), 78, 162
 ————Dhajavibetha (391), 74

- Dhonasākha (353), 97, 133, 192
 —Dhumakāri (413), 133
 —Dummedha (50), 76, 175
 —Ekapaṇṇa (149), 119, 124
 —Ekarāja (303), 154
 —Gagga (155), 201
 —Gaṇḍatindu (520), 135
 —Gandhāra (406), 53, 146
 —Gaṅgamāla (421), 76
 —Ghata (454), 105, 141
 —Ghaṭa (355), 154
 —Guttila (243), 96
 —Haritamāta (239), 154, 206, 210
 —Hatthimaṅgal (163), 323
 —Jayadissa (513), 135
 —Kaliṅga Bodhi (479), 65
 —Khaṇḍahāla (542), 176
 —Kosambi (428), 97, 153
 —Kumbha (512), 105
 —Kumbhakāra (408), 82, 86, 135, 146
 —Kummāsapiṇḍa (415), 76, 210
 —Kunāla (536), 97, 153, 192
 —Kurudhamma (276), 133
 —Kusa (531), 65, 100, 126, 127, 162
 —Lomasa Kassapa (433), 76
 —Machchha (75), 105
 —Mahāassāroha (302), 173
 —Mahājanaka (539), 53, 107
 —Mahā Kaṇha (469), 66
 —Mahā Nārada Kassapa (544), 66
 —Mahāsilava (51), 154
 —Mahāsutasoma (537), 134
 —Mahā Ummagga (546), 53, 136
 —Maṅgala (87), 323
 —Mātāṅga (497), 203
 —Mātīposaka (455), 76
 —Mūsika (373), 206
 —Mandiya Miga (385), 105
 —Nimi (541), 55, 66, 82, 83, 135
 —Padakusalamānava (432), 176
 —Padañjali (247), 161, 174
 —Sabbamitta (512), 105
 —Sachchamkira (73), 161, 176
 —Sambhava (515), 96, 134
 —Sambulā (519), 76
 —Samkiccha (530), 142
 —Samugga (436), 617
 —Samvara (462), 161, 174
 —Sarabhamiga (483), 96
 • Sarabhaṅga (522), 91
 —Sattubhastā (492), 75
 —Serivāñij (3), 92
 —Setaketu (377), 62
 —Seyya (282), 154
 —Somanassa (505), 73, 135
 —Sonaka (519), 161, 174
 —Sopa Nanda (532), 98, 143, 153
 —Suruchi (489), 53, 97, 162
 —Susīma (163), 59
 —Susīma (411), 76, 146
 —Sussondi (360), 614
 —Tschchhasūkara (492), 206, 210
 —Tapdulanāli (5), 74
 —Telapatta (96), 59, 146, 177
 —Tesakuna (521), 154
 —Thusa (338), 206
 —Udaya (458), 98
 —Uddālaka (487), 61, 77
 —Ummadanti (527), 253
 —Vaḍḍhakisūkara (283), 154, 206, 210
 —Vedabbha (48), 130
 —Vessantara (547), 175, 253, 418
 —Vidhurapaṇḍita (545), 87, 106, 110, 134
 Jātakamālā, 10
 Jayaswal, Pt. II, *passim*
 Jinacharita, 125
 Jinaprabha sūri, 351
 Jinasena, 627
 Jñānaprasthāna, 3
 Jonnston, 10
 Jolly, 251
 Journal Asiatique, 109, 150, 305
 —of the American Oriental Society, 86
 —of the Andhra Research Society, 397
 —of the Asiatic Society of Bengal, *passim*
 —of the Bihār and Orissa Research Society, *passim*
 —of Indian History, 49, 51
 —of the Dacca University, 616
 —of the Department of Letters (Calcutta University), 429, 433, 447
 —of the Royal Asiatic Society of Great Britain and Ireland, *passim*
 —of the U. P. Historical Society, 256
 Justin, 233, 238, *et passim*

K

- Kadambakula (Moraes), 505, 630n
 Kādambari, Ridding, 557, 588
 Kālakāchārya Kathaṇaka, 433
 Kalhaṇa, see Rājatarāṅginī
 Kālidāsa, 203, 389, 540, 564
 Kalpadruma Kalikāvyaśākhya, 125
 Kalpanāmaṇḍitikā, 182, 473
 Kāmandaka, 5, 237
 Kāmasūtra, Vātsyāyana, 507, 620, 632
 Kanakasabhai Pillay, 328
 Karpūramañjari, 129
 Kāthaka Samhitā, 25, 159
 Kathākośa, 200, 211, 216
 Kathā-Sarit-Sāgara, Durgaprasād and, Parab, 32 f, 66, 114, 220, 224, 630
 —Tawney, 203, 221, 556
 Kātyāyana (grammarian), 328
 Kaumudi-mabotsava, 527
 Kauṭilya (see Arthashastra)
 Kaveri, Maikhari and the Sangam Age, see Aravamuthan
 Kāvyaadarāśa, 606 n
 Kāvya-mīmāṃsā, 221, 407, 478, 549
 Keith, 1, 6, 13, 19, 77, 82, 136, 158, 164f, 168f, 171, 370, *et passim*
 Kennedy, 456, 465, 478
 Keralaṭpatti, 330
 Kern, 319, 354, 386
 Kielhorn, *passim*
 Kingsmill, 458
 Kittel's Dictionary, 45
 Knights Tale, 382
 Konow, see Sten Konow

- Kramadīvara, 382
 Kshamendra, 223, 381, 664
 Kshīrasvāmin, 290
 Ktesias, 243
 Kumāralāta (Kalpanāmaṇḍitika), 473
 Kuvālayamālā, 629 n.
 L
 Lalitavistara, 678
 Lane, see Arabian Knights
 Lassen, 1
 Law, B. C., 26, 65, 111, 122, 124, 128, 133, 143, 145
 Law, N., 330
 Leeuw, J. E. Van, Lohuizen de, 469
 Legge, 509, also see Fa Hien
 Le Moude Oriental, 298
 Levi, Sylvain, *passim*
 Life of Alexander, 233, 268
 —of Apollonius, 439, 455 f
 —of Buddha (Rockhill), 120
 —of Hsien Tsang, 111, 557, 588, 595
 —of Vasubandhu, Paramārtha, 182
 List of Southern Inscriptions, Kialhorn, 233
 —Northern Inscriptions, 473
 Lokavibhāga, 501
 Lüders, *passim*
 M
 Macauliffe's Sikh Religion, 235
 Macdonell, *passim*, esp. 1, 3, 13, 77, 81, 370
 Macphail, Aśoka, 276
 McGovern, Early Empires of Central Asia, 628 n
 Mahābhārata, 3, *et passim*
 —translation by Dutt (M. N.), 17, *et passim*
 —by Roy (P. C.), 17
 —A Criticism, C. V., Vaidya, 42
 —Java text, 16, 19
 Mahābhāṣya, Patañjali, *passim*
 Mahābodhivaṇṣa, 222, 231, 236, 287
 Mahaffy, A History of Egypt under the Ptolemaic Dynasty, 616
 Mahānāyūri, 434
 Mahāvagga, *passim*, esp. 97, 106, 111, 124, 153, 166, 173
 Mahāvācā, 6, 225, 331, 614, *et passim*
 Mahāvācā, Geiger, 117, *et passim*
 —Tika, 219, 245, 269
 —Turnour, 117, 219, 267, 281
 Mahāvastu, 89, 91, 96, 100, 334, 628
 Mahāvibhāṣā, 3
 Mahāvira-Chorita, 55, 80
 Majumdar, R. C., *passim*
 Majumdar, N. G., 434, 520
 Majumdar, S. N., 136, 567
 Mazata, 423
 Mālikāṅkaravattha, 116
 Mālavikāgnimitram, 329, 369 ff, 390
 —Tawney, 369 ff, 390
 Malcolm, 64
 Mamulanār, 269
 Manuś O Maṇḍavāpi, 309
 Manual of Buddhism, 110
 Maṇḍasāhita, 63, 123
 Margabhūmi Sūtra, 469
 Marshall, Sir John, *passim*
 McCrindle, *passim*
 Medieval Hindu India, 533, 517
 Megasthenes and Arrian, 273 ff, 282, 292, 330
 Meghadūta, 94, 203, 557
 Mehta, Ratilal, 136
 Memoirs of the Archaeological Survey of India, 224, 240, 404, *et passim*
 Memoirs of the Asiatic Society of Bengal, 404
 Milinda Paṭho, (S. B. E.), 236, 269, 416, 432, 507, 620
 —(Trenckner), 361, 338
 Mirashi, 497
 Mitra, S. N., 65
 Mitra, R. L., 3, 61, 300
 Modern Europe, Lodge, 176
 Modern Review, 122, 214, 223, 371, 426, 431, 527, 542, 593
 Monahan, 277, 281, 285, 339
 Monuments of Sāñchi, 405
 Moraes, see Kadambakula
 Mṛgichchhakaṭika, 563
 Mudrārākṣasa, 237, 266, 269, 295, 612, 554, 662
 Mysore and Coorg from the Inscriptions, see Rice
 N
 Nāgari Prachārīgī Patrikā, 371
 Nandīśāstra, 9
 Nariman, 203
 Nātyadarpaṇa, 512
 Nātyaśāstra, 563
 Nazim, Life and Times of Sultan Mahmud, 463
 Nikāya—
 —Aṅguttara, *passim*
 —Dīgha, 99, 207, *et passim*
 —Majjhima, *passim*
 —Samyutta, 155, 206, 210
 Nilakantha Sastri, K. A., see Pandyan Kingdom
 Nilakantha (Commentator), 67, 146
 Nirukta, Yaśka, 111, 112, 161
 —ed. Kābharaja Srikrishna Das Sircathi, 25
 Nītiśāra, Kāmandaka, 237
 Nīvākyaṃpita (Somadeva), 578
 Norris, 331
 Notes on the Ancient Geography of Gandhāra, Foucher, 60
 Numismatic Chronicle, 292
 O
 Ogden, 202
 Old Brāhmī Inscriptions, Barua, 312, 419
 Oldenberg, 1, 13, 24, 52, 54, 68, 73, 113, 121
 Olcott, see Arabian Nights
 Oldham, 544
 Onesikritos, 251
 Origin and Development of Bengali Language (Chatterji), 535

Origin of the Chalukyas, R. S. Satyasray, 608

Orcinus, 555, 425

Oxford History of India, V. A. Smith, 223, 276, 295, 302, 348, 373, 463, 581

P

Pali English Dictionary, Rhys Davids, and William Stede, 299, 520, 525, etc.

Pandyan kingdom, 328 f, 420, 488, 546

Panku, 456, 459

Pan-yong, 460

Papācchāsādanī, 26

Paramatthadipani, 65

Paramatthajotikā, 83, 124, 125

Parapar, 269

Pargiter, I, *et passim*

Parīśhataparvan, 207, 216, 224, 231, 265, 269, 295, 296, etc.

Parthian Stations, Schoff, 427 f, 430

Pātimokkha, 617

Pāṭaliputrakalpa, Jinaprabhasuri, 351

Patañjali (see Mahābhāṣya)

—Index of words, 520

Pavanadūtām, 539

Penzer, The Ocean of Story, 617

Periplus of the Erythraean Sea, Schoff, 60, 263, *et passim*

Pischel, 162

Philostrotos, 430, 458

Pliny, 93, 239, 281, 299, 310, 462

Plutarch, 233, 269, 291, 268, 269, 272

Political History, Raychandhuri, 41

Polybius, 361 f, 379

Pompeius Trogus, 426

Prabodha-chandrodaya, 602 n

Pracharjā-Pāṇḍava, Cappelle, 5

Prajāpānā, 309

Pratijñā Yaugandharāyana, 47, 131

Pravachanasāroddhāra, 507

Prāśasti, 593 n, 596 n

Pre-Aryen et Pre-Dravidien dans l'Inde, S. Lévi, 109, 150, 305, 309

Pre-Buddhist India, 126

Priyadarśikā, Śrī Harsha, 110, 203

Proceedings of the Second Oriental Conference, 296

Proceedings of the Seventh Oriental Conference, 593

Proceedings of the Sixth Oriental Conference, 148

Proceedings of the Third Oriental Conference, 369, 555

Proceedings of the Seventh Session of the Indian History Congress, 465, 593

Przyłski, 413

Ptolemy, Geographer, *passim*

Ptolemy, Historian, 250

Purāṇa—

—Agni, 520, 620

—Bhāgavata, 4, 5, 15, 350, 380, *et passim*

—Brahma, 71, 72

—Brahmāṇḍa, 407 f

—Bṛihadharma, 112

—Kalki, 220

—Kūrma, 304, 632

—Liṅga, 632

—Mārkaṇḍeya, Pargiter, 5, 72, 94, *et passim*

—Matsya, *passim*

—Padma, 414

—Skanda, 620

—Vāyu, *passim*

—Viṣṇu, *passim*

R

Raghuvamśa, 91, 281, 304, 327, 479, 576, 606 n

Rājasekhara, 5

Rajasthan, Tod, 268

Rājatarāṅginī, Kalhapa, 148, 325, etc.

Rājāvalkatho, 204, 296

Rāma-charita (Sandhyākara Nandī), 533

Rāmāśa, 539

Rāmāyana, 3, *et passim*

Rapson, *passim*

Ratnāvalī, 203

Raverty (Tabaqāt), Vol. I, 517

Rawlinson, 300

Ray, H. C., 65

Records of the Western World, see Beal, 460

Religion and Philosophy of the Veda and Upanishads (Keith), 19, 184 f

Religions of India, Hopkins, 40, 430

Renou, Louis, 165

Rhys Davids, I, *passim*

Rhys Davids, Mrs, 200

Rice, 235, 270, 295, 356, 582

Ridding, 557

Rig Veda Brāhmaṇas, Keith, 37, 167

Rivett-Carnac, 391

Rockhill, 120

Roth, 13

S

Sāhitya Parishat Patrikā, 633

Sachau, Alberuni's India, see Alberuni

Sahui, Dayārām, 464

Saint-Martin, V. De, 257

Salestere, B. A., 330

Sallet, 585

Sāhkhya System, Keith, 5

Saṅgharakṣa, 469

Sanskrit Drama (Keith), 391, 430, 563

Sanskrit English Dictionary, Apte, 365

Sāṅkara (Commentator), 512

Sarkar, B. K., 168

Saraswati, Rangaswami, 512

Saraswati, S. K., 586

Sāstrī, Pandit Ganapati, 47, 131, 316

Sāstrī, Pandit H. P., 223, 254 f, 535, 600 n

Saundarananda, 145

Sāvya, 158

Schoff, 60, 263, 435, 482, 505

Schwanbeck, 274

Sen, J., 292

Sen, P. C., 275

Sen, Sukumar, 147 n, 243 n

Senart, *passim*

Shabārquan, Shapurkhan, 616

Shah, C. J., 295, 543

- Shah, H. A., 569
 Shāma Sastry (see Arthashastra)
 Siddhanta, N. K., Heroic Age of India, 17
 Sigilovāda, 341
 Sircar, D. C., 171, 393, 407, 507, 523, 603 n, 627 n
 Si-yu-ki, Beal, 63, 126, 215, 333, 583, 595
 Sketch of the Sikhs (Malcolm), 64
 Smith, V. A., 1, *et passim*
 Somadeva (Author of the Kathā-Sarit-Sāgara), 223, *et passim*
 Somadeva (Nīṭivākyāmṛita), 578
 Some Kāstriva Tribes of Ancient India, 63, 124, 128
 Sonadanda sutta, 207
 South Indian Inscriptions, Hutzsch, 16, 323, 328, *et passim*
 Spooner, 276
 Sridhara, 112
 Śrīgāraprakāśa, 512, 564
 Srinivasachari, C. S., 466, 517
 Sse-ki, 459
 Ssu-ma-chien, 458
 Steds, 99, 525
 Stein, Sir Aurel, Penares Hindu University Magazine, Jan., 1927, 246
 Stein, Sir Aurel, Naḥaqa's Rajataranginī, 305
 Stein (Megasthenes and Kautilya), 285
 Steen Konow, *passim*, 618
 Strabo, see Hamilton and Falconer
 Studies in Indian Antiquities, H. C. Ray Chandhuri, 25, 454
 Subandha, 296
 Subramaniam, 899
 Successors of the Śātavāhanas in the Eastern Deccan, see Sircar, D. C.
 Sukbthankar, 47, 412, 496
 Sukranthi, B. K. Sarker, 158
 Sumāṅgalavilāsinī, 311, 343
 Sung-yun, 460
 Śūra Kānta, 255
 Sūtra—
 —Dharma:—
 —Āpastamba, 35
 —Bodhāyana (Bandhāvāna), 83, 88
 —Grihya:—
 —Āśvalāyana, 53, 41
 —Śākḥāyana, 33
 —Jaina:—
 —Aupapātika, 209
 —Āvadyaka, 417, 495
 —Āvāraṅga, 118, 487
 —Bhagavattī, 94, 207
 —Kalpa, 120, 135, 128, 209, 213
 —Nirayāvalī, 125, 207, 213
 —Sotrakṛitāṅga, 118
 —Uttarādhvayana, 57, 81, 82, 86, 87, 136 f, 146 f
 —Sūtra, Śrauta:—
 —Āpastamba, 103, 170
 —Āśvalāyana, 53, 370
 —Bandhāyana, 18, 56, 90, 101, 103, 369, 398
 —Kātyāyana, 158
 —Śākḥāyana, 42, 44, 74, 94, 103
 Sūtra, Buddhist, 11
 —Aggañña, 99
 —Ambaṭṭha, 34, 99, 258
 —Chakkavatti Sihanāda, 327
 —Kālakārāma, 614
 —Lohiccha, 34, 154
 —Mahāgovinda, 75, 87, 109, 144, 170
 —Mahāli, 124
 —Mahāparinibbāna, 105, 107, 119, 120, 192, 126 f, 212, 287
 —Mahāsudassana, 126
 —Makhāḍeva, 82
 —Pāvāsi, 99, 155
 —Sangiti, 126
 Sutta Nipāta, 89, 99, 120, 198
 Suvarṇadvīpa, R. C. Majumdar, 330
 Svapana-vāsavadattā, 47, 131, 133, 203, 216
- T
- Tabard, 202
 Tabaqāt-i-Nasiri, 517
 Takakusu, I-tsing, 340
 Tamils Eighteen Hundred Years Ago, 328
 Tantri Kāmandaka, 528
 Tārānāth, 236, 296 f, 351, 371, 609
 Tarn, Greeks in Bactria and India, 363, 272 f, 317, 390, 456
 Tawney, see Kathā-Sarit-Sāgara
 —The Ocean of Stories, Penzer, 617
 The North Western Provinces of India (Crooke), 241
 Therīgāthā, 65
 Thoma, 230
 Thomas, F. W., 248, 291, 334, 376, 419, 430, 434 f, 466, *et passim*
 Tirthakalpa, 417
 Tod, see Rajasthān
 Tolman, 147, 240
 Trenckner, 381, 388
 Trinathī, 604
 Triptaka (Chinese), 469
 Turnour, see Mahāvastu, 117
- U
- Upanishad:—
 —Bṛihadāraṇyaka, 3, *et passim*
 —Chhāndogya, 3, *et passim*
 —Rājendralāl Mitra's translation, 3, 51
 —Jaiminiya, 25, 50
 —Kaushitaki, 66, 77, 172
 —Mundaka, 355
 —Prasna, 33, 79, 86, 101 f, 166, 293
 —Taittiriya, 101
 Uttara-Rāma-Charita, 80, 171
 Uvāsagadasāho, Horende, 95, 118, 119, 120, 199, 202, 211

V

- Vaidya, C. V., 24, 253, 517
 Vaishnavism, Saivism and Minor Religious
 Systems (R. G. Bhandarkar), 475
 Vākpatisāra, see Gauḍavaho
 Varāhamihira, see Brihat Saṁhitā
 Vārahaganya, 5
 Vāsavadattā Nāṭyadāra, 296
 Vasu, S. C., see Ashṭādhyāyī
 Vats, 123
 Vātsyāyana, see Kāmasūtra
 Veda, Saṁhitā—
 —Atharva, *passim*
 —Bloomfield's translation, 18
 —Paippalāda, recension, 74
 —Kāthaka, 25, 159
 —Maitrāyaṇī, 159
 —Rik, *passim*
 —Taittirīya, 166
 Vedic Index, Macdonell and Keith,
passim
 Venkatesvaraiyar, 329
 Vidyābhūṣaṇa, S. C., 123
 Vidyāsāṅkār, Jaychandra, 618f
 Vīmānavatthū, 165
 Vinaya Texts, 11, 97
 —Chullavagga, 198, 204
 —Mahāvagga, 97, 106, 111, 124, 173, 200,
 207, 212
 Vinācharita, 417
 Viśakhadatta, 188, 513

Vogel, 253, 430

Volume of Indian studies presented to
 Prof. Rapson, 341, 614n

W

- Warren, 125
 Watson, 233, 264, 271, 384
 Watters, see Yuan Chwang
 Weber, 1, 49, 65, 69, 113, 163, 254
 Wei-ho, 464
 Wenger, J., 111
 Westergaard, 331
 Whitehead, see under Catalogue
 Wijk, Van, 464, 618
 Wilkie, W., One World, 289
 Wilson, 126
 Winternitz, 11, 37
 Woolner, 312

Y

- Yāska, 5, 25, 111, 149, 161
 Young Men of India, the, July (1926), 466,
 517
 Yuan Chwang, Watters, 107, 118, 308, 403
 Yu-Houan, 464

Z

- ZDMG, 425, 433
 Zimmer, 13, 64

GENERAL INDEX

A

- Abastanoi, Sambastai, Sabarcas, Sabagrae,
355 f
- Abdagases, 454, 519
- Abbaya, Prince of Magadha, 209 n
- Abhayadatta, 631 n
- Abhipratārin Kakabasenī, 44 ff
- Abhira, Abiria, 257, 446, 498, 509, 544
- Abhisāra, Abisares, 248 f, 260
- Abhisāraprastha, 443
- Abhisheka, 167, 302
- Abhyamtaropasthāvaka, 523
- Abisares, see Abhisāra
- Achyuta, 534, 536
- Adhikṛita, 166 n
- Adhishmakrishna, 43, 69, 105
- Adhishthāna, 519
- Adhyaksha, 283 ff
- Adityasena, 583, 605, 610
- Adityavarman, 604
- Adraistai, 250
- Agalassoi, 254
- Agathokleia, 384, 386, 422
- Agathokles, 422
- Agessilaos, 476
- Agrikhamdha, 340 n
- Agnimitra, Suśa, 369, 371 ff, 391 ff
- Agra-mahishi, 517
- Agrāmātya, 302
- Agrammes, 232 f, 236 f, 261
- Agronomoi, 234 n, 294, 318
- Khāla, Khāra, 317, 523
- Abhishekhata, Adhichkhata, or Chhata-
vati, 135, 393, 536, 550
- Abvata, 66 n
- Akshvāka, 120 and note
- Aila, see Purūratas
- Aindra mahābhishheka, 163 f, 168 f
- Airikina, 537, 595, 629
- Aisvarvapāla, 523 n
- Aioi, 637
- Aiaka, 230 f
- Aiādatra Kāva, 66, 76 f, 63
- Aiādatra Kūpika, 209, 210 ff
- Ailvika, 213, 226, 245, 331
- Ākarāvanti, 506 f, 621
- Akoophis, 247
- Akabadarā, 520 n
- Akshapatāi-adhikṛita, Keeper of the Re-
cords, 559
- Akshāvāpa, 166
- Alasanda, Alexandria, 307, 381
- Alavi, Alabhiya, Alavaka, 197 f, 538
- Alexander of Corinth, 331 f
- Alexander of Epirus, 331 f
- Alexander the Great, 234, 244 f, 260 ff
- Alexandria in Kabul, 262
- Alexandria in Sind, 262
- Alikasudara, 332
- Allakappa, 193
- Allitrochades, 296
- Amachcha, Amātya, 280 ff, 372, 515, 521 f
- Ambashtha, Amhattha, see Abastanoi
- Āmbhi, 248, 260
- Āmbhiyas, 248, 418
- Amgiya family, Āmbhiya family, 417 f
- Amitraghāta, Amitrakhāda, Amitrachates,
see Bindusāra, 277 n, 296
- Āmrakārdhava, 559
- Arha-mahāmātras, 317
- Artekina, 332
- Amyntas, 425
- Asanda kings, 500 n, 538
- Anantadevi, 570
- Anantanemi, 146 n
- Anantapāla (Dandanāyaka), 582
- Anantavarman, 603
- Ānarta, 506, 621
- Ancestry of Chandragupta, 256 f, 355 ff
- Andhapura, 92
- Andhan Inscriptions, 485 f, 506
- Andhra, 5, 92, 312, 398, 403 ff, 602, 604
- Andhrāpata, 92, 492
- Androkottus, see Chandra Gupta Maurya
- Androsthenes, 361, 380
- Ānga, 98, 106 ff, 152, 310 n, 603
- An-Shih-Kao, 469
- Antapāla, 317
- Antarvaidika, 166, 317 n
- Antarvedi, 537
- Antialkidas, Antialkita, 384, 394, 404 n,
424
- Antigonos Gonatas, 331 f
- Antimachos, 422
- Antiochos Soter, 614 n
- Antiochos Theos, 299, 307, 331, 614
- Antiochos the Great, 381, 385, 423
- Anupa, 491, 506 f, 621
- Anupiya, 123
- Anuruddha, 216
- Anushayāna, 319, 336
- Anyatapalaksha, 23
- Aornos, 246 n
- Apara Matayas, 67
- Aparāntas, 314, 491, 502, 507, 526, 602 n
- Aphrikes, 246
- Apollodotos, 384, 386 f, 422
- Apollophanes, 422
- Ārakshādhikṛita, 521
- Archebios, 425
- Ardeshir Bābagān, 479 n
- Argara (Uruga-pura), 687
- Aria, 273
- Āriake, 637
- Aritthapura, 253
- Arjans, of Kanauj, 610

Arjuna (Matsya), 138
 Arjuna Pāṇḍava, 123, 545
 Arjunāyana, 515 n, 544
 Arsakes (Parthian), 379
 Arsakes (Urasā), 248
 Arta, 445 n
 Artaxerxes Mnemon, 243
 Artemidorus, 425
 Arthachintakas, 514
 Arthavidyā, 9 n, 514
 Arupi, 83, 49, 58, 61 f, 64
 Aryaka, 220 f
 Asaghasena, 393
 Asandhimitra, 367
 Asandivant, 23, 39
 Asiani, 426
 Asii, 426
 Asika, 491
 Asitampiga, 38
 Asmaka, Asaka, Asaka, 89, 143 f, 233,
 245 f, 491
 Asoka (in the epic), 5
 Asokachandra, 209
 Asoka's Contemporaries, 331
 Asoka Maurya, 5, 392 ff, 614 ff
 Aspasian, 245
 Aspavarma, 445, 454
 Aspiurus, 425
 Assakenoi, cf. 149 n, 240, 245 f
 Assalāyana Assalāyana, 33, 79
 Assembly of Village Headmen, 173
 Astakenians, 239
 Astes, 247, 261
 Astynomoi, 234
 Asuravijaya, 537 n
 Astvaghosha, 476
 Astaka, cf. 149 n, 245
 Assalāyana, see Assalāyana
 Asvamedha, 170, 377, 388 f, 416, 480, 500 n,
 504 n, 548, 568, 584
 Asvamedha (king), 43
 Asvamedhadatta, 44, 69
 Asvamedha Parākrama, 549, 550
 Asvapati, King of the Kekayas, 56, 63 f
 Asvapati, King of the Madras, 65 n
 Asvavāra, 621
 Atavi, 307, 311
 Atavika, 538
 Athama, 443
 Atpāra, 81, 102
 Attivarman, 540
 Auchchamanyava, see Girikshit
 Audumbaras, 575 n
 Augrasainya, 230
 Aulikara Family, 630
 Avachatnuka, 108 n
 Avanti, 96, 144 f, 204, 214 f, 580
 Avantiputra, 142
 Avantivardhana, 221
 Avantivarman, 606 n, 608, 623
 Aya, 453, 466
 Ayama, 484
 Ayaputa, 318
 Ayasi-Kamuis, 517
 Ayodhya, 99 f, 104, 586 f

Ayogava, 160
 Ayukta, Ayuktaka, 316, 330, 561
 Azes I, 423, 439 ff
 Azes II, 442
 Azilises, 441 f

B

Bactrians, 4, 244, 272, 379 ff, 426
 Bad-kāmta, 543
 Bahasatimitra, see Bṛhaspatimitra, 373
 Bāhli, 25 and note
 Baimbika, 369 f
 Baithan, see Pratishthāna
 Bajji, see Vajji
 Balabhadra, 350
 Balādhiparapa, 563
 Balādhyaksha, 295
 Balādita I, see Narasimha Gupta
 Balāditya II, 568 n, 595 f, 606, 623
 Balapradhāna, 285 n
 Balasāri, 491 ff, 617
 Balavarman, 534
 Balhika, 25, 26
 Bali, 233, 521
 Bandhula, 199
 Bandhupālita, 350
 Bandhuvvarman, 567
 Barabar Hill Cave Inscription, 510
 Bārāṇasī, Benares 74 f, 86, 100 n
 Barbaricum, 435, 455, 620
 Bārhadhrathas of Magadha, 118 f
 Bārhadhrathapura, 111
 Barygaza, 483
 Batoī, 638
 Benakotaka Svāmi, 494
 Bengal, History of, 309, 535, 543 f, 632 ff
 Berar, see Vidarbha
 Besnagar Inscription, 394
 Bhaddā, 219 n
 Bhaddasāla, 239
 Bhaddiya, 106
 Bhadra-ghosha, 392
 Bhadraka, Ādraka, Odraka, Andhraka,
 Antaka, 363
 Bhadrakukha, 468
 Bhadrabāhu, 295
 Bhadrayāsa, 429
 Bhāga, 293, 521
 Bhāgabhadra, 393
 Bhagadatta, 607
 Bhagadugha, 166
 Bhagala, 232
 Bhāgavata (King), 394 f
 Bhāgavata religion, 369, 394
 Bhaggas, 123, 192 f
 Bhageratha, 101
 Bhālleveya, see Indradyumna, 51 n
 Bhāṇḍāgāra, 521
 Bhāṇḍāgārika, 521
 Bhānu Gupta, 588 n, 596, 597 n, 609
 Bhāradvāja, 370
 Bhāradīvas, 480
 Bharata Daughanti, 24 n, 25, 90
 Bharata, son of Rishabha, 24 n
 Bharata of Sora, 144

- Bharata, 23, 24, 40, 73, 75, 142
 Bhāratavarsha, 420
 Bhārata War, 27, 40
 Bharga, see Bhagga
 Bharsar hoard of coins, 587
 Bhartidāman, 510
 Bhaskaravarman, 609
 Bhāṣmanushya, 521
 Bhātārka, 629
 Bhāṣāvapatti, 563
 Bhāṣiprola Inscription, 312 n
 Bhāṣṭiya, 117
 Bhauja, 175 f
 Bhava Naga, 480
 Bhīmasena, 15
 Bhīmasena, Hājan, 531
 Bhīma, King of Vidarbha, 86
 Bhīmavarman, 580
 Bhitarī Inscription, 588, 572
 Bhogas (clan), 120 and note
 Bhoganagara, 120 and note
 Bhogavarman, 610
 Bhoja, Dāṇḍakya, 91
 Bhoja (title), 159
 Bhojaka, 582
 Bhojakata, 91
 Bhojanagara, 66
 Bhojas, 89 f, 180 f, 146, 311 ff
 Bhojyo, Lāhyayani, 49, 88
 Bhukti, 560 f
 Bhūmaka, 484
 Bhūmimitra, 392
 Bhūtapāla, 236
 Bhūtavīras, 88
 Bhūtivarman, 627 n
 Bimbaka, 369 n
 Bimbisāraguri, see Girivraja, 111
 Bimbisāra, 115, 155, 204 ff
 Bindusāra, Amitraghāta, 267, 282 n, 295, 296 ff
 Boar worship (significance), 186
 Boards of Five, 285 f
 Boddas, 617
 Boukephala, 262 f
 Brahmadatta of Aṅga, 110
 Brahmadatta of Assaka, 144, 170 n
 Brahmadatta of Kāśī, 75 f, 163
 Brahmadatta of Pañchāla, 136
 Brahmadatta (Uparika Mahārāja), 593
 Brahmakshatra, 182 and note
 Brahmamitra, 392
 Brahmarshideśa, 68
 Brahmavarddhana, 74
 Brihadishu, 71 n
 Brihadratha (of Girivraja), 113 f
 Brihadratha, Maurya, 350, 368
 Brihadakitha, 82, 125
 Brihaspati Mitra, 373 f, 420
 Brihatphalavyasa, 500 n, 683
 Buddhagupta, 570, 588 n, 593
 Buddha Gupta, 588, 593
 Budharāja, 607 n
 Budhavarman, 501 n
 Buddhism in Iran, 616 f
 Buddhist Council, 215, 229
 Bulis, 123
 Cacouthes, 126
 Cadra Kapishka, 476 n
 Calingao, see Kalinga
 Cambodia, 148
 Care of foreigners, 292
 Ceylon, Sinhala, 330 f, 547 f
 Chagota, 628 n
 Chakrapālita, 580
 Chakravarti-kshetra, 271 n
 Chakrāyaga, 45, 58
 Chalukya, 602 f, 610 f
 Chalukyas (Eastern), 591 f
 Champā City, 107 f, 198, 207, 300
 Chāṅakya, Kauṭṭiya, 287 f, 265 n, 268, 277, 296
 Chandanā, 109
 Chandradēvi, 586
 Chandra Pradyota Mahāsena, 204
 Chandraasena, 527 n
 Chandra of the Mehrauli Iron Pillar Inscription, 481, 535 n
 Chandrabālā, see Chandanā
 Chandragomin, 628
 Chandra Gupta I, 528 n, 530 ff
 Chandra Gupta II, 478 f, 511 f, 563 ff, 600, 612
 Chandragupta Maurya, 194 n, 238, 264 ff, 355 n, 614 n
 Chandragupta's date, 214, 295
 Chandragupta's government, 277 ff
 Chandra Gupta Vikramāditya, see Chandra Gupta II
 Chandraprakāśa, 564 n
 Chandravarman of Bengal, 534
 Chandravarman of Kamboja, 150
 Chang-K'ien, 459
 Chapaḍa, 320
 Chāra, 320
 Charaka, 475
 Chārāyaga, 211
 Chashtana, 469 n, 486 f, 505 f, 622
 Chatrapana, see Vāsishṭhiputra Chatrapana Sātākarpī
 Chauroddharapika, 561
 Checks on absolutism, 172 ff
 Chedis, 68, 128 ff, 151, 418
 Chellanā, 209 n, 211
 Chera, see Kerala
 Chetaka, 125, 211
 Chetas, 418 ff
 Chavillakara, 309
 China, 9 n, 474, 626
 Chiradatta, 566
 Chitrakūṭa, 629
 Chitraratha Ārya, 78
 Chola, 328
 Chora Rajjukas, 318
 Chouang-mi, 459
 Chronology of the Bimbisara-Sisunāga group, 225 ff
 Chukha, 444
 Chūrpi, 330
 Chinapaṭṭa, 9 n, 277

Chujakula, 503
 Cleombora, 138
 Cophueus, see Kophaiois, 260
 Copen, see Kābul, 239
 Coronation Oath, see Oath, 168
 Courts of Justice, 208, 279, 286, 317, 316,
 562
 Cutch, 381 n, 486, 488
 Cyrene, 381
 Cyrus, 339 f

D

Debbasena, 154
 Dabūārā, 589, 598
 Daddarapura, 180
 Dadhivāhana, 109, 123, 170 n
 Dahm, 260
 Dharasena, 499 n
 Daivāpa, see Saunaka, Indrota Daivāpa
 Daivaputra-Shāhi-Shāhānushāhi, 482, 540 f
 Dakash, 139 n
 Daksha, 139 n
 Dakshipa Mathurā, 328
 Dakshipāpadā, 85
 Dakshipāpatha, 85, 268; 403, 538, 636 ff
 Dakshipāpatha-pati, 411, 416, cf. 498 n
 Dakshipātiya, 85
 Dālbya Chaikitāyana, 74
 Dālbya Keśin, 73
 Dāmāghasada I, 509
 Dāmājada Sri, 510, 513
 Dāmāna, 588
 Dāmasena, 510
 Dāmijada (or Namijada), 497 ff, note
 Dāmodara Gupta, 605 f, 625
 Dāmodarasena, 564 f
 Dāmodarpur plates, 543, 561, 567 n, 593
 Dapḍaka, 91
 Dapḍanāyaka, 520, 563
 Dapḍa-pāśādhikarapa, 563
 Dapḍa-pāśika, 561
 Dapḍa-samatā, 588 f
 Dapḍika, 561
 Dantābala Dhamra, 39 n, 51 n
 Dantakūra, 89 n, 305 n
 Dantapura-nagara, 89, 305 n
 Dantavaktra, 89 n
 Darius I, 147, 240, 518
 Darius III, 244
 Dasaka, 216
 Dārvābhīrā, 243
 Dārayavansh, 240
 Dasapura, 484, 567, 630
 Dasaratha (Ikāvāku), 78, 101
 Dasaratha, Maurya, 381
 Dāsārpa, 94, 95 n
 Dattadevi, 551 f
 Dattāmitra, 5, 392
 Dattāmitrī, 393
 Dattas of Puṇḍravardhana, 597
 Davāka, 543
 Deccan, see Dakshināpatha
 Deimechos, 299
 Demetriaspolis, 383

Demetrios, 5, 383 ff, 423
 Democracies, 256, 298
 Derbhaṭa, 629 n
 Deśa, 523, 580
 Deśādhipāta, 524
 Deśika, 285 n
 Devabhūmi, Devabhūti, 395
 Deva Gupta I, 554
 Deva Gupta II, 607 f
 Deva Gupta III, 610 f
 Deva Sri Haraha Gupta, 601
 Devaki, 141 n, 570, 572, 573 n
 Devakulas, 477, 517
 Devānampiya, cf. 271, 303, 326, 381
 Devānampiya Tissa, 383
 Devapāla Gaṇḍa, 537
 Devapāla (Pratihara), 585
 Devāpi, 161
 Devaputra, 477, 516, 518, 547
 Devaraja Chandra Gupta II, 554
 Devaraja Skanda Gupta, 577
 Devarāshtra, 538, 540, 538
 Devāstri, 564, 601
 Devavarman (Eastern India), 528 n, 582 n
 Devavarman Maurya, 380
 Devavarman Śālaśākya, 548
 Devavrata, 452 n
 Devika, 620
 Dhamma, Law of Piety, 324 f, 335, 336 f
 Dhammaghoṣa, 327, 385
 Dhamma-mahāmātra, 316, 336 f, 357 f
 Dhamma-nigama, 525
 Dhamma-niyama, 343 n
 Dhamma Vijaya, Dharma Vijayī, 327, 332,
 365, 516 n, 537, 540
 Dhamma-yutas, 336 f
 Dhamnakaḍa, Dhamnakaḍa, 92, 312 n
 Dhona (Nanda), 237
 Dhanabhūti, 523
 Dhanada-Varuṇendrāntaka-sarna, 547 n, 559
 Dhanadhya of Kusthalapura, 538
 Dhanadhya Koravya, 184
 Dhanika, 353
 Dhanyavishnu, 593, 595
 Dhāra, 604 n
 Dharasena II (Valabhi), 629
 Dharasena IV, 630
 Dharmāditya of Eastern India, 550, 683
 Dharmāditya (Śilāditya II), see Śilāditya
 Dharma-mahāmātras, see Dhamma mahā-
 mātras
 Dharma-Mahārājadhīrāja, 510
 Dharmapāla, 537
 Dharmarakkhita, 304 n
 Dharmārāya-Vihāra, 309
 Dharmasthas, 283 n
 Dharmayuta, 336 f
 Dhanu, 306
 Dhavala, 353
 Dhavalā, 596 n, 597 n
 Dhavalappadeva, 353
 Dhṛiṣṭadyumna, 21 n, 73 n
 Dhṛitarāshtra, Prince of Kāśī, 44, 75, 97
 Dhṛitarāshtra Vaichitravīrya, 7, 25, 351,
 487 n

- Dhruvabhaṭṭa, 629 n
 Dhruva-Devī, Dhruvasvāmīni, 312 n, 562, 564, 573
 Dhvaṣan Dvāitavāna, 67
 Dighati (Dighiti), 106, 153, 173
 Dighāvu, 173
 Diodotos I (King of Bactria), 379, 426
 Diodotos II, 379
 Diomedes, 420 n, 425
 Dion, 394
 Dionysios, Ambassador, 299
 Dionysios, king, 423
 Dioscuri, 424
 Dipt, 243
 Dīrgha Chārāyana, 199
 Divakara, 106, 114
 Divākaraśena, 564
 Divodāsa (of Kāśī), 75
 Divodāsa Paśchāla, 73
 Drangians, 427 f, 621
 Dridhavarman, 110
 Drops of the Epic, 21 n, 371 n
 Droṇamukha, 263 n
 Droṇa Sūbha, 636 n, 629
 Druhya, 146
 Drupada, 73
 Dummukha Lāchchhavi, 124
 Dummukha Paśchāla, 62, 135 f
 Durdharā, 296
 Duryodhana, 487 n
 Duṣṭājit, 175
 Dāta, 316, 320, 522
 Dvādaśāditya, 596 n
 Dvairāja, 437 n, 519
 Dvāitavāna, 63
 Dvārakā, 150, 506
 Dvāmukha, see Dummukha Paśchāla
- E**
- Eastern Chalukya, 591
 Egypt, 276, 284, 290, 331
 Ekachakrā, 71
 Ekarāt, 164, 233, 534
 Embra Topo, 194
 Emetreus, 382
 Enumeration of homonymous Kings, 605 n
 Epander, 425
 Epirus, 331
 Epistopoi, 290
 Era of Samprati, 376 n
 Eran, 593
 Erāṇḍapalla, 538 f
 Erannobee, 274
 Eudemos, 292
 Eukratides, 383 ff, 386, 423 ff
 Euthydemis, 383
 Euthydemus, 379 f
 Euthymedia, 383
- F**
- Female guards, 276 f
 Fo-to-kio-to, 570, 583 n, 593
 Gad, 453
 Gahapati, 695
 Gaggara, 109
 Gadijavara, 521
 Gaṇapati Nāga, 531 ff
 Gaṇarājas, 126, 212
 Gandaris, 250
 Gandhāra, 59 f, 146 ff, 152, 107, 240 ff, 247, 250, 273, 308, 438, 444, 466, 475, 483, 597 n, 602 n
 Gandhāri, 60
 Gaṅgas of Mysore, 639 f
 Gangaridae, 236, 261, 309
 Gardabhillā, 466 n
 Gārgi, 63
 Gārgya Bālāki, 77
 Gauḍas, 603, 604 ff, 608 f, 625, 632 ff
 Gaunimika, 521
 Gaupālāyana, see Suchivṛkaka, 44
 Gaupālāyana Śhapati, 44 n
 Gautamī Bahāri, see Bahāri, 347, 491
 Gautamiputra Śātakarpi, 410 n, 413, 429, 491
 Gaya (Prince), 114
 Gedrosia, 289, 273
 Ghaṭjaka, 450, 484
 Ghaṭjotkacha (Gupta), 529
 Ghaṭjotkacha Gupta, prince, 561, 567, 571, 600 n
 Ghaṭo Kramāditya, 567 n
 Ghora Āṅgirasa, 141 n
 Girinagara (Girmar), 314
 Girivraja (in Kekaya), 62
 Girivraja (in Magadha), 63, 110
 Glauchukāyana, 250 n
 Glauganikai, Glausiana, 250
 Go'dhyakaka, 286
 Gomatikottaka, 610
 Gomitra, 401
 Gonarda, 397
 Gondophernes, 429, 440, 452 f
 Gopa, 293
 Gopachandra, 633
 Gopālī Vaihidari, 393
 Goparāja, 595 f
 Goptri, 317, 371, 561, 679
 Gorathagiri, 420
 Gosāla Maṅkaliputta, 213
 Goshṭhis, 525 f
 Gotama Rāhūgana, 54
 Govardhana, Nāśika, 31, 494, 501 f
 Govikartana, 167
 Govindachandra Gāhaḍavāla, 347
 Govinda Gupta, 561, 566 n, 600 n
 Govindarāja, 367
 Govishāṅga, 237
 Grahavarman, 605, 607 f
 Grāma, 292, 524, 563
 Grāmahṛitaka, 293
 Grāmahāra, 524
 Grāmaṇī, 163, 166, 173, 174, 525
 Grāmaṇipiddha, 293 n, 525
 Grāmeyika, Āyatta, 525

Grāmika, 174, 208, 292, 525, 562
 Grāmabhojaka, 525
 Granavhryaka, 443
 Grumbates, 468
 Guda, 633
 Gūḍha-Purusha, 320
 Guduvhara, 452
 Guṇākhyā Sāṅkhāyana, see Sāṅkhāyana, 33 ff
 Gupta administration, 558 ff
 Gupta Era, 530, 626 n
 Gupta (King), 529
 Guptas (Early), 527 ff, 626 ff
 Guptas (Later), 581 ff, 623 ff, 626 ff
 Guraeans, 245
 Gusana, see Kushān
 Gushtasp, 615
 Guttas (Kanarese), 518, 564

H

Hagāmasha, 445
 Hagāna, 445
 Haihaya, 98, 145 f, 233
 Hairaṇyanābha, 101 ff
 Hakusiri, 417
 Hāla, 407 n
 Halla, 209 n, 211
 Harapna, discoveries at, 2
 Hariśchandra, 101
 Harishena, Praśastikāra and General, 542, 549
 Harishena, Vākātaka king, 499 n, 579, 634
 Hārītiṣputra Siva-Skanda-Varman, 503
 Hārītiṣputra Viśṇukaṣa Chuṭukulānanda Śātakarṇi, 503
 Harivarman, 604
 Harslla of Kanauj, 583, 600, 605 f, 609, 624, 629 n
 Harsha Gupta, 600 f, 604
 Harsha Guptā, 604
 Haryaṅka-kula, 115
 Hastidasanā, 340 n
 Hastin, 313 n, 595
 Hastinapura, 22, 23, 43
 Hastivarman, 538 f
 Hathī Gumpā inscription, 235, 373 ff, 418 ff
 Hathisimha, 419
 Hatthālāvaka, 198 n
 Hatthigāma, 120 and note
 Heliodoros, son of Diya (Dion), 394
 Heliokles, 385 ff, 425
 Hephaestion, 247
 Hermacis, 384, 425, 429, 441, 461, 470
 Hidus, 240
 Hieon-mi, 459
 Hi-beon, 460
 Himsrikās, 286
 Hippokoura, 502, 637
 Hippostratos, 422
 Hiraṇyavāha, 274 n
 Hiraṇyanābha, 79, 101 ff
 Hiraṇyavati, 126
 Hi-thun, 460

Hi-tonen, 460
 Hiung-nū, 431, 458 f
 Ho-ling, 305 n
 Hormisdas, 481
 Ho-ti, 463, 474
 Huṇas, Huns, 575 ff, 583, 595 f, 606, 626 n, 628, 630 f
 Huṇamaṇḍala, 629 n
 Huviṣka, 464, 476 f
 Hydaspes, battle of, 261
 Hydraces, 240
 Hyparch, 319

I

Ibhyas, 337
 Ikshvākus, 100 f, 127, 143, 233, 500
 Indradatta, 499 n
 Indradyumna, 51 n, 64
 Indramitra, 392
 Indrapālita, 350
 Indraprastha, Indrapatta, Indrapattana, 97, 133
 Indravarma, 445
 Indrota, 17, 18, 38, 50
 Irāvati, 38 n
 Irrigation in the Maurya Period, 284
 Isamus, 380
 Išānavarman (Maukhari), 600, 604 ff, 625, 631
 Ishukāra, 134
 Isila, 307, 317
 Išvaradatta, 498 n, 510
 Išvarasena, 499 n
 Išvaravarman, 604 f
 Itihhaka-mahāmātras, 317

J

Jaivali, 74
 Jala Jātukarṇya, 74
 Jalauka, 349 f, 361
 Jāluka, 223
 Jambudīpa, Jambudvīpa, 97, 357
 Janaka (father of Sītā), 54
 Janaka of Kāśī, 74
 Janaka of the Upanishads, 48 ff, 55 ff, 74
 Janaka varṇa, 55
 Janamejaya, 13, 16 f, 36 ff, 50, 51 n
 Jana Sārkarākshya, 64
 Jaraśandha, 113
 Jāratkāra, 58
 Jaugada, 306
 Jaya (Itihāsa), 42
 Jayadāman, 487 f, 506
 Jayadatta, 593
 Jayadeva, 525
 Jayanāga headman, 525
 Jayanāga (Gauḍa king), 538, 634
 Jethamitra, 393
 Jetuttara, Jetuttara, 198, 253
 Jih-kwan, same as Āditya Sena, 611 n
 Jihonika, 444, 462
 Jinasena, 627
 Jivadāman, 509

Jivaka, 206
 Jivita Gupta I, 601
 Jivita Gupta II, 606 n, 610 f, 623
 Jiyasattu, 198
 Jñātrikas, 119
 Jogalthembhi, 489
 Junāgaḍh Rock Inscription, 9 n, 270, 280 n,
 282 n
 Junha, 202
 Jushka, 465, 476
 Jushkapura, 476
 Jyeshtha, see Vasu Jyeshtha, 392

K

Kabandhī Kātyāyana, 34
 Kābul, 239, 381
 Kācha, 533
 Kachcha, 507, 621
 Kadambas, 504 n, 555 n, 564 n, 612
 Kadphises I. see Kujula
 Kadphises II, see Wema
 Kahola Kaushitaki, 33, 58
 Kairiśi Sutra, 192
 Kaisara, 477
 Kaivarta (king), 237
 Kākanāda (Sāñchi), 546
 Kākas, 545 f
 Kākakarna, 112
 Kākavarṇa, 112, 221 f, 232 f
 Kakshasena, 16, 44
 Kakshaseni, 44
 Kakuḍa Kachchāyana, see Pakudha
 Kākutstha, 120
 Kākusthavarman, 504 n, 612
 Kalabhras, 639
 Kālachampā, 107
 Kalachuri Era, 468
 Kalachuris, 579 n, 583 n, 606 n, 607 n,
 608 n, 609, 631
 Kālaḡa, 209 n
 Kālāmas, 99, 155, 193
 Kālāra Janaka, see Karāla
 Kalasa, 449 n
 Kālasena, 105
 Kālāsoka, 221 f, 232 f
 Kālīdāsa, 564 n
 Kālindī, 593
 Kālīṅga, 87 ff, 233, 304 ff, 324, 363 f, 373 f,
 403, 580
 Kālīṅga-nagara, 89 n, 419
 Kālīvuga Era, 27
 Kālār, 479 n, 482
 Kalliope, Calliope, 384, 425
 Kalsigrāma, 381
 Kalyāṇavarman, 528 n
 Kāmandaka, 5
 Kāmarūpa, 310, 546, 607 ff
 Kamboja, 148 f, 243, 283, 307 f
 Kāñchapa-pura, 89
 Kammāssadamma, 134
 Kāmpīlya, Kāmpilla, 135, 198
 Kāṁsa of Kosala, 154
 Kāṁsa of Mathurā, 141
 Kāmruja, 148

Kāmyaka, 22
 Kanakagiri, 311
 Kanakhala, 66
 Kanauj, 136, 532, 584, 604 n, 608 n
 Kāñchi, 501, 538 f
 Kanishka I, 365 ff, 618 ff
 Kanishka II, 465 ff, 477
 Kanishka III, 473 n
 Kanishka-pura, 474
 Kañka, 166 n
 Kañtakasodhana, 319
 Kantha, 251
 Kāntipuri, 481
 Kāpvas, 393 ff
 Kanyākubja, see Kanauj, 136
 Kao-fou, 455 f
 Kapa, 456
 Kapatika, 291
 Kāpeya, 44
 Kapilavastu, Kapilāvata, 191
 Kāpiśa, Kāpiśi, 239, 386 f, 422, 425, 434,
 443, 473
 Kapsha, See Kujula
 Kāpya Patañchala, 65
 Karakaṇḍu, 82, 147
 Karāla, 81, 82
 Kārapaka, 316
 Karaṇḍu, 87
 Karas, 639
 Kāraskara, 527 n
 Karatai, 436, 484
 Kārddamaka, 437, 505, 623
 Kareoi, 637
 Karmamānta, 543
 Karmāntika, 522
 Karma Sachivas, 282 n, 509
 Karṇa, 148, 152
 Karṇadā, 112
 Karṇasuvarṇa, 310, 602, 609, 630
 Karttinura, 544
 Kārttikeya (worship), 478, 568
 Kārusha, 93
 Kāruvāki, 343
 Kāsi, Kāśi, Kāśī, 74 ff, 83, 96 f, 153 f, 206,
 210, 212, 233, 587, 593
 Kasia, 126
 Kāstiputra, Kantsiputra, 393
 Kāsmīra, Kāsmira, 308, 473, 482, 596 n
 Kaspeiroloi, 447
 Kassapiya Arhats, 393
 Kassites, 139 n
 Kaśu Chaidya, 130
 Kaśyapa Mātāṅga, 478
 Kaśyanas, 18, 369 n
 Katachchuris, see Kalachuris
 Katha, 251
 Kathaiot, 250 f
 Katur (Katuria or Katur) rājas, 544
 Kaundinya-pura, 87
 Kaundinya, Vidarbhi, 87
 Kaurāla, 538 f
 Kauravas, 120, and note
 Kauśāmbi, Kosambī, 43, 47, 70 f, 131, 275,
 307, 401
 Kauśiki river, 23

- Kauśikī (lady), 392 n
 Kauṭilya, see Chāṇakya, 9, 62, 237 f, 268, 277, 298
 Kantea, 51
 Kāvasheya, see Tura
 Kavirāja, 549
 Kāvīrīpaṭṭinam, 328
 Kekaya, 62 f
 Keralaputra, 330
 Kesaputta, 99, 193
 Keśins, 72 f, 93
 Ketumattī, 74
 Kevatta, Minister, 136
 Khaddavali, 502
 Khallāṭaka, 298 n
 Khalatika-pavata, 307
 Khāṇḍava, 22
 Khapiṇḍala, 307
 Kharagraha I, 629 n, 631
 Kharaoṣṭa, 449
 Kharapallāna, 473
 Kharaparikas, 544, 546
 Khāravala, 373 ff, 405 ff, 418 ff
 Khassa, 123, 293
 Khemā, 206 n
 Khotan, 309 n
 Khshayārshā, see Xerxes
 Kidāra Kushāns, 482
 Kien-chi, 459
 Kieou-tsieou-kio, 460 ff
 Kikāṣa, 111 f
 Kinds of rulership, 156 ff
 King-maker, 173
 Kingship, 156 ff
 Ki-pin, 432 f, 436 n, 456 ff, 466, 479, 482
 Kinsha, 473
 Kirtivarman I (Chalikya), 603
 Kleopbis, 246
 Kolivas, 192
 Kolkaī, 328
 Kollāga, 119
 Konākamana, 342, 345
 Koṇḍoda, 538 n
 Koṅkan, 580
 Kophaeos (Cophaeus), 260
 Korāṇḍavarṇa, 222
 Kosala (North), 74, 77 ff, 97, 99 ff, 151, 152 f, 199 ff, 211, 212, 235, 371
 Kosala (South), 306 n, 469, 538, 580
 Kośṭhāgāra, 522
 Koṭa, 402, 534, 536
 Koṭāṭavī, 538 n
 Koṭigāma, 119
 Koṭivarsha, 561, 582
 Koṭṭa-Vishayas, 317 n
 Koṭṭura, 538 f
 Kouī Chouang (Kushān), 459
 Krakuchchhanda, 309
 Kramāditya, see Ghaṭotkacha Gupta
 Kramāditya, see Kumāra Gupta II
 Kramāditya, Skanda Gupta, 577
 Krātha, 251
 Krimilāśva, 71 n
 Kṛishṇa Gupta, 600 f, 611 n
 Kṛishṇa Sātavāhana, 414 f
 Kṛishṇavarman, 504 n
 Kṛishṇa Vāsudeva, Devakīputra, see Vāsudeva Kṛishṇa
 Kritakshaṇa, 81
 Kṛitamālā, 328
 Kṛita-Mālava-Vikrama Era, 439
 Kṛitī, 54, 61
 Krivis, 71 f
 Kshaharāta, 444, 483
 Kshatrapas, 443 ff, 483 ff, 491 ff, 523
 Ksbatri (tribe), 257
 Khatṛī (official), 166
 Kshemarāja, 516
 Kshitipāla, 535
 Kshudrakas, 254, 260
 Kubera (ancestor of Bāna), 583 n
 Kubera of Devarāshṭra (king), 533
 Kuberanāgā, 555, 564, 572
 Kubiraka, 312 n
 Kujula Kadphises, 441, 461 ff, 470 f
 Kukura, 491, 507
 Kukurthā, 127
 Kulastambha, 602 n
 Kulūta, 515 n
 Kumāras, 288, 317, 349
 Kumāradevī (Gāhadvāla Queen), 304
 Kumāradevī (Lichchhavi princess), 530
 Kumāragiri, 538 n
 Kumāragupta I, 566 ff, 627
 Kumāragupta II, 589, 590 ff
 Kumāragupta III, 600, 602, 604 f, 606, 625
 Kumāragupta, Prince, 583
 Kumārāmātya, 390 n, 523, 560, 562 n, 567 n
 Kumārapāla, 535
 Kumāravishṇu, 501
 Kumbhavatī, 91
 Kuṇāla, 350 f, 363
 Kuṇḍadhāni, 561
 Kuṇḍagrāma, Kuṇḍapura, 119
 Kuṇḍina, 87
 Kūnika, see Ajātaśatru
 Kunindas, 515 n
 Kuntala, 235, 369, 407, 503 f, 580
 Kuntala Sātakarni, 407 f, 503
 Kuraraghara, 145
 Kura (Kingdom), 21 f, 45, 68, 133 f
 Kuru (dakṣhiṇa), 26 n
 Kurubindas, 129 n
 Kurojāṇḍala, 23
 Kurukshetra, 22
 Kurukshetra, battle of, 40
 Kurus, 12 ff, 21 ff, 25, 41, 68, 73, 233
 Kurush, 239
 Kuruśravaṇa, 23, 25 n
 Kuśadhvasja, 54
 Kuśāgrapura, 111, 208
 Kuśāvati, 126
 Kushāns, 455 ff, 459 ff, 618 ff
 Kushāns (Later), 480 ff
 Kusinārā, 126
 Kuśathala, see Kanauj
 Kusthalapura, 538, 540
 Kusuluka, 444
 Kusumadhvasja, 354

658 POLITICAL HISTORY OF ANCIENT INDIA

Kusumapura, 317
Kuvinda, 143
Kuyula (Kujula) Kadphises, *see* Kadphises I
Knyulakara Kaphsa, 470 n

L

Lagatūrmān, 479 n
Lala (general), 473
Lāla, 331 n
Lālaka, 419
Lalliya, 482
Lampaka, 433
Ladka, 433, *see also* Tāmraparṇī
Lan-shi, 460
Laodike, 335
Lājaviśhaya, 579, 606 n
Lauhitya, Lohitya (Brahmaputra), 597, 625
Lekkhārakas, 320 n
Lekhakas, 333
Liāka, 444, 473, 484
Licchhavis, 83, 118 ff, 122 ff, 211, 401, 530, 605
Lipikaras, 316, 320
Lauṃminigāma, 307
Lyalas, 384, 424

M

Māchalas, 86
Machcha, *see* Matsya
Mādjavika, 623
Madā, 206 n
Mādha Gupta, 593, 601, 605, 609 f, 623
Mādhavaśena, 373
Mādhavarman I, 603
Madhumanta, 91
Madhura, Uttara, 138
Madhvadeśa, Majjimaśeśa, 65, 142, 264, 293, 353, 611
Madhyamika, 253, 337
Madra, Madrakas, 63, 64 f, 152, 250 n, 544 f
Madragāra, 65
Madravañ, 16, 20
Madura, 328
Magadha, 96, 110 ff, 151, 205 ff, 307, 377, 400 f, 420, 629 f, 530 f, 582 n, 603, *et passim*
Magadhapura, 111
Magandiyā, 208
Mazaa, 331 f
Mahābaladhikṛita, High Officer in charge of the Army, 560
Mahābhārataśākhya, 41
Mahābhisheka, 136, 168
Mahābhoja, 314
Mahādāṇḍa-nāyaka, general, 520, 547, 559 n, 563
Mahājānaka I, 57
Mahājānaka II, 57
Mahājānapada, 95 ff
Mahākāntāra, 538 f

Mahākosala (king), 103, 154 f
Mahākhuśhāpāra, 561
Mahāmaṇḍala, 222 n
Mahāmātra, 208, 280, 286, 316 f, 336 ff, 515, 520
Mahānāman, 200
Mahānandin, 218, 223
Mahāpadma (father of Bimbisāra), 117 n
Mahāpadma (Nanda), 231 f, 377
Mahāpratibhāra, 562
Mahārāja, 163
Mahārāshṭra, 314, 483 ff, 542
Mahārathia, 314
Mahāsāmiya, 523
Mahāśena, Pradyota, *see* Chaṇḍa Pradyota
Mahāśena
Mahāśena Gupta, 606 f, 623 ff
Mahāśena Gupta Devi, 606
Mahāśenapati, 371 n, 515, 620
Mahādīkakaṇṭhaka, 213
Mahāśailava, 164
Mahāśiva Gupta, 605 n, 624
Mahāśibhāgarh, 275 n
Mahāśudassana, 127
Mahattara, Mahattarakas, 525, 562
Mahāvīra, 119, 213, 323
Mahendra Maurya, 300, 333, 349
Mahendra (of Kosala), 538
Mahendraditya, Mahendrakarmā, Śrī
Mahendra, *see* Kumāra Gupta I, 566
Mahendragiri, 538 f
Mahendrapāla II (Pratibhāra), 585 n, 631 n
Mahendravarman I, Pallava, 328, 501 n
Mahesvara (sect), 369
Mahesvara Nāga, 480
Mahirakula, *see* Mihirakula
Mahishī, 162, 166, 517, 573
Mahīmatī, 140, 144 f
Mahodva, 180
Maitrakas of Valabhi, 530, 620 f
Makhādeva, 55
Mālava, Mālva, 96, 250 n, 254 f, 260, 494, 489, 515 n, 544, 582, 605 f, 606, *et passim*
Mālavagapa, 544
Malichos, Maliku, 505 n
Mallinī, 107
Malla, Malliki, 95, 126 ff, 219
Mallasākul plate, 633 n
Mallika, 201
Malloi, 254 f
Māmāla, 491
Mambarus, 437, 485
Mandakini, 572 n, 360 n
Mandasor, *et passim*
Māṇḍavya (of Vedic texts), 51
Māṇḍavya (of Epic), 359
Maṇḍala, Maṇḍala, 323, 339
Maṇḍalaśeśa, 585 n
Maṇḍura, 222
Māni, 616 f
Manigol, 444
Manivattappa, 261
Maṇḍhaliputta, *see* Gośāla Maṇḍhaliputta
Manoja, 98

Mānsahra, 307
 Maṇṭarāja of Kaurāla, 538
 Mantrin, 280 ff, 559 f
 Mantripariśad, 281 f, 315 f, 389 f, 560
 Maru, 507, 621
 Marutta, Avikshita, 72
 Masala, 637
 Māski, 303, 357
 Massaga, 261
 Massanoi, 257
 Maṭachi, 45, 70
 Māthara, 476, 638
 Māthava, 77
 Mathurā, Meihora, 138, 381, 401, 468, 481
 Matila, 534
 Matisachivas, Councillors, 509, 520
 Mātrivishnu, 593, 595
 Matsya, 66 f, 137
 Mauakes, Mavaces, 436
 Mauas, 428, 437 ff
 Maukhari, 400, 583, 603 ff, 608 n, 610, 623 ff, 627, 630 ff
 Mauryas, Moriyas, 5 n, 191, 194, 264 ff
 Mayūraposhaka, 266
 Mayūrasārman, 504 n, 604 n
 Medus Hydaspes, 426 n
 Meghas, 532
 Megasthenes, 273 ff
 Meghavarpa, 543
 Mekal-Āmbashṭha, 256 n
 Menander, 381 ff, 423 f, 445
 Meridarch, 319, 512
 Mevaki, Mauakes, Mevaces, 435 f
 Mihirakula, 588, 595 f, 629, 634
 Milinda, see Menander
 Min, 437, 621
 Minnāgara, 435, 453, 485, 621
 Mitanni, 189 n
 Mithradates, Mithridates, 425
 Mithi, 54
 Mithilā, 53, 118
 Mitras, 391, 400 ff, 433
 Mitra coins, 390 ff
 Mitradevi, 589
 Modo-galingae, 94
 Modubae, 94
 Moga, 437
 Mokhalisa or Mokhalinam, 604 n
 Mo-la-po, 629
 Moli, 96
 Molini, 74
 Mopbis, Āmbhi, 248
 Mou-lo-san-pu-lu, see Mūlasthāna-pura
 Mousikanos, 258
 Mousopalle, 637
 Mrigadhara, 202
 Mrigaśikhāvana, 528
 Mrigeśa-varman, 504 n
 Mūchipa, Mūṭiba, Mūvipa, 94
 Muchukarpa, 258 n
 Mudgala, 71 n
 Mūjavats, 60
 Mukhalingam, 89 n
 Mukhara, see Maukhari
 Mūlaka, 143, 491

Mūlasthāna-pura, 619
 Mukuda, 525
 Muṇḍa (king), 218
 Muṇḍas (class of spies), 291
 Muriya kāla, 373 n
 Muruṇḍa, 401, 430, 546 f
 Mūshika, 94, 258 n, 330
 Musikanagara, 419
 Mūtibas, 94
 Muziris, 330

N

Nabataeans, 505 n
 Nābhaka, 309
 Nābhapaṃti, 309
 Nāchne-ki-talai, 541
 Nāga, 145, 413, 468, 480 f, 500 n, 535 f, 555
 Nāgabhaṭṭa, 480
 Nāga Dāsaka, 216, 218
 Nāgadatta, 534
 Nagala Viyohālaka, Nagara-vyāvahārika, 317, 520
 Nāganikā, Nāyanikā, 404 f, 417, 517
 Nagara-bhukti, 560
 Nagarādhyaksha, 285
 Nagaraka, 317
 Nagarākshadarśa, 520
 Nagarāśreshṭhin, 561
 Nāgarjuna, 468, 476
 Nāgarjuni Hill, 351
 Nāgasāhvaya (Hastinapura), 23
 Nāgasena, King, 534 ff
 Nagnajit, Naggaji, Naggati, 146
 Nahapāna, 469 n, 484 ff, 495
 Naigamas, 631 n
 Naimishas, 151
 Nakhavant, 481, 535 n
 Naksh-i-Rustam, 240
 Nalas, 639
 Nambanus, 437, 465
 Nami, Sāpya, 55, 57, 81 f
 Nāpaka coins, 475
 Nanda, 219 n, 224, 229 ff, 375 n, 376 f, 419
 Nanda, Śaka, 547
 Nandi, King, 534 ff
 Nandinagar, 150
 Nandivardhana, 218, 222
 Nandivarman, 501 n
 Nandiyāsas, 536
 Na-pei-kea, 309
 Narasiṃha Gupta, Bālāditya, 588 f, 601 n, 635
 Narasiṃha Varman, 501 n
 Naravarman, 567 n
 Nārāyaṇa Kāṇva, 398
 Nārāyaṇapāla, 403 n
 Narendrachandra, 553
 Narendragupta, 608 n
 Narendrasena Vākāṭaka, 579, 634
 Narendrasimha, 553
 Nāsatyas, 139 n
 Nāsik Prasasti, 491 ff

Nāṭikas, 119
 Nau-Nand-Dahra (Naander), 235
 Nāvadyaksha, 286
 Navananda, 223 f
 Navanara, 496
 Navy, 286, 498
 Navyāvakāśikā, 630, 634
 Nāyaka, 521
 Nāyanika, 404 f
 Nemi, 81
 Nepāl, 53, 509, 530 n, 544
 Neyika, 523
 Ngan-si, 480
 Nichakahu, 43, 70 f, 131
 Nichchhavi, see Lichchhavi
 Nigama, 525
 Nigamapradhānāḥ, 235 n
 Nigamasabdhā, 519
 Nigantṛa Nātaputta, see Mahāvīra, 523
 Nijhati, 337
 Nikāsa, 262
 Nikias, 425 n
 Nilapalli, 540
 Nilarāja, 538 f
 Nimi, 54, 135
 Nipishṭa, 243
 Nirgranthas, 328
 Nirvāpa (of Mahāvīra and Gotama), 213 n,
 215, 228 f
 Nirvāpa Temple, 126
 Nishāda, 507
 Nishadha, 636
 Nishishṭārtha, 253, 320
 Nomarch, 250
 Nyagrodhavana, 194
 Nyasa, 246

Q

Oath (coronation), 163
 Oḍḍavādi, 138
 Oḍḍiyāna, 245
 Odraka, Udāka, 393
 Ohind, 463
 Okkāka, 127, 162
 Omphis, 243
 Ophir, 2
 Orthagnes, 453
 Ousadi, 257
 Oxydrakai, see Kahudraka, 254
 Oxykance, 259
 Ozene, see Ujjain

P

Pabbosa Inscription, 393
 Padmāvati, city, 463, 480, 536 n
 Padmāvati, queen of Ajātasatru, 211
 Padmāvati, queen of Udayana, 203
 Pahlavas, 451 f
 Paithao, see Pratishthāna
 Paithānakes, 311 n
 Pakoree, 454

Pakthas, 241, 253
 Paktyike, 241
 Pakudha, Kachchāyana, 34
 Paladas, 311, 313
 Palasimundu, 330 n
 Pāṅgala (courier), 167
 Pālagall, 162
 Pālaka, 218
 Pāla Kings, 371 n, 473 n
 Pālaka, Pālakkada, 538, 540
 Pālāśikā, 504 n
 Palibothra, Palimbothra, 235
 Palibothri, 310
 Pallava, 500
 Paloura, 305 n
 Pampā, 540
 Pañcha Gauda, 633
 Pañchāla, 90, 134 f, 151, 233, 391
 Pañchamaka, 223
 Pān-chiao, 474
 Pāṇḍava, Pāṇḍas, 33, 40 f, 147, 329, 544
 Pandion, 456 n
 Pāṇḍugati, 226
 Pāṇḍuka, 236
 Pāṇḍya, 328, 421
 Pāpiyagharika, 523
 Panku, 455, 459
 Pantaleon, 422
 Para Ātṛāra, see Ātṛāra
 Pāradae, 313
 Parākramāśoka, 533, 550
 Paramadivata, 559
 Pārameshṭhya, 163
 Pāraamudra, 330
 Pārasika, 505 n, 623
 Parasūratna, 414
 Parikshit, 12 f, 27 f
 Pārikshitas, 12 f, 46
 Parimitārthah, 320
 Parishad (Parishā), 174 f, 230 n, 231,
 313 f, 341, 525
 Parivakrā, Parichakrā, 71
 Parivrajaka Mahārājas, 542, 595
 Parivrajikās, 291
 Parivṛkṣi, 162
 Pāriyātra, 491
 Parkham Statue, 214 n
 Parpadatta, 579 f, 629
 Paropaniśadai, 273
 Paros, 139
 Pārva (Buddhist), 475
 Pārva, Jina, 97
 Pārtha of Kāmīra, 449 n
 Parthalia, 305
 Parthians, 425, 429
 Parushni, 63
 Pasonadi, see Prasenañjit
 Patala, Patalene, see Taula, 259, 331, 446
 Pātāliputra, 217, 234, 274 f, 239, 307, 310,
 351, 401, 473, 530, 543, 557
 Patānchala, 65
 Patika, 444, 447 f, 484
 Pativedaka, 316, 320, 337
 Patna Statues, 218 n, 223 n
 Patrokles, 299

- Paudanya, 143 n
 Pāṇḍavai, wife of Ajātaśatru, 211
 Paurava, 23, 249
 Paura Vyāvahārika, 317
 Paushkarnādi, 34
 Pāvā, 127
 Pavvaiyā, 629
 Pāyāsi, Chief of Satavyā, 165
 Pedda-Vagi, 540
 Perimuda, 328 n
 Periyar, River, 330
 Persians, 239 f
 Pettanika, Pittinika, 311
 Peukelaotis, 247
 Peukalaos, 425
 Phagala (Phagens), 252
 Philadelphos (Ptolemy, II), 299
 Philippos, 262
 Philoxenos, 425
 Phraotes, 451
 Phryni, 381
 Pihunda, 420
 Pimprama, 250
 Piṇḍola, 203
 Piṅgala, 289
 Pippalāda, 79
 Pippalivana, 194, 267
 Pīprāwā, 191 n
 Pishāpura, Pīṭhapuram, 583 f, 633
 Pithundā, Pitundra, 420
 Piyadasi, see Aśoka
 Podiyil Hill, 269, 310
 Po-ho, 63
 Pokharapa, 534 f
 Poling, 305 n
 Polyandry, 41
 Poros, 249, 252 n
 Portikanos, 259
 Po-ta, 456, 460
 Potali, Potana, 80, 98, 143
 Po-t'iao, 464, 479
 Pounnata, 637
 Prabhākara, 661 n
 Prabhākaravardhana, 605 f, 605 f, 608
 Prabhāvatī (of Utkala), 137
 Prabhāvatī (Guptā), 584
 Prachānta, see Pratyanta, 315, 326, 543
 Prāchināsāla, Anpamanyava, 64
 Pāchya, 156, 268
 Prāchya Paścāllas, 71
 Pradeśas, 317 n, 560
 Prādeśikośvara, 319
 Pradeshris, 303, 319
 Pradesikas, Pradesikas, 316, 319, 336
 Pradyota of Avanti, 114, 146, 204
 Praesti, 259
 Prakāśāditya, 597, 591 n
 Prakāśāditya, 588, 596 n, 597 n, 633 n
 Pramagaṇḍa, 113
 Prapaya, 9 n, 509, 522
 Prārjunas, 544 f
 Prasenañjit (Pasanadi), 103 f, 154 f, 199 f, 210
 Prasenañjit, successor of Kākavarṇin, 222 n
 Prasians, Prasii, 236, 251, 310
 Prānīputra, 51
 Pratardana, 75, 83, 93
 Prathama-Kāyastha, 861
 Prathama-Kulika, 661
 Pratihāras, 631
 Pratipa, 13
 Pratishphāna, 311 n, 369, 415, 495
 Pratiśarvas, 13
 Pravāhana Jaivali, see Jaivali
 Pravarasena I, 541 f
 Pravarasena II, 564, 579
 Pṛathivīahepa I, 541 f, 554
 Pṛathivīahepa II, 541
 Pṛithivīahepa, mantṛin, 559 n, 587
 Priyaka, 219 n
 Proti Kauśāmbaya, 69
 Ptolemy Philadelphos, King, 331 f
 Puā-d seu, 464
 Pugār, 323
 Pukkuśāti, 147, 227
 Pulakeśin II, 323, 585 n
 Pulika, Pūpika, Pūpaka, 146
 Pulindas, 94, 313
 Pūṣā, 316, 399
 Pulumāvi of Sātavahāṇihāra, 412
 Pulumāvi of Baithana, 495 f
 Pūnarabhisheka, 163, 167 f
 Pundranagara, 275
 Puṇḍravardhana, 310, 453, 560, 593, 597 f, 631
 Pūpphavatī, 74
 Pura Gupta, 560, 572, 585 f, 593
 Purikā, 396
 Pūrpavarman, 553, 523 n, 609, 624
 Purohita, 165, 359
 Pūru, 23 f, 249
 Purukuta, 100
 Purūras, 25
 Purnashapura, 473 f
 Pūrva-Mālava, 582 n
 Pushkara, 484
 Pushkarana, 534 f
 Pushkaiavati, 60, 247, 260, 492, 425, 444
 Pushpapura, 354, 461, 443
 Pushyabhūti, 583, 604 n, 606 f, 606 n, 627
 Pushyadharman, 350
 Pushyagupta, 271, 269
 Pushyamitra (King), 350, 360 n, 361, 398 f, 399, 429
 Pushyamitras, 563 f, 575 f, 627
 Pustapala, 563

R

- Rājha, Rājhapuri, 331 n, 602
 Rādhagupta, 303
 Raghu, 511, 540
 Rahmasala, 213
 Rahasyādhiprita, 590
 Rāhula, 103
 Rājagriha (Kekaya), 62
 Rājagriha (Magadha), 63, 106, 110, 111, 116, 309, 320, 374, 490

662 POLITICAL HISTORY OF ANCIENT INDIA

- Rājagriha (Balkh), 63
 Rājākarti, Rājakṛit, 163, 173
 Rājālipikara, 520
 Rājāmātya, 521
 Rājan, 53, 159
 Rājapura (Kaliṅga), 89
 Rājapura (Kamboja), 148 f
 Rājaputra-deva-bhaṭṭāraka, 561
 Rājāsāsana, 279
 Rājāsitha, 527
 Rājāsūya, 139, 165 f
 Rājātirāja, 516
 Rājavaidya, 520
 Rājaviśaya, 310, 315
 Rājayuktas, 316 n
 Rājyugābhaka, 318
 Rājukas, Rājukas, 286, 287, 318 f, 306,
 306 n, 515, 520
 Rājula, Rājuvula, 445 f
 Rājyaśrī, 608
 Rājyavardhana, 553, 604 n, 606 n
 Rāma, 78, 101
 Rāmagāma, 191
 Rāma (Sarma) Gupta, 553 n
 Rāmapāla, 585
 Rauma, city, 74
 Rapa-Bhāṇḍagār-ādhiparaka, 563
 Rashada, 291
 Rāshṭra, 12, 523
 Rāshṭrakūṭas, 631
 Rāshṭrapāla, King, 236
 Rāshṭrapāla official, 317
 Rāshṭrapati, 523
 Rāshṭrikas, 311 f
 Rāshṭriya, 289, 316 n
 Rathagṛīva, 44
 Rathika, 290 n, 311 f, 315
 Ratna, 168, 173
 Ravideva, 371 n
 Raṇu, 87, 89, 144
 Republics, 121, 128, 134, 137, 140, 150, 173,
 191 ff, 245 ff, 515, 544 f
 Revottaras Pātava Chākra Sthapati, 175
 Riksha (mountain), 145 n
 Rishabhadatta, see Ushavadāta
 Rituparna, 101, 103
 Roads (Maurya), 294, 343
 Rohini, 192
 Romakas, Rome, 4, 462
 Roruka, 197
 Rudrabhūti, 509
 Rudradāman I, 9 n, 304, 467, 485 f, 496,
 505 ff, 618 ff
 Rudradāman II, 510
 Rudradeva, 534
 Rudradhara Bhaṭṭāraka, 509
 Rudrasena I, Kshatrapa, 510
 Rudrasena II, 510
 Rudrasena III, 511
 Rudrasena (I) Vakātaka, 534, 541
 Rudrasena II, 541, 554
 Rudrasimha I, 509
 Rudrasimha III, 510 f, 543 n
 Rudrayaga, 197
 Rummindol, 309, 342
 Rūpadarśaka, 385
 Rūpnāth, 313
 S
 Śāba, 555, 559
 Sabarua, 93
 Sabbamitta, 105 n
 Sabbatthaka, 208
 Sacarauli, 426
 Sachiva, 280, 372, 555
 Sadānirā, 52
 Saffarids, 482
 Sāgala, Sāgalanagara, 64, 65 n, 381, 422,
 545, 629
 Sahadeva Śārājaya, 121
 Sahaja, 137
 Sahajāti, 129
 Sahalāṭari, 538 n
 Sahāli, 222, 236 n
 Sahasrāṅga, 132
 Saivism, 464, 478
 Sai-wang, 431 f
 Saka (people), 3, 426 f, 431 ff, 505 ff
 Saka era, 29, 469 n, 618 f
 Śākala, see Sāgala
 Śākalya, 65
 Saka Murugda, 545 f
 Sakasthāna, 434 f, 479, 483, 621
 Śāketa, 99, 105, 378
 Śakraditya, 501, 570 f
 Śakti-Kumāra, Śakti-Sri, 417
 Śākya, 102
 Śākya, 99, 155, 191
 Śakkenoi, Śalankāyanas, 500 n, 649
 Śāliśūka, 350, 352
 Śālivāhana, 403 n, 466 n
 Śāltas, 68, 151
 Samāchāradeva, 639
 Samāharti, 293, 319, 531
 Samājas, 326, 334 f, 366 n
 Samāpa, 306, 311
 Samatāta, 310, 632
 Sambhuttara, 96
 Sambodhi, 339
 Sambos, 259
 Saṁchārasthaka, Saṁchārīn, 291, 515, 526
 Sāṁdhivigrahika (Minister of Peace and
 War), 522, 580
 Saṁgrahitṛi, 166
 Samiti, 174
 Saṁkara-gaṇa, 631
 Samkasa (Sāṁkṣāya), 54, 108
 Saṁkashobha, 580, 595
 Samprati, Sampadi, 351 f
 Samrāj, Samrāt, 58, 159
 Sāmrajya, 157 f
 Saṁsthāp, 291
 Saṁtanu, 25
 Samudra Gupta, 463, 482, 533 ff
 Samudra Vijaya, 114
 Sanabaras, 454
 Sanakānīkas, 544 f

- Sandanes, 483
 Sandrokottos, see Chandragupta, Maurya.
 Sangous, 260
 Sangala, 251
 Saṅghadāman, 510
 Saṅghamukhya, 140
 Saṅgharaksha, 476
 Saṅgrahapa, 233 n
 Sañjaya of Magadha, 222
 Sañjaya of Pañchāla, 137
 Sañjaya of Pushkarāvati, 260
 Sañjaya (Śāta), 166 n
 Saṅkaragapa, 631
 Saṅkhyāyaka, 285
 Sāṅkhyāyana, (Gupākhyā), 33 f
 Sannidhātṛi, 165, 294, 521
 Sapodanes, 454
 Sarabha, 246
 Saragous, 415, 483
 Saravarma, 603 n
 Sārṅgulavarman, 603 f
 Sarpikā, 99
 Sārthavāha, 561
 Sarvabhauma, Sarvabhūmi, 37, 163, 170
 Sarva-kshatrīntaka, 233, 554
 Sarvanāga, 537, 561
 Sarvajñas, 222
 Sarvarāi-ochchettā, 533 f, 551
 Sarvastivādin School, 616
 Sarvaśāta, 398 n, 543
 Sarvavarma, 605 n, 623
 Śaśana-hara, 320
 Śaśāka, 608 f, 633 f
 Sasa, 445, 454
 Sassanians, 479, 510, 623
 Sātadhanvan, Sātadhanno, 350, 352
 Sātahapirāthas, 412, 523
 Śātakarṣi I, 406 ff, 410 n, 548
 Śātānika, of Kauśāmbī, 132, 202
 Śātānika Sātrājita, 44, 75, 97, 162
 Śātānika, son of Janamejaya, 43, 50
 Sātavāhana, 395, 403 ff, 433, 483
 Sātavāhani-hāra, 412, 623
 Satavastra, 454
 Sattvanetra, 329 f
 Sātrāsaha, 71
 Satri, 291
 Sattabhu, 87, 144, 170 n
 Sātvas, Sātvasas, 26, 87 n, 90, 138 ff, 142
 Satyayajña, 50, 54, 69
 Saubhūti (Socothos, Sophytes), 251 f
 Saudumni, 25
 Saunaka, Indrota Daivāpa, 17, 18, 36, 44, 50
 Saunaka Kāpeya, 44
 Sauvira, Sovira, 2, 197, 507, 619
 Savaras, 93 f
 Sāvasthi (Śāvastī in Kosala), 99, 105, 198, et passim, 633
 Scylax, 241
 Scythian Administration, 514 ff
 Selenkos, 271 ff, 299
 Senāgopas, 521
 Sena king, 192
 Senānāyaka Mahāmāttas, 208
 Senāni, 166
 Senapati, 202, 278, 320, 521
 Seniya, 205
 Seres, 361
 Seri, 92
 Setakappika, 412
 Setaryā, 92, 155
 Seyanāga, 211
 Seyaviya, 64
 Shāhān-Shāh, 518
 Shābhāgarhi, 307
 Shapur II, 479 n, 481, 511
 Sibi, Siboi, 66, 95 n, 252 f, 257
 Sikipura, 253
 Sibirios, 274
 Siddhārtha, father of Mahāvira, 119
 Siddhārtha (Buddha), 102
 Sigal, 428 n
 Sigerdis, 361
 Sihapura, 130
 Sikkapdin, 73
 Sikkharastāmin, 559
 Śilāditya Dharmāditya of Mo-la-po, 606 n, 629 n
 Silaka Salāvatiya, 74
 Silavat, 209
 Silavati, 162
 Śrīhachandra, 533
 Sihhala, see also Ceylon, 547
 Sindhapura, 89
 Sindhāsana, 295, 298
 Sindhavarman (Mandasor), 535
 Sindhavarman (Pallava), 501 n
 Sindhā Vikrama (Chandra Gupta II), 533
 Sindhavishnu, 501 n
 Simuka, 403 ff, 416
 Sindhu-Sauvira, 257, 467, 507, 618 ff
 Singapuram, 89 n
 Sinthos, 435
 Sin-tu, see Sindhu, 620
 Stradhvaṛa (Janaka II), 54, 56, 80
 Śrī-Vaddha, 202
 Siskottos (Sasigupta), 260
 Sūnāga (Susanāga), 115, 219 f
 Sūsanandi, 396, 536
 Siānpāla, 180
 Sita, 78
 Śiva (worship of), 322 n, 464, 568
 Sivas, Sivas, see Sibi, Siboi
 Śiva-Bhāgavata, 464
 Śiva-datta, 499 n
 Śiva Gupta, 526
 Sivalakura, 503
 Śivamegha, 531
 Śiva Nandi, 536
 Sivapura, 253
 Sivaseña, 444
 Śiva-Skanda-Datta, 524
 Śiva-Skanda-Gupta, 503
 Śiva-Skanda-Nāga Śrī, 503
 Śiva-Skanda-Varman, 548
 Śiva-Śrī, Āpilaka, 409, 497
 Sivi, 176, 252 f
 Skanda (God), 322 n
 Skanda Gupta, 481, 560, 572 ff, 638
 Skanda Nāga, 483

- Skanda Nāga Sāteka, 407, 503
 Skandasvāti, 407, 523
 Skandavarman, 501 n
 Slaves, 268, 276 n, 339
 Soastus, 247
 Sodasa, 446
 Sodrai (Sogdoi), 257
 Sogdiana, 244, 426 f, 486
 Soked (Sāketa), 473
 Solaki, Solāki, 603
 Solar race, 99
 Solasa Mahājanapada, 95 ff
 Somadeva, 623
 Somakas (tribe), 73
 Somaka Sāhaderva, 82, 86, 121
 Somasārman, 360
 Soṇa, 274 n
 Soṇa dēḍa, 207
 Soṇa Kolivisa, 174
 Soṇa Sātrāsāha, 71
 Sonhon the Indian, 613
 Sophagasena, see Subhāgasena
 Soohytes, see Saubhuti
 Sothiṣena, 76
 Sothivattinagara, 129
 Sovira, see Saṇvira
 Spalagadama, 428
 Spalahora, 428
 Spallises, 428, 440
 Spies, 298 f
 Sramana Mahāmātra, 340 n
 Śrāvastī, see Śāvatthī
 Śrāvastī bhukti, 680
 Srenika, 205
 Sreṇa, 115, 205
 Sreethikārtthavāha-kolika-nigama, 563
 Śrīdhara-varman, 457
 Śrī Gupta, 523 f
 Śrī Haridāsa, 528
 Śrīpaṇtha, 582, 606
 Śrīmāra rāṣa (kings of the family of), 103 n
 Śrinagarī, 309
 Śrīṣṭava of Vaiśālī, 123
 Śrīṣṭava (tribe), 26, 40 n, 71 f
 Śrī Prāṇa, 568 n
 Śrīnara, 533
 Śkrāva, 92
 Śrī Śita, 415
 Śrī Viṣva, 92 n
 Śrī Vikramah, 556
 Śrī Vira Puruṣadatta, 500 n
 Śrī Viśava, 92 n
 Śrūta coins, 536
 Śrīhānika, 293
 Śhānva, 293 n
 Śhanatī, 167 n
 Strategos, 443, 515
 Strato, 384, 386 f, 423
 Strvāthyakaba, 517
 St. Thomas, 453 n, 453
 Suari, 93
 Subābu, 197
 Subandho, 293
 Subhāgasena, 350, 361 f
 Suchivṛkha, 44
 Sudakshipa, 150
 Sūdās, Suddasa, 73
 Sudarāṇa Lake, 271, 580
 Sudarāṇa-pura, 145
 Suddasana, 74
 Suddhodana, 102
 Sūdra kings, 355
 Sūdra (Sodrai of Alexander) (tribe), 267, 498 n, 545 n
 Sūdraka, 321, 533
 Sugāṅga palace, 275 n
 Sui Vihār, 435, 455, 467, 618 ff
 Sniveshtha, see Vasujyeshtha, 392
 Sukalpa, 236
 Sukeśā Bhāradvāja, 79, 103
 Suketuvarman, 367
 Sulehamāva, 610
 Suktimati, Suktisāhaya, city, 129
 Suktimati river, 129
 Suktidēśa, 560
 Sūfikas, 602 f, 604
 Sūka, 521
 Samana, 300
 Samantra, 165 n
 Samati of Vaiśālī, 120
 Samātra, 92 n
 Samanmāragiri, 133, 193
 Sanahāpa, 165
 Sanakkhatta, 124
 Saṅga, 369 ff, 393 ff
 Saṇḍ-vaṇ, 460 n
 Saṇḍha, 212
 Saṇḍha, 130
 Saṇḍan Sārāṇa, 120
 Sārasenas, Sārasenakas, 63, 138, 142 f, 151, 197, 224
 Saṇḍhira, 270, 288, 297, 314, 321, 434, 446, 491, 506 f, 546
 Saṇḍmlechandra, 593
 Sārāṇaka, 484, 507 n
 Saṇḍdhana, 74
 Sārva-varman, 605 n
 Sārman, 393, 403
 Sashena, 16
 Saṇḍkaletra, 303
 Saṇḍma, 303 f
 Saṇḍhita-varman, 583, 607, 609, 623
 Sāta, 163, 166, 173, 174
 Saṇḍasoma, 134
 Saṇḍabhūmi, 107, 333
 Saṇḍnagiri, 288, 307, 311
 Saṇḍatu (Swāt), 245, 247
 Saṇḍākha, 508
 Saṇḍas, 350
 Saṇḍha, 507, 621
 Saṇḍidatta, 538
 Saṇḍāva, 157 f
 Saṇḍra, 147
 Saṇḍa, 233, 304, 309 n
 Saṇḍamvara, 576
 Saṇḍaketu, 49, 62, 74, 174
 Saṇḍikā, 99
 Saṇḍonloi, 283
 Saṇḍroi, 283
 Saṇḍtrane, 446

T

Ta-hia, 427, 479
 Takka country, Cha-ka, 619
 Takahadilā, Taxila, 36 f, 59, 61, 146, 247 f, 275, 287, 307, 309 n, 363, 422, 446 f
 Talarara, 583
 Taxila University, 62
 Tālagund, 500 n
 Talaśaṅghaa, 178
 Tambapaṇṇi, Tāmraparṇi, 330
 Tāmraparṇi, river, 331
 Tāmralipti, 558
 Taprobane, see Tambapaṇṇi
 Tathāgata, 3
 Tathāgata Gupta, 588, 595
 Tazala, 259
 Ta-yue-tchi, see Yue-chi
 Tel or Telavāha, 92
 Telephos, 425 n
 Terebinthus, 617
 Thāesar, 606 f
 Theodamas, 429 n
 Theōdora, 516 n
 Thullakopphita, 128
 Tianshan, 504
 Tien-tchou, 429, 464, 479
 Tikhapa, 291
 Timitra, 382
 Tirabhukti, Tirhut, 52, 560 f
 Tirabhukty-Upārik-ādhikaraga, 568
 Tiāya, 200
 Tiāyarakahitā, 367
 Tiase, king of Ceylon, 331
 Tivara, 343, 349
 Tochari, 426 f
 Togara, 602 n
 Toramāpa, 561, 595 f, 629
 Tosali, 298, 306 n, 308, 311
 Too-mi, 455, 460 n
 Traikūṭaka, 499 n
 Traikūṭaka Era, 468
 Traṇakeyiro, 417
 Traśadasyu, 101
 Trigartaa, 68
 Trikamala, 400
 Trikoṭa, 580
 Triparvata, 504 n
 Tripuri, 129
 Tripuri Viśhaya, 560, 595
 Triśālā, 123
 Triśāma, 580 n
 Tsang-Huang, 468
 Tsang-ling mountains, 474
 Tukhāras, 148 n, 427
 Tulakuchi, 223 n
 Tulaa, 329
 Tumain, Tumbavara, 567
 Tupdikeras, 146
 Tura Kāvaabeyā, 13, 15, 17, 19, 32
 Turamāya, 332
 Turghaa, 22
 Turva, 425
 Turvaśa, 71 f
 Tushāspa, 263, 280, 304, 314, 508 n
 Tuthila, 523

U

Ubbhaṭṭaka, 127
 Ubarae, 94
 Ubbaka, 222
 Uchchaṭṭaravas, 25, 28
 Uchchaṭṭiṅgi, 504 n
 Udaka, 393
 Udakasena, 68 n
 Udānakūpa, 560, 563
 Uddāhita, 291
 Udaya of Kāsi, 76, 98 n
 Udaya, Udayabhadda, Udayin of Magadha, 216, 217 f
 Udayana, 47, 202 f
 Uddālaka, Arupi, see Arupi
 Udichyas, 68, 157
 Udyāna, Oḍḍiyāna, 246
 Ugra, Ugraputra, Ugras, 120 and note
 Ugrasena, Mahāpadma, 231 ff, 289, 293
 Ugrasena of Palakka, 538
 Ugrasena Pārikahita, 16
 Ujjain (Ujjeni) Viśālā, Padmāvatī, Bhoga-vatī, Hiranyavatī, 275, 287, 298, 307, 382, 384, 434, 505, 557, 596 n
 Ukkachellā, 110 n
 Ukkatṭha, 99, 198
 Ukkāvelā, 110 n
 Una, 246 n
 Upachara, 130
 Upagupta, 591 n
 Upaguptā, 591 n, 604
 Upaplayya, 67
 Uparichara, 130
 Uparika Mahārāja, 561
 Urāgapura, 328, 541
 Urayūr, see Urāgapura
 Uraśā, 248, 447
 Uravelakappa, 128
 Ushasti Chākṛāyapa, see Chākṛāyapa
 Ushavadāta, 484 ff
 Uśnara, 65 f
 Utkala, 137, 696
 Uttamābhadras, 489, 155 n
 Uttamanjas, 73
 Uttarāśhyakabha, 295
 Uttara Kuroa, 64, 157
 Uttara Madra, 64, 157
 Uttara Paśchāla, 70, 134
 Uttarāpatha, 59, 308, 420
 Uttara Tosala, 306 n
 Uvima Kavithaa, 462

Y

Yachabhūmika, 316, 320
 Yachchha, see Yates, 131
 Yāhlikas, Bāhli, 25, 535 n
 Yaichitravīrya, see Dhritarāshṭra Yaichitra-vīrya
 Vaidehas, Later, 80 f
 Vaidehiputra, Vedehiputta, 132, 206 n
 Vaidya, 256 n
 Vaigai, 328
 Vaihāra, 111

- Vajrayanti, 492, 502, 504 n
 Vainyadevi, 586
 (Valjaya Gu(p)ta), 596 n, 601 n
 Vairāja, 156 f
 Vairocana, 108
 Vaisali, 118, 206, 211, 219, 531, 552
 Vaisālīka Dynasty, 120 f
 Vaisāly-ādhisthān-ādhikarapa, 563
 Vaidampayana, 7, 18, 39, 41
 Vaidravapa, 218 n
 Vajapeya, 159, 163 f
 Vājshika, 465, 477
 Vajrā, 201, 210
 Vajji, 83, 118 f, 212
 Vajra, 568, 597
 Vākātaka, 541 f, 551, 564, 576, 612, 634
 Valsabhi, 680, 626, 629 f
 Valavi, 561
 Vāmadeva, 82
 Varnataksha (ma ?), 459 n
 Vamba Moriyar, 270
 Vamsā, see Vatsa, 131
 Vamsadhara, 89 n
 Vanshpara, 473
 Vansavasi, 602 n
 Vansa, 106, 309 n, 331 n, 585 n, 603, 624
 Vapiyagāma, 198
 Vanji, 330
 Vaska, 105, 154
 Vāṣkaḥ, 628
 Varadā, 373
 Varadātaka, 86
 Vārakamāṇḍala, 680, 684
 Vārāpsi, see Bhārāpsi, 74, 96, 134
 Vārāṇasī, 134
 Vardhamānabhatti, 680, 684
 Vardhamāna, see Nigantha Nātaputta
 Mahāvira, 119, 215
 Varhran, 479 n, 481, 510
 Varmana, 605 n, 624
 Vārebaganya, 5
 Vāsas, 65, 131 f
 Vāsabha-Khattiyā, 200
 Vāṣāti, 257
 Vāsavadattā, 202
 Vāsetṭhas, 127
 Vāsishka, 465, 477
 Vāsishka Dynasty, 543
 Vāsishthiputra Chatrapana Satākapi, 496
 Vāsishthiputra Ehuvala Chāntamūla, 500 n
 Vāsishthiputra Pulunāyi, 410 n, 492 f
 Vāsishthiputrā Siva Sri Satākapi, 496
 Vāsishthiputra Sri Chagga Sati, 497 n
 Vāsishthiputra Sri Satākapi, 496, 507
 Vas Kushāpa, 464 n
 Vassakāra, 212
 Vasebandhu, 564 n, 587
 Vasa of Chedi, 113, 130
 Vasudāna, 132
 Vasudeva Kāva, 392, 395, 398
 Vasudeva Kṛishpa, see Kṛishpa Vasudeva,
 141, 394, 478
 Vasudeva Kushān, 468, 478
 Vaso Jyeshtha, 392
 Vasuladattā, see Vāsavadattā
 Vasumati, 111
 Vasumitra, King, 379, 388, 393, 475
 Vasumitra, sage, 478
 Vastāvi, 538 n
 Vatsa, Varsa, 131, 192, 201 f
 Vāṭayāna, 408, 526
 Vāvātā, 162
 Vayurakeshuta, 561 n
 Vedebaputta, 76
 Vedebiputta, 296 n
 Vedhas, 104
 Vehalla, 209 n, 211
 Vejayanti, 491 n
 Vengi, 600 n, 538 f
 Vesali, see Vāsāli
 Vespasi, 473
 Vessantara, Prince, 178
 Vējhadipa, 193 and note
 Vicitravirya, 302
 Vidagdha, Sakalya, 58
 Vidarbha, 86 f, 91, 148, 372 f, 602 n
 Videgha, Māthava, 54, 77
 Videna, 48 f, 52 f, 74, 80 f, 118, 132, 200 n
 Vidisa, 369 f, 393 f, 396, 460, 555, 606 n,
 609
 Viṇḍabha, 200, 211, 323 n, 537 n
 Vigatāsoka Tishya, see Tishya
 Vigatāsoka II, 390
 Vighnāpala, 223 n
 Vinārayātrā, 323
 Vijaya (conquest), 327, 365, 537
 Vijaya (prince), 530 n
 Vijaya Buddha Varman, 519
 Vijayakirti, 468
 Vijayamitra, 445
 Vijayesa, 306
 Vikrama era, 465 f, 472 n
 Vikramāditya, Chandragupta II, 563 f
 Vikramāditya of Ayodhya, 586
 Vikramāditya (Skanda), 577
 Vikramāditya Sakāri, 465 n, 556, 596
 Vikrama, Puru (Buddha ?) Gupta, 596
 Vilivāyakura, 502, 637
 Village Administration, 203, see Grāma
 Vima Kadphises II, see Wema
 Vinala-Kopḍahā, 209 n
 Vimanadasana, 340 n
 Vināsana, 545
 Vinayāditya, 611
 Vinayakapala (Pratihāra), 585 n
 Vinaya-sūtri-sūpaka, 563
 Vindhyaśaki, 541
 Vipśā, 380 n
 Vira Choda, 16
 Virakūcha, 501 n
 Vira Matasya, 67
 Virasena, 371, 390 n
 Virasena Maurya, 360, 361
 Virasena, Sāha, 555, 559
 Viraṭa, 67, 187
 Virāṭanagara, 67, 187
 Viravarman, 601 n
 Visudeva, 528

Viśakha, 323 n
 Viśakhaśatta's Mudrārākahase, 563
 Viśakhayūpa, 220 n
 Viśāla, King, 120
 Viśāla (Ujjain), 557
 Viśāla (Vaidālī), 120
 Viśāpina, 253
 Viśaya, 321, 523, 537, 560
 Viśayapati, 534, 537, 561
 Viśva Worship, 568
 Viśvugopa, 538
 Viśvugopa (of Pālakkada), 519
 Viśvugupta, Chandraditya, 611
 Viśvukada-Chetu-Kulānanda Satakarni, 503
 Viśvukundin, 500 n, 602, 638
 Viśvumitra, 401
 Viśvupada, 106
 Viśvupalita, 524
 Viśvuvardhana, 585 n, 631 n
 Viśvī, 9 n, 284 n, 514
 Viśvakṣena, 98 n
 Viśvasiṃha, 510
 Viśvavarman, 567 n
 Viśabhaya, 507 n
 Viśabhavyas, 98
 Viśaṅkapura, 106
 Viśastātra, 308
 Viśihotras, 146, 233
 Viśārika Mahāmāttas, 209, 286
 Vekkaṇa, 602 n
 Vonones, 427 f, 622
 Vraja, 320
 Vratya, 112, 123, 127, 142
 Vriddhadyumna, 44
 Vrihaspati (King), 350, 352
 Vrijika, 309
 Vriśala, 295 n, 355 n
 Vriśalla, 291
 Vriśasena, 350
 Vriśnis, 140 ff
 Vyaghra-bala-parākrama, 566 n, 569
 Vyaghra-deva, 541 f
 Vyaghra-parākrama, 550
 Vyaghra-rāja, 538
 Vyaghra-sena, 409 n
 Vyāpita, 524
 Vyāvahāra samatā, 358 f
 Vyāvahārika Mahāmāttas, 208, 286
 Vyāsa, 49
 Vyūṣha, 341 n

W

Wardak, 435

Wei, 454
 Wema Kadphises, 463 f, 470
 Wu-sun, 458
 Wu-t'-ou-lao, 432

X


Xandrames, 233, 296, 519 n
 Xathroi, 257/
 Xerxes, 242 f

Y

Yahou, Yavuga, 480
 Yādava, Yada, 138, 145
 Yaśasena of Vidarbha, 373
 Yaśasena of Pañchāla, 73
 Yajña śrī, 497 f, 502
 Yājñavalkya, 49 f
 Yajnavarman, 608
 Yaśaskara, 592
 Yaśodāman, 510, 513
 Yaśodharman, 595 ff, 601, 625, 630
 Yaśomati, 573
 Yaśovarman, 588 n, 611
 Yandheya, 250 n, 467 f, 508, 515 n, 544 f, 619, 621
 Yanna, Yavana, Yona, 3, 5, 307, 354, 366, 373 ff, 397
 Yauvarkīva, 519
 Yavātī, 25, 63
 Yavatīnagarī, 539 n
 Yen-kao-tchen. see Wema Kadphises
 Yin-mo-fu, 432, 439, 466
 Yonaka, 424, 433
 Yaśmotka, 487, 506
 Yudhiśthira, Yudhithila, 40, 81, 133, 166
 Yuch-chi, Yü-ch (Yü-ti, Yoo-tchi), 427, 431, 468 ff, 473
 Yuktas, Yutas, 316, 319 f, 336
 Yung-ku, 432
 Yuva Mahārāja, 519

Z

Za Haksle, Zoscales, 505 n
 Zeda, 473
 Zelonises, see Jihonika, 462
 Zollos, 422
 Zoroastrians, 276, 475, 615



SOME ADDITIONS AND CORRECTIONS

Page	Line	
148	fn1	Add "in the Pāla-Pratihāra age they are also found in Pehoa (Ep. Ind. I. 247) and Bengal.
240	4	For contact between the Medes and India, see <i>India Antiqua</i> , 1947, 180ff.
	28	(Satrapy of Indus was formed before 513 B.C., Olmstead, <i>History of the Persian Empire</i> , p. 145. Some scholars believe that the conquest of Sind preceded Scylax's exploration of the Indus— <i>India Antiqua</i> , p. 181).
241	24	after 'was' add 'at first'.
241	28	There is no reason to believe that the Indian satrapy of Darius refers to Sind or to some small territory to the west of the Indus. The account of Herodotus III. 94-98 seems to suggest that it extended eastwards beyond the Beas as far as the river Sarasvatī which flowed past the Marudhansu in the days of the Mahābhārata (see 22n 2 ante; cf., "desert beyond the Beas, ANM, p. 16) and finally disappeared in the sands of Rājaputāna. "Eastward of India lies a tract which is entirely sand . . . the Indians dwell nearest to the east, and the rising of the Sun. Beyond these the whole country is desert on account of the sand." The Sattagydiāns, the Gandarians, the Dadicm and the Aparytāc, constituted the seventh satrapy and the Indians the twentieth (Herod. III. 91-94).
262		The completion of Nikāia is doubted by Tarn (<i>Alexander the Great</i> , II, 238),
262		The confluence of the Indus and the Akseines was fixed as the boundary of the Upper and Lower Indus satrapies,
262		Nikāia and Boukephala stood one on each side of the Jhelum. Tarn thinks (<i>Alexander the Great, Sources and Studies</i> , p. 236) that "Boukephala stood on the east bank of the Jhelum and Nikāia on the west bank (<i>ibid</i> p. 238).
265		After his (Sandrocottus') victory he forfeited, by his tyranny, all title to the name of a liberator, for he oppressed with servitude the very people whom he had emancipated from foreign thralldom (Justin). The tyranny of the <i>dushāmātyas</i> is known to Indian literature. But the sovereign himself is noted for his justice in early Maurya times.
273	18	Dr. G. C. Raychandhuri draws my attention to an Aramaic inscription of Devānampiya found at Laghman (ancient Lampāka,

670 SOME ADDITIONS AND CORRECTIONS

Page Line

BSOAS, Vol. XIII, pt. I, 1949, 80ff). This confirms the Greek evidence about the inclusion of Kābul and its neighbourhood within the dominions of the early Mauryas.

277 For the date of the *Arthashastra*, see also Raychaudhuri, *The History and Culture of the Indian People*, Vol. II, ed. by R. C. Majumdar, pp. 265-67.

301-2 For the date of Aśoka, see Raychaudhuri, *History and Culture of Indian People*, Vol. II, 92ff; for the views of Eggermont, *Acta Orientalia* (1940) 103ff. For the views of Filliozat, see *Manuel des études indiennes*, Vol. I, pp. 913-19. Filliozat prefers the Jaina date 313 B.C. for the accession of Chandragupta, ignoring not only the evidence of the Ceylonese Chronicles but also the fact that the Jaina verses refer to the commencement of Maurya rule in Avanti, not in Magadha or the Indus Valley. For the date of Magas, see also Cary, *A History of the Greek World*, 393ff.

337 For the *Aśoka chakra*, see IC, XV (1948-49), pp. 173ff.

354 5 Cf. Strabo, XV. I. 27—"We became acquainted with the eastern parts of India on this side of the Hypanis and whatever parts beside which have been described by those who after Alexander advanced beyond the Hypanis to the Ganges and Palibothra".

362 18 Add after Selenkos "The Antiochos-Sophaganeus alliance may also have been directed against the Imperial Mauryas of Pāṭaliputra". Greek intrigue may have played a part in the disintegration of the empire before the Greek raids.

372 33 A Suṅgarāja (Agarāja?) is known from certain coins found at Kauśāmbī (*JNSI*, IV, i, 14). His identity is, however, uncertain.

382 For Coins of Apollodotus and Menander in Gujrat, see *Gaz. Bomb.* I, i, pp. 16-17; *Num. Chr. JRNS* (1950) 207.

382 18 After "Strato I" add the following: "Saltman (*Greek Coins* 235) refers to a large gold coin which Eukratides struck to mark his triumph over Demetrius. Some distinguish between a Bactrian and an Indo-Bactrian Heliodotus (*JRNS*, 1950, 211-12.) The duplication of the Indian Heliodotus requires cogent proof.

422 Whitehead in *JAOS*, 1950, 216, throws doubt on the conjecture that Agatbokles was the mother and not the wife of Strato I. In that case the theory of her marriage with Menander requires more convincing proof than that adduced by Rapson and Tarn.

423 fn 2 Tarn, *Greeks*, second edition, 527n. Deb'unda mural crown: J. Banerji *yakshis*.

424 The from Yona is also found in the Post-Aśokan period (cf. the Besnagar inscription of Heliodorus). Doubts were raised by Tarn *Greeks in Bactria and India*, 2nd. ed, 538.

SOME ADDITIONS AND CORRECTIONS 671

Page	Line	
427		Tahia is apparently different from the "Dahæ" of the classical writers which, says Macgovern, lay far to the west. According to Trogus the Asiani were the lords of the Tochari (<i>Reges Thocarorum Asiani</i> , JAOS, 61. 246ff; 65, 71ff).
431		For the <i>Scythian Period</i> , see now a monograph by Johanna Engelberta von Lohuizen de Leeuw.
439		Leeuw suggests that the era of the old Saka inscriptions began from the Yue-chi conquest of Bactria c 129 B.C.
444		The Charsadda Inscriptions of the year 303 refers to a grāmasvāmin and satrap (of Chukhsa?) named Avakhajbāda (Konow, <i>Acta Orientalia</i> XX, p. 103ff).
445	fn4	Add at the end "Also Whitehead, <i>Numismatic Chronicle</i> , 1944, pp. 19-104. <i>Apacharaja</i> of the Bajaur inscription is taken by some to mean 'ruler of the West'.
458		The periods of Yue-chi migration have been discussed by several scholars. The first period of march from Kanshu to the Upper Li, c. 173-161 B.C. Second stage from the Upper Li to the Oxus between 133-129 B.C. The third period began with the conquest of Bactria (c. 129 B.C.) Leeuw, <i>The Scythian Period</i> , pp. 31-33.
469	12	Bachhofer, JAOS, 61, 242.
540, 627		Recently Dr. D. C. Sircar has come across evidence in the Sumanḍala (Orissa) inscription which indicates that in 569 one Prithivi-Vigraha held Kaliṅga apparently as a Gupta vassal. Cf IHQ, XXVI, March, 1950.
593	11	Add after 476-7 "together with the Benares Stone Pillar ins. of 169 (=A.D. 478-79)" noted by Dr. D. C. Sircar (A.S.B. 6-12-48). (JRASB, 1949, 5ff).

SOME CORRECTIONS

<i>Page</i>	<i>Line</i>	<i>For</i>	<i>Read</i>
21	31	text	texts
38	19	the Pargiter	Pargiter
148	31	distinguisbes	distinguish
162	17	(aggamahī)	(aggamahisī)
168	23	difficult	difficult
190	16	Jam ndvipa	Jambudvipa
198	37	Hammurabi	Hammurabi
199	23	Mgadha	Magadha
201	28	Viśvāparāṇa	Viśva Parāṇa
200	29	girl	girl
200	31	Devanumpiya	Devanupiya
232	34	Kālavarpa	Kākavarpa
237	38	avarice	avarice and parentage
245	33	1494	149
263	24	Giger's	Geiger's
266	33	Erakine	Erskine
270	35	ocean	ocean
270	40	sceptica	sceptical
313	35	Ma Crindle	Mo Crindle
313	35	Gedrolic	Gedrosia
332	34	at	list
338	26	Buddist	Buddhist
350	8	successor	successors
361	35	1857	1878
372	12	Vidharbha	Vidarbha
378	13	Predecessor	predecessor
349	25	Devadhuti	Devabhuti
401	15	Bṛihaspatimītra	Bṛihaspatimītra
407	1	DIVERSE LINEAGE	DIVERSE LINEAGE OF
409	22	cessatio	cessation
486	12	regin	reign
549	23	Kmarupa	Kamarūpa
566	8	Basin	Basin
612	31	xistence	existence
614	24	studica	studies
620	37	ksetra	ksetra
628	38	1	7

OPINIONS AND REVIEWS

I.—Political History of Ancient India

From the Accession of Parikshit to the Extinction of
the Gupta Dynasty

Published by the Calcutta University

Opinions on the earlier editions and on Part I:—

The Hindusthan Review.—It is learned and luminous and is a scientific treatise based on the results of research into the records and materials of ancient Indian history, of which it is a sound and an accurate digest, interestingly put together. It is about the best text-book of the subject it deals with.

Dr. L. D. Barnett, London.—The author treats his materials with a certain degree of originality, but at the same time he preserves throughout a well-balanced judgment and never sacrifices critical caution to the passion for novel theories.....This interesting bookshews judgment, ingenuity, and learning. And not the least of the author's merits is that he can write plain English.

Dr. F. W. Thomas.—I have profited by a closer acquaintance with your Political History and other writings, which are really models of sound judgment combined with full knowledge.

Professor Hultzsch, Halle, Germany.—Your valuable workis the outcome of extensive researches and throws much light on darkest and most debated periods of Indian history. You have succeeded in building up an intelligible account from the stray and imperfect materials which are available to the historian of those times.

Professor Jolly, Wurzburg, Germany.—Your splendid volumeWhat an enormous mass of evidence has been collected and discussed in this work, an important feature of which is the quotation of the original texts along with their translation which makes it easy to control the conclusions arrived at. The ancient geography, not less than the ancient history of India, has been greatly furthered by your researches and much new light has been thrown on some of the most vexed problems of Indian Archaeology and Chronology. The indices are very copious and the study of your work is greatly facilitated by them.

Professor Pelliot, Paris.—Le nom de l'auteur est garant du sérieux du travail.

Professor Jarl Charpentier, Upsala, Sweden.—Professor Ray Chaudhury belongs to a set of young Hindu scholars who, combining the traditional education of a Pandit with a thorough training in English, German or French Universities, have lately been carrying on deep and fruitful researches in the various domains of Indian loreEven the student, who on essential points does differ widely from the opinions expressed by Professor Ray Chaudhury, must willingly recognize his high merits as a scholar.

Professor A. Schepotieff, Ufa, Russia.—For our study of the history of the Ancient Age your Political History of Ancient India is of very great importance (trans. from original).

C. E. A. W. Oldham (J. R. A. S., 1928, July)—Part I of Professor Ray Chaudhuri's work deals with the period from Parikṣit to Bimbisāra. The author seeks to show, as he tells us in his preface, "that chronological relation of the national transactions before 600 B.C. is not impossible." He has laid under contribution the usual authorities, the Vedic, Puranic, Buddhist, and Jaina texts—though he does not appear to place much reliance upon the last-named (cf. pp. 6 and 72). A vast mass of records has been collated, and the evidence marshalled in a very concise and able, and in some respects original, manner. The apposite quotations from the original texts are useful. Professor Ray Chaudhuri regards Parikṣit I and Parikṣit II, as they are named by the late Mr. Pargiter in his *Ancient Indian Historical Tradition*, as being probably one and the same king, and as identifiable with the Vedic Parikṣit. By "the great Janaka" he refers to the Janaka of the later Vedic texts, whose court is said to have been thronged with Brāhmanas, and not to the traditional first king Janaka, the eponymous founder of the Janakavamsa, or to Janaka Siradhvaja, the reputed father of Sītā. Synchronizing Guṇākhyā Sāṅkhāyana with Āśvalāyana and the Buddha, he inclines, it seems, to place Parikṣit in the ninth, and the "great Janaka" in the seventh century B.C. though he wisely avoids coming to any positive conclusion as to these debatable dates, and points out that if the evidence of the Purāṇas were accepted we would have to place them some five centuries earlier. If it could be established that Parikṣit came into power at the beginning of the ninth century, or the end of the tenth, this would help to corroborate the approximate chronology suggested by Mr. Pargiter, having regard also to the synchronism between Senajit Bārhadratha and Adhisimakṣa. But until more convincing evidence is discovered most scholars will probably agree in the verdict of Vincent Smith that nothing approaching exact chronology is yet available for periods anterior to about 650 B.C.

Much of the matter in Part II will perhaps be familiar to students of Indian history; but it has been arranged in a fresh and scholarly manner, while several important suggestions have been made on different questions. One or two of these may be cited as examples. On pp. 72-73 reasons are set forth for accepting the Ceylon tradition that Siśunāga was later than Bimbisāra. The view recorded by Mahamahopadhāya (sic) H. P. Śāstri that the ultimate dismemberment of the Mauryan empire was due to a reaction promoted by the Brāhmanas, is vigorously controverted. Whatever other causes may have operated, and Professor Ray Chaudhuri undoubtedly lays his finger on more than one such, Brāhmanical influences cannot be ignored. The arguments used for holding that Demetrius,¹ rather than Menander, was the Yavana invader of the Madhyadeśa in the time of Puṣyamitra and that Simuka, the founder of the Śātavāhana dynasty, must be placed in the first century B.C., deserve careful consideration.

Since Hoernle made his well-known suggestions as to the identity of Devagupta, mentioned in two inscriptions of Harṣavardhana,

¹ For the latest reading of the Hāthigumphā inscription reference to the Yavans king, see *JBORS.*, XIII, 223.

several writers have attempted to frame the history of the later Guptas of Eastern Mālava and Bihār and the Maukharis of Kanauj. The period presents many difficulties, which are not likely to be solved until some further evidence reveals itself. Having regard to the conditions of the times and the bitter enmity of the Maukharis, who were then very powerful, it seems unlikely that the Susthitavarman mentioned in the Aṣṣand (*sic*) inscription of Ādityasena as having been defeated by Mahāsenagupta of E. Mālava, could have been the king of Kāmarūpa, as the author states. Fleet's suggestion that he was the Maukhari king of that name,¹ whom we know to have been contemporaneous with Mahāsenagupta, seems more probable.

Not the least valuable part of the contents of this volume are the numerous comments on the geographical information supplied in the records quoted; and it is a matter of regret that of the five maps entered in the table of Contents (p. xvi), only one, *viz.*, that of "Bhāratavarsha" appears in the volume before us. As regards this map we are not told what specific period, if any, it refers to. In any case, the positions assigned to the Nisādas, S. Kosala, Kamboja, and the Rikṣa mountains seem to call for some explanation. On the other hand, the geographical information given in the text is extensive, and often suggestive, and it indicates that much attention has been devoted to this important auxiliary to ancient Indian historical research. The indexes, both bibliographical and general, have been very well prepared.

Professor A. Berriedale Keith, Edinburgh.—I have read through the work and find it to contain much that is valuable. The author has arrived at clearly cut opinions on many of the chief difficulties in the history of early India; he has formulated them effectively, and as a result, even when they do not commend themselves as final solutions, they will serve to promote the discussion and to facilitate further fruitful research. He observes a due sense of proportion and is well read in the literature. The work accordingly may justly be deemed a most valuable contribution to the subject-matter of which it treats.

Professor Wilh. Gelger, Munchen-Neubiberg, Germany.—I highly appreciate Mr. Ray Chaudhuri's work as a most happy combination of sound scientific method and enormous knowledge of both Brahmanical and non-Brahmanical literature. The work is written in lucid style in spite of its intricate subject and affords a mass of valuable evidence, throwing much light on the whole period of Indian History dealt in it. I see with special pleasure and satisfaction that we now are enabled by the author's penetrating researches to start in Indian chronology from the 9th instead of the 6th or 5th century B.C.

Professor Jackson, Columbia University, New York.—I can see the scholarly research which you have put into the volume, and am glad to have such a work for future reference in my historical studies.

Professor Louis de la Vallée Poussin, Brussels, Belgium.—I believe that the book is well designed and has the twofold merit of collecting a vast amount (and in some chapters, an exhaustive one) of references, and of giving a clear and reasonable *exposé* of the main

¹ No Maukhari king of that name is known (H. C. R. C.).

676 POLITICAL HISTORY OF ANCIENT INDIA

line of this history. I agree with the author on several controverted points of chronology.

Mrs. C. A. F. Rhys Davids.—Dr. Chaudhuri has made debtors of us all.

S. M. Edwardes (*The Indian Antiquary*, July, 1927, p. 140).—

Professor Raychaudhuri's book forms a solid contribution to the discussion of the various problems implicit in the early history of India.

Professor E. J. Rapson, Cambridge.—My best thanks for the kind present of a copy of the "Political History of Ancient India," which I am very glad to possess and which I shall find most useful for reference.

Professor Sten Konow, Norway.—The book is a very useful contribution.

Dr. Y. S. Sukthankar.—I have to refer to it very often, both for corroboration of historical facts of the epic and for geographical information and the excellent maps included in the volume. It has been always a matter of great gratification to me that you have adopted my views with reference to the Sātavāhanas and at last given them, in a standard history of India the appellation by which they call themselves...rather than accept the doubtful description of them given by the late Purāṇas.

Professor Nilakanta Sastri.—Your excellent Ancient History of India. I have been using it on every conceivable occasion.

Sitaram Kohli, Lahore.—I have immensely liked your book "Political History of Ancient India."

C. S. Srinivasachari, South India.—Our author rightly holds the balance between the views of Pargiter which would give excessive value to Kshatriya tradition whose date allowed of manipulation to serve dynastic ends and the value of Vedic tradition whose two strong points are its priority of date and freedom from textual corruption.

W. Charles de Silva, Colombo.—I have the greatest pleasure to express my high appreciation of your very valuable and learned article (Part I of the Political History).

Professor E. Washburn Hopkins.—It is a fine augury for Indian scholarship when native scholars of the first rank take seriously in hand the great problem of untangling the web of Indian history. To this work your book is a valuable contribution.

Professor H. Jacobi, Bonn.—Very suggestive and contains some important details.

Professor F. Otto Schrader.—I have read the book with increasing interest and do not hesitate to say that it contains a great many details which will be found useful by later historians. The portion I enjoyed most is that on the sixteen Mahājanapadas.

II. The Early History of the Vaishnava Sect

Published by the Calcutta University

Professor E. Washburn Hopkins, Yale University, America.—Your book has given me great satisfaction.....I am particularly pleased to see an incisive study of this kind in the realm of religious history.....Believe me, in the hope of further contributions of this character from your able pen.....

Professor A. Berriedale Keith, Edinburgh University.—While I do not concur in your view as to the original character of Kṛṣṇa, I recognise the care with which you have investigated the issue, and value highly the elaborate collation of the evidence which your work contains, and which will render it of much service to all students of this doubtless insoluble problem. The stress laid on the epigraphic evidence and the full use made of it is of special value, while in many details your opinions are of interest and value, as in the case of the date of Pāṇini.....

Sir George Grierson.—Very interesting and informing..... The book is full of matter which is of great importance for the history of religion in India and will form a valued addition to my collection of books on the subject.....

F. E. Pargiter, Oxford.—I agree with you in discarding various theories, but I don't think Kṛṣṇa Devakīputra is the famous Kṛṣṇa, and it seems to me your exposition can stand just as well without the identification as with it. Your book will help to elucidate the whole matter, but are you sure that the cult does not owe something to Christianity?

Professor F. Otto Schrader, Kiel, Germany.—I perfectly agree with your opinion that Chāndogya passage on Kṛṣṇa Devakīputra and his teaching is to be considered as the first historical record of Bhāgavatism. There were, of course, many Kṛṣṇas, but to conjecture that more than one was (sic) also a Devakīputra, is to my mind an unscientific boldness which is the less justifiable as the teachings mentioned in that passage, as you show, perfectly agree with those, e.g., of the Bhagavad-gītā and the Rk. quoted with the famous तद्धियोः परमं पदं.....

Professor Garbe, Tübingen, Germany.—I have read your book with the greatest interest and perfectly agree with you in the main points, as to the personality of Kṛṣṇa and the development of Bhāgavatism..... You have brought together much important material and elucidated the dark early history of Bhāgavatism as far as possible.

The Times Literary Supplement, May 12, 1921.—The lectures of Mr. Hemchandra Rav Chaudhuri on the early history of the Vaiṣṇava Sect read almost as would a Bampton lecture on the "Historical Christ" to a Christian audience. They are an attempt to disentangle the authentic figure of Kṛṣṇa from the mass of Puranic legend and gross tradition, from the wild conjectures and mistaken, if reasoned, theories which surround his name. The worship of Kṛṣṇa is not a superstitious idolatry; it is the expression of the Bhakti, the devotional faith of an intellectual people, and many missionaries, ill-equipped for dealing with a dimly understood creed would do well to study this little volume.....

Journal Asiatique, January-March, 1923, Paris.—Dans le domaine historique, signalons un travail plein de mérite de M. Hemchandra Rav Chaudhuri. *Materials for the Study of the Early History of the Vaiṣṇava Sect* (Dr. Jules Bloch of Paris).

Dr. Jules Bloch, Paris.—My Guru, Sylvain Lévi, who has come back from his travels, told me also of his esteem for that book.

Journal of the Royal Asiatic Society of Great Britain.—The scope of this small book is rightly expressed in its title. The author who is Lecturer in History in the Calcutta University, has collected and discussed statements, references, and allusions from the early literature to throw light on the position and life of Kṛṣṇa and the growth of Bhāgavatism. He deals with the various theories that have been put forward, and with good reasons discredits the views that Kṛṣṇa Vāsudeva was a solar deity or a tribal god or a vegetation deity. He is right in treating Kṛṣṇa Vāsudeva as one person, the Vṛṣṇi chief, but he unnecessarily identifies him with Kṛṣṇa Devakīputa, the scholar mentioned in the Chāndogya Upanishad.....(F. E. Pargiter).

The Bombay Chronicle, June 19, 1921.—Mr. Hemchandra Raychaudhuri of the Calcutta University has collected much valuable material from which he has succeeded in tracing the origin and growth of the Vaishnava creed. The Historicity of Srikrishna—or as the author calls him, Krishna Vāsudeva, is also handled with remarkable clearness.....

A. Govindacharya Svamin.—I pay you a most deserved compliment upon your acquaintance with the Azhvars and Sri Vaishnavism of southern India as evidenced in your learned book *the Early History of the Vaishnava Sect*.

III. Studies in Indian Antiquities

Demy 8vo. Pp. xvi, 211

Published by the Calcutta University

Professor E. J. Rapson, Cambridge.—Dr. Raychaudhuri's essays on Indian History and Antiquities are always well-informed, thoughtful and suggestive.

E. J. Thomas (J. R. A. S., October, 1933, p. 925).—The study which Dr. Raychaudhuri has already devoted to ancient Indian history is well known. In the present book he discusses some of the geographical problems which still face the historians, as well as Vedic, epic, and specially historical questions.....He has shown that Indian historical scholarship is proceeding on sound lines of its own and achieving independent results.

O. C. Gangoly.—Permit me to thank you for your valuable gift of *Studies in Indian Antiquities* in which I have read with great profit your article: *Vanga Kon Des?* It is an excellent contribution to our knowledge of the little known phase of old Bengal. You do not try to prove too much, yet you have given very much based on solid data. It is a pity many scholars do not know of this article—buried in a series of Essays in English.

Opinions on some of the Papers incorporated in the Volume.

Dr. Barnett.—They are very interesting and critically sound.

Dr. Keith.—They are all very interesting, and I am glad to note the very useful information elicited as to Bhoja.

Professor Dr. Sten Konow, Kristiania, Norway.—They are written in a thoroughly scholar-like way, and more especially it seems to me that your paper about the Laksmana Sena era deserves very careful attention.

Professor H. Jacobi.—The verification of the Bhāgavata credo in the Besnagar inscription is a find on which you may be congratulated.

Professor Schrader, Kiel, Germany.—The Antiquity of the *Rig Veda* is a sober and useful little piece of research work with which, on the whole, I fully agree. If we follow Jacobi and Tilak we create a gap (which we cannot bridge over) between the Mantras and the Brāhmaṇas, for the latter are certainly not far removed from early Buddhism. On the other hand, if Hertel were right, the *Rig Veda* would immediately precede Buddhism, and there would be no room at all for Brāhmaṇas and Upaniṣads.

Your important paper on the inter-relation of the two epics: The opinion held by Macdonell, Winternitz, and others, viz., that the heroes of the Mahābhārata are unknown to the Rāmāyaṇa, seems, indeed, to be untenable.....Again, I find it difficult, as you do, to distinguish between a Pāṇḍava story and a Kuru-Bharata Epic.

Professor Jarl Charpentier.—The identification of some words in this very important document (the Besnagar Inscription) with a passage in the Mahābhārata seems to be a most happy find.

Professor E. Washburn Hopkins.—It is certainly a remarkable resemblance which you have established and I should be inclined to agree with your conclusion.

IV. An Advanced History of India

Opinion on the book and particularly on the chapters contributed by the author of the Political History of Ancient India

PROFESSOR LOUIS RENOÜ, PARIS.—C'est un ouvrage tout-à-fait remarquable, destiné à mon avis à remplacer pour les étudiants avancés le Vincent Smith (et autres) un peu vieillis. Votre exposé est très clair, sobre, prudent, éloigné de toute hypothèse inutile.

Journal of the Royal Asiatic Society of Great Britain and Ireland.

Parts 1 and 2, 1949. Pp. 103-104. L. D. Barnett.

An Advanced History of India.—By R. C. Majumdar, H. C. Raychaudhuri, Kalikinkar Datta. Second edition, pp. ix, i, 1081; 10 maps. London: Macmillan and Co., 1948.

One of the most hopeful features in the mental life of modern India is its thirst for history. Schools, Colleges and Universities pursue this study with vigour. The favours of Clio are not easy to win: she loves to walk especially in the domain of India's past, though darkling ways.....But her Indian suitors have urged their quest with courage and often with notable skill, and their labours have borne fruit in a large number of works, many of high merit. In this book three distinguished Indian scholars have collaborated in order to produce for advanced students an outline of their country's history from the earliest ages down to our time, in which are summarized the main results of modern studies. In this

they have been on the whole very successful. Their attitude is generally fair and reasonable, their narrative lucid and straightforward. Naturally specialists, particularly in the realm of ancient Indian annals, on which opinions are very often divergent, will find food for criticism in some of the views presented ; but our authors may justly claim a right to their opinions.


It must, however, be acknowledged that in at least one respect their work shows some lack of proportion. They are Bengalis whose studies have been mainly concerned with the history of Northern India ; and this has led them to allot a very small space to the annals of the great kingdoms of the South from the decline of the Sātavāhanas to the end of the rule of the Calukyas, the Cōlas, and their epigoni (pp. 172-180 and 188-190). In some minor matters also there is room for improvement. Thus, the account of administration on p. 71 f. seems a little too summary and hardly critical enough ; and the statement on p. 81 that "another (highway) stretched from Rājagriha in South Bihār by way of Srāvastī in Oudh to the banks of the Godāvari" contradicts the facts,¹ for the highway ran from Srāvastī through Rājagriha to the Godāvari. The diacritic marking length of vowels is so often misplaced that one is led to think that the authors would have done better to have never used it at all. To quote a few examples, we find *passim* errors such as "Konkān," "Mālābār," "Peshāwar," "Māndalay," "Kathakālī," "Ālī," "Ālivardi" (for "Ilahvirdi") "Kāshmir," "Wāzīr," and both "Qāsim" and "Kāsīm," with other inconsistencies in representing the Arabic gutturals. On p. 71 we note with sorrow the misspelling "diarchy" ; on p. 202 f. we regret to see Basava presented as "Vasava," while on p. 203 Vātsyāyana appears as "Vātsāyana," both errors being due to the influence of Bengali pronunciation.² It is disagreeable also to meet hybrid spellings of names such as "Hyder 'Alī" and "Omdut-ul-Umarā."


In a work of this kind there should have been some recognition of Warren Hastings' enlightened and successful efforts to revive Hindu education and law ; absence is to be regretted.


This book, now in its second edition, will surely be soon reprinted ; and then, we hope, blemishes will be eliminated.

¹ Not, it may humbly be pointed out, the facts recorded in some early Buddhist texts (cf. *Sutta-Nipāta* and its trans. by Fausbøll, 1881, SBE, x, pt. ii, pp. 187-188, 209) which narrate a journey from Patitthāna (on the Godāvari) to several places including Sāvattthī and thence to the city of Magadha and to Pāsānaka cetiya in Magadha.

² That the errors in spelling are not all due to the influence of Bengali pronunciation will be apparent from the *Political History of Ancient India*, 4th ed. 1938, p. 339, line 29 ; and the *Ground-Work of Indian History* by Sen and Raychaudhuri, seventh edition (1945), p. 112, which gives a brief account of "Basava (not Vasava)." As to "diarchy" for which the authors are criticised attention may be invited to *The Universal Dictionary of the English Language*, edited by Henry Cecil Wyld (sixth impression, 1946) p. 304 where we have the following : "diarchythe irregularly formed 'dyarchy' is common and should be avoided." The explanation for many of the blemishes will be found in the Preface, especially on p. vi.







Col
N 26.8.74

CATALOGUED.

Central Archaeological Library,

NEW DELHI.

1633

Call No. 934-018

Ray

Author—

Hemchandra

Title—

Raychaudhuri

political history

Borrower No.

Date of Issue

Date of Return

of Ancient India

Indic

UPC 20/8/86

21.10.82

Sharma